HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-SRDD-CB-CTR-NIT-2024-25- 17480 -99 Dated:- 15-6-2025

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Scanned with OKEN Scanner

HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **24-01-2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **23.01.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **22.01.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be dept open for 75 days. **The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons.** If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	R/R damages on various roads under Totu section (SH: Hiring of JCB & Tipper for clearance of land slide) Job No.1.	99080/-	2000/-	One Month	Rs.350/-
2	R/R damages on various roads under Totu section (SH: Hiring of JCB & Tipper for clearance of land slide) Job No.2.	99080/-	2000/-	One month	Rs.350/-
3	R/R damages on MLA crossing to Tawi More road under totu section (SH: Hiring of JCB & Tipper for clearance of land slide) Job No.3.	99080/-	2000/-	One month	Rs.350/-
4	R/R damages on MLA crossing to Tawi More road under totu section (SH: Hiring of JCB & Tipper for clearance of land slide) Job No.4.	99080/-	2000/-	One month	Rs.350/-
5	R/R damages on Totu Tara Devi road Km. 0/00 to 4/105 (SH: C/O R/Wall at Rd. 1/775 to 1/778.35).	98516/-	2000/-	One month	Rs.350/-
6	R/R damages on Totu Tara Devi road Km. 0/00 to 4/105 (SH: C/O R/Wall at Rd. 1/778.35 to 1/781.70).	98440/-	2000/-	One month	Rs.350/-
7	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/979.09 to 0/982.79).	98898/-	2000/-	One Month	Rs.350/-
8	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/982.79 to 0/986.53).	99966/-	2000/-	One Month	Rs.350/-
9	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/975.35 to 0/979.09).	99966/-	2000/-	One Month	Rs.350/-
10	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/968 to 0/971.70).	98898/-	2000/-	One Month	Rs.350/-
11	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/971.50 to 0/975.35).	97581/-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

12	A/R & M/O Bag to Kayalu road portion Km. 0/00 to 10/500 (SH: Maintenance of drain, trimming of Grass, Maintenance of berms/shoulder, Maintenance of Hume pipe culvert in Km. 5/00 to 10/500).	99899/-	2000/-	One month	Rs.350/-
13	A/R & M/O Bag to Kayalu road portion Km. 0/00 to 10/500 (SH: Maintenance of drain, trimming of Grass, Maintenance of berms/shoulder, Maintenance of Hume pipe culvert in Km. 0/00 to 5/00).	99899/-	2000/-	One month	Rs.350/-
14	R/R damages on various road under Shoghi Sub Division (SH: Removal of slips (i) Sadhupul geha road Km. 3/300 to 5/600).	98961/-	2000/-	One month	Rs.350/-
15	A/R & M/O Salana Sari road Km. 0/00 to 4/200 (SH: Maintenance of drain, trimming of Grass & Maintenance of eartehen shoulder in Km. 0/00 to 2/100) Job No. I	99855/-	2000/-	One Month	Rs.350/-
16	A/R & M/O Salana Sari road Km. 0/00 to 4/200 (SH: Maintenance of drain, trimming of Grass & Maintenance of eartehen shoulder in Km. 2/100 to 4/200) Job No. 2	99855/-	2000/-	One Month	Rs.350/-
17	A/R & M/O Hanuman Mandir to Trari road Km. 0/00 to 2/300 (SH: Maintenance of drain, trimming of Grass & Maintenance of eartehen shoulder in Km. 0/00 to 2/300) .	97455/-	2000/-	One Month	Rs.350/-
18	A/R & M/O Phayal Daunti via Shamleeg (SH: Maintenance of drain, trimming of Grass & Maintenance of eartehen shoulder in Km. 2/117 to 4/135) Job No.2.	96259/-	2000/-	One Month	Rs.350/-
19	A/R & M/O Taradevi Gamber road Km. 0/00 to 11/500 (SH: Maintenance of drain, trimming of Grass & Maintenance of eartehen shoulder in Km. 9/00 to 11/500).	99810/-	2000/-	One Month	Rs.350/-
20	A/R & M/O on Kanda Ladvi Kunihar road in Km. 0/00 to 9/150 (SH: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulders & catch pits / pot hole etc. in Km. 0/00 to 6/00).	98550/-	2000/-	One Month	Rs.350/-
21	C/O link road from Piplughat to Pergaina Km. 0/00 to 2/100 (SH: C/O wire crate for dumping site).	98063/-	2000/-	One Month	Rs.350/-
22	C/O link road from Piplughat to Pergaina Km. 0/00 to 2/100 (SH: C/O wire crate for dumping site).	99999/-	2000/-	One Month	Rs.350/-
23	R/R damages on Dhanpar Sandoa galah Saraiya road Km. 0/00 to 8/100 (SH: C/O B/Wall at Km. 3/355 to 3/362) (PCC).	95369/-	2000/-	One Month	Rs.350/-
24	R/R damages on Dhanpar Sandoa galah Saraiya road Km. 0/00 to 8/100 (SH: C/O B/Wall at Km. 4/420 to 4/426.80) (PCC).	96413/-	2000/-	One Month	Rs.350/-
25	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 1, (Shimla Nalagarh road).	96000/-	2000/-	One Month	Rs.350/-
26	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 2, (Shimla Nalagarh road & MLA crossing to Tawi).	96000/-	2000/-	One Month	Rs.350/-
27	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 3, (MLA crossing to Tawi).	99200/-	2000/-	One Month	Rs.350/-
28	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 4 (MLA crossing to Tawi totu Bazar & Jathiadevi Rampuri road).	97600/-	2000/-	One Month	Rs.350/-
29	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 5, (Jathiadevi Rampuri road).	98400/-	2000/-	One Month	Rs.350/-
30	A/R & M/O various road under sub division Jutogh (SH: Supplying & Stacking VI pot seal bag cold mix) Job No. 6, (Jathiadevi Rampuri & Neri Sangti road).	99200/-	2000/-	One Month	Rs.350/-

Scanned with OKEN Scanner

31	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/720 to 0/724).	98254/-	2000/-	One Month	Rs.350/-
32	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/960 to 0/964).	98325/-	2000/-	One Month	Rs.350/-
33	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/769 to 0/773).	98363/-	2000/-	One Month	Rs.350/-
34	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/765 to 0/769).	98482/-	2000/-	One Month	Rs.350/-
35	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 0/724 to 0/728).	98254/-	2000/-	One Month	Rs.350/-
36	Improvement of black spot on Badheri Shilly roa Km. 0/00 to 4/500 (SH: C/O Edge wall in Rd. 3/080 to 3/087.30).	96405/-	2000/-	One Month	Rs.350/-
37	Improvement of black spot on Badheri Shilly road Km. 0/00 to 4/500 (SH: C/O Edge wall in Rd. 3/020 to 3/027.50).	99002/-	2000/-	One Month	Rs.350/-
38	Improvement of black spot on Badheri Shilly road Km. 0/00 to 4/500 (SH: C/O Edge wall in Rd. 3/040 to 3/047.30).	96405/-	2000/-	One Month	Rs.350/-
39	Improvement of black spot on Badheri Shilly road Km. 0/00 to 4/500 (SH: C/O Edge wall in Rd. 3/048 to 3/055).	99002/-	2000/-	One Month	Rs.350/-
40	Improvement of black spot on Badheri Shilly road Km. 0/00 to 4/500 (SH: C/O Edge wall in Rd. 3/280 to 3/287.50).	99002/-	2000/-	One Month	Rs.350/-
41	R/R damages on MLA crossing to Tawi More road Km. 0/00 to 1/630 (SH: C/O R/Wall at Rd. 0/420 to 0/422.20 Balance work).	85418/-	2000/-	One Month	Rs.350/-
42	A/R & M/O on Chailly Kadachi via Beount road Km. 0/00 to 10/00 (SH: C/O V-shape drain at Rd. 0/350 to 0/590).	99502/-	2000/-	One Month	Rs.350/-
43	R/R damages on Ghanahatti Nehra Bhukoo road Km. 0/00 to 8/00 (SH: C/O R/Wall at Rd. 4/990 to 4/996).	99995/-	2000/-	One Month	Rs.350/-
44	C/O Bainsh Bangera road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 1/179.50 to 1/182.20).	98278/-	2000/-	One Month	Rs.350/-
45	R/R damages on Shimla Nalagarh road Km. 7/00 to 22/00 (SH: C/O R/Wall at Rd. 8/452 to 8/455).	98254/-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

(i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.

(ii) Special care would be taken to write the percentage rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhami.

Certificate

Certified that the tenders called vide this notice inviting tender for 45 (forty five) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhami.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various Roads under Totu Section (Sh: Hiring of JCB & Tipper for Clearence of Land Slide) Job No. 1

Estimated Cost: - Rs 99080 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		4	5	6	7
1	Hiring of JCB Machime for removal of Malwa / debris and Dressing of Berms along road with capacity 45 Cum Per hour minimum six hours per day including pay of operator, P.O.L. charges, maintenance of any minor or major accidents and other damages to private and Govt. Property occur during working hours is whole responsibility of contractor disposal of unserviceable materials and stacking of serviceable material along road side in all leads and lifts and as per the direction by the Engineer in Charge.	64.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	70080.00
2	Hiring of Tipper for removal pof slips / debries with minimum capacity of 5.50 cum per and minimum working 6 hours per day. The contractor / over of the tipper all beer the expansion of P.O.L. charges repair of mechineries. Any accident and other damages to be the private and Govt. property access during the working hours is responsibility of the contractor including all leads and lifts as per the direction of Engneer in Charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Day	29000.00
						Total:	**99080.00**
0							
	Amount Quoted by the Contractor in Percentage					Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various Roads under Totu Section (Sh: Hiring of JCB & Tipper for Clearence of Land Slide) Job No. 2

Estimated Cost: - Rs 99080 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		4	5	6	7
1	Hiring of JCB Machime for removal of Malwa / debris and Dressing of Berms along road with capacity 45 Cum Per hour minimum six hours per day including pay of operator, P.O.L. charges, maintenance of any minor or major accidents and other damages to private and Govt. Property occur during working hours is whole responsibility of contractor disposal of unserviceable materials and stacking of serviceable material along road side in all leads and lifts and as per the direction by the Engineer in Charge.	64.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	70080.00
2	Hiring of Tipper for removal pof slips / debries with minimum capacity of 5.50 cum per and minimum working 6 hours per day. The contractor / over of the tipper all beer the expansion of P.O.L. charges repair of mechineries. Any accident and other damages to be the private and Govt. property access during the working hours is responsibility of the contractor including all leads and lifts as per the direction of Engneer in Charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Day	29000.00
0						**Total:**	**99080.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on MLA Crossing to Tawi More Road unde Totu Section (Sh: Hiring of JCB & Tipper for Clearence of Land Slide) Job No. 3

Estimated Cost: - Rs 99080 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		4	5	6	7
1	Hiring of JCB Machime for removal of Malwa / debris and Dressing of Berms along road with capacity 45 Cum Per hour minimum six hours per day including pay of operator, P.O.L. charges, maintenance of any minor or major accidents and other damages to private and Govt. Property occur during working hours is whole responsibility of contractor disposal of unserviceable materials and stacking of serviceable material along road side in all leads and lifts and as per the direction by the Engineer in Charge.	64.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	70080.00
2	Hiring of Tipper for removal pof slips / debries with minimum capacity of 5.50 cum per and minimum working 6 hours per day. The contractor / over of the tipper all beer the expansion of P.O.L. charges repair of mechineries. Any accident and other damages to be the private and Govt. property access during the working hours is responsibility of the contractor including all leads and lifts as per the direction of Engneer in Charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Day	29000.00
0						**Total:**	**99080.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on MLA Crossing to Tawi More Road unde Totu Section (Sh: Hiring of JCB & Tipper for Clearence of Land Slide) Job No. 4

Estimated Cost: - Rs 99080 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		4	5	6	7
1	Hiring of JCB Machime for removal of Malwa / debris and Dressing of Berms along road with capacity 45 Cum Per hour minimum six hours per day including pay of operator, P.O.L. charges, maintenance of any minor or major accidents and other damages to private and Govt. Property occur during working hours is whole responsibility of contractor disposal of unserviceable materials and stacking of serviceable material along road side in all leads and lifts and as per the direction by the Engineer in Charge.	64.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	70080.00
2	Hiring of Tipper for removal pof slips / debries with minimum capacity of 5.50 cum per and minimum working 6 hours per day. The contractor / over of the tipper all beer the expansion of P.O.L. charges repair of mechineries. Any accident and other damages to be the private and Govt. property access during the working hours is responsibility of the contractor including all leads and lifts as per the direction of Engneer in Charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Day	29000.00
0						**Total:**	**99080.00**
	Amount Quoted by the Contractor in Percentage					**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Restoration of Rain Damages on Totu Tara devi road km. 0/00 to 4/105 (SH:- C/O R/wall at Rd .1/775 to 1/778.35)

Estimated Cost:- 98,516.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	10.62	Per cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3786
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 20 mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.99	Per cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	89253
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	11.90	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2261
4	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.82	Per cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3216
	Total Rs.						**98516**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 98,440.00

Name Of Work :- Restoration of Rain Damages on Totu Tara devi road km. 0/00 to 4/105 (SH:- C/O R/wall at Rd .1/778.35 to 1/781.70)

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	10.62	Per cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3786
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 20 mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.99	Per cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	89253
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	11.50	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2185
4	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.82	Per cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3216
	Total Rs.						**98440**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Road Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at Rd. 0/979.09 to 0/982.79)

Estimated Cost: - Rs 98898 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.33	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1944.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.81	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1715.00
3	Providing and Laying cement concrete for plain / reinforced conc In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.98	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91908.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.22	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1869.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1462.00
0						**Total:**	**98898.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Road Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at Rd. 0/982.79 to 0/986.53)

Estimated Cost: - Rs 99966 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.42	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1965.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.86	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1733.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92920.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.24	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1886.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1462.00
0						**Total:**	**99966.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Road Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at Rd. 0/975.35 to 0/979.09)

Estimated Cost: - Rs 99966 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.42	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1965.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.86	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1733.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.20	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92920.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.24	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1886.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1462.00
0						**Total:**	**99966.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Road Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at Rd. 0/968 to 0/971.70)

Estimated Cost: - Rs 98898 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.33	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1944.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.81	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1715.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.98	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91908.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.22	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1869.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1462.00
0						**Total:**	**98898.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Okhroo Nehra via Keru Road Km. 0/00 to 3/00 (Sh: Construction of Retaining wall at Rd. 0/971.50 to 0/975.35)

Estimated Cost: - Rs 97581 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

	Sub head and items of work	Qty.		Rate	figures	Unit	Amount
	2	3		4	5	6	7
	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	8.21	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1916.00
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.75	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1693.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.71	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90666.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.19	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1844.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	8.60	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1462.00
0						**Total:**	**97581.00**
	Amount Quoted by the Contractor in Percentage					**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work :- A/R & M/O Bag to Kayalu road portion Km 0/00 to 10/500 SH: Maintenance of drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance Of Hume Pipe Culvert in Km 5/00 to 10/500

Estimated Cost:- ₹ 99,899.00 Only.
Earnest Money: ₹ 2,000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2175.00	Rmt			Rmt	
2	Trimmmg ot grass and weeds from the shoulders/berms and disposing offthe same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1845.00	Sqm			Sqm	
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1327.50	Sqm			Sqm	
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	7.00	Nos.			Nos.	
					Total		
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Scanned with OKEN Scanner

Schedule of Quantity

Name of Work :- A/R & M/O Bag to Kayalu road portion Km 0/00 to 10/500 SH: Maintenance of drain, Trimming of Grass, Maintenance of berms/shoulders, Maintenance Of Hume Pipe Culvert in Km 0/00 to 5/000

Estimated Cost:- ₹ 99,367.00 Only.
Earnest Money: ₹ 2,000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1425.00	Rmt			Rmt	
2	Trimmmg ot grass and weeds from the shoulders/berms and disposing offthe same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	2745.00	Sqm			Sqm	
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	1098.00	Sqm			Sqm	
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repar repairs to cracks parapet wail and protection work as per drawing and technical specification Clause 1908 carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	11.00	Nos.			Nos.	
					Total		
	Amount procured by the contractor in percentage	**Rs.**					
	Conditions:- All the Machineries/materials will be procurred by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- Restoration of Rain Damages on various road under Shoghi Sub Divisiom (SH:- Removal of Slips (i) Sadhupul Geha road km. 3/300 to 5/600)

Estimated Cost:- 98,961.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1099.57	Cum	90.00	Rupees Ninety Only	Per cubic metre	98961
	Total Rs.						**98961**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 99,855.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :- A/R & M/O to Salana Sari road km. 0/00 to 4/200 (SH:- Maintenance of drain, Trimming of Grass, & Maintenance of earthen Shoulder in km. 0/00 to 2/100) Job No. 1

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2100.00	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	9450
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	4410.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	19845
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2940.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	70560
	Total Rs.						**99855**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,855.00	
Name of Work :- A/R & M/O to Salana Sari road km. 0/00 to 4/200 (SH:- Maintenance of drain, Trimming of Grass, & Maintenance of earthen Shoulder in km. 2/100 to 4/200) Job No. 2						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2100.00	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	9450
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	4410.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	19845
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2940.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	70560
	Total Rs.						99855
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O on Hanuman Mandir to Trari road km. 0/00to 2/300 (SH:- Maintenance of drain, Trimming of Grass, & Maintenance of earthen Shoulder in km. 0/00 to 2/300)

Estimated Cost:- 97,455.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2300.00	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	10350
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3410.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15345
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2990.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	71760
	Total Rs.						**97455**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- A/R & M/O on Phayal Dawanti via Shamleeg (SH:- Maintenance of drain, Trimming of Grass, & Maintenance of earthen Shoulder in km. 2/117 to 4/135) Job No. 2	Estimated Cost:- 96,259.00 Earnest Money:- 2000.00 Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907, including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2018.00	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	9081
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3228.80	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	14530
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3027.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	72648
	Total Rs.						96259
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 99,810.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :- A/R & M/O on Tara Devi Gamber road km. 0/00 to 11/500 (SH:- Maintenance of drain, Trimming of Grass, & Maintenance of earthen Shoulder in km. 9/00 to 11/500)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2430.00	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	10935
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3750.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	16875
3	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3000.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	72000
	Total Rs.						**99810**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kanda Ladvi Kunihar Road in Km. 0/00 to 9/150 (Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulders & catch pits / pot hole etc, in km. 0/00 to 6/00)

Estimated Cost: - Rs 98550 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate	Rate figures	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of Excavator-cum-Loader for removal of slips including cost of fuel oil lubricants wages of operational staff any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor & including all leads and lifts & work shall be executed as per the direction of Engineer -in-Charge.	90.00 Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550.00
0					Total:	98550.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name Of Work :- C/O link road from Piplughat to pergaina km. 0/00 to 2/100 (SH:- C/o wire crate for Dumping site)

Estimated Cost:- 98,063.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1.	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	4.38	Per cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1561
2.	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.34	Per cum	3529.70	Rupees Three Thousand Five Hundred Twenty Nine and Paise Seventy Only	Per running Metre	96502
	Total Rs.						98063
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity						Estimated Cost:- 99,999.00	
Name Of Work :- C/O link road from Piplughat to pergaina km. 0/00 to 2/100 (SH:- C/o wire crate for Dumping site)						Earnest Money:- 2000.00 Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1.	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6.64	Per cum	356.50		Per cubic metre	2367
2.	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.66	Per cum	3529.70		Per running Metre	97632
							99999
	Total Rs.						
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 95,369.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :- R/R damages on Dhanpar Sandoa Gallah Saraiya road km.0/00 to 8/100. (SH:- C/O B/wall at km 3/355 to 3/362) (PCC)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited), all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	2.94	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	585
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.19	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	424
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth, including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	18.34	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	91700
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	14.00	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2660
	Total Rs.						**95369**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP.PWD. Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 96,413.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :- R/R damages on Dhanpar Sandoa Gallah Saraiya road km.0/00 to 8/100. (SH:- C/O B/wall at km. 4/420 to 4/426.80) (PCC)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited) all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	2.86	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	569
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.16	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	414
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	17.82	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	89100
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	14.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running Metre	2660
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.67	Cum	1000.00	Rupees One Thousand Only		3670
	Total Rs.						**96413**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD. Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 1 Shimla Nalagarh Road .

Estimated Cost: - Rs 96000 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	120.00 No.	800.00	Rupees Eight Hundred Only	Each	96000.00
0					**Total:**	**96000.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 2 (Shimla Nalagarh Road & MLA crossing to Tauni road)

Estimated Cost: - Rs 96000 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	120.00	No.	800.00	Rupees Eight Hundred Only	Each	96000.00
0						Total:	96000.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 3 MLA Crossing To Tanai

Estimated Cost - Rs 99200 /- only
Earnest Money - Rs 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge	124.00	No.	800.00	Rupees Eight Hundred Only	Each	99200.00
0						Total	99200.00

Amount Quoted by the Contractor in Percentage Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 4 MLA Crossing To TAXI Stand Totu Bazar & Jathia Devi Pant Puri.

Estimated Cost: - Rs 97600 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	122.00 No.	800.00	Rupees Eight Hundred Only	Each	97600.00
					Total:	**97600.00**
0						
	Amount Quoted by the Contractor in Percentage				**Rs.**	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 5 (Jathia Devi Rmpuri)

Estimated Cost: - Rs 98400 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	123.00 No.	800.00	Rupees Eight Hundred Only	Each	98400.00
0					**Total:**	**98400.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair and Maintenance of Various Road under Sub Division Jutogh (Sh: Supplying and Stacking VI pot seal bag cold mix) Job No. 6 Jatia Devi Rampur of Nesi Sangti Road.

Estimated Cost :- Rs 99200 /- only
Earnest Money :- Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	figures	Unit	Amount
1	2	3		4	5	6	7
1	Supplying and stacking VI pot seal beg of 25 kgs cold mix including carriage of materials upto all leads and lifts as per diretion of Engineer in Charge.	124.00	No.	800.00	Rupees Eight Hundred Only	Each	99200.00
0						Total:	99200.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Construction of Okhroo Nehra via Keru road km. 0/00 to 3/00
(SH:- Construction of Retaining wall at Rd. 0/720 to 0/724)

Estimated Cost:- 98,254.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1050
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	5.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1854
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same	19.40	Cum	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	90210
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7	11.10	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2109
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.60	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030
	Total Rs						**98254**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 98,325.00
Earnest Money:- 2000.00
Time:- One Months.

Name of Work :-Construction of Okhroo Nehra via Keru road km. 0/00 to 3/00 (SH:- Construction of Retaining wall at Rd. 0/960 to 0/964)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1050
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	5.40	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1925
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same	19.40	Cum	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	90210
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7	11.10	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2109
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.60	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030
	Total Rs						**98325**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Construction of Okhroo Nehra via Keru road km. 0/00 to 3/00 (SH:- Construction of Retaining wall at Rd. 0/769 to 0/773)

Estimated Cost :- 98,363.00
Earnest Money :- 2000.00
Time :- One Months.

S.No	Description of Work	No of Qty		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	P excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including dewatering and removing of mixed soil, ordinary rock and hard rock all kinds of rock cutting by blasting shall be carried out by taking all necessary precautions against land erosion, damage to hill soils water pollution, shaking and to protect stability of hill soils track shall be completed with shooting and wedging but rock (where blasting is prohibited) all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades and slopes width, camber super elevation and level as shown in the drawings including carriage of material within all leads and lifts	4.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1050
2	Earth work in excavation for structures as per drawing and technical specification clauses 308.1 including setting out, construction of shoring, bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 5m depth, including carriage of material within all leads and lifts	5.40	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1925
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in foundation and plinth, including carriage of material The rate including octroi, royalty, Wallkera toll tax GST or any other taxes inputtio or output by the contract shall be payable to the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.40	Cum	4630.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	90210
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structure with slop of 1 in 20(H) towards drawing face complete as per drawing and technical specification clauses 314.705.1220.3.7	11.30	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2147
5	Back filling filling behind abutment wing wall and retaining wall and breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1996 volume-I including carriage of material within all leads and lifts	3.60	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030
	Total Rs						**98363**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Name of Work :- Construction of Okhroo Nehra via Keru road km. 0/00 to 3/00 (SH:- Construction of Retaining wall at Rd. 0/765 to 0/769)

Estimated Cost:- 98,482.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts	4.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1050
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts	5.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1854
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	19.40	Cum	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	90210
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	12.30	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2337
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.60	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030
	Total Rs						**98482**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

Schedule Of Quantity

Estimated Cost:- 98,254.00

Earnest Money:- 2000.00

Time:- One Months.

Name of Work :- Construction of Okhroo Nehra via Keru road km. 0/00 to 3/00 (SH:- Construction of Retaining wall at Rd. 0/724 to 0/728)

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shallbe carried,out true tolines,grades,side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	4.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1050
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	5.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1854
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin Foundation and plinth. including carriage of material The rate including octroi, royality, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same	19.40	Cum	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	90210
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	11.10	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2109
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	3.60	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3030
	Total Rs						**98254**
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black Spot on Badheri Shilly Road Km. 0/00 to 4/500 (Sh: Construction of Edge wall in Rd. 3/080 to 3/087.30)

Estimated Cost: - Rs 96405 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.14	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3067.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	10.51	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3747.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.40	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	84640.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.67	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3931.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1020.00
0						**Total:**	**96405.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black Spot on Badheri Shilly Road Km. 0/00 to 4/500 (Sh: Construction of Edge wall in Rd. 3/020 to 3/027.50)

Estimated Cost: - Rs 99002 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3151.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	10.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3850.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.90	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	86940.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4041.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1020.00
						Total:	99002.00
0							
	Amount Quoted by the Contractor in Percentage					Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black Spot on Badheri Shilly Road Km. 0/00 to 4/500 (Sh: Construction of Edge wall in Rd. 3/040 to 3/047.30)

Estimated Cost: - Rs 96405 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.14	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3067.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	10.51	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3747.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.40	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	84640.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.67	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3931.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1020.00
0						**Total:**	**96405.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black Spot on Badheri Shilly Road Km. 0/00 to 4/500 (Sh: Construction of Edge wall in Rd. 3/048 to 3/055)

Estimated Cost: - Rs 99002 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3151.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	10.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3850.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.90	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	86940.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise	Per cubic metre	4041.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1020.00
0						Total:	99002.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black Spot on Badheri Shilly Road Km. 0/00 to 4/500 (Sh: Construction of Edge wall in Rd. 3/280 to 3/287.50)

Estimated Cost: - Rs 99002 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	13.50	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3151.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	10.80	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3850.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	18.90	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	86940.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.80	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4041.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	6.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1020.00
						Total:	**99002.00**
0							

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on MLA Crossing to Tawi More Km. 0/00 to 1/630 (Sh: Construction of R-wall at R.D. 0/420 to 0/422.20 Balance work)

Estimated Cost: - Rs 85418 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3.17	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	740.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	4.29	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1529.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	17.50	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	80500.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	3.80	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	646.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.38	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2003.00
0						**Total:**	**85418.00**

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- annual Repair & maintenance on Chailly Kadachi via Beaunt road km. 0/00 to 10/00 (Sh: Construction of V-shape drain at RD. 0/350 to 0/590)

Estimated Cost: - Rs 99502 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	25.60	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	9126.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Milimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	17.38	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	90376.00
0						Total:	99502.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Construction of Bainsh Bangera Road km. 0/00 to 3/00 (Sh: Construction of R-wall at R.D. at 1/179.50 to 1/182.20)

Estimated Cost: - Rs 98278 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	5.24	Cum	233.40	Rupees Two Hundred Thirty Three and Paise	Per cubic metre	1223.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	9.50	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3387.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.49	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	89654.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.86	Cum	841.80	Rupees Eight Hundred Forty One and	Per cubic metre	1566.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	14.40	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2448.00
0						Total:	98278.00

Amount Quoted by the Contractor in Percentage	Rs.	

Note : (i) All the material will procured by the contractor him self.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Shimla Nalagarh Road Km. 7/00 to 22/000 (Sh: C/o R-wall at RD. 8/452 to 8/455)

Estimated Cost. - Rs 98139 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate	Rate figures	Unit	Amount
1	2	3		4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deletorius materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge	6.00	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1400.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitabale material as per MORD specification directed by Engineer-in-Charge.	9.00	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	3209.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.62	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90252.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.40	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2020.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.40	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1258.00
						Total:	**98139.00**
0							
	Amount Quoted by the Contractor in Percentage					**Rs.**	

0

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Scanned with OKEN Scanner