

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2024:-
To,

5621-30

Dated:-

15/01/2025

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:-

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tenders on the form 6&8 are hereby invited by the Executive Engineer Fatehpur Division HPPWD., Fatehpur on behalf of the Governor of HP for the below noted works from eligible Contractors/firms registered in HPPWD in appropriate class as per revised enlistment rules. So as to reach in this office on or before 29-01-2025 up to 12:00 Noon and the same shall be opened on the same day at 12:30 PM in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 28.01.2025 upto 4:00 PM. The application for issued of tender form shall be received for 27-01-2025 up to 4:30.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/ bank in HP duly pledged in the favour of undersigned.

Conditional tenders telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Fatehpur Division HP PWD at Fatehpur reserves the right to accept or reject the tenders. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	Construction of Mahila Bathroom (SNAN GHAR) near Sookha Khoo in village Chandrehar in G.P Thehar (Under SDP) Deposit work (SH:- Construction of Bathroom).	98372.00	2000.00	One Month	350/-	Class D&C
2	Construction of Mahila Bathroom (SNAN GHAR) in village Jhanjhal in G.P Diyana (Under SDP) Deposit work (SH:- Construction of Bathroom).	98378.00	2000.00	One Month	350/-	Class D&C
3	Re-Construction of Retaining wall near the house of Narsingh Temple Habitation village Fatehpur G.P Fatehpur (Under SDRF) Deposit work (SH:- Construction of PCC Retaining wall (1st step) at RD. 0/0 to 0/015.60).	93608.00	1900.00	One Month	350/-	Class D&C
4	Re-Co Retaining wall near house of Vijay Kumar in village Reeng G.P. Thehar (Under SDF) Deposit work (SH:- Construction of R/wall at RD 0/0 to 0/009).	94353.00	1900.00	One Month	350/-	Class D&C
5	Construction of Pucca Path from Mela Ram Machine to Dhiman Basti village Mudda in GP Thehar (Under SDP) Deposit work (SH:- Providing and Laying Cement concrete Pavement at RD. 0/0 to 0/038)	95427.00	1900.00	One Month	350/-	Class D&C
6	Construction of Pucca Path from Prithi House to Malkiyat Singh House village Bankehar in GP Kutwasi (Under SDP) Deposit work (SH:- Providing and Laying Cement concrete Pavement at RD. 0/0 to 0/034)	71153.00	1500.00	One Month	350/-	Class D&C
7	Construction of Pucca Path from Pratap Singh house to Joginder House village Bankehar in G.P. Kutwasi (Under SDP) Deposit work (SH:- Const. of Edge wall with C.C Pavement at RD. 0/0 to 0/023)	70383.00	1500.00	One Month	350/-	Class D&C
8	Re-Construction of Retaining wall near the house of Ramesh Singh village Bari in G.P. Hatli (Under SDRF) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/009.50)	94673.00	1900.00	One Month	350/-	Class D &C


9	Construction of MTN road Sohar to Gurial road Km. 0/00 to 2/000 (SH:- Construction of U-Shape drain at Km. 1/315 to 1/345).	83810.00	1700.00	One Month	350/-	Class D&C
10	Construction of Culvert on Hatli Maukhar road at village Loh Near Chakki and Ravinder Kumar House (Under MLALAD) Deposit work (SH:- Construction of Slab on existing U-shape Drain).	96345.00	1900.00	One Month	350/-	Class D&C
11	Re-Construction of R-wall near the house of Rakesh Kumari in village Sanaurth in G.P. Bagroli (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/009).	94673.00	1900.00	One Month	350/-	Class D&C
12	Re-Construction of R-wall near the house of Gurbachan Singh in village Badnad in G.P. Bagroli (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/010).	70517.00	1400.00	One Month	350/-	Class D&C
13	Re-Construction of Retaining wall near house of Gorkhi Ram in village Bassi in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/007).	69708.00	1400.00	One Month	350/-	Class D&C
14	Re-Construction of Edge wall near the house of Sudarshan to Ridku Ram Ke Ghar tk village Bassi in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/010).	70517.00	1400.00	One Month	350/-	Class D&C
15	Re-Construction of R-wall behind house of Balwinder Kaur W/o Rajinder Singh village Kutt in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/007).	69708.00	1400.00	One Month	350/-	Class D&C
16	Re-Construction of Retaining wall near house of Gurcharan Singh in village Khudial in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/010).	70515.00	1400.00	One Month	350/-	Class D&C
17	Re-Construction of R/wall near Mahila Mandal Bhawan village Kutt in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/007).	69708.00	1400.00	One Month	350/-	Class D&C
18	Re-Construction of R-wall near the house of Kushla Devi in village Khudial in G.P. Kutwasi (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/010).	70517.00	1400.00	One Month	350/-	Class D&C
19	Construction of Pucca Path from Magar Singh house House to Kulveer House in village Badnad in G.P Bagroli (Under SDP) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/010 and P/L Cement concrete pavement at RD. 0/0 to 0/024)	69523.00	1400.00	One Month	350/-	Class D&C
20	Re-Construction of Retaining wall near house of Madan Lal R/o village Badnad Hourri Devi in G.P Bagroli (Under SDRF) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/010)	94353.00	1900.00	One Month	350/-	Class D&C
21	Construction of Pucca path from Harbans Singh House to Rajesh house village Bamboti in GP. Lohara Under MLALAD (Deposit work). (SH:- P/L Cement concrete pavement at RD. 0/0 to 0/050).	99645.00	2000.00	One Month	350/-	Class D&C
22	Re-Construction of Retaining wall near the house of Surinder Singh in Ward No. 05 in G.P Nangal (Under SDRF) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/009.50)	94673.00	1900.00	One Month	350/-	Class D&C

23	Construction of Pucca path from Ram Rakha house to the house of late Sh. Amarnath village Rudi GP Diyana under (MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/022).	97803.00	2000.00	One Month	350/-	Class D&C
24	Construction of Pucca Path near the house of Paras Ram, Pavan Kumar village Kut in G.P. Kutwasi (Under SDP) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/009.30).	68325.00	1400.00	One Month	350/-	Class D&C
25	Re-Construction of R-wall near the land of Chaman Lal village Khairian in G.P. Bagroli (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/013)	93419.00	1900.00	One Month	350/-	Class D&C
26	Re-Construction of Retaining wall near house of Ghanshyam S/o Chanda Singh Village Kharian in G.P. Bagroli (Under SDRF) Deposit work (SH:- C/o R/wall at RD. 0/0 to 0/013)	93419.00	1900.00	One Month	350/-	Class D&C
27	Construction of Pucca path from sadak to Rashpal House uppli Mohli GP Samlet under MLALAD (Deposit Work)(SH:- Providing and laying interlocking concrete block pavement at RD 0/0 to 0/022.)	95262.00	1900.00	One Month	350/-	Class D&C
28	Construction of Pucca path from Sarai to Jondu Ram house in village Pehadi GP Lohara under (MLALAD) Deposit work (Providing and laying Interlocking concrete Block pavement at RD 0/0 to 0/029)	97264.00	2000.00	One Month	350/-	Class D&C
29	Others Renovation of Sarai at Village Bassi GP Kutwasi Under SDP Deposit Work. (SH:- Providing and laying interlocking paver block)	93494.00	1900.00	One Month	350/-	Class D&C
30	Construction of Pucca Path from Gyan Singh House to Dilwag Singh House village Nanooh Tehsil Fatehpur District Kangra HP Under SDP Deposit work (SH: Providing and laying interlocking paver block at RD 0/0 to 0/026)	97166.00	2000.00	One Month	350/-	Class D&C
31	Construction of Pucca Path from Inder Singh House to Gagan Singh House village Nanooh Tehsil Fatehpur Dist. Kangra HP Under SDP Deposit work (SH:- Providing and laying interlocking paver block at RD 0/0 to 0/026)	97166.00	2000.00	One Month	350/-	Class D&C
32	Construction of Pucca Path from Balvinder Singh House to Pooran Singh House village Larhun Tehsil Fatehpur Distt. Kangra HP Under SDP Deposit Work (SH:- Providing and laying interlocking paver block at RD 0/0 to 0/028)	95920.00	2000.00	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions :-

1. The Contractor/Firm shall have his GST-NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders from will be issued to the contractor/ firms which may be noted.
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- Construction of Mahila Bathroom (Snan Ghar) near Sookha Khoo in village Chandrehar G.P. Thehar (Under SDP) Deposit Work (SH:- Construction of Bathroom).									
Estimated cost:- Rs.98372/- only									
Earnest Money : Rs.2000/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	In words	Rate		Unit	Amount		
				In figures					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five meter) in width or 10 sqm (ten square meter) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (fifty meter) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.33 cubic meter	339.40	Rupees Three Hundred Thirty Nine And Paise Forty Only		Per cubic meter	451.00		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:3:6 (one cement isto three coarse sand isto six graded stone aggregate) 40mm (forty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.58 cubic meter	4710.60	Rupees Four Thousand Seven Hundred Ten And Paise Sixty Only		Per cubic meter	7443.00		
3	15mm (fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement isto six fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	22.88 square meter	185.60	Rupees One Hundred Eighty Five And Paise Sixty Only		Per square meter	4247.00		
(i) Outer side.									
(ii)	6mm (six millimetre) cement plaster of mix 1:3 (one cement isto three fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.88 square meter	190.20	Rupees One Hundred Ninety And Paise Twenty Only		Per square meter	928.00		
4	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to steel windows by welding including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	5.67 Killogra me	120.75	Rupees One Hundred Twenty And Paise Seventy Five Only		Per Killograme	685.00		

5	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimetre) (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetre) thick cement mortar 1:4 (one Cement isto four Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.38 Square meter	1120.40	Rupees One Thousand One Hundred Twenty And Paise Forty Only	Per Square meter	8269.00
6	Providing and fixing 1st quality ceramic wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (twelve millimetre) thick bed of cement Mortar 1:3 (one cement isto three coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	24.99 Square meter	1240.30	Rupees One Thousand Two Hundred Forty And Paise Thirty Only	Per Square meter	30995.00
7	Providing and fixing 0.60mm (zero point sixty millimetre) thick prepainted steel sheet in roofing with hot dipped metalling zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washer complete with all accessories as required as per the direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.04 Square meter	1650.80	Rupees One Thousand Six Hundred Fifty And Paise Eighty Only	Per Square meter	11622.00
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	98.56 Killogra me	125.20	Rupees One Hundred Twenty Five And Paise Twenty Only	Per Killograme	12340.00
9	Finishing walls with water proofing cement paint of required shade New work (two or more coats applied @3.84 kg/10 sqm) (three decimal eight four kilogram/ten square metre) including cost of Priming coat including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	16.42 Square meter	74.55	Rupees Seventy Four And Paise Fifty Five Only	Per Square meter	1224.00

10	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimetre) C.P. brass pillar taps, 32 mm (twenty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a pair of 15 mm (fifteen millimetre) C.P. brass pillar taps including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	2980.40	Rupees Two Thousand Nine Hundred Eighty And Paise Forty Only	Each	2980.00
11	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fitting including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	1960.55	Rupees One Thousand Nine Hundred Sixty And Paise Fifty Five Only	Each	1961.00
12	Providing and fixing unplasticised PVC connection pipe with PTMT Nuts, Collar and bush of approved quality and colour 15mm (fifteen millimetre) nominal bore with 45 cm (forty five centimetre) length including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Number	140.20	Rupees One Hundred Forty And Paise Twenty Only	Each	280.00
13	Providing and fixing PTMT soap dish Holder having length of 138mm (one hundred thirty eight millimetre) breadth 102mm (one hundred two millimetre) height of 75 mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six gramme) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Number	130.50	Rupees One Hundred Thirty And Paise Fifty Only	Each	261.00
14	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450 mm (four hundred fifty millimetre) long towel rail with total length of 495 mm (four hundred ninety five millimetre), 78 mm (seventy eight millimetre) wide and effective height of 88 mm (eighty eight millimetre), weighing not less than 170 gms (one hundred seventy grams) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Number	415.15	Rupees Four Hundred Fifteen And Paise Fifteen Only	Each	830.00
15	Providing and fixing C.P. brass bic cock of approved quality conforming to IS: 8931 15mm (fifteen millimetre) nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.00 Number	418.95	Rupees Four Hundred Eighteen And Paise Ninety Five Only	Each	1257.00

16	Providing and fixing G.I pipes complete with G.I. fittings and clamps including cutting and making good the walls etc. intrenal work exposed on wall 15mm (fifteen millimetre) dia nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	18.00	255.50	Rupees Two Hundred Fifty Five And Paise Fifty Only	Per Running metre	4599.00
17	Providing and fixing water tank 1000 litre including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1000.00	8.00	Rupees Eight Only	Per litre	8000.00
						98372.00
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Mahila Bathroom (Snan Ghar) in village Jhanjhal in G.P. Diyana (Under SDP) Deposit Work (SH:- Construction of Bathroom).							Estimated cost:- Rs.98378/- only	
							Earnest Money : Rs.2000/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five meter) in width or 10 sqm (ten square meter) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (fifty meter) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government	2.30 cubic meter	339.40	Rupees Three Hundred Thirty Nine And Paise Forty Only	Per cubic meter	781.00		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:5:10 (one cement isto five coarse sand isto ten graded stone aggregate) 40mm (forty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.80 cubic meter	3550.60	Rupees Three Thousand Five Hundred Fifty And Paise Sixty Only	Per cubic meter	9942.00		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level upto V level in all shapes and sizes in cement mortar 1:6 (one cement isto six coarse sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.50 cubic meter	6560.20	Rupees Six Thousand Five Hundred Sixty And Paise Twenty Only	Per cubic meter	29521.00		
4	Centering and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.62 square meter	243.65	Rupees Two Hundred Forty Three And Paise Sixty Five Only	Per square meter	1857.00		
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement All work upto plinth level 1:2:4 (one cement isto two sand isto four graded stone aggregate) 20mm (twenty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.19 cubic meter	5650.40	Rupees Five Thousand Six Hundred Fifty And Paise Forty Only	Per cubic meter	6724.00		
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild steel and Medium Tensile steel bars including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	107.43 kilogram	90.00	Rupees Ninety Only	Per kilogram	9669.00		
7	15mm (fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement isto six fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	45.21 square meter	165.00	Rupees One Hundred Sixty Five Only	Per square meter	7460.00		
(ii)	6mm (six millimetre) cement plaster of mix 1:3 (one cement isto three fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.54 square meter	150.00	Rupees One Hundred Fifty Only	Per square meter	1131.00		

8	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimetre) (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetre) thick cement mortar 1:4 (one Cement into four Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.08 Square meter	1120.40	Rupees One Thousand One Hundred Twenty And Paise Forty Only	Per Square meter	4571.00
9	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawlplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge 1217601000 For doors windows and ventilators and glazed partitions frames Per Kg. ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately) Per kg. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	16.72 kilogram me	330.00	Rupees Three Hundred Thirty Only	Per kilogra mme	5518.00
10	Providing and fixing glazing aluminium door, windows, ventilators and partitions PVC/neoprens gasket etc. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.15 Square meter	1210.00	Rupees One Thousand Two Hundred Ten Only	Per Square meter	3812.00
11	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to steel windows by welding including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.56 Killogra me	105.00	Rupees One Hundred Five Only	Per Killogra me	794.00
12	Finishing walls with water proofing cement paint of required shade New work (two or more coats applied @3.84 kg/10 sqm) (three decimal eight four kilogram/ten square metre) including cost of Priming coat including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	55.21 Square meter	61.20	Rupees Sixty One And Paise Twenty Only	Per Square meter	3379.00
13	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimetre) C.P. brass pillar taps, 32 mm (twenty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a pair of 15 mm (fifteen millimetre) C.P. brass pillar taps including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	2980.40	Rupees Two Thousand Nine Hundred Eighty And Paise Forty Only	Each	2980.00

		1.00 Number	1960.55	Rupees One Thousand Nine Hundred Sixty And Paise Fifty Five Only	Each	1961.00
14	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fitting including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number				
15	Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC waste fittings complete Flexible pipe 32mm (thirty two millimetre) dia including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	101.10	Rupees One Hundred One And Paise Ten Only	Each	101.00
16	Providing and fixing PTMT soap dish Holder having length of 138mm (one hundred thirty eight millimetre) breadth 102mm (one hundred two millimetre) height of 75 mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six gramme) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	130.50	Rupees One Hundred Thirty And Paise Fifty Only	Each	131.00
17	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450 mm (four hundred fifty millimetre) long towel rail with total length of 495 mm (four hundred ninety five millimetre), 78 mm (seventy eight millimetre) wide and effective height of 88 mm (eighty eight millimetre), weighing not less than 170 gms (one hundred seventy grams) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Number	315.15	Rupees Three Hundred Fifteen And Paise Fifteen Only	Each	630.00
18	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931 15mm (fifteen millimetre) nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Number	418.95	Rupees Four Hundred Eighteen And Paise Ninety Five Only	Each	838.00
19	Providing and fixing unplasticised PVC connection pipe with PTMT Nuts, Collar and bush of approved quality and colour 15mm (fifteen millimetre) nominal bore with 45 cm (forty five centimetre) length including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	112.45	Rupees One Hundred Twelve And Paise Forty Five Only	Each	112.00
20	Providing and placing on terrace(at all floor levels) polythylene water storage tank, IS:12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	500.00 litre	8.00	Rupees Eight Only	Per litre	4000.00
21	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting and making good the walls etc. intrenal work exposed on wall 15mm (fifteen millimetre) dia nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	12.00 Running metre	205.50	Rupees Two Hundred Five And Paise Fifty Only	Per Running metre	2466.00
					Total:-	98378.00

Amount quoted by the contractor in % Above/Below

SCHEDULE OF QUANTITY

Name of work:- Re-Construction of Retaining wall near the house of Narsingh Temple habitation village Fatehpur G.P. Fatehpur Estimated cost:- Rs.93608/- only
(SH:- Construction of P.C.C. Retaining wall (1st step) at R.D. 0/0 to 0/015.60) Under SDRF Deposit Work. Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	21.60 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	7333.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.30 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	86275.00
					Total:-	93608.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house of Vijay Kumar in village Reeng in G.P. Thehar (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/009).

Estimated cost:- Rs.94353/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In -meter. Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.97 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4064.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.89 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	88369.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1920.00
					Total:-	94353.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from Mela Ram Machine to Dhiman Basti village Mudda GP Thahar Under SDP Deposit work Estimated cost:- Rs.95427/- only
(SH):- Providing and laying cement concrete pavement at R.D. 0/0 to 0/038) Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heighis/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.10 Cubic meter.	5580.50	Rupees Five Thousand Five Hundred Eighty meter And Paise Fifty Only	Per cubic meter	95427.00
Amount quoted by the contractor in % Above/Below						Total:- 95427.00

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from Prithi House to Malkiat Singh house village Bankehar GP Kutwasi Under SDP Deposit work (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/034)

Estimated cost:- Rs.71153/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.75 Cubic meter.	5580.60	Rupees Five Thousand Five Hundred Eighty And Paise Sixty Only	Per cubic meter	71153.00
Amount quoted by the contractor in % Above/Below						Total:- 71153.00


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from Pratap Singh house to Joginder Singh house village Bankhar in GP Kutwasi Under SDP Estimated cost:- Rs.70383/- only
 Deposit work (SH):- Construction of Edge wall with cement concrete pavement at R.D. 0/0 to 0/023 Earnest Money : Rs.1500/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.18 Cubic meter.	339.45	Rupees Three Hundred Thirty Nine And Paise Forty Five Only	Per cubic meter	1758.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	5.18 Cubic meter.	3950.60	Rupees Three Thousand Nine Hundred Fifty And Paise Sixty Only	Per cubic meter	20464.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.63 Cubic meter.	5580.60	Rupees Five Thousand Five Hundred Eighty And Paise Sixty Only	Per cubic meter	48161.00
					Total:-	70383.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path near the house of Ramesh Singh village Bari GP Hatli Under SDRF Deposit
Work (SH):- Construction of Retaining wall at R.D.0/0 to 0/009.50)

Estimated cost:- Rs.94673/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.97 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4064.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.89 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	88369.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	94673.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Dist. Kanpur (U.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of MTN road Sohar to Gurial road km.0/0 to 2/0 (SH:- Construction of U-shape drain at R.D.1/315 Estimated cost:- Rs.83810/- only to 1/345). Earnest Money : Rs.1700/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	29.00 Cubic meter.	350.90	Rupees Three Hundred Fifty And Paise Ninety Only	Per cubic meter	10176.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	15.50 cubic meter	4430.50	Rupees Four Thousand Four Hundred Thirty And Paise Fifty Only	Per cubic meter	68673.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.00 Numbers	310.05	Rupees Three Hundred Ten And Paise Five Only	Each	4961.00
					Total:-	83810.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur (Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of culvert on Hatli Maukhar road at village Loh near Chakki and Ravinder Kumar house G.P. Bagroli Under (MLALAD) Deposit Work (SH:- Construction of slab on exiting U-shape drain)				Estimated cost:- Rs.96345/- only		
				Earnest Money : Rs.1900/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	5.85 Cubic meter.	5281.20	Rupees Five Thousand Two Hundred Eighty One And Paise Twenty Only	Per cubic meter	30895.00
2	Supplying, fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002, 1010 &1202 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any floor level as per the direction of the Engineer-in-charge including carriage of materials. The rate is including octroi, royalty, Malkana, toll tax, Sale tax, GST or any other taxes imposed by the Government.	0.70 metric tonne	93500.00	Rupees Ninety Three Thousand Five Hundred Only	Per metric tonne	65450.00
						96345.00
Total Rs.:-						
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near house of Rakesh Kumari in village Sanaurth in G.P. Bagroli
(Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/009.50)

Estimated cost:- Rs.94673/- only
Earnest Money : Rs.1900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.97 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4064.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.89 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	88369.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	94673.00
	Amount quoted by the contractor in % Above/Below					


Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house Gurubachan Singh in village Badnad in G.P. Bagroli (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/010).

Estimated cost:- Rs.70517/- only
Earnest Money : Rs.1400/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.27 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2808.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.44 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65469.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	70517.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house of Gokhi Ram in village Bassi G.P. Kutwasi (Under SDRF)
Deposit work (SH):- Construction of Retaining wall at R.D. 0/00 to 0/007).

Estimated cost:- Rs.69708/- only
Earnest Money : Rs.1400/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.82 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2994.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.34 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65114.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1600.00
					Total:-	69708.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (P.D.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Edge wall near the house of Sudarshan to Ridku Ram Ke Ghar Tak in village Bassi G.P.
Kutwasi (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/010).

Estimated cost:- Rs.70517/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including cartiage of materials within all leads and lifts and other incidental .	8.27 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2808.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including cartiage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.44 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65469.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square, weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including cartiage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	70517.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall behind house of Balwinder Kaur W/O Rajinder Singh village Kutt in G.P. Kutwasi (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/007).

Estimated cost:- Rs.69708/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.82 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2994.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D. technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.34 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65114.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1600.00
					Total:-	69708.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house of Guruchan Singh in village Khudial in G.P. Kutwasi (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/010).

Estimated cost:- Rs.70515/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.27 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2806.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.44 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65469.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	70515.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur (Distt. Kangra (H.P.))

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near Mahila Mandal Bhawan village Kutt in G.P. Kutwasi (Under SDRF)
Deposit work (SH):- Construction of Retaining wall at R.D. 0/00 to 0/007).

Estimated cost:- Rs.69708/- only

Earnest Money : Rs.1400/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.82 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2994.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.34 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65114.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1600.00
					Total:-	69708.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Patnagar Division HPPWD
Patnagar Dist. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house of Kushla Devi in village Khudial in G.P. Kutwasi (Under SDRE) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/007).

Estimated cost:- Rs.70517/- only
Earnest Money : Rs.1400/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.27 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2808.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.44 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	65469.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	70517.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Patanjali Division HPPWD
 Patanjali Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Magar Singh house to Kulveer house in village Bdanad GP Bagroli Under
SDP Deposit Work (SH):- Construction of Retaining wall at R.D.0/0 to 0/010 and providing and laying cement concrete
pavement at RD 0/0 to 0/024)

Estimated cost:- Rs.69523/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	2.30 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	781.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.50 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	19527.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1600.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00 Cubic meter.	5290.60	Rupees Five Thousand Two Hundred Ninety And Paise Sixty Only	Per cubic meter	47615.00
					Total:-	69523.00

Amount quoted by the contractor in % Above/Below

SCHEDULE OF QUANTITY

Name of work:- Re-Construction of Retaining wall near the house of Madan Lal R/O village Badnad Hourri Devi in G.P. Bagroli (Under SDRF) Deposit Work (SH:- Construction of Retaining wall at R.D.0/0 to 0/010)

Estimated cost:- Rs.94353/- only
Earnest Money : Rs.1900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.97 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4064.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.89 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	88369.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1920.00
Amount quoted by the contractor in % Above/Below						Total:- 94353.00

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt Kanpur (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca path from Harbans Singh house to Rajesh house village Bamboti GP Lohara Under MLALAD (Deposit work) (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/050)						
Estimated cost:- Rs.99645/- only						
Earnest Money : Rs.2000/- only						
Time limit:- One month						
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying granular sub-base/surface with well graded material, spreading in uniform layers with motor grader on prepared surfaces mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density, complete as per technical specification clause-401.4 for using naturally occurring gravel as per the entire satisfaction and direction of Engineer-in-charge. The rate including octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.50 Cubic meter.	850.20	Rupees Eight Hundred Fifty And Paise Twenty Only	Per cubic meter	6377.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.90 Cubic meter.	5210.50	Rupees Five Thousand Two Hundred Ten And Paise Fifty Only	Per cubic meter	93268.00
	Total Rs.:-					99645.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Re-Construction of Retaining wall near the house of Surinder Singh in Ward No.-05 G.P. Nangal Under SDRF
Deposit Work (SH:- Construction of Retaining wall at R.D.0/0 to 0/009.50)

Estimated cost:- Rs.94673/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.97 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4064.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.89 cubic meter	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	88369.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2240.00
					Total:-	94673.00
	Amount quoted by the contractor in % Above/Below					

 Engineer
 District Engineer
 Division: HPPWD
 District: Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca path from Ram Rakha house to the house of Late Sh. Amarnath village Rudi G.P. Diyana Under (MLALAD) Deposit Work (SH:- Construction of Retaining wall at R.D.0/0 to 0/022)

Estimated cost:- Rs.97803/- only

Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.12 Cubic meter.	310.50	Rupees Three Hundred Ten And Paise Fifty Only	Per cubic meter	3142.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.20 cubic meter	3501.10	Rupees Three Thousand Five Hundred One And Paise Ten Only	Per cubic meter	84727.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	3840.00
4	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	4.62 Cubic meter.	750.20	Rupees Seven Hundred Fifty And Paise Twenty Only	Per cubic meter	3466.00
5	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet the requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per the entire satisfaction and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax,GST or any other taxes imposed by the Government.	26.73 Cubic meter.	98.30	Rupees Ninety Eight And Paise Thirty Only	Per cubic meter	2628.00
Total Rs:-						97803.00
Amount quoted by the contractor in % Above/Below						

Ex-Officio Engineer
Patancheru Division HPDWD

SCHEDULE OF QUANTITY

Name of work:- Construction of of Pucca Path near the house of Paras Ram, Pawan Kumar village Kut GP Kutwasi Under SDP Deposit Work (SH:- Construction of Retaining wall at R.D.0/0 to 0/009.30)

Estimated cost:- Rs.68325/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	6.88 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2336.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	17.11 cubic meter	3750.10	Rupees Three Thousand Seven Hundred Fifty And Paise Ten Only	Per cubic meter	64164.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614, 709, 1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.00 Numbers	304.10	Rupees Three Hundred Four And Paise Ten Only	Each	1825.00
					Total:-	68325.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD

Name of work:-Re-Construction of Retaining wall near the land of Chaman Lal village Khairan in G.P. Bagroli
(Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/013).

SCHEDULE OF QUANTITY

Estimated cost:- Rs.93419/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.14 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3443.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	22.62 cubic meter	3850.40	Rupees Three Thousand Eight Hundred Fifty And Paise Forty Only	Per cubic meter	87096.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2880.00
					Total:-	93419.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-Construction of Retaining wall near the house Ghanshyam S/O Chanda Singh village Khairian in G.P. Bagroli (Under SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/013).

Estimated cost:- Rs.93419/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.14 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3443.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	22.62 cubic meter	3850.40	Rupees Three Thousand Eight Hundred Fifty And Paise Forty Only	Per cubic meter	87096.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204 3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	2880.00
					Total:-	93419.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Farangpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Sadak to Rachhpal house Upli Mohli GP Samlet Under (MLALAD) Deposit Work (SH:- Providing and laying Interlocking concrete Block pavement at R.D. 0/0 to 0/022.)

Estimated cost:- Rs.95262/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	3.30 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	1120.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	5.50 Cubic meter.	3980.50	Rupees Three Thousand Nine Hundred Eighty And Paise Fifty Only	Per cubic meter	21893.00
3	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	55.00 Square meter	995.00	Rupees Nine Hundred Ninety Five Only	Per Square meter.	54725.00
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.30 Cubic meter.	5310.20	Rupees Five Thousand Three Hundred Ten And Paise Twenty Only	Per cubic meter	17524.00
					Total:-	95262.00

Amount quoted by the contractor in % Above/Below


 Engineer
 Fatenpu Division HPPWD
 Fatenpu, Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Sarai to Jundu Ram house in village Pehadi GP Lohara Under (MLALAD) Deposit Work Estimated cost:- Rs.97264/- only
(SH:- Providing and laying Interlocking concrete Block pavement at R.D. 0/0 to 0/029.) Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	13.50 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	4583.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8.(One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	6.75 Cubic meter.	3980.50	Rupees Three Thousand Nine Hundred Eighty And Paise Fifty Only	Per cubic meter	26868.00
3	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	67.50 Square meter	975.00	Rupees Nine Hundred Seventy Five Only	Per Square meter.	65813.00
					Total:-	97264.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Others Renovation of Sarai at village Bassi G.P. Kutwasi Under SDP Deposit work (SH:- Providing and laying interlocking paver block)

Estimated cost:- Rs.93494/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	6.38 Cubic meter.	3850.60	Rupees Three Thousand Eight Hundred Fifty And Paise Sixty Only	Per cubic meter	24567.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	85.00 Square meter	810.90	Rupees Eight Hundred Ten And Paise Ninety Only	Per Square meter.	68927.00
					Total:-	93494.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehrad Division HPPWD
Fatehgarh Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Gyan Singh House to Dilwag Singh House village Nanooh Tehsil Fatehpur District Kangra (HP) Under SDP Deposit work (SH):- Providing and laying interlocking paver block at R.D. 0/00 to 0/026)

Estimated cost:- Rs.97166/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.80 Cubic meter.	3950.10	Rupees Three Thousand Nine Hundred Fifty And Paise Ten Only	Per cubic meter	30811.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	78.00 Square meter	850.70	Rupees Eight Hundred Fifty And Paise Seventy Only	Per Square meter.	66355.00
					Total:-	97166.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Inder Singh House to Gagan Singh House village Nanooch Tehsil Fatehpur District Kangra Estimated cost:- Rs.97166/- only
(HP) Under SDP Deposit work (SH):- Providing and laying interlocking paver block at R.D. 0/00 to 0/026) Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.80 Cubic meter.	3950.10	Rupees Three Thousand Nine Hundred Fifty And Paise Ten Only	Per cubic meter	30811.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	78.00 Square meter	850.70	Rupees Eight Hundred Fifty And Paise Seventy Only	Per Square meter.	66355.00
					Total:-	97166.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from Balvinder Singh House to Pooran Singh House village Larhun Tehsil Fatehpur District Kangra(HP) Under SDP Deposit work (SH:- Providing and laying interlocking paver block at R.D. 0/00 to 0/28)

Estimated cost:- Rs.95920/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	7.70 Cubic meter.	3950.10	Rupees Three Thousand Nine Hundred Fifty And Paise Ten Only	Per cubic meter	30416.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	77.00 Square meter	850.70	Rupees Eight Hundred Fifty And Paise Seventy Only	Per Square meter.	65504.00
					Total:-	95920.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)