Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 17235-284 Dated/ 15-1-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pardesh Shimla -2.

Subject:- **Publication of Tender Notice.**

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of HP letter No. PBW(B) A 9(3) 1/2020 dated Shimla -26th July 2021

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 23.01.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 22.01.2025 up to 4.00 P.M and the application for issue of tender form shall be received 21.01.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Improvement & Widening of Dharamshala Yol Dadh Palampur via Nagri road Km 0/00 to 33/00 (SH:- C/o R/Wall at RD 22/120 to 22/130 (MNP)	Rs. 97,496.00	Rs. 2,000.00	Two Months
2	C/o GPS Ram Rachhan to Foot Bridge road on Neugal Khad in GP Kusmal Bhagotla road Km 0/00 to 0/500 (SH:- C/o U-Shape drain at RD 0/00 to 0/047 & Grating (MNP)	Rs. 93,494.00	Rs. 1,900.00	Two Months
3	Restoration of rain damages repair of road from Dharamshala Dadh Palampur Holta Chadiyar Sandhole road Km 15/00 to 27/00 (SH:- C/o U-Shape drain at RD 21/170 to 21/220 (DC Deposit)	Rs. 98,620.00	Rs. 2,000.00	Two Months
4	Restoration of rain damages repair of road from Dharamshala Dadh Palampur Holta Chadiyar Sandhole road Km 15/00 to 27/00 (SH:- C/o U-Shape drain at RD 21/00 to 21/150 (DC Deposit)	Rs. 98,620.00	Rs. 2,000.00	Two Months
5	Restoration of rain damages repair of road from Dharamshala Dadh Palampur Holta Chadiyar Sandhole road Km 15/00 to 27/00 (SH:- C/o U-Shape drain at RD 19/400 to 19/430 & Grating (DC Deposit)	Rs. 94,714.00	Rs. 1,900.00	Two Months
6	C/o Jia to Chamotu road Km 0/00 to 3/00 (SW:- C/o R/Wall in crate wall at RD 2/610 to 2/615 (MNP)	Rs. 93,617.00	Rs. 1,900.00	Two Months
7	C/o Jia to Chamotu road Km 0/00 to 3/00 (SW:- C/o R/Wall in crate wall at RD 2/620 to 2/625 (MNP)	Rs. 93,617.00	Rs. 1,900.00	Two Months
8	C/o link road from Badsar to Ardi road Km 0/00 to 4/00 (SW:- Improvement of road between Km 3/500 to 4/00)	Rs. 96,075.00	Rs 2,000.00	Two Months
9	C/o link road from Badsar to Ardi road Km 0/00 to 4/00 (SW:- Improvement of road between Km 3/00 to 3/380)	Rs. 99,050.00	Rs. 2,000.00	Two Months
10	Restoration of Rain damages on link road from Badsar to Ardi road Km 0/00 to 4/00 (SW:- C/o Un-lined drain at RD 2/400 to 4/000)	Rs. 99,200.00	Rs. 2,000.00	Two Months
11	C/o Dharaman Rajehar to GwalTikkar road Km 0/00 to 8/300 (SW:- Providing and fixing Crash Barrier at various RD's between Km 3/510 to 3/545 (Black Spot Demand No. 10)	Rs. 99,865.00	Rs. 2,000.00	Two Months
12	C/o Dharaman Rajehar to GwalTikkar road Km 0/00 to 8/300 (SW:- Providing and fixing Crash Barrier at various RD's between Km 3/550 to 3/600 (Black Spot Demand No. 10)	Rs. 99,865.00	Rs. 2,000.00	Two Months

	No.32)			
14	C/o link road from GPS Lambapatt on Gopalpur Drati road to Join Garh Mata Km 0/00 to 9/00 (SH:- C/o B/Wall on RD 4/120 to 4/127 (MNP)	Rs. 99,995.00	Rs. 2,000.00	Two Months
15	C/o link road from GPS Lambapatt on Gopalpur Drati road to Join Garh Mata Km 0/00 to 9/00 (SH:- C/o B/Wall on RD 4/135 to 4/142 (MNP)	Rs. 99,995.00	Rs. 2,000.00	Two Months
16	C/o link road from Jia to Village Fotta Ward No. 4 Km 0/00 to 2/500 (SW:- C/o Wire crate at RD 0/700 to 0/705(MNP)	Rs. 95,017.00	Rs. 2,000.00	Two Months
17	C/o link road from GPS Lambapatt on Gopalpur Drati road to join Garh Mata Km 0/00 to 9/00 (SW:- C/o B/Wall on RD 0/120 to 0/127 (MNP)	Rs. 99,939.00	Rs. 2,000.00	Two Months
18	C/o Bramtheru to Gopalpur road (Portion Dharot to Harizan Basti in GP Lahla (Lahla section) (SH:- F/C at RD 0/965 to 0/980) (OFC Deposit)	Rs. 99,002.00	Rs.2,000.00	Two Months
19	C/o Parour Lahla Darati Gopalpur Rakh Ghamrota Sukeri Bandla road KM 0/00 to 33/00 (SH:- P/L Interlocking Tiles at RD 20/505 to 20/520 (MDR)	Rs. 99,028.00	Rs. 2000.00	Two Months
20	Restoration of rain damages on Bagora Bhagotla road Km 0/00 to 2/00 (SW:- Balance work of existing 10.00 mtrs Bridge at RD 1/405 LHS)	Rs. 67,640.00	Rs. 1400.00	Two Months
21	C/o link road from Janj Ghar in Village Khalet Chowki to Maranda Km 0/00 to 3/00 (SW:- P/L Interlocking Tiles at RD 2/400 to 2/425) (MNP)	Rs. 99,966.00	Rs. 2,000.00	Two Months
22	C/o Somkunj Circuit House at Palamapur Distt. Kangra (SW:- Providing Glass, Jug, Bowl Melamine etc)	Rs. 89,081.00	Rs. 1,800.00	Two Months
23	C/o Somkunj Circuit House at Palamapur Distt. Kangra (SW:- Providing and fixing Premium Quality Fabric Curtain and Liners in Drawing Room)	Rs. 99,978.00	Rs. 2,000.00	Three Months
24	C/o Somkunj Circuit House at Palamapur Distt. Kangra (SW:- Providing and fixing Premium Quality Fabric Curtain and Liners in VIP (GF) Set.	Rs. 99,826.00	Rs. 2,000.00	Three Months
25	C/o Somkunj Circuit House at Palamapur Distt. Kangra (SW:- Providing and fixing Premium Quality Fabric Curtain and Liners in Dormatory Set No. 1)	Rs. 99,673.00	Rs. 2,000.00	Three Months
26	C/o Somkunj Circuit House at Palamapur Distt. Kangra (SW:- Providing and fixing Premium Quality Fabric Curtain and Liners in VIP (FF) Set.	Rs. 99,623.00	Rs. 2,000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1 G.S.T. No.

2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division

(1)

SCHEDULE OF QUANTITY

Name of work:- Imp. & Widening of Dharamshala Yol Dadh Palampur Via Nagri road Km 0/0 to 33/00. (SH:- C/o R/wall at Rd 22/120 to 22/130). **MNP**	Estimated cost Rs.	97496.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm(one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	7.20			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia U.P.V.C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	10.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o GPS Ram Rachhan to Foot Bridge road on Neugal Khad in G.P. Kusmal Bhagotla Km 0/00 to 0/500. (SH:- C/o U-Shape drain at Rd 0/00 to 0/047 & Grating). **MNP**

				Estimated cost Rs.		93494.00
				Earnest Money Rs.		1900.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm(one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	20.58			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M 1on) nominal mix 1:3:6 (one cement Three sand Six graded crushed /broken stone aggregate 20 mm (twenty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, toyality, Malkana, toll tax or other taxes imposed by the government	12.18			Per cubic metre	
3	Steel work welded in built up sections Trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works The rate is including octroi, toyality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	320.91			Per Kilogram	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

(3)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages repair of road from Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 15/00 to 27/00. (SH:- C/o U-Shape drain at Rd 21/170 to 21/220). **(D.C. Deposit)**	Estimated cost Rs.	98620.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including clearing of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	16.50			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 tone cement Three sand Six graded crushed /broken stone aggregate 20 mm (twenty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals The rate including of octroi, royality, Malkana, toll tax, or other taxes imposed by the government	20.00			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

(4)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages repair of road from Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 15/00 to 27/00. (SH:- C/o U-Shape drain at Rd 21/100 to 21/150). **(D.C. Deposit)**	Estimated cost Rs.	98620.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift, including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	16.50			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed broken stone aggregate 20 mm (twenty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royality, Malkana, toll tax, or other taxes imposed by the government	20.00			Per cubic metre	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages repair of road from Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 15/00 to 27/00. (SH:- C/o U-Shape drain at Rd 19/400 to 19/430 & Grating). (D.C. Deposit)

Estimated cost Rs.	94714.00
Earnest Money Rs.	1900.00
Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	12.60			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, toll tax, or other taxes imposed by the government.	7.88			Per cubic metre	
3	Steel work welded in built up sections Trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required. In gratings frames, guard bar, ladder, railings, brackets, gates and similar works. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	570.00			Per Kilogram	
	Total					

Executive Engineer
Palampur Division
HP.PWD Palampur

(6)

SCHEDULE OF QUANTITY

Name of work:- C/o Jia to Chamotu road Km 0/00 to 3/00. (C/o R/wall in crate wall at Rd 2/610 to 2/615). **MNP**

Estimated cost Rs.	93617.00
Earnest Money Rs.	1900.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift, including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm(one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.00			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental The rate includes octroi, royalty,Malkana,Tol tax GST or any other taxes imposed by the Government.	31.26			Per cubic metre	
				Total		

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jia to Chamotu road Km 0/00 to 3/00. (C/o R/wall in crate wall at Rd 2/620 to 2/625). **MNP**

Estimated cost Rs.	93617.00
Earnest Money Rs.	1900.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.00			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In- Charge including carriage of materials within all leads and lifts and other incidental.The rate includes octroi, royality,Malkana, Tol tax, GST or any other taxes imposed by the Government	31.26			Per cubic metre	
				Total		

Executive Engineer,
Palampur Division
HP.PWD Palampur

8

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Badsar to Ardi road Km 0/00 to 4/00. (SH:- Imp. of road between Km 3/500 to 4/00).	Estimated cost Rs.	96075.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling line dressing and hauling /carriage of machineries, materials, tools equipments and safety measures all useful material such as stone single aggregate and slates etcetera shall be shorted out and stacked in proper stack. Recovery for useful stone of 27.45 cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) only per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	274.50			Per cubic metre	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

9

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Badsar to Ardi road Km 0/00 to 4/00. (SH:- Imp. of road between Km 3/000 to 3/380).	Estimated cost Rs.	99050.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures all useful material such as stone single aggregate and slates etectera shall be shorted out and stacked in proper stack. Recovery for useful stone of 28.30 cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) only per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	283.00			Per cubic metre	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road from Badsar to Ardi road Km 0/00 to 4/00. (SH:- C/o Unlined drain at Rd 2/400 to 4/000).	Estimated cost Rs.	99200.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	1600.00			Per Running metre	
	Total					

Executive Engineer
Palampur Division
HP.PWD Palampur

(11)

SCHEDULE OF QUANTITY

Name of work:- C/o Dhraman Rajehar to Gawaltikkar road Km 0/00 to 8/300. (SH.:- P/F crash barrier at various RD's between Km 3/510 to 3/545). **Black Spot Demand No.10**

Estimated cost Rs.	99865.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including clearing of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement , Two Sand four crushed stone aggregate) Nominal Mix, P.C.C grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	1.19			Per cubic metre.	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post: 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm. (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long-complete as per clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.30			Per running metre	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Dhraman Rajehar to Gawaltikkar road Km 0/00 to 8/300. (SH:- P/F crash barrier at various RD's between Km 3/550 to 3/600). **Black Spot Demand No.10**	Estimated cost Rs.	99865.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials, upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana toll tax, GST or other taxes imposed by the Government time to time	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royality, Malkana toll tax, GST or other taxes imposed by the Government time to time	1.19			Per cubic metre	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long complete as per clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	23.30			Per running metre	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Patti Bodhal Pahra road Km 0/00 to 5/000. (S.H.:- P/T crash barrier at various RD's between Km 3/400 to 3/700). **Black Spot Demand No.32**

Estimated cost Rs.	99865.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause. 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royality, Malkana toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long complete as per clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana toll tax, GST or other taxes imposed by the Government.	23.30			Per running metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GPS Lambapatt on Gopalpur Darati road to join Garh Mata Km 0/0 to 9/00. (Sh:- C/o B/wall on Rd 4/120 to 4/127). **MNP**

Estimated cost Rs.	99995.00
Earnest Money Rs.	2000.00
Time Limits	TwoMonths

Sr No	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3 as per specifications, approved drawing , design as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.60			Per Cubic Metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift, including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	6.30			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	22.05			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	8.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GPS Lambapatt on Gopalpur Darati road to join Garh Mata Km 0/0 to 9/00. (Sh:- C/o B/wall on Rd 4/135 to 4/142). **MNP**

Estimated cost Rs.	99995.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3 as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	12.60			Per Cubic Metre	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.30			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera complete as per the direction of Engineer-in-Charge as per the drawing and hauling /carriage of labour equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government	22.05			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	8.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

16

SCHEDULE OF QUANTITY

Name of work:- C/o link road from Jia to village Fotta ward No. 4 Km 0/00 to 2/500. (SH:- C/o Wire Crate on Rd 0/700 to 0/705). MNP	Estimated cost Rs.	95017.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.00			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental. The rate includes octroi, royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	31.26			Per cubic metre	

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GPS Lambapatt on Gopalpur Darati road to join Garh Mata Km 0/0 to 9/00. (Sh:- C/o B/wall on Rd 0/120 to 0/127). MNP

Estimated cost Rs.	99939.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	6.30			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of 10rm work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government	22.05			Per cubic metre	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	12.00			Each	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

ork :- C/o Bramtheru to Gopalpur Road (Portion Dharot to Harizan Basti in G.P. Lahla (Lahla Section). (SH:- F/C at Rd 0/965 to 0/980). **(OFC**	Estimated cost Rs.	99002.0
	Earnest Money Rs.	2000.00
	Time Limits	Two Mo

Description of Item	Quantity	Rate		Unit	Amo
		In Figures	In Word		
avation for roadway in hard rock (requiring blasting) by drilling, blasting and breaking, trimming of bottom and side slopes in accordance with irements of lines, grades and cross-sections, loading and disposal of cut rock with a lift upto 1.5 m and leads upto 1000 m as per Technical cification Clause 302.3.5. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	309.38			Per cubic metre	
al					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Parour Lahla Darati Gopalpur Rakh Ghamrota Sukeri Kandi Bandla road Km 0/00 to 33/00. (SH:- P/L Interlocking Tiles at Rd 20/505 to 20/520). **MDR**

					Estimated cost Rs.	99028.00
					Earnest Money Rs.	2000.00
					Time Limits	Two Months
Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying Cement concrete 1:4:8 (One Cement Four Sand Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads lifts and other incidental including the cost of form work in Retaining Wall, Breast Wall etcetera complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government	4.22			Per cubic metre	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government	56.25			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement Two Sand four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.45			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Bagora Bhagotla road Km 0/00 to 2/00. (SH:- Balance work of existing 10.00 mtr. Bridge at Rd 1/405 LHS).

				Estimated cost Rs.		67640.00
				Earnest Money Rs.		1400.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer incharge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.42			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M. Len) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royality, Malkana, toll tax, or other taxes imposed by the government.	14.28			Per cubic metre	
	Total					

Executive Engineer,
Palampur Division,
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Janj Ghar in village Khalet Chowki to Maranda Km 0/00 to 3/00. (SH:- P/L interlocking tiles at Rd 2/400 to 2/425). **MNP**	Estimated cost Rs.	99966.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 using cement ,Three sand ,Six graded crushed /broken stone aggregate 40 mm (Forty Milimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royality, Malkana toll tax, or other taxes imposed by the government	1.50			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government	67.50			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement ,Two Sand ,four crushed stone aggregate) Nominal Mix, P.C.C grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time	1.07			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

Schedule of quantity

Name of Work :- C/O Somkunj Circuit House at Palampur Distt. Kangra (HP)
Sub Work :- Providing and Supplying Glass Jug, Bowl Melamine etc.

Estimated Cost : Rupees 89,081/-
Earnest Money : Rupees 1800/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and Supplying Glass Jug of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	4.00	Nos.			Each	
2	Providing and Supplying Glass Jug of normal quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	6.00	Nos.			Each	
3	Providing and Supplying Fry Pan of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.00	Nos.			Each	
4	Providing and Supplying Soup Plate of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	2.00	Nos.			Each	
5	Providing and Supplying Chimta of Superior quality steel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	2.00	Nos.			Each	
6	Providing and Supplying Spoon of Superior quality steel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	9.00	Set			Per Set	
7	Providing and Supplying Spoon of Normal quality steel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	4.00	Set			Per Set	
8	Providing and Supplying Lemon Set of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.00	Set			Per Set	
9	Providing and Supplying Ladle of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	5.00	Nos.			Each	
10	Providing and Supplying Parantha Palta of Superior quality steel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	2.00	Nos.			Each	
11	Providing and Supplying Jhara of Superior qualitysteel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.00	Nos.			Each	
12	Providing and Supplying Jhara of normal quality steel with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	1.00	Nos.			Each	

13	Providing and Supplying Bowl Melamine of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	8.00	Nos.			Each	
14	Providing and Supplying Tray of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	7.00	Nos.			Each	
15	Providing and Supplying Tray of normal quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	3.00	Nos.			Each	
16	Providing and Supplying Knife of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	7.00	Nos.			Each	
17	Providing and Supplying Medium Size Tray of Superior quality with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	3.00	Nos.			Each	
18	Providing and Supplying Curved Sofa Type Chair made of Polished teak wood with in all leads, lifts and other incidental .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	2.00	Nos.			Each	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Somkunj Circuit House at Palampur Distt. Kangra
Sub Work :- Providing and fixing Premium Quality Fabric Curtain and Liners in Drawing Room

Estimated Cost : Rupees 99,978/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and fixing Curtains in Circuit House Palampur width of cloth 147 cm. made of premim fabric with all fitings leads, lift and as per the Direction of Engineer_in-Charge. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	98.500	Running Metre			Per Running Metre	
2	Providing and fixing Curtains Lining of lining Cloth for curtains with in all leads, lifts and other incidental as per the Direction of Engineer-in-Charge. The rate includes octroi, royality ,Malkana, Tol tax, GST or any other taxes imposed by the Government.	98.500	Running Metre			Per Running Metre	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Somkunj Circuit House at Palampur Distt. Kangra
Sub Work :- Providing and fixing Premium Quality Fabric Curtains and Liners in Dormatory Set No.1

Estimated Cost : Rupees 99,673/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and fixing Curtains in Circuit House Palampur width of cloth 147 cm. made of premim fabric with all fitings leads, lift and as per the Direction of Engineer_in-Charge. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	98.20	Running Metre			Per Running Metre	
2	Providing and fixing Curtains Lining of lining Cloth for curtains with in all leads, lifts and other incidental as per the Direction of Engineer-in-Charge. The rate includes octroi, royality ,Malkana, Tol tax, GST or any other taxes imposed by the Government.	98.20	Running Metre			Per Running Metre	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Somkunj Circuit House at Palampur Distt. Kangra
Sub Work :- Providing and fixing Premium Quality Fabric Curtains and Liners in VIP (FF) set

Estimated Cost : Rupees 99,623/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and fixing Curtains in Circuit House Palampur width of cloth 147 cm. made of premim fabric with all fitings leads, lift and as per the Direction of Engineer_in-Charge. The rate includes octroi, royality, Malkana,Tol tax, GST or any other taxes imposed by the Government.	98.150	Running Metre			Per Running Metre	
2	Providing and fixing Curtains Lining of lining Cloth for curtains with in all leads, lifts and other incidental as per the Direction of Engineer-in-Charge. The rate includes octroi, royality ,Malkana, Tol tax, GST or any other taxes imposed by the Government.	98.150	Running Metre			Per Running Metre	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur