HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Telephone No: 01782-233017
e-mail: ee-ram-hp@nic.in

No. PW/ RMP/TA-I/Publication/2024- 13314 Dated:- 30-01-2025

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of tender Notice.

Enclosed please find herewith the tender Notice of various works as given in the tender inviting tender for uploading on department website as per notification Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(#)1/2024 dated 03.01.2024 as the works mentioned in the tender Notice are urgent nature and public interest.

DA: - As above.

Shakti Negi
Executive Engineer,
B&R Division HPPWD,
Rampur.

Telephone No: 01782-233017
e-mail: ee-ram-hp@nic.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed item rate tender(s) on PWD form No. 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD, Rampur Distt. Shimla (HP) on behalf of the Governor of H.P. for the following works from registered contractors in HP.PWD (B&R) in appropriate class so as to reach in this office on **07.02.2025.** upto 10:30 A.M. and will be opened on the same day at 11:00 A.M. in the presence of contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **06.02.2025** between 10:00 A.M. to 2:00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **06.02.2025** between 02:00 PM to 5:00 PM.

The earnest money in the shape of National Saving Certificate/Time Deposit Account/ Saving Account of the Post office in Himachal Pradesh duly pledged in favour of the Executive Engineer, B&R Division, HP. PWD, Rampur Bushahr Distt. Shimla H.P. must accompany with the tender form. Ambiguous/Telegraphically/conditional tenders or tender by FAX shall not be entertained/considered in any case. The tenders without earnest money shall summarily be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer, B&R Division, HP.PWD, Rampur Bushahr reserve the right to reject/accept any offer of tender without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of tender form	Time limit
1	R/R damages on link road to village Runpoo Km. 0/000 to 6/400 (SH:- C/O R/wall in wire crate at RD 6/162 to 6/171.60)	99,000/-	2,000/-	350/-	One month
2	R/R damages on link road to village Runpoo Km. 0/000 to 6/400 (SH:- C/O R/wall in wire crate at RD 6/150 to 6/159.60)	99,224/-	2,000/-	350/-	One month
3	Repair and maintenance of Bridges on Gharat Sarahan road Km. 0/000 to 5/000 (SH:- Painting and welding of deck plate, other parts and concreting on bed level to protect abutments of Sarahan bridge at Km. 4/510)	95,925/-	2,000/-	350/-	One month
4	Repair and maintenance of Bridges on RGMS road Km. 0/000 to 61/000 (SH:- Painting and welding of deck plate, other parts and concreting on bed level to protect abutments of Sarahan bridge at Km. 49/045)	98,218/-	2,000/-	350/-	One month
5	C/O Mahatma Gandhi Govt. Engg. College Kotla (Jeori) in Tehsil Rampur Distt. Shimla (SH:- Brick work, painting and steel work for installation of lifts at mechanical and lecture theatre block)	99,307/-	2,000/-	350/-	One month

Terms and conditions:-

1. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which the tender is liable to be rejected.

2. The contractor will produce show their enlistment/renewal documents at the time of obtaining tender form.
3. Latest Income tax and sale tax clearance certificates as well as Pan Number and GST number must be attached with the application failing which tender documents will not be issued.
4. The tender forms will be issued to only those contractors who have not more than two works in hand in any of HP.PWD. Circles.
5. The contractor will have to submit the proof. of registration under Employees Providing Funds & Miscellaneous provision Act. 1952 at the time of tender. Failure to observe this condition shall render the tender of the contractor liable to summary rejection.

Executive Engineer,
Rampur Division (B&R),
HPPWD, Rampur Bsr.

No: - RMP/Tender/2024 1335-16 Dated:- 30-01-2025

Copy forwarded for information:-

1. The Superintending Engineer 11th Circle HPPWD, Shimla.
2. Copy to Notice Board.

Executive Engineer,
Rampur Division (B&R),
HPPWD, Rampur Bsr.

256 (1)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- **99,000.00**
Earnest money 2,000.00
Time One Month

NAME OF WORK:- R/R damages on link road to village Runpoo Km 0/0 to 6/400 road Kmm 0/00 to 4/500.
(SH:- C/O R/wall in wire crate at 6/162 to 6/171.60)

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hardd rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock(where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	8.45	per cubic metre	222.90	(Rs. Two hundred twenty two and paise ninty)only	1884.00
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	4.61	per cubic metre	391.15	(Rs.Three hunderd ninty one and paise fifteen)only	1,803.00
3	Providing and laying boulder apron laid in wire crates mate with G.I.wire confirming to IS :280 & IS 4826 in 100mmx100mm mesh (weaved diagonally including 10% extra for laps and joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including hauling of materials through all modes of transportation within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.(Labour rate)	27.65	Per Cubic metre.	3040	(Rs.Three thousand forty and paise zero)only	84056.00
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.44	Per Cubic metre.	1513.1	(Rs. One thousand five hundred thirteen and paise ten)only	11257
					Total:-	**99,000.00**

D.N.I.T. checked and approved for Rs. **99,000.00**

Executive Engineer,
Rampur Division (B&R)
RP.PWD., Rampur.

257(2)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- **99,224.00**
Earnest money 2,000.00
Time One Month

NAME OF WORK:- R/R damages on link road to village Runpoo Km 0/0 to 6/400 road Kmm 0/00 to 4/500.
(SH:- C/O R/wall in wire crate at 6/150 to 6/159.60)

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hardd rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock(where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	8.64	per cubic metre	222.90	(Rs. Two hundred twenty two and paise ninty)only	1926.00
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	4.61	per cubic metre	391.15	(Rs.Three hunderd ninty one and paise fifteen)only	1,803.00
3	Providing and laying boulder apron laid in wire crates mate with G.I.wire confirming to IS :280 & IS 4826 in 100mmx100mm mesh (weaved diagonally including 10% extra for laps and joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including hauling of materials through all modes of transportation within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.(Labour rate)	27.65	Per Cubic metre.	3040	(Rs.Three thousand forty and paise zero)only	84056.00
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.56	Per Cubic metre.	1513.1	(Rs. One thousand five hundred thirteen and paise ten)only	11439
					Total:-	**99,224.00**

D.N.I.T. checked and approved for Rs. **99,224.00**

Executive Engineer,
Rampur Division (B&R)
HP PWD., Rampur.

258 (3)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- 95,925.00
Earnest money 2,000.00
Time One Month

Name of work:- Repair and maintenance of Bridges on Gharat Sarahan road Km 0/00 to 5/0 (SH:- Paing and welding of Deck plate,other parts and concreteing on bed level to protect abutments of Sarahan bridge at Km 4/510

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	326.00	per Kg	6.80	Rs.(Six and Paise eighty) only	2,217.00
2	Welding by gas or electric paint including transportiation of plant at site complete and as per the direction of the Engineer-in-charge including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	2804.00	per Cm	11.9	Rs (Eleven and Paise Ninty) Only	33,368.00
3	providing nd fixing M.S. angle 5x50x5mm to etc. as nosing with lugs of M.S.flat 10x5mm ,10cm lomg forked at end 60cm apart (Minimum three lugs to be provided) including necessary welding and applying a priming caot of approved primer on exposed surface etc. complete including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	74.10	per kg	127.85	Rs. (One hundred twenty seven and Paise eighty five) only	9,474.00
4	Painting two coat(excluding priming coat) on new steel and oither metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt,dust and other forign matters and ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	72.04	per Square metre	128.60	Rs. (One hundred twenty eight and Paise sixty) only	9,264.00
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repar to scratches etc. complete,nnd ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	36.02	per Square metre	11.34	(Rs. Eleven and Paise thirty four) only	408.00
6	Primer caot with ready mixed redoxide zinc chromape primer of approved brand and manufacture on nsteel galvinsed iron /stell works complete,and ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	36.02	per Square metre	44.70	(Rs.Fortv four and paise seventy)only	1,610.00
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10(1) (Mechanincal mix and vibrated graded crushed stone aggregate) 1:3:6 Including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of Engineer- in Charge.	6.86	per cubic metre	5,770.30	(Rs. Fivethousand seven hundred seventy and paise thirt) only	39,584.00
					Total:-	**95,925.00**

D.N.I.T. checked and approved for Rs. **95,925.00**

Shakti Negi
Executive Engineer,
Rampur Division (B&R)
H.P.PWD., Rampur.

259 (4)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- 98,218.00
Earnest money 2,000.00
Time One Month

Name of work:- Repair and maintenance of Bridges on R.G/M/S>J road Km 0/00 to 61/0 (SH:- Paing and welding of Deck plate,other parts and concreteing on bed level to protect abutments of Sarahan bridge at Km 49/045)

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	407.50	per Kg	6.80	Rs.(Six and Paise eighty) only	2,771.00
2	Welding by gas or electric paint including transportiation of plant at site complete and as per the direction of the Engineer-in-charge including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	3384.00	per Cm	11.9	Rs (Eleven and Paise Ninty) Only	40,270.00
3	providing nd fixing M.S. angle 5x50x5mm to etc. as nosing with lugs of M.S.flat 10x5mm ,10cm lomg forked at end 60cm apart (Minimum three lugs to be provided) including necessary welding and applying a priming caot of approved primer on exposed surface etc. complete including carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	96.90	per kg	127.85	Rs. (One hundred twenty seven and Paise eighty five) only	12,389.00
4	Painting two coat(excluding priming coat) on new steel and oither metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt,dust and other forign matters and ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	72.04	per Square metre	128.60	Rs. (One hundred twenty eight and Paise sixty) only	9,264.00
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repar to scratches etc. complete,nnd ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	43.22	per Square metre	11.34	(Rs. Eleven and Paise thirty four) only	490.00
6	Primer caot with ready mixed redoxide zinc chromape primer of approved brand and manufacture on nsteel galvinsed iron /stell works complete,and ancluding carriage of materials within all lead and lifts as per direction by the Engineer-in-charge.	43.22	per Square metre	44.70	(Rs.Fortv four and paise seventy)only	1,932.00
7	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C grade M 10(1) (Mechanincal mix and vibrated graded crushed stone aggregate) 1:3:6 Including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of Engineer- in Charge.	5.39	per cubic metre	5,770.30	(Rs. Fivethousand seven hundred seventy and paise thirt) only	31,102.00
					Total:-	**98,218.00**

D.N.I.T. checked and approved for Rs. **98,218.00**

Shalini Negi
Executive Engineer,
Rampur Division (B&R)
H.P.PWD., Rampur.

245

(5)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- **99,307.00**
Earnest money :- 2,000.00
Time One Month

NOW:- C/O Mahatma Gandhi Govt. Engg. College Kotla (Jeori) in Tehsil Rampur Distt. Shimla

(SH:- Brick work,painting and steel work for installation of lifts at Mechanical and Lecture theatre block)

Sr. No.	Description	Qty.	Unit	Rate in figure	Rate in words	Amount.
1	Providing and laying second class half brick masonry in common burnt clay building bricks in all levels in all heights with cement mortar 1:4 (One cement : 4 sand) and curing complete including carriage of materials labour ,tool and plants through all modes of transportation as per HP. PWD. specifications of 1990 volume-I.including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	4.35	Per Cubic Metre	9,459.04	Nine Thousand Four Hundred Fifty Nine Rupees Four Paise	41,147.00
2	15mm thick cement plaster in single coat on the rough side of brick/ concrete/ stone walls for interior plastering up to floor all level including arises internal rounded angles chamfers and / or rounded angles not exceeding 80mm in girth and finished even and smooth: in cm 1:6 including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	42.81	Per sqm Metre	278.35	Two Hundred Seventy Eight Rupees Thirty five Paise	11,916.00
3	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	42.81	Per sqm Metre	109.58	One Hundred Nine Rupees Fifty Eight Paise	4,691.00
4	Providing mild / tor steel reinforced cement for RCC. Work including bending binding and placing in position complete up to floor all level. including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	11.40	kg	101.42	One Hundred One Rupees Forty two Paise	1,156.00
5	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint In trusses and trussed purlins in buildings including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	153.42	kg	103.20	One Hundred Three Rupees Twenty Paise	15,833.00
6	Painting two costs (excluding priming cost on new steel and other metal surfaces eith enamel paint brushin to give an even shade including cleaning the surface of all dirt,dust and other foregin matters Enamel white paint including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	4.86	Per sqm Metre	128.64	One Hundred Twenty Eight Rupees Sixty Four Paise	625.00
7	Painting two coats (excluding priming coat) with enamel paint of approved design or its equalent on undecorated wall surfaces to give an even shade including cleaning the surface of all dirt,dust and sand papered smooth to give final finish to the surface complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportion within all leads and lifts and as per direction of Engineer-in-Charge.	42.81	Per sqm Metre	107.29	One Hundred Seven Rupees Twenty Nine Paise	4,593.00
8	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6 mm dia metre with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	10.44	Per sqm Metre	1,853.06	One Thousand Eight Hundred Fifty Three Rupees Six Paise	19,346.00
					Total	**99,307.00**

Executive Engineer,
Rampur Division (B&R)
P.W.D. Rampur (H.P.)