



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811

E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-2024-25- 12620-28

Dated:- 23⁰¹/₂₀₂₅


To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Exigency

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	27.01.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	28.01.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	29.01.2025	Upto 10.30 P.M.
4	The date of opening of tender	29.01.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 29.01.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1	A/R & M/o salogra ashwanikhad road km 0/0 to 7/500 (SH: Clearance of side drain, trimming of grass, white washing and dressing of berms in km 5/550 to 7/0)	99160/-	2000/-	One Month	Rs.350/-
2	A/R & M/o salogra ashwanikhad road km 0/0 to 7/500 (SH: Clearance of side drain, trimming of grass, white washing and dressing of berms in km 0/00 to 2/00)	99160/-	2000/-	One Month	Rs.350/-
3	A/R & M/O Solan Kumarhatti via Barog road km 0/0 to 5/0 (SH: Clearance of side drains, trimming of grass and whitewashing in km 0/0 to 2/500)	99123/-	2000/-	One Month	Rs.350/-
4	A/R & M/O Solan Kumarhatti via Barog road km 0/0 to 5/0 (SH: Clearance of side drains, trimming of grass and whitewashing in km 2/500 to 5/00)	99123/-	2000/-	One Month	Rs.350/-
5	A/R & M/O Phaskanah Kanah Bajnal road km 0/0 to 4/645 (SH: Clearance of side drains, trimming of grass and removal of slips at RD 2/500 to 4/645)	98443/-	2000/-	One Month	Rs.350/-
6	A/R & M/O Phaskanah Kanah Bajnal road km 0/0 to 4/645 (SH: Maintenance of earthen shoulder at RD 2/500 to 4/645)	91120/-	2000/-	One Month	Rs.350/-


7	C/o Model career center at Jatoli, Solan (SH: Preparation of approval of NOC case from town and country planning)	49500/-	1000/-	Two Months	Rs.350/-
8	R/R damages on Bangar Kunipul road under Kandaghat sub-division (SH: Hiring of JCB loader cum excavator for removal of slip)	99750/-	2000/-	One Months	Rs.350/-
9	R/R damages on Sayri Damti road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips)	99750/-	2000/-	One Months	Rs. 350/-
10	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Mumligh section	99750/-	2000/-	One Months	Rs.350/-
11	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Kandaghat section-I	99750/-	2000/-	One Months	Rs.350/-
12	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Kandaghat section-II	99750/-	2000/-	One Months	Rs. 350/-
13	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Chausha section-I	99750/-	2000/-	One Months	Rs. 350/-
14	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Chausha section-II	99750/-	2000/-	One Months	Rs. 350/-
15	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Sadhupul section	99750/-	2000/-	One Months	Rs. 350/-
16	R/R damages on Kehlog Basha road and Dam site to Bisha road under Kandaghat Sub-division (SH: Hiring of JCB loader cum excavator for removal of slips)	99750/-	2000/-	One Months	Rs. 350/-
17	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Chail section	99750/-	2000/-	One Months	Rs. 350/-
18	R/R damages on Kufri Chail Kandaghat roads under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slips) Chail section	99750/-	2000/-	One Months	Rs. 350/-
19	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of tipper for carriage of slips) Mamligh section	96000/-	2000/-	One Months	Rs. 350/-

20	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of tipper for carriage of slips) Kandaghat section	96000/-	2000/-	One Months	Rs. 350/-
21	R/R damages on various roads under Kandaghat sub-division (SH: Hiring of tipper for carriage of slips) Chail section	96000/-	2000/-	One Months	Rs. 350/-
22	A/R & M/O on Jatoli Damrog Solan road km 0/0 to 3/340 (SH: Clearance of side drain in between km 0/0 to 3/340)	98956/-	2000/-	One Months	Rs. 350/-
23	R/R Damages on Kiari More to Kot road km 0/0 to 2/450 (SH: C/o wing wall at RD 0/263 to 0/266)	98840/-	2000/-	One Months	Rs. 350/-
24	R/R damages on Oachghat Kalaghat Nandal road km 0/0 to 4/625 (SH: C/o PCC R/wall at RD 2/550 to 2/553)	99404/-	2000/-	One Months	Rs. 350/-
25	A/R & M/O on Galanag Matial road km 0/0 to 2/0 (SH: Clearance of side drain in km 0/0 to 2/0)	98599/-	2000/-	One Months	Rs. 350/-
26	A/R & M/O PWD rest house at Solan Distt. Solan (SH: Providing sanitation services by deployment of one beldar/sweeper/part time worker)	99898/-	2000/-	One Months	Rs. 350/-
27	C/o Govt. Sr. Sec. School at karog Solan (SH: Conducting bearing capacity of soil test)Job No. 3	99600/-	2000/-	One Months	Rs. 350/-
28	C/o Govt. Sr. Sec. School at karog Solan (SH: Conducting bearing capacity of soil test)Job No. 2	99600/-	2000/-	One Months	Rs. 350/-
29	C/o Govt. Sr. Sec. School at karog Solan (SH: Conducting bearing capacity of soil test)Job No. 1	99600/-	2000/-	One Months	Rs. 350/-
30	A/R & M/O Kandaghat sub-division (SH: supplying and stacking of crushed sand to treat various icy pavements in snow bound reaches etc.) Chail section	98350/-	2000/-	One Months	Rs. 350/-
31	A/R & M/O mini secretarial building at Solan (SH: P/F tiles in Superintendent of police office)	65602/-	1300/-	One Months	Rs. 350/-
32	A/R & M/O mini secretarial building at Solan (SH: P/F interlocking paver block at approach road at mini secretariat Solan)	81467/-	1700/-	One Months	Rs. 350/-
33	C/o additional accommodation building for Govt. Sr. Sec. School at Dol Ka Jubbar, solan (SH: Conducting bearing capacity of soil test) Job No. 1	99600/-	2000/-	One Months	Rs. 350/-
34	C/o additional accommodation building for Govt. Sr. Sec. School at Dol Ka Jubbar, solan (SH: Conducting bearing capacity of soil test) Job No. 2	99600/-	2000/-	One Months	Rs. 350/-

35	C/o Deothi Delgi road portion Bara to Delgi km 10/150 to 19/500 under MNP (SH: ROFD at RD 11/230 to 11/299)	99895/-	2000/-	One Months	Rs. 350/-
36	C/o Chail Gaura road km 0/0 to 29/350 under MNP (SH: ROFD at RD 3/060 to 3/100)	98238/-	2000/-	One Months	Rs. 350/-
37	C/o Chail Gaura road km 0/0 to 29/350 under MNP (SH: ROFD at RD 8/410 to 8/439)	98352/-	2000/-	One Months	Rs. 350/-
38	Balance work of repair and maintenance of Govt. women polytechnic college at Kandaghat Distt. Solan (SH: Dismantling of roofing sheet)deposit work	93146/-	1900/-	One Months	Rs. 350/-
39	Balance work of repair and maintenance of Govt. women polytechnic college at Kandaghat Distt. Solan (SH: Providing and fixing of roofing sheet)deposit work	99625/-	2000/-	One Months	Rs. 350/-
40	C/o 60.00 mtr span bridge over ashwani Khad at RD 2/870 on DDL factory to Chaura road km 0/0 to 3/420 (SH: Conducting bearing capacity of soil test of middle pier)Job No 1	97920/-	2000/-	One Months	Rs. 350/-
41	C/o 60.00 mtr span bridge over ashwani Khad at RD 2/870 on DDL factory to Chaura road km 0/0 to 3/420 (SH: Conducting bearing capacity of soil test of middle pier)Job No 2	99360/-	2000/-	One Months	Rs. 350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.



Executive Engineer,
B&R Division,
HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/2024-25- 12620 -28 Dated: 23⁰¹/₂₅ are of emergent nature of work and in public interest.

Dated:-

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan

Draft Schedule of Quantity

Description of work

Job No. :- /

Name of Work :- Annual repair and maintenance of Salogra Ashwanikhad road km.0/00 to 7/500 (SH:- Clearance of side Drains, trimming of grass, white washing and dressing of berms in km.5/550 to 7/00)

1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	1450.00	Per running meter.	34.50	Rupees Thirty Four and Paise Fifty Only	50025.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	4200.00	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	9450.00
3	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	500.00	Per Square Meter	17.45	Rupees Seventeen and Paise Forty Five Only	8725.00
4	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface and dressing it in entire length to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	900.00	Per Square Meter	34.40	Rupees Thirty Four and Paise Forty Only	30960.00
Total :-						99160.00
Rupees Ninety Nine Thousand One Hundred Sixty Or						

Rupees Ninety Nine Thousand One Hundred Sixty Or

T/S No.171 for the 2024-25
Sr. No.216 for the year 2024-25
Draft Schedule of Quantity approved for Rs. 99160.000

Executive Engineer
B&R Division, HP.PVD. Solan.

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 2.						
Name of Work :- Annual repair and maintenance of Salogra Ashwani Khad road Km.0/00 to 7/500 (SH:- Clearance of side Drains, trimming of grass, white washing and dressing of berms in Km.0/00 to 2/00)						
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	1450.00	Per running meter.	34.50	Rupees Thirty Four and Paise Fifty Only	50025.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	4200.00	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	9450.00
3	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	500.00	Per Square Meter	17.45	Rupees Seventeen and Paise Forty Five Only	8725.00
4	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface and dressing it in entire length to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	900.00	Per Square Meter	34.40	Rupees Thirty Four and Paise Forty Only	30960.00
Total :-						99160.00
Rupees Ninety Nine Thousand One Hundred Sixty Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No. 170 for the 2024-25
 Sr. No. for the year 2024-25
 Executive Engineer
 B&R Division, HP.PWD, Solan.

Sr. No.		Description of work		Schedule of Quantity			Amount	
Job No. :- 3		Qty.	Unit	Rate in words				
				Figures		Estimated Cost :-	96123.00	
						Earnest Money:-	2000.00	
						Time limit :-	One Month	
Name of Work :-Annual repair and maintenance of Solan Kumarhathi via Barog road Km.0/00 to 5/00 (SH:- Clearance of side Drains, trimming of grass and white washing a in Km.0/00 to 2/500)								
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2000.00	Per running meter.	34.50	Rupees Thirty Four and Paise Fifty Only		69000.00	
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	5850.00	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only		13163.00	
3	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	800.00	Per Square Meter	17.45	Rupees Seventeen and Paise Forty Five Only		13960.00	
Total :-							96123.00	
Rupees Ninety Six Thousand One Hundred Twenty Three Only								
Quoted Percentage rate upto Three Digits :-				(+) / (-)				

T/S No.173 for the 2024-25

T/S No.173 for the 2024-25
Sr. No. for the year 2024-25

Atul
Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 4				Estimated Cost :-		96123.00
				Earnest Money :-		2000.00
				Time limit :-		One Month
Name of Work :- Annual repair and maintenance of Solan Kumarhati via Barog road Km.0/00 to 5/00 (SH:- Clearance of side Drains, trimming of grass and white washing in Km.2/500 to 5/000)						
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2000.00	Per running meter.	34.50	Rupees Thirty Four and Paise Fifty Only	69000.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	5850.00	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	13163.00
3	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 (One nine one five) and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	800.00	Per Square Meter	17.45	Rupees Seventeen and Paise Forty Five Only	13960.00
		Total :-				96123.00
Rupees Ninety Six Thousand One Hundred Twenty Three Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No.174 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 5				Estimated Cost: -		98443.00
				Earnest Money: -		2000.00
				Time limit : -		One Month
Name of Work :-Annual repair and maintenance of Phaskanah Kahan Bajnal road Km.0/00 to 4/645 (SH:- Clearance of side Drains, trimming of grass and removal of landslide slips at Rd.2/500 to 4/645)						
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2145.00	Per running meter.	35.00	Rupees Thirty Five Only	75075.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2788.50	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	6274.00
3	Removal of slips in all kinds of soil (including saturated soil but excluding boulders and rocky portion requiring blasting only disposing of un-serviceable materials, stacking serviceable materials and neatly dressing the surface PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	132.00	Per Cubic Meter	129.50	Rupees One Hundred Twenty Nine and Paise Fifty Only	17094.00
Total :-						98443.00
Rupees Ninety Eight Thousand Four Hundred Forty Three Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No.175 for the 2024-25

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Sr. No.	Description of work	Schedule of Quantity					
		Qty.	Unit	Rate in		Amount	
Figures	words						
Job No. :- 6							
Name of Work :- Annual repair and maintenance of Phaskanah Kahan Bajnal road Km.0/00 to 4/645 (SH:- Maintenance of earthen Shoulder at Rd.2/500 to 4/645)							
1	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface and dressing it in entire length to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	2574.00	Per Square Meter	35.40	Rupees Thirty Five and Paise Forty Only	91120.00	
	Total :-					91120.00	
Rupees Ninety One Thousand One Hundred Twenty Only							
Quoted Percentage rate upto Three Digits :-							
				(+) / (-)			

T/S No.176 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 7				Estimated Cost: -		49500.00
				Earnest Money: -		1000.00
				Time limit : -		Two months
Name of Work :- -Construction of Model career centre at Jatoli, Solan.(SH: Preparation of approval of NOC case from town and country planning).						
1	Preparation of NOC case from town and country planning department including preparation of architectural drawings (i.e cross section, plan, elevation, rear view) visiting the site with the TCP officials. Any correction/amendment will be desired and directed by engineer in charge and complete in all respect. After the approval from the same from the TCP department the same should be submitted to this office in two fair copies and soft copy as per the requirement of this office and upto entire satisfaction of engineer in charge including all type of incidental charges.	1.00	Per Job	49500.00	Rupees Forty Nine Thousand Five Hundred Only	49500.00
Total:-						49500.00
Quoted Percentage rate upto Three Digits :-				Rupees Forty Nine Thousand Five Hundred Only		
			(+) / (-)			

T/S No 271 for the 2022-23
Sr. No. for the year 2024-25

AKL
Executive Engineer
B&R Division, HP.PWD. Solan.

0.-:-

SCHEDULE OF QUANTITY.


Name of work: -Restoration of Rain Damages on Bangar Kunipul road under Kandaghat Sub-Division (SH.- Hiring of JCB/Loader cum-excavator for removal of slips).

Estimated Cost: -	99750.00
Earnest Money: -	2000.00
Time Limit: -	One Month.

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .					
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL, Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Ruppes nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
		Total in words.		Rupees Ninety nine thousand seven hundred fifty only.		
		Quoted Percentage rate		(+)/(-)		
				Total:- 99750.00		

Sno 724 for the year 2024-25

Sno. 224 for the year 2024-25.


 Executive Engineer,
 Solan B&R Division,
 H.P.W.D; Solan.

No.:-

Name of work: -Restoatation of Rain Damages on Sayri Danni road under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.						
Sno.	Description of items	Estimated Cost: -		Earnest Money: -		One Month.
1	2	Time Limit: -				
1	Hiring of JCB / loader cum-excavator .	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
(a)	Terms and Conditions :-	3	4	5	6	7
	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in words.		Rupees Ninety nine thousand seven hundred fifty only.				
Quoted Percentage rate		(+) / (-)				
Total:-		99750.00				

Sno. 725 for the year 2024-25

Sno. 225 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solan.

Name of work: - Restoration of Rain Damages on various roads under Kandaghal Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (Mainly Section).						
SCHEDULE OF QUANTITY.						
Sno.	Description of items	Estimated Cost: -		One Month.		
		Earnest Money:-	Time Limit:-	2000.00		
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
(a)	Terms and Conditions :- Hire charges should include expenses on account of establishment, POL, Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.	3	4	5	6	7
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in words.		Rupees Ninety nine thousand seven hundred fifty only.				
Quoted Percentage rate		(+) / (-)				
Total:-		99750.00				

Sno. 226 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solani.

2. No.:-

SCHEDULE OF QUANTITY.

Name of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (Kandaghat Section-I).

Sno. Description of items

Estimated Cost: - 99750.00
Earnest Money: - 2000.00
Time Limit: - One Month.

1	2	Quantity	Unit	Rate in figure.	Rate in Words.	Amount
1	Hiring of JCB / loader cum-excavator.	3	4	5	6	7
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Ruppes nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model.					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
		Total in words.		Ruppes Ninety nine thousand seven hundred fifty only.		
		Quoted Percentage rate		(+)/(-)		
				Total:-		99750.00

Sno. 227 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solani.

SCHEDULE OF QUANTITY,
ADVANTAGES ON VARIOUS

Sno.	Description of items	Time Limit:-	One Month.
	roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (2000.00

	Hiring of JCB / loader cum-excavator.	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.	3	4	5	6	7
(b)	Hire charges should also include insurance of machinery/vehicles and establishments and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Ruppes nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model.					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
	Total in words.				Total:-	99750.00
	Quoted Percentage rate					

Sno. 228 for the year 2024-25.

1/12/1
Executive Engineer,
Solani B & R Division,
H.P.P.W.D.; Solani.

No.:-

Name of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (

SCHEDULE OF QUANTITY.

Name of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (Estimated Cost: -	
Chausa Section-I).		Earnest Money: -	
Sno		Time Limit: -	
Description of items		One Month.	
1	2	3	4
1	Hiring of JCB / loader cum-excavator .	Quantity.	Unit.
(a)	Terms and Conditions :-	Rate in figure.	Rate in Words.
(b)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.	5	6
(c)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.	7	Amount.
(d)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.		
(e)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.		
(f)	Minimum work as per PWD norms must be executed by the machinery hired.		
(g)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .		
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour		
Total in words.		Rupees Ninety nine thousand seven hundred fifty only.	
Quoted Percentage rate		Total:-	
		99750.00	

Sno. 229 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solani.

SCHEDULE OF QUANTITY.
Chausa Section-II).

Name of work: - Restoration of Rain Damages on various roads under Kandaghal Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips). (Estimated Cost: -	99750.00
Chausa Section-II).							Earnest Money: -	2000.00
Sno.							Time Limit: -	One Month.
Description of items								
1	2	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.		
1	Hiring of JCB / loader cum-excavator .	3	4	5	6	7		
Terms and Conditions :-								
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.							
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.							
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.							
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00		
(e)	Minimum work as per PWD norms must be executed by the machinery hired.							
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .							
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour							
		Total in words.		Rupees Ninety nine thousand seven hundred fifty only.		Total:-	99750.00	
		Quoted Percentage rate		(+)/(-)				

Sno. 230 for the year 2024-25

Sno. 230 for the year 2024-25.


Executive Engineer,
Solani B&R Division,
H.P.W.D; Solani.

SCHEDULE OF QUANTITY.

of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/L loader cum-excavator for removal of slips). (Input Section).

SCHEDULE OF QUANTITY.		Estimated Cost: -		99750.00		
		Earnest Money: -		2000.00		
		Time Limit: -		One Month.		
a. Description of items						
1	2	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	Hiring of JCB / loader cum-excavator .					
Terms and Conditions :-		3	4	5	6	7
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					

Sno. 231 for the year 2024-25.


Executive Engineer,
Solan B&R Division,
H.P.P.W.D; Solan.

SCHEDULE OF QUANTITY.		
	Earnest Money: -	One Month.
	Time Limit: -	
One of work: - Restoration of Rain Damages on Kehlog Basla road and Dam site to Bisha Road and ...		
acavator for removal of slips).		

SCHEDULE OF QUANTITY.		
	Earnest Money: -	One Month.
	Time Limit: -	
One of work: - Restoration of Rain Damages on Kehlog Basla road and Dam site to Bisha Road and ...		
acavator for removal of slips).		

Sn0. 232 for the year 2024-25.

Amil
Executive Engineer,
Solani B&R Division,
H.P.P.W.D.; Solani.

SCHEDULE OF QUANTITY.

Particulars	One month.
Hiring of JCB/Loader cum-excavator for removal of slips)	

Sno. 233 for the year 2024-25.

W.L.
Executive Engineer,
Solani B & R Division,
H.P.P.W.D.; Solani.

SCHEDULE OF QUANTITY.						
Name of work: - Restoration of Rain Damages on Kufri Chail Kandaghat road under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).						
				Estimated Cost: -	99750.00	
				Earnest Money: -	2000.00	
				Time Limit: -	One Month.	
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2					
1	Hiring of JCB / loader cum-excavator .	3	4	5	6	7
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL, Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model.					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
		Total in words.		Rupees Ninety nine thousand seven hundred fifty only.		
		Quoted Percentage rate		(+) / (-)		
				Total:-		99750.00

Sno. 234 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solani.

SCHEDULE OF QUANTITY.

of work: -

Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of Tipper for carriage of slips) Mumtigh

Section.

SCHEDULE OF QUANTITY.							Estimated Cost: -	96000.00	
of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of Tipper for carriage of slips) Mumligh							Earnest Money:-	2000.00	
Section.							Time Limit: -	One Months	
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.			
1		3	4	5	6	7			
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Per day	4000.00	Rupees four thousand and paise nil only.	96000.00			
							Total:-	96000.00	
		Total in words.						Rupees Ninety Six thousand only.	
		Quoted Percentage rate						(+)/(-)	

Sno. 235 for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D;Solani.


SCHEDULE OF QUANTITY.

Name of work: - **Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of Tipper for carriage of slips)**
Kandaghat Section.

Estimated Cost: -	96000.00
Earnest Money:-	2000.00
Time Limit: -	One Months

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1		3	4	5	6	7
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Per day	4000.00	Rupees four thousand and paise nil only.	96000.00
Total in words.		Rupees Ninety Six thousand only.				
Quoted Percentage rate		Total:- 96000.00				
		(+) / (-)				

Sno. 236 for the year 2024-25.


 Executive Engineer,
 Solan B&R Division,
 H.P.P.W.D;Solan.

SCHEDULE OF QUANTITY.

Job No.:-

Name of work: -

Estimated Cost: -	96000.00
Earnest Money: -	2000.00
Time Limit: -	One Months

Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of Tipper for carriage of slips) Chail

Sno.

Section.

Description of items

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1		3	4	5	6	7
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Per day	4000.00	Rupees four thousand and paise nil only.	96000.00
Total in words.						Total:- 96000.00
Quoted Percentage rate		(+)/(-)				


Sno. 237 for the year 2024-25.

A. M. W.
Executive Engineer,
Solani B&R Division,
H.P.W.D.;Solani.

Job No.: 25/2024		Estimated Cost: -		98956.00		
		Earnest Money: -		2000.00		
		Time Limit: -		Two Months.		
Name of work: -A/R and M/O on Jatoli Damrog Solan road km. 0/0 to 3/340(SH:-Clearance of line drain in between km. 0/0 to 3/340).						
SCHEDULE OF QUANTITY.						
Sno.	Description of items	Quantity.	Unit.	Rate in figure	Rate in Words	Amount.
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2860.00	Per running meter.	34.60	Rupees thirty four and paise sixty only.	98956.00
					Total:-	98956.00
					Total in words.	Rupees Ninety eight thousand Nine hundred fifty six only.
					Quoted Percentage rate	(+)/ (-)

Sno. 10 for the year 2024-25.

Executive Engineer,
B&R Division, HP.PWD,Solan.



Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 2623				Estimated Cost: -		98840.00
				Earnest Money:-		2000.00
				Time limit :-		One month

Name of Work :- Restoration of rain damages on Kiari More to Kot road Km.0/00 to 2/450 (SH:- Construction of Wing wall at RD.0/263 to 0/266)

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chisling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	9.87	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	3820.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.29	Per Cubic Meter	3721.00	Rupees Three Thousand Seven Hundred Twenty One Only	4800.00

Schedule of Quantity

Job No. :- 24

Description of work

Qty.

Unit

Rate in
Figures words
Estimated Cost:-
Earnest Money:-
Time limit :-

Amount

99404.00

2000.00

One month

Name of Work :- Restoration of Rain damages on Oachghat Kalaghat Nandal road Km.0/00 to 4/625 (SH:- Construction of PCC Retaining wall at Rd.2/550 to 2/553)

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly	11.01	Per Cubic Meter	367.00	#NAME?	4261.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.15	Per Cubic Meter	3645.00	#NAME?	4192.00
3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	20.37	Per Cubic Meter	4229.00	#NAME?	86145.00

brick masonry/stone masonry/plain reinforced concrete return wall with 100mm (one hundred millimeter) dia PVC pipe full width of the structure with slope of 1:20 (One verticle istowards drawing face complete as per drawing and technical clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one hundred four point three point seven) or as directed by the Engineer-in-charge of materials with in all lead and lift and other incidentals.	3.00	Each	231.00	#NAME?	693.00
ing behind abutment, wing wall and return wall, breast walls, retaining walls parapets up to all heights, depths and levels complete as per HP.PWD. specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental	3.91	Per Cubic Meter	1052.00	#NAME?	4113.00
Total:-					99404.00
					#NAME?
Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.294 for the 2023-24.
Sr. No.446 for the year 2023-24

Amit
Executive Engineer
B&R Division, HP.PWD. Solan.

Job No.: 82		Estimated Cost: -		98599.00		
		Earnest Money: -		2000.00		
		Time Limit: -		Two Months.		
Name of work: -A/R and M/O on Galanag Matinal Road km. 0/0 to 2/0 (SH:-Clearance of line drain in between km. 0/0 to 2/0).						
SCHEDULE OF QUANTITY.						
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2200.00	Per running meter.	34.60	Rupees Thirty four and paise sixty only.	76120.00
2	Maintenance of earthen shoulders (filling with fress selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fress approved selected soil and compacting itg with appropriate equipment at OMC upto a lead of 1000 meters as per technical specifications Clause 1003.	635.00	P/Square meter.	35.40	Rupees thirty five and paise forty only.	22479.00
		Total:-				98599.00
		Rupees Ninety eight thousand five hundred ninety nine only.				
		Total in words.				
		Quoted Percentage rate				
		(+)/(-)				

Sno. 06 for the year 2024-25.

Executive Engineer,
B&R Division, HP.PWD,Solan.

[Signature]


Schedule of Quantity

Description of work		Quantity		Rate in words		Amount
Job No.	Qty.	Unit	Figures	Estimated Cost:-	Earnest Money:-	Time:-
				99898.00	2000.00	Twelve months

name of work :- A/R & M/O PWD Rest House at Solan , Distt. Solan (SH :- Providing sanitation services by deployment of one welder / sweeper / Part time worker)

1	Sweeping in and around the circuit house / Rest house including cleaning and washing of floors out side and inside rest house, wash room, kitchen, drain by deploying labour (Timing of labour shall be 7.30am to 10.00am and 4.00pm to 6.30pm at specified places i.e. five hours per day or one thousand eight hundred twenty five hours per annum i.e. 1 Job) as per direction of Engineer in Charge including carriage of all labour, equipment and material to various location through all modes of transportation in all lead, lift and other incidental charges.	1.000	Per Job	99898.00	Rupees Ninety Nine Thousand Eight Hundred Ninety Eight Only	99898.00
Total :-						99898.00
Total in Words		Rupees Ninety Nine Thousand Eight Hundred Ninety Eight Only				
Percentage rate to be quoted by the contractor :-		(+) / (-)				

Sr. No. 228 for the year 2024-25


 Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :-	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost :-		99600.00
				Earnest Money :-		2000.00
				Time limit :-		One month

Name of work: - Construction of Government Senior Secondary School at Karog Solan (SH:- Conducting bearing capacity of soil test) (Job No. 3)

1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose laocation of the building by drilling 3 (three) Nubmers bore hole 10 (ten) metre deep at site as per IS 2800-1979 using percussion/Catryx/ RC . ODEX method required for drilling in collapsible strata, conglomerate boulder, pebbles, sand, gravels, site and clay etc. including cost of attachment, extractable casing,consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	12.000	Per running meter.	8300.00	Rupees Eight Thousand Three Hundred Only	99600.00
	Total:-					99600.00
	Quoted Percentage rate upto Three Digits :-		(+) / (-)		Rupees Ninety Nine Thousand Six Hundred Only	

Sr. No. 239 for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.


Schedule of Quantity

Job No. :-	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost :-		99600.00
				Earnest Money :-		2000.00
				Time limit :-		One month

Name of work: - Construction of Government Senior Secondary School at Karog Solan (SH:- Conducting bearing capacity of soil test) (Job No. 2)

1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose location of the building by drilling 3 (three) Nubmers bore hole 10 (ten) metre deep at site as per IS 2800-1979 using percussioin/ Caty/ RC . ODEX methed required for drilling in collepsible strata, conglomerate boulder , pebbles , sand , gravels, site and clay etc. including cost of attachment, extractable casing, consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	12.000	Per running meter.	8300.00	Rupess Eight Thousand Three Hundred Only	99600.00
Total:-						99600.00
Quoted Percentage rate upto Three Digits :-		Rupess Ninety Nine Thousand Six Hundred Only		(+) / (-)		

Sr. No. 210 for the year 2024-25


Executive Engineer
 B&R Division, HP.PWD. Solan.

Figures	Rate in words	Amount
Estimated :-		

Schedule of Quantity

Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	

Estimated Cost:-	99600.00
Earnest Money:-	2000.00
Time limit :-	One month

Name of work:- Construction of Government Senior Secondary School at Karog Solan (SH:- Conducting bearing capacity of soil test) (Job No. 1)

1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose laocation of the building by drilling 3 (three) Nubmers bore hole 10 (ten) metre deep at site as per IS 2800-1979 using percussison/ Catyx/ RC . ODEX methed required for drilling in collepsible strata, congolomerate boulder, pebbles, sand, gravels, site and clay etc. including cost of attachment, extractable casing, consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	12.000	Per running meter.	8300.00	Rupees Eight Thousand Three Hundred Only	99600.00
	Total:-					99600.00
	Quoted Percentage rate upto Three Digits :-					
					Rupees Ninety Nine Thousand Six Hundred Only	
			(+) / (-)			

Sr. No. 241 for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

name of work: - Annual repair and maintenance of Kandaghat Sub Division (SH :- Supply and stacking of crushed Sand to treat various icy pavements in now bound reaches etc.) (Chail Section)

Qty.	Unit	Rate in		Amount		
		Figures	words			
		Estimated Cost: -		98350.00		
		Earnest Money: -		2000.00		
		Time limit : -		Fifteen days		
Name of work: - Annual repair and maintenance of Kandaghat Sub Division (SH : - Supply and stacking of crushed Sand to treat various icy pavements in snow bound reaches etc.) (Chail Section)						
1	Supplying and stacking at site sand of approved quarry which should be sharp clelan and chemically free from adhesive coating, partical of shanke and organic matter and free from impurities like iron particles, alkalis, salt and laminated material which may effect adversely its strength and appearances of mortar. Amount of defective substances, fine clay, fine silt etc. shall not exceed by more than 4% (four percent) as per direction of Engineer-in-Charge at site.	70.00	Per Cubic Meter	1405.00	Rupees One Thousand Four Hundred Five Only	98350.00
Total in figures :-						
Total in Words :-						98350.00
Quoted Percentage rate :-		Rupees Ninety Eight Thousand Three Hundred Fifty Only				
			(+) / (-)			

Sr. No. 242 for the year 2024-25

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

of Work :- Annual Repair and maintenance of Mini Secretariat building at Solan (SH:- Providing and fixing in Superintendent of Police)

of Work :- Annual Repair and maintenance of Mini Secretariat building at Solan (SH. - Providing and fixing in Superintendent of Police)							Estimated Cost :-	65602.00
							Earnest Money :-	1300.00
							Time limit :-	One Month
2	Dismantling for thickness of tiles 10 mm to 25 mm tile work in floor sand roofs laid increment mortar including stacking material within 50 metres lead lead as per direction of Engineer - in - charge.	37.44	Per Square Meter	50.29	Rupees Fifty and Paise Twenty Nine Only	1883.00		
2	Demolishing cement concrete 1:3:6 or richer mix (i/c equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	2.81	Per Cubic Meter	1547.30	Rupees One Thousand Five Hundred Forty Seven and Paise Thirty Only	4345.00		
3	Providing and laying Vitrified tiles in different sizes 600x600 mm (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622 of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete as per HP.PWD. Specification and as per direction of Engineer in Charge including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges	37.44	Per square meter.	1444.65	Rupees One Thousand Four Hundred Forty Four and Paise Sixty Five Only	54088.00		
4	Providing and fixing 2nd class teak wood 50 x 20 mm wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete	24.80	Per Running Meter	213.15	Rupees Two Hundred Thirteen and Paise Fifteen Only	5286.00		
Total:-						65602.00		
Rupees Sixty Five Thousand Six Hundred Two Only								
Quoted Percentage rate upto Three Digits :-		(+) / (-)						

Quoted Percentage rate upto Three Digits :-

T/S No. for the 2024-25

Sr No. 243 for the year 2024-25

[Signature]
Executive Engineer

B&R Division, HP.PWD, Solan.

No. :-

Schedule of Quantity

Work :- Annual Repair and maintenance of Mini Secretariat building at Solan (SH: - Providing and fixing interlocking paver block at approach road at Mini Secretariat Solan)

Estimated Cost :-		81467.00
Earnest Money :-		1700.00
Time limit :-		One Month

Name of Work :- Annual Repair and maintenance of Mini Secretariat building at Solan (SH:- Providing and fixing interlocking paver block at approach road at Mini Secretariat Solan)						
1	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	5.40	Per Cubic Meter	4557.19	Rupees Four Thousand Five Hundred Fifty Seven and Paise Nineteen Only	24609.00
2	Providing and laying cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size), in position cement concrete of specified grade excluding the cost of centering and shuttering as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	0.45	Per Cubic Meter	6294.16	Rupees Six Thousand Two Hundred Ninety Four and Paise Sixteen Only	2858.00

and Laying factory made chamfered edge Cement Concrete paver blocks 60mm (millimetre) thick of M-30 (M-Thirty) grade with approved colour, design & pattern of strength, thickness & size/shape, made by table vibratory method, to attain smooth finish using PU or equivalent moulds, laid in required Grey colour & in over 50mm (fifty millimetre) thick compacted bed of coarse sand, compacting and embedding/ laying of interlocking paver blocks into the sand bedding layer through factory compacting by using plate vibrator, filling the joints with jamuna sand and cutting paver blocks as per required size and pattern, finishing and sweeping extra sand in top/side path, parks lawns, drive ways or light traffic parking etc. all complete as per manufacturer's specification & direction of Engineer-in-charge including carriage of material within all leads, lifts, height and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.

	54.00	Per Square Meter	1000.00	Rupees One Thousand Only	54000.00
<p>and last ... concrete edge Cement Concrete paver blocks 60mm (millimetre) thick of M-30 (M-Thirty) grade with approved colour, design & pattern of strength, thickness & size/shape, made by table vibratory method, to attain a smooth finish using PU or equivalent moulds, laid in required Grey colour & over 50mm (fifty millimetre) thick compacted bed of coarse sand, compacting and or embedding/ laying of interlocking paver blocks into the sand bedding layer through a trowel compacting by using plate vibrator, filling the joints with jamuna sand and cutting paver blocks as per required size and pattern, finishing and sweeping extra sand in the path, parks lawns, drive ways or light traffic parking etc. all complete as per manufacturer's specification & direction of Engineer-in-charge including carriage of material within all leads, lifts, height and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.</p>					
Total:-					81467.00
Rupees Eighty One Thousand Four Hundred Sixty Seven Only					

Quoted Percentage rate upto Three Digits :-

T/S No.	for the 2024-25
Sr. No.	for the year 2024-25

PWD
Executive Engineer
B&R Division, HP.PWD. Solan.

Quantity	Unit	Figures	Estimated Cost:-	One month
		Estimated Money:-		
		Earnest Money:-		
		Unit :-		School at Dol

Schedule of Quantity

Job No. :-

Name of work :- Construction of additional accomodation building for Government Senior Secondary School at Dol
 Ka Jubbar Solan (SH:- Conducting bearing capacity of soil test) (Job No. 1)

Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
1 Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose laocation of the building by drilling 3 (three) Nubmers bore hole 10 (ten) metre deep at site as per IS 2800-1979 using percussin/ Catyx/ RC . ODEX methed required for drilling in colapsible strata, conglomerate boulder, pebbles , sand , gravels, site and clay etc. including cost of attachment, extractable casing,consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	12.000	Per running meter.	8300.00	Rupees Eight Thousand Three Hundred Only	99600.00
Total:-					99600.00
Quoted Percentage rate upto Three Digits :-					Rupees Ninety Nine Thousand Six Hundred Only
		(+) / (-)			

Sr. No. 245 for the year 2024-25

Executive Engineer
 B&R Division, HP.PWD. Solan.

Sr.

Description of work

Job No. :- 347

Name of work:-	Earliest money:-	
	Time limit :-	One mo
Ka Jubbar Solan (SH:- Conducting bearing capacity of soil test) (Job No. 2)		

No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Name of work: - Construction of additional accomodation building for Government Senior Secondary School at Dol Ka Jubbar Solan (SH:- Conducting bearing capacity of soil test) (Job No. 2)						
				Estimated Cost: -		99600.00
				Earnest Money:-		2000.00
				Time limit :-		One month
1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose laocation of the building by drilling 3 (three) Nubmers bore hole 10 (ten) metre deep at site as per IS 2800-1979 using percussison/ Catyx/ RC ODEX methed required for drilling in collepsible strata, conglomerate boulder, pebbles, sand, gravels, site and clay etc. including cost of attachment, extractable casing, consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	12.000	Per running meter.	8300.00	Rupess Eight Thousand Three Hundred Only	99600.00
Total:-						99600.00
Rupees Ninety Nine Thousand Six Hundred Only				(+) / (-)		
Quoted Percentage rate upto Three Digits :-						

Sr. No. 246 for the year 2024-25

A. Patel
Executive Engineer
B&R Division, HP.PWD. Solan.

No. :-

Schedule of Quantity

Estimated Cost :-	99895.00
Earnest Money :-	2000.00
Time limit :-	One Month

of Work :- Construction of Deothi Delgi road portion Bara to Delgi Km.10/150 to 19/500 under MNP (SH: - ROFD A.11/230 to 11/299)

Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site, according to the HP.PWD. specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machines, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	500.40	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	99895.00
Total:-					99895.00
Rupees Ninety Nine Thousand Eight Hundred Ninety Five Only					
Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.182 for the 2024-25
Sr. No 247 for the year 2024-25

Executive Engineer
B&R Division, HP.PWD, Solan.

Draft Schedule of Quantity

Job No. :-

39A

Estimated Cost :- 98238.00

Earnest Money :- 2000.00

Time limit :- One Month

Name of Work :- Construction of Chail Gaura Road Km. 0/00 to 29/350 under MNP (SH:- ROFD at Rd.3/060 to 3/100)

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site according to the HP.PWD. specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and un-serviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	492.10	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	98238.00
	Total:-					98238.00
	Rupees Ninety Eight Thousand Two Hundred Thirty Eight Only					

T/S No.179 for the 2024-25

Sr. No. 248 for the year 2024-25

Draft Schedule of Quantity approved for Rs. 98238.00 only.

Executive Engineer
B&R Division. HP.PWD. Solan.

Schedule of Quantity

Job No. :-

870

Name of Work :- Construction of Chail Gaura Road Km. 0/00 to 29/350 (SH: - ROFD at Rd.8/410 to 8/439)

Estimated Cost :-	98352.00
Earnest Money :-	2000.00
Time limit :-	One Month

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site according to the HP PWD specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	492.67	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	98352.00
Total:-						98352.00
Rupees Ninety Eight Thousand Three Hundred Fifty Two Only						
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

T/S No.180 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Work :- Balance work of Repair and Maintenance of Govt. Women Polytechnic College at Kandaghat Distt.
 HP(SH:- Dismantling of roofing sheet)(Deposit work)

Estimated Cost :-	93146.00
Earnest Money :-	1900.00
Time limit :-	One Month

Providing and fixing 0.60mm (Zero point Sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating fixing with pre-painted iron J or L hooks, bolts and nuts 6mm diameter with pre-painted impet and rubber washers complete with all accessories as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	210.90	Per square meter	69.80	Rupees Sixty Nine and Paise Eighty Only	14721.00
	62.74	Per square meter	1250.00	Rupees One Thousand Two Hundred Fifty Only	78425.00
Total:-					93146.00
Rupees Ninety Three Thousand One Hundred Forty Six Six Only					
Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.165 for the 2024-25
 Sr. No. 250 for the year 2024-25

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 39
42

Estimated Cost :-	99625.00
Earnest Money :-	2000.00
Time limit :-	One Months

Name of Work :- Balance work of Repair and Maintenance of Govt. Women Polytechnic College at Kandaghat Dist.
Solana (HP)(SH:- Providing and fixing of roofing sheet) (Deposit work)

1	Providing and fixing 0.60mm (Zero point Sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of bolts and nuts 6mm diameter with pre-painted impet and rubber washers complete with all accessories as per H P PWD Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	19.95	Per square meter	1250.00	Rupees One Thousand Two Hundred Fifty Only	24938.00
2	Providing corrugated G.S. sheet 1.00 mm thick with zinc coating not less than 275 gm/m ² roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. impet washers or with G.I. impet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per H.P.PWD. specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	89.20	Per square meter.	837.30	Rupees Eight Hundred Thirty Seven and Paise Thirty Only	74687.00
Total:-						99625.00
Rupees Ninety Nine Thousand Six Hundred Twenty Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.178 for the 2024-25
Sr. No.251 for the year 2024-25

Executive Engineer
B&R Division, HP.PWD, Solana.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 1473				Estimated Cost: -		97920.00
				Earnest Money: -		2000.00
				Time limit : -		One month
Name of work:- Construction of 60 mtr Span Bridge Over Ashwani Khad at Rd.2/870 on DDL Factory to Chaura road						
Km.0/00 to 3/420 (SH:- Conducting bearing capacity of soil test of Middle Pier) Job No.1						
1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose location of the Bridge by drilling 3 (three) Nubmers bore hole 13.80 (Thirteen point Eighty) metre deep at site as per IS 2800-1979 using percussion/ Catyx/ RC.ODEX method required for drilling in collepsible strata, conglomerate boulder . pebbles . sand , gravels, site and clay etc. including cost of attachment, extractable casing,consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	13.600	Per running meter	7200.00	Rupees Seven Thousand Two Hundred Only	97920.00
Total:-						97920.00
Rupees Ninety Seven Thousand Nine Hundred Twenty Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

Sr. No.

for the year 2024-25

Executive Engineer

B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :-

Name of work:- Construction of 60 mtr Span Bridge Over Ashwani Khad at Rd.2/870 on DDL Factory to Chaura road
Km.0/00 to 3/420 (SH:- Conducting bearing capacity of soil test of Middle Pier) Job No.2

Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
			Estimated Cost:-		99360.00
			Earnest Money:-		2000.00
			Time limit :-		One month
1 Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose laocation of the Bridge by drilling 3 (three) Nubmers bore hole 13.80 (Thirteen point Eighty) metre deep at site as per IS 2800-1979 using percussison/ Catyx/ RC.ODEX methed required for drilling in collepsible strata. conglomerate boulder . pebbles , sand , gravels, site and clay etc. including cost of attachment, extractable casing,consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	13.800	Per running meter	7200.00	Rupees Seven Thousand Two Hundred Only	99360.00
Total:-					99360.00
Rupees Ninety Nine Thousand Three Hundred Sixty Only					
Quoted Percentage rate upto Three Digits :-					
		(+) / (-)			

Sr. No.

for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.