

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2024-25-4343-4345
To

Dated:- 01-10-2024

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 14.10.2024.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature due to disaster happened in the area in the month of September and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.
2. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 14.10.2024 up to 2:00 PM and shall be opened on 14.10.2024 the same day at 2:30 PM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 11.10.2024 for which the applications should reach in this office up to 4.00 PM on 10.10.2024. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1 ✓	Restoration of rain damages to various roads under Kolar section under Dhaulakuan Sub Division. (SH:- Removal of slips, Clear of HPC & C/O unlined surface drain in various roads).	Rs. 4,64,076/-	Rs. 9500/-	Three months	350/-	C & D Class
2 ✓	Restoration of rain damages on link road village Katwari Bagrath to Jalal river km. 0/0 to 5/0. (SH:-C/O Retaining wall in wire crate at RD. 3/895 to 3/922).	Rs. 4,96,026/-	Rs. 10000/-	Three months	350/-	C & D Class
3 ✓	Restoration of rain damages to link road from Lohgarh to Banda Bahadur road km. 0/0 to 2/990 and link road to village Lohgarh km. 0/0 to 5/150. (SH:- Removal of slips and debris in various RDs).	Rs. 4,99,010/-	Rs. 10000/-	Three months	350/-	C & D Class
4 ✓	Restoration of rain damages in Baila section at various road. (SH:-Removal of slips & Dressing of berms on Katwari Bagrath road km. 0/0 to 5/0, Mehat Gawana Khalli Achhon Naddi road km. 0/0 to 12/0, Link road to Thakkar Kujjewala km. 0/0 to 4/700, Girinagar Jatton road km.0/0 to 25/0 & Jamta Rajban road km. 23/0 to 43/0).	Rs. 4,66,793/-	Rs. 9500/-	Three months	350/-	C & D Class

5	✓ Preparation of detailed Project report of 3 Nos. and Hydraulic data for the C/O 35.00mtr, 30.00mtr. PSC Girder & 19.02 Multi box cell concrete bridge at chainage 4/320 to 4/355, 4/113 to 4/143 & 2/573 to 2/592 in Gram Panchayat Haripur khol from Banda Bahadur Gurudwara to village Lohgarh road) Under NABARD.	Rs. 4,98,000/-	Rs. 10000/-	Two months	350/-	C & D Class
6	✓ Repair and maintenance to various roads under Baila & Dhaulakuan Section. (SH:- Repair of Pot holes by filling with local granular material on Girinagar Jatton road km. 0/0 to 23/0, Jamta Rajban road km. 23/0 to 43/0 & Badripur Jamniwala Parduni road km. 15/0 to 19/750).	Rs. 4,98,419/-	Rs. 10000/-	Three months	350/-	C & D Class
7	✓ Restoration of rain damages to Badripur Jamniwala Parduni road km. 0/0 to 15/0 . (SH:- Hiring of JCB and Tractor with Trolley for removal of slips/debries, Dressing of berms, C/O unlined surface drain and making up loss on shoulders and alternative/diversion of road due to fully damage of Abhi Ka Khala bridge at RD. 7/900).	Rs. 2,71,625/-	Rs. 5500/-	Two months	350/-	C & D Class
8	✓ C/O link road to village Jhinvar Basti km. 0/0 to 1/460. (SH:- C/O 2.00 mtr. slab culvert (Slab & Steel) & Interlocking tiles at RD. 0/040 to 0/094). Under MNP.	Rs. 4,94,345/-	Rs. 10000/-	Three months	350/-	C & D Class
9	✓ Preparation of detailed estimate/ working estimate & D.N.I.T. on detailed analysis of rates of various works of building head under Paonta Division).	Rs. 3,01,000/-	Rs. 6230/-	Two months	350/-	C & D Class
10	✓ R/R damages on various roads under Majra Section, Dhaulakuan & Baila Section. (SH:- Hiring of Tractor with trolley hydraulic lift for carriage of Gatka and other material and shifting of debris and Hiring of JCB for removal of slips/ Debris, Dressing of berms, Filling of pot holes, opening of block drain).	Rs. 4,99,430/-	Rs. 10000/-	Two months	350/-	C & D Class
11	✓ C/O link road to village Jhinvar Basti km. 0/0 to 1/460. (SH:- C/O 2.00 mtr. slab culvert, edge wall both side in cement concrete, embankment at RD. 0/040). Under MNP.	Rs. 4,74,923/-	Rs. 10000/-	Three months	350/-	C & D Class

82

12	C/O link road from Lohgarh to Banda Bahadur road km. 0/0 to 4/200. (SH:- Providing and laying GSB in km. 1/876 to 2/294). Under MNP.	Rs. 4,99,698/-	Rs. 10000/-	Three months	350/-	C & D Class
13	C/O link road from Lohgarh to Banda Bahadur road km. 0/0 to 4/200. (SH:- Providing and laying GSB in km. 2/294 to 2/376 and retaining structure in wire crate). Under MNP.	Rs. 4,98,259/-	Rs. 10000/-	Three months	350/-	C & D Class
14	Repair of link road to Kodewala km. 0/0 to 1/0. (SH:- C/O wing wall D/S of approach slab and abutment protection of Nimbuwala bridge at RD.1/0). (Repair of bridge).	Rs. 4,63,268/-	Rs. 9500/-	Three months	350/-	C & D Class
15	Restoration of rain damages on various roads under Dhaulakuan section in HP. PWD.(B&R) Sub-Division Dhaulakuan. (SH:- Hiring of JCB and tractor with trolley for removal of slips and debris, dressing of berms, filling of pot holes & opening of block drain/road of various RDs).	Rs. 1,51,460/-	Rs. 3100/-	Three months	350/-	C & D Class
16	C/O link road from Singhpura to Shamshanghat near Police Chowki Singhpura km. 0/0 to 0/450. (SH:- Providing and laying Wet mix macadam in km. 0/0 to 0/450). Under SCSP.	Rs. 4,93,875/-	Rs. 10000/-	Two months	350/-	C & D Class
17	C/O Widening of Salwala Singhpura Bhagani road km. 0/0 to 15/0. (SH:- C/O retaining wall in wire crate from RD.14/525 to 14/535 for removal of formation deficiencies).Under MNP.	Rs. 3,66,885/-	Rs. 7500/-	Two months	350/-	C & D Class
18	Periodical renewal on Badrinagar Jamniwala Parduni road km. 0/0 to 15/0. (SH:- Providing and laying of thermoplastic compound 2.5 mm thick in km. 4/0 to 5/0 & 6/0 to 7/0 and P/F road stud in km. 4/0 to 5/0). Under AMP for the year 2024-25.	Rs. 4,98,515/-	Rs. 10000/-	Three months	350/-	C & D Class
19	Periodical renewal on Paonta to Nawada road km. 0/0 to 5/0. (SH:-Providing and fixing thermoplastic compound 2.5 mm thick and P/F road stud in km. 0/0 to 1/200). Under AMP for the year 2024-25.	Rs. 4,98,838/-	Rs. 10000/-	Three months	350/-	C & D Class
20	Restoration of rain damages on Kolar Bilaspur road km.0/0 to 12/0. (SH:- C/O retaining wall in wire crate at RD 7/249 to 7/259).	Rs. 1,87,122/-	Rs. 4000/-	Three months	350/-	C & D Class

21	C/O link road from Haripur Tohana to Mashuta Basti Garibnath Mandir at Shivpur km. 0/0 to 1/675. (SH:- Providing retaining structure in PCC 1:3:6 and 450 mm dia RCC pipe at various essential RDs for removal of formation deficiencies) Under MNP.	Rs. 4,32,950/-	Rs. 9000/-	Two months	350/-	C & D Class
22	C/O link road from Haripur Tohana to Mashuta Basti Garibnath Mandir at Shivpur km. 0/0 to 1/675. (SH:-C/O 5/7 mtr. wide road, embankment in filling in km. 0/075 to 1/675 for removal of formation deficiencies) Under MNP.	Rs. 4,57,726/-	Rs. 10000/-	Two months	350/-	C & D Class
23.	Restoration of rain damages to various roads under Paonta Local Section & Puruwalla Section of Paonta Sub Division No.I, HPPWD Paonta Sahib. (SH:- Hiring of JCB and Tractor with Trolley for removal of slips, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes on various roads).	Rs. 1,98,935/-	Rs. 4000/-	Two months	350/-	C & D Class
24.	C/O link road from Khushal Aara Machine along canal to friends colony Housing board Devinagar Km. 0/0 to 0/700. (SH:- Providing and laying interlocking paver block in Km. 0/155 to 0/205) Under MNP.	Rs. 4,92,390/-	Rs. 10000/-	Two months	350/-	C & D Class
25.	C/O link road from Khushal Aara Machine along canal to friends colony Housing board Devinagar Km. 0/0 to 0/700. (SH:- C/o wire crate edge wall from RD 0/0 to 0/095 on RHS for removal of formation deficiencies) Under MNP.	Rs. 4,96,959/-	Rs. 10000/-	Two months	350/-	C & D Class
26.	C/O link road from Khushal Aara Machine along canal to friends colony Housing board Devinagar Km. 0/0 to 0/700. (SH:- C/o cement concrete edge wall from RD 0/035 to 0/105 LHS and 0/155 to 0/230 on RHS for removal of formation deficiencies) Under MNP.	Rs. 3,97,526/-	Rs. 8000/-	Two months	350/-	C & D Class
27.	C/O link road from Khushal Aara Machine along canal to friends colony Housing board Devinagar Km. 0/0 to 0/700. (SH:- Providing and laying interlocking paver block in Km. 0/205 to 0/255) Under MNP.	Rs. 4,92,390/-	Rs. 10000/-	Two months	350/-	C & D Class


28.	C/O link road from Khushal Aara Machine along canal to friends colony Housing board Devinagar Km. 0/0 to 0/700. (SH:- Providing and laying interlocking paver block in Km. 0/255 to 0/305) Under MNP.	Rs. 4,92,390/-	Rs. 10000/-	Two months	350/-	C & D Class
29.	A/R & M/O Residential housing board colony at Devinagar Paonta Sahib (HP). (SH:- Providing and Fixing wood work, repair to plaster, tiles work, distempering & painting and sanitary fittings in existing at type-III qtr No. 117)	Rs. 2,22,485/-	Rs. 4500/-	One month	350/-	C & D Class

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis for bitumen work.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

No.PWP/CB-Tender Notice/2024-25- **4346-4395**

Dated:- **01-10-2024**

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Job No- 1

Schedule of Quantity						
Name of work:- Restoration of rain damages to various roads under Kolar section under Dhaulakuan Sub Division(SH:- Removal of slips, clear of HPC & C/o unlined surface drain in various roads).						
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in	Amount
					Words	
1	Removal of land slides/slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within a left upto 1.5 mtr and lead upto 1000 mtrs as per technical specification clause 302.3.5. and 1611 including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	2450.80	Per cubic metre	147.50	Rs One hundred forty five and paise five zero only	361493
2	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908.including all eads lifts and carriage of materials, as per the direction of Engineer-In charge.	22.00	each	2482.40	Rs Two thousand four hundred eighty two and paise forty only	54613
3	Construction of unlined surface drains by mechanical of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including all eads lifts and carriage of materials, as per the direction of Engineer-In charge.	1950.00	Per running metre	24.60	Rs Twenty four and paise sixty only	47970
Total						464076



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

②

Job No - 2

Schedule of Quantity						Estimated cost:-496026/- only	
Name of work:- Restoration of rain damage on link road Village Katwari Bagrath to Jallal river Km 0/0 to 5/00.(SH:- Construction of Retaining wall in wire crate at RD 3/895 to 3/922).						Earnest Money:-10000/- only	
						Time:- Three Months	
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount	
o							
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	64.80	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	12312	
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	153.560	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only	483714	
					Total	496026	



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

3

Job No- 3

Schedule of Quantity						
Name of work:- Restoration of rain damages to link road from Lohgarh to Banda Bhadur road Km 0/0 to 2/990 and link road to village Lohgarh Km 0/0 to 5/150. (SH:- Removal of slips and debris in various RDs).						
S.No	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Removal of land slides/slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within a left upto 1.5 mtr and lead upto 1000 mtrs as per technical specification clause 302.3.5. and 1611 including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	3383.12	Per cubic metre	147.50	Rs One hundred forty five and paise five zero only	499010
Total						499010



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 4

Schedule of Quantity						Estimated cost:-466793/- only
Name of work:- Restoration of rain damages in Biala section at various road (SH:- Removal of slips & dressing of berms on Katwari Bagrath road km 0/0 to 5/0, Mehat Gawana Khalli Achhon naddi road km 0/0 to 12/0, Link road to Thakkar Kujjewala road km 0/0 to 4/700, Ginegar Jatton road km 0/0 to 25/0 & Jamta Rajban road Km 23/0 to 43/0).						Earnest Money: -9500/- only
Sub heads and items of work						Time: - Three Months
S.No	Qty	Unit	Figures	Rate in Words	Amount	
1	2445.00	Per cubic metre	147.50	Rs One hundred forty seven and paise fifty only	360638	
2	1685.00	Per square metre	63.00	Rs Sixty three and paise nil only	106155	
				Total	466793	

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 5

SCHEDULE OF QUANTITY

Name of work:- Preparation of detailed Project report of 3 Nos and Hydraulic data for Construction of 35.00 mtr, 30.00 mtr. PSC Gieder & 19.02 Multi box cell concrete bridges at chainage 4/320 to 4/355, 4/113 to 4/143 & 2/573 to 2/592 in gram Panchayat Haripur Khol from Banda Bahadur Gurudwara to village Lohgarh road) Under NABARD

Estimated cost :- Rs :- 4,98,000/-
Earnest Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Preparation of detailed Project repor and 3 Nos Hydraulic data, Contour site plan along with cross section, L-section, , complete in all respect in manuscript alongwith working estimate from and submission of the same to higher office for approval. If any correction/ammdments will be desired by the head office the same may be corrected as desired and directed by the Engineer -In charge and complete in all respect. After approval the same from the head office should be submitted in five fair copies and soft copy.	3.000	Per Job	166000.00	Rs. Twenty Six Thousand & paise Nil only	498000
	Total :-					498000

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Conditions:-

- 1). Submission of manuscript, fair copies and working estimate of detailed project report along with analysis of rates to get these approved from competent authorities and letter on after approval from NABARD preparing the working estimate of same along with bill of quantity and schedule of quantity of the job.

Payment Schedule:-

- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

- 3 Work will be carried out strictly as per guide lines and specification of HP PWD.

- 4 40% Payment will be released after submission of Hydraulic data.

- 5 Balance 60% Payment will be paid after getting approval from competent authority.

- 6 In case of delay in completion of services, a penalty equal to 0.05% of the contract price per day subject to maximum 5% of the contract value will be imposed and shall be recovered from payment due. However, in case of delay due to reasons beyond the control of consultant, suitable extension of time will be granted.

Signature of the contractor with full address:-


Executive Engineer,
Paonta HP PWD, Division
Paonta Sahib

Job No. 6

Schedule of Quantity

Name of work:- Repair and Maintenance to various roads under Baila & Dhaulakuan Section (SH:- Repair of pot holes by filling with local granular material on Girinagar Jatton road Km 0/0 to 23/0 ,Jamta Rajban road Km 23/0 to 43/0 & Badripur Jamniwala Parduni road Km 15/0 to 19/750).					Estimated cost:-498419/- only	
					Earnest Money: -10000/- only	
					Time: - Three Months	
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
1	Granular sub-base/surface course with local material(table 400.13) by mix in place method normal construction of granular sub base by providing local material,spreading in uniform layer with motor grader on prepared surface mixing by mix in place method with rotavator at once complete as per Clause 401.4 including haulage of materials with in all leads, lifts and carriage of materials and as per the direction of the Engineer-in Charge.	435.30	Per cubic metre	1145.00	Rs One thousand one hundred forty five and paise nil only	498419
					Total	498419



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No- 7

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Badripur Jamiwala Parduni road km 0/0 to 15/0, (SH):- Hiring of JCB and tractor with trolley for removal of slips/ debris , dressing of berms, construction of unlined surface drain and making up loss on shoulders and alternative / diversion of road due to fully damage of Abhi ka khala bridge at RD 7/900) Estimated Cost:- 271625/- Only. Earnest Money:- 5500/- Only Time Limit: - Two Months.

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loader I cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol chgarge , maintenance or any minor or major accidents and other damage to private and Govt . property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	215.00	Per hour	1055.00	Rs. One thousand fifty five and zero paise only	226825.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	14.00	Per day	3200.00	Rs. Three thousand two hundred and zero paise only.	44800.00
					G.Total	271625.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No. 8.

Schedule of Quantity

Name of work:- Construction of link road to village Jhivar Basti Km 0/0 to 1/460. (SH):- Construction of 2.00mtr slab culvert (slab & steel) & interlocking tile at RD 0/040 to 0/094). under MNP.						Estimated cost:-494345/- only
						Earnest Money:-10000/- only
						Time:- Three Months
S.N o	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
					Rs Seven thousand eight hundred fifty and paise nil only	
1	Providing and laying Cement Concrete 1:1.5:3 (One cement :One and half sand : Three aggregate) for plain /rain forced cement concrete in super structure M-25 grade as per grade & technical specification clause 802,803,1202 & 1204. including centering & shuttering, including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	5.36	Per Cubic metre	7850.00		42076
2	Supplying fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 &1202 as per entire satisfaction of the Engineer-in-charge.	0.640	Per Tonne	98217.30	Rs Ninety eight thousand two hundred seventeen and paise	62859
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size)including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	33.75	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	167238
4	Providing and laying of interlocking concrete block pavement (ISI Marka) having thickness 80 mm (eighty millimetre)as per drawing and technical specification clause 1504. including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	219.38	Per Square metre	960.00	Rs Nine hundred sixty and paise nil only	210605
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	1.89	Per cubic metre	6120.00	Rs Six thousand one hundred twenty and paise nil only	11567
					Total	494345

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No- 9.

SCHEDULE OF QUANTITY

Name of work :- Preparation of detailed estimate/working estimate & D.N.I.T on detailed analysis of rates of various works of building head under Paonta Division).

ESTIMATED COST :- Rs. 3,01,000 /- only

EARNEST MONEY :- Rs. 6,230 /- only

TIME ALLOWED :- Two Months

S.N o.	Sub-head & item of works	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of following detailed estimate & working estimates & DNIT on detailed analysis of rates of various works under building heads under Paonta Sahib Division including drawings complete in all respect & submission of the same to higher office for approval (If any correction/amendment if desired by the head office, the same may be corrected as desired & directed by the Engineer-in-Charge and complete in all respect). After approval the same from the head office should be submitted with soft copy.	7	43000.00	Rs. Forty three thousand & paise nil only).	Each	301000
1	Detailed estimate for the Seismic Vulnerability assessment & retrofit of health/lifeline of Community Health centre building at Paonta Sahib.					
2	Detailed estimate for the Seismic Vulnerability assessment & retrofit of health/lifeline of Govt. Senior Secondary School (Girls) building at Paonta Sahib.					
3	Detailed estimate for the Seismic Vulnerability assessment & retrofit of health/lifeline of Govt. Senior Secondary School building at Bhagani.					
	Note :- The sanction of the works mentioned in Sr. 1 to 3 was given by the D.C. Office & detailed estimates of these work have been prepared separately. Now as per the direction of higher authority a consolidated working estimate alongwith the DNIT to be prepared for the said works & tender to be floated as one job. Hence the same is prepared accordingly.					
4	DNIT for the Construction of Single lane PSC bridge 150 metres span over Bata River between Kiratpur to Toka including approaches 25.00 metres on either side in Tehsil Paonta Sahib, District Sirmour (HP).					
5	DNIT for the construction of Double lane PSC bridge 180 metres span over Bata River between Puruwala Kanshipur to Kundian including approaches 50.00 metres on either side in Tehsil Paonta Sahib, District Sirmour (HP).					
6	Working/Detailed estimate & DNIT for the construction of PHC building at Bhagani.					
7	Detailed/Working estimate & DNIT for the construction of road from Paonta Sahib Dakpathar road (MDR -94) to connect bridge over Yamuna river at Naughat Bhimawala Km. 0/0 to 0/650 (Under MNP).					
	Total :-					301000

Quoted rate in Figure (+ / -) (..... %)

Quoted rate in works (+ / -) %)

Conditions :-

- 1 Submission of manuscript, flat copies & working/detailed estimate/project report alongwith analysis of rates to get these approved from competent authorities and letter on after approval from NABARD preparing the working estimate of same alongwith bill of quantity and schedule of quantity of the job.

Payment Schedule :-

- 2 The contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- 3 Work will be carried out strictly as per guide lines and specification of HP. PWD.
- 4 40% payment will be released after submission of DPR & Hydraulic data.
- 5 Balance 60% payment will be paid after getting approval from competent authority.
- 6 In case of delay in completion of services, a penalty equal to 0.05% of the contract price per day subject to maximum 5 % of the contract value will be imposed and shall be recovered from payment due. However, in case of delay due to reasons beyond the control of consultant. Suitable extension of time will be granted.

Executive Engineer,
Paonta, HP-PWD., Division,
Paonta Sahib.

Job No - 10

SCHEDULE OF QUANTITY					
Name of work :- R/R Damage on various roads under Majra section, dhaulakuan & Baila section ((SH: Hiring of tractor with trolley hydraulic lift for carriage of Gatka and other material and shifting of debris and Hiring of JCB for removal of slips / debris, dressing of berms , filling of pot hole , opening of block drain).			Estimated Cost: 499430/- only Earnest Money: 10000/- only Time Allowed: Two month only		
S.No	Sub Head and item of work	Quantity	Unit	Rate in	
				Figures	Words
1	Hiring of tractor with trolley hydraulic lift for carriage of Gatka and other material of 9.00 A.M. to 5.00 P.M.(Nine A.M. to Five P.M.). The contractor / Owner of tractor shall bear the expensive of POL charges, repair of machineries. Any accident and other damages to private and govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all lead and lifts as per direction of Engineer in Charge with in all leads and lifts.	42	Per day	3200.00	Rupees Three Thousand two hundred and paise nil only
2	Hiring of hydraulic excavator cum loader 1 cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol cgarage , maintenance or any minor or major caaidents and other damage to private and Govt . property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	346	Per Hours	1055.00	Rupees one thousand fifty five and paise nil only
				Total :	
				4,99,430	


Executive Engineer,
Paonta(B&R) Division,
HP.PWD. Paonta Sahib

Job No. 11.

I

Schedule of Quantity

Name of work:-Construction of link road to village Jhivar Basti Km 0/0 to 1/460.(SH):- Construction of 2.00mtr slab culvert , edge wall both side in Cement Concrete,embankment at RD 0/040). under MNP.

Estimated cost:-474923/- only
Earnest Money: -10000/- only
Time: - Three Months

S.N	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	30.16	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	5730
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size)including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	48.40	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	239832
3	Providing and laying of interlocking concrete block pavement (ISI Marka) having thickness 80 mm (eighty millimetre)as per drawing and technical specification clause 1504. including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	64.50	Per Square metre	960.00	Rs Nine hundred sixty and paise nil only	61920
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	21.61	Per cubic metre	6120.30	Rs Six thousand one hundred twenty and paise thirty only	132260
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-	20.00	each	367.00	Rs Three hundred sixty seven and paise nil only	7340

6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	92.19	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	27841
					Total	474923



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 12.

Schedule of Quantity					
Name of work:- Construction of link road from Lohgarh to Banda Bhadur road Km 0/0 to 4/200.(SH:- Providing and laying GSB In Km 1/876 to 2/294). under MNP.					
			Estimated cost:-499698/- only		
			Earnest Money:-10000/- only		
			Time:- Three Months		
S.N	Sub heads and items of work	Qty	Unit	Rate in	
				Figures	Words
1	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto lead of 1000 m spreading in uniform layer with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading 1 material (size range 75mm to 0.075mm) having CBR value-30, including haulage of materials with in all leads, lifts and carriage of materials and as per the direction of the Engineer-in Charge.	241.40	Per Cubic metre	2070.00	Rs Two thousand seventy and paise nil only
				Total	499698



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 13.

Schedule of Quantity

Name of work:- Construction of link road from Lohgarh to Banda Bhadur road Km 0/0 to 4/200 (SH:- Providing and laying GSB In Km 2/294 to 2/376 and retaining structure in wire crate). under MNP.					Estimated cost:-498259/- only Earnest Money:-10000/- only Time:- Three Months	
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
0					Rs	
1	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto lead of 1000 m spreading in uniform layer with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 for grading 1 material (size range 75mm to 0.075mm) having CBR value-30, including haulage of materials with in all leads, lifts and carriage of materials and as per the direction of the Engineer-in-Charge.	47.36	Per Cubic metre	2070.00	Rs Two thousand seventy and paise nil only	98035
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	39.38	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	7482
3	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	124.680	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only	392742
					Total	498259



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 14.

Schedule of Quantity

Repair of

Name of work:- Restoration of rain damages link road to Kodewala Km 0/0 to 1/00. (SH:- Construction of wing wall D/S of approach slab and abutment protection of Nimbuwala bridge at RD 1/0). **(Repair of Bridge)**

Estimated cost:-463268/- only

Earnest Money:-9500/- only

Time:- Three Months

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	10.50	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	1995	
2	Providing and laying concrete 1:3:6 (One cement: three sand: six graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (Mechanical mix) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer in Charge	81.12	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	440064	
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	15.00	each	367.00	Rs Three hundred sixty seven and paise nil only	5505	
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	52.00	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	15704	
					Total	463268	



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 15.

Schedule of Quantity

Name of work:- Restoration of rain damages on various roads under Dhaulakuan section in HP.PWD (B&R) Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolley for removal of slips and debris, dressing of berms, filling of pot holes & opening of block drains/road of various RDs.).					Estimated cost:- 151460/- only	
					Earnest Money:- 3100/- only	
					Time:- Three Months	
S.N	o	Sub heads and items of work	Qty	Unit	Rate in	
					Figures	Words
1		Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer - in- Charge.	92.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only
2		Hiring of tractor with trolley i/c operating and service staff as required and including Pol and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of Machinery or operating staff shall be met out of his own cost. Other condition shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer - in-	17.00	Per day	3200.00	Rupees three thousand two hundred and paise nil only
					Total	151460

Note:- The cost of P.O.L.charge wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc. shall be born by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. - 16.

SCHEDULE OF QUANTITY

Name of work:- Constnction of link road from Singhpura to Shamshanghat near Police Chowki
Singhpura km 0/0 to 0/450 (SH:- Providing and laying Wet mix macadam in km 0/0 to 0/450
(Under SCSP)

Estimated cost :- Rs :- 4,93,875/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. Complete including carriage of materials upto all leads lift and carriage of materials complete as per the entire satisfactions of the Engineer in charge at site.	237.440	Per Cubic metre	2080.00	Rs. Two thousand eighty and paise Nil only	493875.00
Total :-						493875.00

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-



Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No. 17.

SCHEDULE OF QUANTITY
Name of work :- Construction of Windening of Salwala Singhpura Bhagani road Km.0/0 to 15/0(SH:-
Construction of retaining wall in wire crate from RD 14/525 to 14/535 for removal of formation deficiencies)
under MNP.

Estimated cost :- Rs :- 3,66,885/-
Earnist Money:- Rs:- 7,500/-
Time:- Two Months.


Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all lead, lift upto as per technical specification clause 1603.1 including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	40.20	Per Cubic metre	198.50	Rs. One hundred ninety eight & paise fifty only	7980/-
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (weaved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	1121.50	Per Cubic metre	3150.00	Rs. Three thousand one hundred fifty & paise Nil only	354375/-
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	51.30	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	4530.00
	Total:					366885/-

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 18.

Schedule of Quantity

Name of work:- Periodical renewal on Badrinagar Jamiwala Parduni road Km 0/0 to 15/0. (SH:- Providing and laying of thermoplastic compound 2.5mm thick in km 4/0 to 5/0 & 6/0 to 7/0 and PIF road stud in km 4/0 to 5/0). under AMP for the year 2024-25.

S.No	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications	500.20	Per square metre	635.10	Rs Six hundred thirty five and paise ten only	317677
2	Providing and fixing road stud 100*100 mm dia cast in aluminium, resistant to corrosive effect of Salt and grit, fitted with lence reflectors, installed in concrete or asphaltic surface by drilling holes 30mm upto depth of 600mm and bedded in suitable bituminous grout or epoxy mortar, all as per BS:873(part 4)1973, including all leads, lifts and carriage of materials, as per the direction of Engineer-in charge.	575.00	Nos	314.50	Rs Three hundred fourteen and paise fifty only	180838
					Total	498515



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. - 19.

Schedule of Quantity						
Name of work:-Periodical renewal on Paonta to Nawada road Km 0/0 to 5/0.(SH):- Providing and fixing of thermoplastic compound 2.5mm thick and P/F road stud in km 0/0 to 1/200) under AMP for the year 2024-25.						
Sub heads and items of work						
S.No	Qty	Unit	Figures	Words	Rate in	Amount
1	530.42	Per square metre	635.10	Rs Six hundred thirty five and paise ten only		336870
Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications						
2	515.00	Nos	314.50	Rs Three hundred fourteen and paise fifty only		161968
Providing and fixing road stud 100*100 mm dia cast in aluminium ,resistent to corrosive effect of Salt and grit,fitted with lence reflectors,installed in concrete or asphaltic surface by drilling holes 30mm upto depth of 600mm and bedded in suitable bituminous grout or epoxy mortar,all as per BS:873(part 4)1973,including all leads,lifts and carriage of materials, as per the direction of Engineer-In charge.						
					Total	498838



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 20.

Schedule of Quantity					Estimated cost:-187122/- only	
Name of work:-Restoration of rain damages on Kolar Bilaspur road Km 0/0 to 12/0.(SH:- Construction of retaining wall in wire crate at RD 7/249 to 7/259)					Earnest Money:- 4000/- only	
					Time: - Three Months	
S.No	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	18.00	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	3420
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	56.880	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only	179172
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	15.00	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	4530
					Total	187122


Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 21.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Haripur tohana to Mashuta Basti Garibnath Mandir at Shivpur Km. 0/0 to 1/675 (SH):- Providing retaining structures in PCC 1:3:6 and 450 mm dia RCC pipe at various essential RDs for removal formation deficiencies) under MNP.

Estimated cost :- Rs :-4,32,950/-
Earnest Money:- Rs:- 9,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	33.30	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	6327.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	58.20	Per Cubic metre	5424.00	Rs. Five thousand four hundred twenty four and paise Nil only	315677.00
3	Providing weep holes in plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structure with slope of 1 V:20 H towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	85.00	Each	232.00	Rs. Two hundred thirty two & paise Nil only	19720.00
4	Excavating trenches of required width for pipes, cables, etc. including excavation for sockets, depth upto 1.5 m, including getting out the excavated materials, returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layers by ramming, watering etc., stacking serviceable material for measurements and disposal of unserviceable material as directed, within a lead of 50 m in all kinds of soils for pipes, cables etc. exceeding 300 mm dia but not exceeding 600 mm dia including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	37.50	Per Running metre	499.00	Rs. Four hundred ninety nine & paise Nil only	18713.00
5	Providing and laying 450 mm dia non-pressure NP2 class (light duty) RCC pipe with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two sand) including testing of joints etc. complete including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	37.50	Per Running metre	1931.00	Rs. One thousand nine hundred thirty one & paise Nil only	72413.00
Total:						432850.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- The Rates should be quoted for all heights including all leads and lifts.
- The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 22.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Haripur tohana to Mashuta Basti Garibnath Mandir at Shivpur Km. 0/0 to 1/675 (SH):- Construction of 5/7 mtr. Wide road, embankment in filling in km 0/075 to 1/675 for removal of formation deficiencies) under MNP.

Estimated cost :- Rs :- 4,57,726/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.


Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	1515.65	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	457726.00
	Total:					457726.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 23.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to various roads under Paonta Local Section & Puruwalla section of Paonta Sub Division No. I HP PWD Paonta Sahib (SH):- Hiring of JCB and Tractor with trolley for removal of slips, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of potholes on various roads).

Estimated cost :- Rs :- 1,98,935/-
Earnist Money:- Rs:- 4,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate Figure	Words	Amount
1	Hiring of hydraulic excavator cum loader I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, Pol chgarge, maintenance or any minor or major accidents and other damage to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	137.00	Per Hour	1055.00	Rupees one thousand fifty five and paise nil only	144535.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	17.00	Per day	3200.00	Rupees three Thousand two hundred and paise nil only	54400.00
Total :-						198935.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- 2).

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No. 24.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Khushal Aara Machine along canal to friends colony Housing Board Devingar Km. 0/0 to 0/700 (SH: Providing and laying interlocking paver block in km 0/155 to 0/205) under MNP.

Estimated cost :- Rs :- 4,92,390/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	28.13	Per cubic metre	4955.00	Rs. four thousand nine hundred fifty five & paise Nil only	139384.00
2	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification close 1504 including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	350.00	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	336000.00
3	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 III. P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.88	Per Cubic metre	5,905.00	Rs. Five thousand nine hundred five & paise Nil only	17006.00
	Total:					492390.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-



Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 25.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Khushal Ara Machine along canal to friends colony Housing Board Devingar Km. 0/0 to 0/700 (SH):- Construction of wire crate edge wall from RD 0/0 to 0/095 on RHS for removal of formation deficiencies) under MNP.

Estimated cost :- Rs :- 4,96,959/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all lead, lift upto as per technical specification clause 1603.1 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	71.25	Per Cubic metre	194.80	Rs. One hundred ninety four & paise eighty only	13880.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (weaved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	148.44	Per Cubic metre	3150.00	Rs. Three thousand one hundred fifty & paise Nil only	467586.00
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	51.30	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	15493.00
	Total:					496959.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

The Rates should be quoted for all heights including all leads and lifts.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

- 1).
- 2).



Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 26.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Khushal Araa Machine along canal to friends colony Housing Board Devingar Km. 0/0 to 0/700 (SH:- Construction of cement concrete edge wall from RD 0/035 to 0/105 LHS and 0/155 to 0/230 on RHS for removal of formation deficiencies) under MNP.

Estimated cost :- Rs :- 3,97,526/-
Earnist Money:- Rs:- 8,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all lead, lift upto as per technical specification clause 1603.1 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	42.05	Per Cubic metre	194.80	Rs. One hundred ninety four & paise eighty only	8191.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	71.78	Per Cubic metre	5424.00	Rs. Five thousand four hundred twenty four and paise Nil only	389335.00
Total:						397526.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta (B&R) Division
HP/PWD Paonta Sahib

Job No. 27.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Khushal Aara Machine along canal to friends colony Housing Board Devingar Km. 0/0 to 0/700 (SH: Providing and laying interlocking paver block in km 0/205 to 0/255) under MNP.

Estimated cost :- Rs :- 4,92,390/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	28.13	Per cubic metre	4955.00	Rs. four thousand nine hundred fifty five & paise Nil only	139384.00
2	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification close 1504 including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	350.00	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	336000.00
3	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 III, P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed atone aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.88	Per Cubic metre	5,905.00	Rs. Five thousand nine hundred five & paise Nil only	17006.00
	Total:					492390.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No. 28.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Khushal Aara Machine along canal to friends colony Housing Board Devingar Km. 0/0 to 0/700 (SH: Providing and laying interlocking paver block in km 0/255 to 0/305) under MNP.

Estimated cost :- Rs :- 4,92,390/-
Earnest Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No.	Description of items	Qty.	Rate.		Unit.	Amount.
			Figure	Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	28.13	Per cubic metre	4955.00	Rs. four thousand nine hundred fifty five & paise Nil only	139384.00
2	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification close 1504 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	350.00	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	336000.00
3	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 III. P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.88	Per Cubic metre	5,905.00	Rs. Five thousand nine hundred five & paise Nil only	17006.00
	Total:					492390.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-



Executive Engineer,
Paonta (B&R) Division
HP PWD Paonta Sahib

Job No-29 ①

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O residential Housing board colony at Devi Nagar Paonta Sahib Tehsil Paonta Sahib HP.
 (SH :- Providing and fixing wood work, repair to plaster, tiles work, distempering & painting & sanitary fittings in existing at type-III qtr no.117)

Estimated cost :- Rs :- 2,22,485/-
 Earnest Money:- Rs:- 4,500/-
 Time:- One Month.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhat, architraves, hold fasts and other attachments etc. complete and stacking them within 50 metres laid : of area 3 sq.metres and below including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.00	Each	229.70	Rs. Two hundred twenty nine and Paise seventy only	459.00
2	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	16.00	each	123.00	Rs. One hundred twenty three & Paise Nil only.	1968.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works as directed by the Engineer-In-Charge as per HPPWD specifications Volume-I including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.45	Per kg	163.20	Rs. One hundred sixty three & Paise twenty only.	1705.00
4	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. 35 mm thick shutter Klin seasoned selected planks of sheesham wood including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.24	Per square metre	2854.00	Rs. Two thousand eight hundred fifty four only	9247.00
5	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 35mm thick shutter including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.60	Per square metre	3368.00	Rs. Three thousand three hundred sixty eight only	12125.00

6	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 2nd class teak wood beading 62X19 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	8.03	Per square metre	1233.10	Rs. One thousand two hundred thirty three and paise ten only	9902.00
7	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250X16 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	4.00	each	187.00	Rs. One hundred eighty seven only	748.00
8	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 250X10 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.00	each	88.75	Rs. Eighty eight and paise seventy five only	888.00
9	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 125mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	8.00	each	62.50	Rs. Sixty two and paise fifty only	500.00
10	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge With cement mortar 1:4 (1 cement : 4 fine sand) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	26.30	per square metre	374.40	Rs. Three hundred seventy four and paise forty only	9847.00
11	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	40.85	per square metre	131.70	Rs. One hundred thirty one and paise seventy only	5380.00
12	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	22.99	per square metre	1600.00	Rs. One thousand six hundred only	36784.00

13	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately) 11.47.2 Size of Tile 600x600 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	12.71	per square metre	1779.94	Rs. One thousand seven hundred and seventy nine and paise ninety four only	22623.00
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.73	cum	5122.40	Rs. Five thousand one hundred twenty two and paise forty only	13984.00
15	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	39.38	per square metre	467.85	Rs. Four hundred sixty seven and paise eighty five only	18424.00
16	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete 32 mm dia including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.00	each	91.00	Rs. Ninety one only	182.00
17	Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete. 10 litre (full flush) capacity-coloured including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.00	each	936.10	Rs. Nine hundred thirty six and paise ten only	936.00
18	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm nominal bore including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.00	each	365.00	Rs. Three hundred sixty five only	365.00
19	Providing and fixing 15mm dia brass bib tap (Superior or heavy type) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	7.00	each	516.50	Rs. Five hundred sixteen and paise fifty only	3616.00
20	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	5.00	each	652.90	Rs. Six hundred fifty two and paise ninety only	3265.00
21	Providing and fixing uplasticsed PVC connection pipe with brass unions : 15 mm nominal bore including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	4.00	each	98.20	Rs. Ninety eight and paise twenty only	393.00

22	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1000.00	per litre	9.10	Rs. Nine and paise ten only	9100.00
23	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required: White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.00	each	2636.00	Rs. Two thousand six hundred thirty six only	2636.00
24	Providing and fixing 32mm (thirty two milli metres) M.I. Union wash basin or sink as per entire satisfaction of the Engineer-In-Chief. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.00	each	500.60	Rs. Five hundred & Paise sixty only	1001.00
25	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board 17.10.2.1 610x510 mm bowl depth 200 mm including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.00	each	3300.00	Rs. Three thousand three hundred only	3300.00
26	Providing and fixing Polyethylene-Aluminium Polyethelene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints comple. INTERNAL WORK - EXPOSED ON WALL 1216 (16 mm OD) pipe including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	28.00	per square metre	250.60	Rs. Two thousand fifty hundred only and paise sixty only	7017.00
27	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	48.72	per square metre	113.80	Rs. One hundred thirteen and paise eight only	5544.00
28	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water r thinnable priming coat with cement primer including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	270.30	per square metre	69.00	Rs. Sixty nine only	18651.00

29	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	40.05	per square metre	118.30	Rs. One hundred eighteen and paise thirty only	4738.00
30	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	131.08	per square metre	75.50	Rs. Seventy five and paise fifty only	9897.00
31	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.00	each	50.30	Rs. Fifty and paise thirty only	151.00
32	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall : 15 mm dia nominal bore including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	18.00	meter	263.40	Rs. Two hundred sixty three and paise forty only	4741.00
33	Providing and fixing bright finished brass helical door spring (superior quality). including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.00	each	466.00	Rs. Four hundred sixty six only	932.00
34	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.00	each	1436.00	Rs. One thousand four hundred thirty six only	1436.00
Total:						222485.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta (B&R) Division,
HP, PWD, Paonta Sahib.