

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Dal/TA/Tender /2024-25 - **6393-95**  
To

Dated: - **27-02-25**


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

**DA/ As above.**

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.


Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie




Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:- 6396-6445 dated 27.02.25 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25: 6396-6445 dated 27.02.25 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

7 Date of receipt of application for the tender Form a/w requisite documents:- 27.02.2025 onward (between 2:00 p.m.to 4:30.p.m.)

8 Date of issued/sale of tender form against Cash payment (non refundable).

The tender shall be received up to 3:00 PM on 07.03.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 05.03.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restration of raim damage on Orumour to Sherpur rod k.m. 0/0 to 3/750 (SH:- Removal of Slips at RD 1/280 to 1/290.	99598.00	2000.00	350.00	One Month	D & C
2.	Restration of raim damage on Orumour to Sherpur rod k.m. 0/0 to 3/750 (SH:- Removal of Slips at RD 1/290 to 1/300	99192.00	2000.00	350.00	One Month	D & C
3	A/R & M/O Residential Building at Banikhet(SH:- Repair of AE Residence at PWD Colony Banikhet)	88826.00	2000.00	350.00	One Month	D & C
4	A/R & M/O Residential Building at Banikhet(SH:- Repair of AE Residence Slab at PWD Colony Banikhet)	99505.00	2000.00	350.00	Two Months	D & C
5	Restration of raim damage on Orumour to Sherpur rod k.m. 0/0 to 3/750 (SH:- Removal of Slips at RD 1/310 to 1/320	99255.00	1000.00	350.00	Two Months	D & C
6	Restration of raim damage on Orumour to Sherpur rod k.m. 0/0 to 3/750 (SH:- Removal of Slips at RD 1/300 to 1/310	99611.00	2000.00	350.00	Two Months	D & C
7	Construction of link road to village China k.m. 0/0 to 0/750 (SH:- Formation Cutting between km 0/415 to 0/520	89673.00	2000.00	350.00	Two Month	D & C
8	Restoration of Rain damage on Dalhousie Jandrihat Chamba via Kohlari road under Dalhousie Sub Division (SH:-Removal of Slips/ Snow on Dalhousie Jandrihat Chamba via Kohlari road at RD0/0 to 6/00	97476.00	2000.00	350.00	One Month	D & C
9	Restoration of Rain damage on Dalhousie Jandrihat Chamba via Kohlari road under Dalhousie Sub Division (SH:-Removal of Slips/ Snow on Dalhousie Jandrihat Chamba via	98337.00	2000.00	350.00	One Month	D & C



1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

No. PWD/TA/Tender /2024-25-6396-6445

Dated:- 27-02-25

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie



## Schedule of Qty.

Job No. --- TS 82

Estimated Cost: - Rs.

0.00

Earnest Money :- Rs.


2000.00

Time Limit :-

One Month

Name of work: - Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD 1/280 to 1/290).


Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	797.55			Per Cubic Metre	
	Total:-					

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie



## Schedule of Qty.

<b>Name of work: -Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD 1/290 to 1/300).</b>						Job No. --- TS	
						Estimated Cost: - Rs.	0.0
						Earnest Money :- Rs.	2000.0
						Time Limit :-	One Month
Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	794.30			Per Cubic Metre		
<b>Total:-</b>							


  
**Executive Engineer**  
 Dalhousie Division,  
 HPWD, Dalhousie



**Schedule of Qty.****Name of work :- A/R & M/O Residential Building at Banikhet (SH: - Repair of AE Residence at PWD Colony Banikhet).**

Estimated Cost: - Rs.	0.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	17.40			Per Square Metre	
2	Providing and fixing 10 mm (ten millimeter) thick antiskid water proof stain and impet resistant heavy duty vetrified tiles Nitco, Kajaria, Orient Bell or equivalent 600mmx600mmx10mm (six hundred millimeter into six hundred millimeter into ten millimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12 mm (twelve millimeter) thick cement mortar 1:4 (one cement isto four sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete and as per directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	37.24			Per Square Metre	
3	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	211.61			Per Square Metre	
4	Painting one coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Deluxe Paint on previously painted wood or wood based furface with enamel paint other than white to gave a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	105.48			Per Square Metre	
	<b>Total: -</b>					

  
 Executive Engineer  
 Dalhousie Division,  
 HPPMD, Dalhousie




Job No. --- TS 87

**Schedule of Qty.**

Estimated Cost: - Rs.	0.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work :- A/R &amp; M/O Residential Building at Banikhet (SH: - Repair of AE Residence Slab at PWD Colony Banikhet).

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying water proofing treatment with Dr. Fixit-FASTFLEX, Polymer, Bitumen, Vinyl-Ester-Resin or equivalent with two components polymer modified cementitious coating consisting of cementitious powder and a polymer liquid in two coats for first coat:- clean and saturate surface and then applying a coat of Dr. Fixit -FASTFLEX by maintaining a coverage of 6-7 square foot per kg to achieve one mm thickness and the same process shallended upto 300 mm (three hundred millimeter) vertically. The second coat shall be applied in opposit direction after four six-hours of application of first coat then sprinkle sand on top surface of applied Dr. Fixit-FASTFLEX while still tacky over the second coat. Then apply cement mortar 1 : 4 (1 cement :m 4 sand) admioxed with 200 ml (two hundred Millimeter) of pidiproof LW @ 200ml per 50 kg (fifty kilogram) bag of cement over the floor with the suitable grediant towards drain pipe, while tyhe second coat of Dr. Fixit is still tacky as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	69.11			Per Square Metre	
					Total: -	

  
 Executive Engineer  
 Dalhousie Division,  
 HPBWD, Dalhousie




Job No. --- TS 84

## Schedule of Qty.

Name of work: -Restoration of rain damage on Orumour to Shertpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD 1/310 to 1/320).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	794.80			Per Cubic Metre	
Total:-						

  
 Executive Engineer  
 Dalhousie Division,  
 APPWD, Dalhousie



## Schedule of Qty.

Name of work: - Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD 1/300 to 1/310).


Job No. --- TS 85

Estimated Cost: - Rs. 0.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	797.65			Per Cubic Metre	
	Total:-					

  
 Executive Engineer  
 Dalhousie Division,  
 HPBMD, Dalhousie




## Schedule of Qty.

Job No. --- WA

Name of work: - Construction of Link road to village China Km. 0/0 to 0/750 (SH: - Formation Cutting between Km. 0/415 to 0/520).

Estimated Cost: - Rs.	0.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rates is inclusive of the octroi, royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	371.78			Per Cubic Metre	
					Total: -	

  
 Executive Engineer  
 Dalhousie Division,  
 HPBWD, Dalhousie



**Schedule of Qty.**


Estimated Cost: - Rs. 0.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Dalhousie Jandrighat Chamba via Kohlari road under Dalhousie Sub-Division (SH: - Removal of Slips/Sow on Dalhousie Jandrighat Chamba via Kohlari road at RD. 5/0 to 11/040).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	787.45			Per Cubic Metre	
Total:-						

  
 Executive Engineer  
 Dalhousie Division,  
 APPWD, Dalhousie



**Schedule of Qty.**


Estimated Cost: - Rs. 0.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: - Restoration of rain damage on Dalhousie Jandriqhat Chamba via Kohlari road under Dalhousie Sub-Division (SH: - Removal of Slips/Sow on Dalhousie Jandriqhat Chamba via Kohlari road at RD. 0/0 to 6/0).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	780.56			Per Cubic Metre	
Total:-						

  
 Executive Engineer  
 Dalhousie Division,  
 HPBWD, Dalhousie