

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

12131-SD

DATED: 20/02/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President NAC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:


- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 01.03.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 03.03.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 04.03.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 04.03.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	C/o Link Road from Chanour Bridge to Ghosi Basti G.P. Chaplah KM 0/0 to 6/500 (Portion KM 3/500 to 6/500) (SH: Preparation of Detailed Project Report).	Rs. 81,000.00	Rs.2,000/-	One Month	Rs.350/-
02	C/o Link Road from Chanour Bridge to Ghosi Basti G.P. Chaplah KM 0/0 to 6/500 (Portion KM 0/0 to 3/500) (SH: Preparation of Detailed Project Report).	Rs. 94,500.00	Rs.2,000/-	Three Months	Rs.350/-
03	C/o Link Road from Barwara Chintpurni to GPS and Panchayat Ghar to Main Road G.P. Dhounta in KM 0/0 to 6/250 (Portion KM 3/250 to 6/250) (SH: Preparation of Detailed Project Report).	Rs. 81,000.00	Rs.2,000/-	Three Months	Rs.350/-
04	C/o Link Road from Barwara Chintpurni to GPS and Panchayat Ghar to Main Road G.P. Dhounta in KM 0/0 to 6/250 (Portion KM 0/0 to 3/250) (SH: Preparation of Detailed Project Report)..	Rs. 87,750.00	Rs.2,000/-	Three Months	Rs.350/-
05	C/o Link road GSSS Sera Bari to Dehra Jawali via Dhiman Basti, Choudhary Basti, Harizan Basti in KM 0/0 to 1/345 (SH: C/o C.C. Pavement at RD 0/781 to 0/801.60).	Rs. 99,352.00	Rs.2,000/-	One Month	Rs.350/-
06	C/o Link road GSSS Sera Bari to Dehra Jawali via Dhiman Basti, Choudhary Basti, Harizan Basti in KM 0/0 to 1/345 (SH: C/o C.C. Pavement at RD 0/802 to 0/823.30).	Rs. 99,616.00	Rs.2,000/-	One Month	Rs.350/-
07	C/o Link road GSSS Sera Bari to Dehra Jawali via Dhiman Basti, Choudhary Basti, Harizan Basti in KM 0/0 to 1/345 (SH: C/o C.C. Pavement at RD 0/850 to 0/871.30).	Rs. 99,616.00	Rs.2,000/-	One Month	Rs.350/-
08	Restoration of Rain Damages on PWD Rest House to JHD Road in KM 0/0 to 1/825 (SH: C/o Cement Concrete Berms at RD 0/610 to 0/655.30).	Rs. 99,314.00	Rs.2,000/-	One Month	Rs.350/-
09	Restoration of Rain Damages on PWD Rest House to JHD Road in KM 0/0 to 1/825 (SH: C/o Cement Concrete Berms at RD 0/660 to 0/705.30).	Rs. 99,314.00	Rs.2,000/-	One Month	Rs.350/-
10	Construction of CHC Building at Haripur in District Kangra (H.P.) (SH: P/L Interlocking Paver Block and Kerb Stone).	Rs. 86,510.00	Rs.2,000/-	One Month	Rs.350/-
11	Construction of CHC Building at Haripur in District Kangra (H.P.) (SH: P/L Interlocking Paver Block and Kerb Stone).	Rs. 86,510.00	Rs.2,000/-	One Month	Rs.350/-
12	Construction of CHC Building at Haripur in District Kangra (H.P.) (SH: P/L Interlocking Paver Block and Kerb Stone).	Rs. 86,510.00	Rs.2,000/-	One Month	Rs.350/-
13	Road Side Amenities under HPPWD Sub Division Haripur (SH: Painting and Writing on KM Stones, Culverts, Bridges, Sign Boards and Rain Shelter etc. in Haripur).	Rs. 96,161.00	Rs.2,000/-	One Month	Rs.350/-
14	Road Side Amenities under HPPWD Sub Division Haripur (SH: Painting and Writing on	Rs. 96,690.00	Rs.2,000/-	One Month	Rs.350/-

15	Construction of Upper Pragpur to Karol via Dadari in KM 2/00 to 3/300 (SH: P/L 60mm thick Interlocking Paver Block at RD 2/660 to 2/681.40).	Rs. 99,117.00	Rs.2,000/-	One Month	Rs.350/-
16	Construction of Upper Pragpur to Karol via Dadari in KM 2/00 to 3/300 (SH: P/L 60mm thick Interlocking Paver Block at RD 2/682 to 2/703.40).	Rs. 99,117.00	Rs.2,000/-	One Month	Rs.350/-
17	A/R & M/O PWD Staff Type-III Quarter in PWD Colony Dehra in District Kangra (H.P.) (SH: Distempering, Alluminium Work etc.).	Rs. 97,791.00	Rs.2,000/-	One Month	Rs.350/-
18	Balance Work of link road Barial Railway Station to Ghanban (Village Ghanban Panchayat Nandpur Barial) KM 0/0 to 1/250 (SH: C/o Approach Wall for Hume Pipe Culvert on Both Side from KM 0/840 to 0/844).	Rs. 99,792.00	Rs.2,000/-	One Month	Rs.350/-
19	Balance Work of link road Barial Railway Station to Ghanban (Village Ghanban Panchayat Nandpur Barial) KM 0/0 to 1/250 (SH: C/o Approach Wall for Hume Pipe Culvert on Both Side from KM 0/844 to 0/848).	Rs. 99,882.00	Rs.2,000/-	One Month	Rs.350/-
20	Balance Work of link road Barial Railway Station to Ghanban (Village Ghanban Panchayat Nandpur Barial) KM 0/0 to 1/250 (SH: C/o Embankment Filling in Approach Wall for Hume Pipe Culvert at RD 0/850).	Rs. 98,434.00	Rs.2,000/-	One Month	Rs.350/-
21	Balance Work of link road Barial Railway Station to Ghanban (Village Ghanban Panchayat Nandpur Barial) KM 0/0 to 1/250 (SH: C/o R/Wall & Embankment Filling at RD 1/290 to 1/297).	Rs. 96,548.00	Rs.2,000/-	One Month	Rs.350/-
22	Construction of Jawalamukhi Dehra Jawali Raja-Ka-Talab Road KM 4/00 to 39/180 (SH: Providing and Fixing Informatory Board) under Road Side Amenities.	Rs. 95,200.00	Rs.2,000/-	Three Months	Rs.350/-
23	Construction of Jawalamukhi Dehra Jawali Raja-Ka-Talab Road KM 4/00 to 39/180 (SH: Providing and Fixing Informatory Board) under Road Side Amenities.	Rs. 95,200.00	Rs.2,000/-	Three Months	Rs.350/-
24	Construction of Jawalamukhi Dehra Jawali Raja-Ka-Talab Road KM 4/00 to 39/180 (SH: C/o U-Shape Drain at RD 12/200 to 12/243).	Rs. 98,715.00	Rs.2,000/-	Three Months	Rs.350/-
25	Construction of Jawalamukhi Dehra Jawali Raja-Ka-Talab Road KM 4/00 to 39/180 (SH: C/o U-Shape Drain at RD 12/243 to 12/296).	Rs. 98,715.00	Rs.2,000/-	Three Months	Rs.350/-
26	Landscaping CHC Haripur in District Kangra (H.P.) (SH: Providing Land Scapping work in CHC Haripur).	Rs. 99,280.00	Rs.2,000/-	One Month	Rs.350/-
27	Landscaping CHC Haripur in District Kangra (H.P.) (SH: Providing Land Scapping work in CHC Haripur).	Rs. 99,280.00	Rs.2,000/-	One Month	Rs.350/-
28	Landscaping CHC Haripur in District Kangra (H.P.) (SH: Providing Land Scapping work in PWD Residential Colony at Haripur).	Rs. 99,280.00	Rs.2,000/-	One Month	Rs.350/-
29	Landscaping CHC Haripur in District Kangra (H.P.) (SH: Providing Land Scapping work in PWD Residential Colony at Haripur).	Rs. 99,280.00	Rs.2,000/-	One Month	Rs.350/-
30	Repair and Maintenance of Type-II Quarter in PWD Colony at Dehra in District Kangra (H.P.) (SH: C/o R/Wall, P/F ACP Sheet, Steel Work etc.).	Rs. 99,077.00	Rs.2,000/-	One Month	Rs.350/-
31	Repair and Maintenance of Type-II Quarter in PWD Colony at Dehra in District Kangra (H.P.) (SH: P/L Wall Tiles, P/F Ply, Wood Work etc.).	Rs. 99,656.00	Rs.2,000/-	One Month	Rs.350/-
32	Construction of road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under G.P. Sherlohara (SH: C/o R/Wall at RD 1/350 to	Rs. 99,208.00	Rs.2,000/-	One Month	Rs.350/-

33	Construction of road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under G.P. Sherlohara (SH: C/o R/Wall at RD 1/355 to 1/360).	Rs. 96,548.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				


 Executive Engineer
 HPPWD Division Dehra
 Distt Kangra H.P
 on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT No.....12131-50.....dated....20-02-25. are of emergent nature of work and in public interest.

Place:

Dated:

Executive Engineer,
HPPWD Division,
Dehra.

PERCENTAGE BILL OF QUANTITY

Name of work:- C/o link road from Chanour Bridge To Choi Basti Gp Chaplah 0/00 to 6/500. (Portion 3/500 to 6/500)

Estimated Cost:- 81,000.00
Earnest Money:- 2,000.00
Time Limit:- Three Months

Sub Head:-Preparation of Detailed Project Report

Sr. No.	Description of Items	Quantity	Rate in		Unit	Amount
			In Figures	In Words		
1	2	3	4	5	6	7
1	Preparation of detailed project report and drawing complete in all respect in manuscript form and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the engineer in - charge complete in all respect. After approval, the same should be submitted in six nos. Set of fair copy alongwith 03 set of drawings (manuscript included). The payment excludes any kind of soil investigations and shall be made as per actual length of road.	3,000	27,000.00	Rupess Twenty Seven Thousand Only	Per Kms	81,000.000
a	Topography survey by digital Total station / dual frequency DGPS with two second accuracy, showing all offsets such as trees, culverts, bridge, electric poles, hand pump schools, habitants villages etc.					
b	Draw cross section at 15 m (fifteen meter) intervals, 1- section & calculate the quantity of earth work in standard format of auto cad showing all layers of pavement components.					
c	Preparation Of Survey Plan Showing All Provision As Per Hppwd Specification.					
d	Preparation Of Survey Plan Showing All Existing Provisions And Preparation Of Detailed Project Report As Per Hppwd Specification.					
					TOTAL	81,000.00

% Above/below

Quoted Amount in Figures

Quoted Amount in Words

Bill of quantity checked & approved for 81,000/-

Executive Engineer
Dehra Division
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Name of work:- C/o link road from Chanour Bridge To Ghoi Basti Gp Chaplah 0/00 to 6/500. (Portion 0/00 to 3/500)							Estimated Cost:-	94,500.00
							Earnest Money:-	2,000.00
							Time Limit:-	Three Months
Sub Head:- Preparation of Detailed project Report								
Sr. No.	Description of Items	Quantity	Rate in		Unit	Amount		
			In Figures	In Words				
1	2	3	4	5	6	7		
1	Preparation of detailed project report and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the engineer - in - charge complete in all respect. After approval, the same should be submitted in six nos. Set of fair copy alongwith 03 set of drawings (manuscript included). The payment excludes any kind of soil investigations and shall be made as per actual length of road.	3.500	27,000.00	Rupees Twenty Seven Thousand Only	Per Kms	94,500.000		
a	Topography survey by digital Total station / dual frequency DGPS with two second accuracy, showing all offsets such as trees, culverts, bridge, electric poles, hand pump schools, habitants villages etc.							
b	Draw cross section at 15 m (fifteen meter) intervals, 1- section & calculate the quantity of earth work in standard format of auto cad showing all layers of pavement components.							
c	Preparation Of Survey Plan Showing All Provision As Per Hppwd Specification.							
d	Preparation Of Survey Plan Showing All Existing Provisions And Preparation Of Detailed Project Report As Per Hppwd Specification.							
						TOTAL	94,500.00	
							% Above/below	
							Quoted Amount in Figures	
							Quoted Amount in Words	

1344 of 94,500.00 / Hc checked-16
 01/12/2021 for Rs 94,500/-


 Executive Engineer
 Dehra Division
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Name of work:- C/o link road from Barwara chintpurni road to Gps and Panchayat ghar to main road G.P Dhaunta Dehra 0/00 to 6/250.(Portion 3/250 to 6/250)

Estimated Cost:- 81,000.00
 Earnest Money:- 3,500.00
 Time Limit:- Three Months

Sub Head:-Preparation of Detailed project Report

Sr. No.	Description of Items	Quantity	Rate in		Unit	Amount
			In Figures	In Words		
1	2 Preparation of detailed project report and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the engineer in - charge complete in all respect. After approval, the same should be submitted in six nos. Set of fair copy alongwith 03 set of drawings (manuscript included). The payment excludes any kind of soil investigations and shall be made as per actual length of road.	3 3,000	4 27,000.00	5 Rupees Twenty Seven Thousand Only	6 Per Kms	7 81,000.000
a	Topography survey by digital Total station / dual frequency DGPS with two second accuracy, showing all offsets such as trees, culverts, bridge, electric poles, hand pump schools, habitants villages etc.					
b	Draw cross section at 15 m (fifteen meter) intervals, 1- section & calculate the quantity of earth work in standard format of auto cad showing all layers of pavement components.					
c	Preparation Of Survey Plan Showing All Provision As Per Hppwd Specification.					
d	Preparation Of Survey Plan Showing All Existing Provisions And Preparation Of Detailed Project Report As Per Hppwd Specification.					
					TOTAL	81,000.00

% Above/below

Quoted Amount in Figures

Quoted Amount in Words

*Blank quantity sheet
 approved for Rs. 81,000/-*

[Signature]
 Executive Engineer
 Dehra Division
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Name of work:- C/o link road from Barwara chintpurni road to Gps and Panchayat ghar to main road G.P Dhaunta Dehra 0/00 to 6/250. (Portion 0/00 to 3/250)			Estimated Cost:- Earnest Money:- Time Limit:-		87,750.00 3,500.00 Three Months
Sub Head:- Preparation of Detailed project Report					
Sr. No.	Description of Items	Quantity	Rate in		Unit
			In Figures	In Words	Amount
1	2	3	4	5	6
1	Preparation of detailed project report and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the engineer - in - charge complete in all respect. After approval, the same should be submitted in six nos. Set of fair copy alongwith 03 set of drawings (manuscript included). The payment excludes any kind of soil investigations and shall be made as per actual length of road.	3.250	Kms	Rupees Twenty Seven Thousand Only	Per Kms
a	Topography survey by digital Total station / dual frequency DGPS with two second accuracy, showing all offsets such as trees, culverts, bridge, electric poles, hand pump schools, habitants villages etc.				
b	Draw cross section at 15 m (fifteen meter) intervals, 1- section & calculate the quantity of earth work in standard format of auto cad showing all layers of pavement components.				
c	Preparation Of Survey Plan Showing All Provision As Per Hppwd Specification.				
d	Preparation Of Survey Plan Showing All Existing Provisions And Preparation Of Detailed Project Report As Per Hppwd Specification.				
TOTAL					87,750.00
		% Above/below			
		Quoted Amount in Figures			
		Quoted Amount in Words			

13.11.19 quantity checked
9/11/2024 for Rs. 87750/-

Executive Engineer
Dehra Division
UPPWD Dehra

347

(5)

PERCENTAGE BILL OF QUANTITY						
Name of work:- C/O Link road GSSS Sera Bari to Dehra Jawali road via Dhiman Basti, Choudhary Basti, Harizan Basti in km 0/000 to 1/345.				Estimated Cost:- 99352.00		
Sub Head:- C/O CC Pavement at RD 0/781 to 0/801.60				Earnest Money :- 20000.00		
Sr. No.	Description of Item	Qty.	Rate	Unit	Amount	Time Limit :- One Month
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.80	290.00	Cum	1971.00	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.80	4050.00	Cum	27532.00	
3	Providing and laying mechanically mixed and vibrated cement concrete 1:1:1/2:3 (one cement isto one & half sand isto three graded crushed stone aggregate M-25 (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	10.20	6850.00	Cum	69849.00	
Total					99352.00	
		% Above/Below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Bill of quantity checked and
approved for Rs. 99352/- only.

Executive Engineer
H.P.W.D Division
Dehra - 177101

349

PERCENTAGE BILL OF QUANTITY

Name of work:- C/O Link road GSSS Sera Bari to Dehra Jawali road via Dhiman Basti, Choudhary Basti, Harizan Basti in

km 0/000 to 1/345.

Sub Head:- C/O CC Pavement at RD 0/802 to 0/823.30

Name of work:- C/O Link road GSSS Sera Bari to Dehra Jawali road via Dhiman Basti, Choudhary Basti, Harizan Basti in km 0/000 to 1/345.		Estimated Cost:- 99616.00			
Sub Head:- C/O CC Pavement at RD 0/802 to 0/823.30		Earnest Money :- 2000.00			
		Time Limit :- One Month			
Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.82	290.00	Cum	1977.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.82	4050.00	Cum	27605.00
3	Providing and laying mechanically mixed and vibrated cement concrete 1:1:1/2:3 (one cement isto one & half sand isto three graded crushed stone aggregate M-25 (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	10.22	6850.00	Cum	70034.00
Total					99616.00
		% Above/Below			
		Quoted Amount in Figures			
		Quoted Amount in Words			

Bill of quantity checked and approved for Rs. 99616/- only.

Executive Engineer
H.P. W.D. Division
Dehra - 177101

346

PERCENTAGE BILL OF QUANTITY

Name of work:- C/O Link road GSSS Sera Bari to Dehra Jawali road via Dhiman Basti, Choudhary Basti, Harizan Basti in km 0/000 to 1/345.

Sub Head:- C/O CC Pavement at RD 0/850 to 0/871.30

Sr. No.	Description of Item	Qty.	Rate	Unit	Amount
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.82	290.00	Cum	1977.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	6.82	4050.00	Cum	27605.00
3	Providing and laying mechanically mixed and vibrated cement concrete 1:1:1/2:3 (one cement isto one & half sand isto three graded crushed stone aggregate M-25 (forty millimeter) nominal size)as per drawing and MORD technical specification 802, 803, 1202 & 1203 as per drawing complete as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	10.22	6850.00	Cum	70034.00
Total					99616.00
% Above/Below					
Quoted Amount in Figures					
Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99616/- only.

Executive Engineer
H.P.W.D Division
Dehra - 177101

PARCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99314.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of work :- Restoration of Rain Damages on PWD Rest House to JHD Road in Km 0/0 to 1/825 (SH - C/o Cement concrete berms at RD 0/610 to 0/655 30).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.80 Cubic metre	290 00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,972 00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.80 Cubic metre	4050 00	Rupees Four Thousand Fifty Only	Per Cubic metre	27,540 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated Reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix 1:1.5:3 (One cement is to one and half sand is to three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation as per drawing and MORD technical specification clause 802. 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.19 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	69,802.00
	TOTAL					99,314.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Qty quantity checked and approved
for Rs 99,314/-*

*Executive Engineer
Dehra Division,
UPPWD Dehra*

PARCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99314.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- Restoration Of Rain Damages on PWD Rest House to JHD Road in Km 0/0 to 1/825 (SH.-C/o Cement concrete berms at RD.0/660 to 0/705.30).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.80 Cubic metre	290 00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,972 00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.80 Cubic metre	4050 00	Rupees Four Thousand Fifty Only	Per Cubic metre	27 540 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated Reinforced cement concrete Grade-M-25 (M-Twenty five) nominal mix 1:1.5:3 (One cement into one and half sand into three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royalty, Maikhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	10.19 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	69 802.00
	TOTAL					99 314.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity checked and approved for
Rs 99314/-*

Executive Engineer,
Dehra Division,
HPPWD Dehra

384

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 86510.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of CHC Building at Haripur Tehsil Haripur (SH:- P/L Interlocking Paver Block and Kerb Stone)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps, and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	824.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty Malkhana Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	3.12 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	12636.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	16,472.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.21 Square metre	925.00	Rupees Nine Hundred Twenty Five Only	Per Square metre	28,869.00
5	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government.	2.63 Cubic metre	7945.40	Rupees Seven Thousand Nine Hundred Forty Five And Paise Forty Only	Per Cubic metre	20,896.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
6	Construction of embankment with approved materials deposited at site obtained from approved source or roadway cutting and excavation from drains and other structures, graded and completed to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, pumping or bailing out water (surface/sub-soil water) up to any depth or any quantum of water, including spreading the embankment material with motor -Grader in successive layers of 20mm (twenty millimeter) uniform thickness, compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification clause 301.5 and as per the entire, satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government.	27.25 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	6,813.00
	Total					86,510.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for
Rs 86510/-

Executive Engineer
Dehra Division
Hapur Dehra

385

11

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 86510.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of CHC Building at Haripur Tehsil Haripur (SH:- P/L Interlocking Paver Block and Kerb Stone)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Maikhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	824.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty Maikhana, Octroi, Toll tax, Sale tax GST or any other taxes imposed by the Government	3.12 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	12636.00

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	16,472.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.21 Square metre	925.00	Rupees Nine Hundred Twenty Five Only	Per Square metre	28,869.00
5	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line level and curvature, jointed with cement mortar 1:3 (1 cement 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST sales tax or any other taxes imposed by the Government.	2.63 Cubic metre	7945.40	Rupees Seven Thousand Nine Hundred Forty Five And Paise Forty Only	Per Cubic metre	20,896.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
6	Construction of embankment with approved materials deposited at site obtained from approved source or roadway cutting and excavation from drains and other structures, graded and completed to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, pumping or bailing out water (surface/sub-soil water) up to any depth or any quantum of water, including spreading the embankment material with motor -Grader in successive layers of 20mm (twenty millimeter) uniform thickness, compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government.	27.25 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	6,813.00
	Total					86,510.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill quantity checked and approved
for Rs 86,510/-

Executive Engineer
Dehra Division,
UPPWD Dehra

386

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.86510.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of CHC Building at Haripur Tehsil Haripur (SH:- P/L Interlocking Paver Block and Kerb Stone)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstruction necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	824.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm i forty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	3.12 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	12636.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement two sand four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-In-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.84 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	16,472.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	31.21 Square metre	925.00	Rupees Nine Hundred Twenty Five Only	Per Square metre	28,869.00
5	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment) (Precast C.C kerb stone shall be approved by Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government	2.63 Cubic metre	7945.40	Rupees Seven Thousand Nine Hundred Forty Five And Paise Forty Only	Per Cubic metre	20,896.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
6	Construction of embankment with approved materials deposited at site obtained from approved source or roadway cutting and excavation from drains and other structures graded and completed to meet requirement, including setting out true to the lines, grades, width and side slopes in accordance with drawings, pumping or bailing out water (surface/sub-soil water) up to any depth or any quantum of water, including spreading the embankment material with motor -Grader in successive layers of 20mm (twenty millimeter) uniform thickness, compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government.	27.25 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	6,813.00
	Total					86,510.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 86,510/-

Executive Engineer
Dehra Division,
UPPWD Dehra

PERCENTAGE BILL OF QUANTITY

JOB:-

Estimated Cost: Rs. 96261.00

Earnest Money: Rs. 2000.00

Time Limit : One Month.

Name of Work: Road Side amenities under Haripur Sub Division (SH:- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc in Haripur Section)

Sl. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government	31.50 Square metre	55.00	Rupees Fifty Five Only	Per square metre	1733.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government	31.50 Square metre	65.00	Rupees Sixty Five Only	Per square metre	2048.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government	73.00 Square metre	85.00	Rupees Eighty Five Only	Per square metre	6205.00
4	Writing letter in figures of any surface with Black Japan Paint (stops, commas, hyphens and the like not to be measured and paid separately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government	32550.00 Per Cm height per letter	2.50	Rupees Two And Paise Fifty Only	Per centimet re height per letter	81375.00
5	Painting index hands normal size or arrow (up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government	70.00 Figure	70.00	Rupees Seventy Only	Per figure	4900.00
	TOTAL					96261.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked 15/4/2024
for Rs. 96261/- only

Executive Engineer,
HPPWD Dehra,
Division Dehra.

PERCENTAGE BILL OF QUANTITY

JOB:
Estimated Cost: Rs. 96690.00
Earnest Money: Rs. 2000.00
Time Limit : One Month.

Name of Work: Road side amenities under Haripur Sub Division (SH):- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc in Masroor Section)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government.	33.00 Square metre	55.00	Rupees Fifty Five Only	Per square metre	1815.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government.	33.00 Square metre	65.00	Rupees Sixty Five Only	Per square metre	2145.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government.	74.00 Square metre	85.00	Rupees Eighty Five Only	Per square metre	6290.00
4	Writing letter in figures of any surface with Black Japan Paint (stops, commas, hyphens and the like not to be measured and paid separately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government.	32560.00 Per Cm height per letter	2.50	Rupees Two And Paise Fifty Only	Per centimetre height per letter	81400.00
5	Painting index hands normal size or arrows (up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST sale tax, goods service tax, labour cess or other taxes imposed by the Government.	72.00 Figure	70.00	Rupees Seventy Only	Per figure	5040.00
	TOTAL					96690.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & approved by Mr. 96690/-

*Executive Engineer,
HPPWD Dehra,
Division Dehra.*

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99117.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of Upper Pragpur to Karol via Dadari in Km.2/00 to 3/300 (SH:- P/L 60mm thick Interlocking Paver Block 2/660 to 2/681.40)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.05 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	4,655.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	5.42 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	26,001.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax GST or any other taxes imposed by the Government.	2.93 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	15,994.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc., of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax GST or any other taxes imposed by the Government.	55.64 Square metre	925.00	Rupees Nine Hundred Twenty Five Only	Per Square metre	51,457.00
Total						99,117.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Bill of quantity checked and approved
Pr. No. 99/11/71-

Executive Engineer,
Dehra Division,
UPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99117.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of Upper Pragpur to Karol via Dadari in Km.2/00 to 3/300 (SH:- P/L 60mm thick Interlocking Paver Block 2/682 to 2/703.40)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.05 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	4,655.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax GST or any other taxes imposed by the Government	6.42 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	26,001.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax GST or any other taxes imposed by the Government.	2.93 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	16,994.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	55.64 Square metre	925.00	Rupees Nine Hundred Twenty Five Only	Per Square metre	51,457.00
Total						99,117.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Billofquantity checked and approved for
AS 9811 7/1

MD
 Executive Engineer,
 Dehra Division,
 UPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 97791.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- A/R & M/O to PWD Staff tr. Type-III in PWD Colony Dehra Tehsil Dehra District Kangra (H.P) (SH:- Distempereing, Aluminium work etc).

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Distempereing two coat with oil washable distemper of approved brand and manufacture (two or more coats) of required shade on undercoated wall surface to give an even shade complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	611.07 Square metre	96.85	Rupees Ninety Six And Paise Eighty Five Only	Per Square metre	59,182.00
2	Providing and fixing anodised aluminium work for frame of doors, windows, ventilators and glazed partitions of Jindal/Hindalco aluminium with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS:1285 anodised transparent or dyed to required shade according to IS : 1868. (Minimum anodic coating of grade AC-15) fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions. at top, bottom and sides with required PVC/neoprene felt etcetera (Section No. 14081 of Jindal / Hindalco etcetera. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleat angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws all complete as per architectural drawings specifications, design and as per the directions of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	39.90 Killogra mme	630.00	Rupees Six Hundred Thirty Only	Per Killogra mme	25,137.00
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge (Cost of aluminium snap beading shall be paid in basic item). With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) complete as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government	4.76 Square metre	832.95	Rupees Eight Hundred Thirty Two And Paise Ninety Five Only	Per Square metre	3,965.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Painting wood work with Deluxe Surface Multi surface Paint of approved brand and manufacture (two or more coats) applied @ 0.90ltr /10sqm over an under coat of primer applied @0.75ltr/10 sqm to give an even shade complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	78.85 Square metre	94.30	Rupees Ninety Four And Paise Thirty Only	Per Square metre	7,436.00
5	Painting Steel work with Deluxe Surface Multi surface Paint of approved brand and manufacture (two or more coats) applied @ 0.90ltr /10sqm over an under coat of primer applied @0.80ltr/10 sqm to give an even shade complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	23.04 Square metre	89.90	Rupees Eighty Nine And Paise Ninety Only	Per Killogramme	2,071.00
						97,791.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Bill of quantity checked &
approved on 27.7.2021

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,792.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- Balance work of link road Barial Railway Station to Ghanban (Village Ghaban Panchayat Nandpur Barial) Km 0/00 to 1/250 (SH:- Construction of Approach wall for Hume Pipe Culvert on both side from RD 0/840 to 0/844).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	11.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,318.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	15.96 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	64,638.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, in Toe wall and parapets etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	2.83 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	14,716.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	8.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	2,000.00
5	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	5.76 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	4,320.00
6	Construction of embankment with approved materials obtained from borrow pits with all lifts upto transporting to site spreading grading and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 as per MORD technical specification section 300 & 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	43.20 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	10,800.00
	Total					99,792.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bide of quantity checked and approved for Rs. 99,792.00/- only

*Executive Engineer,
Dehra Division,
HPPWD Dehra*

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,882.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Balance work of link road Barial Railway Station to Ghanban (Village Ghaban Panchayat Nandpur Barial) Km 0/00 to 1/250 (SH:- Construction of Approach wall for Hume Pipe Culvert on both side from RD 0/844 to 0/848).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of slumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including storing strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	11.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,318.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	15.96 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	64,638.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, in Toe wall and parapets etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	2.83 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	14,716.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	8.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	2,000.00
5	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	5.28 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	3,960.00
6	Construction of embankment with approved materials obtained from borrow pits with all lifts upto transporting to site spreading grading and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 as per MORD technical specification section 300 & 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	45.00 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	11,250.00
	Total					99,882.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved
for Rs. 99,882.00/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98,438.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Balance work of link road Barial Railway Station to Ghaniban (Village Ghaban Panchayat Nandpur Barial) Km 0/00 to 1/250 (SH:- Construction of Embankment filling in Approach wall for Hume Pipe Culvert from RD 0/850).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved materials obtained from borrow pits with all lifts upto transporting to site spreading grading and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 as per MORD technical specification section 300 & 1500 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	393.75 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	98,438.00
	Total					98,438.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 98,438.00/-only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 96,548.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- One Month.

Name of work :- Balance work of link road Barial Railway Station to Ghanban (Village Ghaban Panchayat Nandpur Barial) Km 0/000 to 1/250 (SH:- Construction of Retaining wall & Embankment filling from RD 1/290 to 1/297).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	8.82 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,558.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	15.08 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	61,074.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, in Toe wall and parapets etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	1.39 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	7,228.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/plain reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government	12.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	3,000.00
5	Construction of embankment with approved materials obtained from borrow pits with all lifts upto transporting to site spreading grading and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 as per MORD technical specification section 300 & 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government	90.75 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	22,688.00
	Total					96,548.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved
for Rs. 96548.00 only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

406

72

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 95200.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- Three months.

Name of work:- C/o Jawalamukhi- Dehra- Jawali- Raja ka Talab road km 4/00 to 39/180. (S.H.-:Providing and fixing informatory board (under road side amenities)

Sr. No.	Description of Item	Qty.		Rate in		Unit	Amount
		No.		Figures	words		
1	Providing and fixing informatory board of size 750x750mm (seven hundred fifty into seven hundred fifty millimetres) nominal size with 3mm thick ACP panel type-II retro reflective sheet with reflective tape of Avery Dennison both side with back support of 25x25x3mm M.S angle as per clause number 800 of MORT&H complete. Front side to have High intensity micro prismatic reflective sheeting conforming to ASTM type-XI computerized designed & cut on computer plotter and back side to be painted with epoxy. This shall be fixed with medium size pipe of size 50x50-height 3 meter painted with first quality enamel paint of alternate colour black and white strips, the post shall be fixed in cement concrete 1:2:4 (one cement : Two sand : Four graded crushed stone aggregate 20mm size 60x60x60cm size complete as per directed by Engineer-Incharge, including carriage of materials within all loads, lifts of materials and other incidentals.	14		6800.00	Rupees Six Thousand Eight Hundred Only	Each	95200.00
	Total=						95200.00
	% Above/below						
	Quoted Amount in Figures						
	Quoted Amount in Words						

Bill of quantity checked and approved for Rs. 95,200.00/- only

Executive Engineer
 Dehra Division
 HP.PWD. Dehra

467

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 95200.00

Earnest Money :- Rs. 2000.00

Time Limit :- Three months.

Name of work:- C/o Jawalamukhi- Dehra- Jawali- Raja ka Talab road km 4/00 to 39/180. (S.H.:-Providing and fixing informatory board (under road side amenities)

Sr. No.	Description of Item	Qty.		Rate in		Unit	Amount
			No.	Figures	words		
1	Providing and fixing informatory board of size 750x750mm (seven hundred fifty into seven hundred fifty millimetres) nominal size with 3mm thick ACP panel type-II retro reflective sheet with reflective tape of Avery Dennison both side with back support of 25x25x3mm M.S angle as per clause number 800 of MORT&H complete. Front side to have High intensity micro prismatic reflective sheeting confirming to ASTM type-XI computerized designed & cut on computer plotter and back side to be painted with epoxy. This shall be fixed with medium size pipe of size 50x50-height 3 meter painted with first quality enamel paint of alternate colour black and white strips, the post shall be fixed in cement concrete 1:2:4 (one cement : Two sand : Four graded crushed stone aggregate 20mm size 60x60x60cm size complete as per directed by Engineer-Incharge, including carriage of materials within all leads, lifts of materials and other incidentals.	14		6800.00	Rupees Six Thousand Eight Hundred Only	Each	95200.00
	Total=						95200.00
	% Above/below						
	Quoted Amount in Figures						
	Quoted Amount in Words						

*Bill of quantity checked and approved
for Rs 95200.00/- only*

Executive Engineer
Dehra Division
HP.PWD. Dehra

904

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98715.00
Earnest Money :- Rs. 2000.00
Time Limit :- Three months.

Name of work:- C/o Jawalamukhi- Dehhra- Jawali- Raja ka Talab road km 4/00 to 39/180. (S.H):- Construction of U-Shape drain at Rd 12/200 to 12/243)

Sr. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figures	words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	27.09	290.00	Rupees Two Hundred Ninety Only	Per Cubic Meter	7856.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size) as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.34	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Meter	80883.00
	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C M 20 nominal mix 1:2:4 in Dirt wall and bed block as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.72	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	9976.00
	Total=					98715.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 98,715.00/- only

Executive Engineer
Dehra Division
HP.PWD. Dehra

403

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98715.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- Three months.

Name of work:- C/o Jawalamukhi-Dehbra- Jawali- Raja ka Talab road km 4/00 to 39/180. (S.H.:- Construction of U-Shape drain at Rd 12/243 to 12/296)

Sr. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figures	words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	27.09	290.00	Rupees Two Hundred Ninety Only	Per Cubic Meter	7856.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size/as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	16.34	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Meter	80883.00
	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C M 20 nominal mix 1:2:4 in Dirt wall and bed block as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.72	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	9976.00
	Total=					98715.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for
 Rs 98,715.00/- only

Executive Engineer
 Dehra Division
 HP.PWD. Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,280.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Months.

Name of work:- Landsacping CHC Haripur Tehsil Haripur Distt. Kangra (H.P) (SH:- Providing Land Sacppping work in CHC Haripur).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in dumped stones of malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable material with in all leads and lifts, disposed material to be neatly dressed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	67.50 Cubic metre	241.50	Rupees Two Hundred Forty One And Paise Fifty Only	Per Cubic metre	16,301.00
2	Trenching in ordinary soil upto a depth of 60cm including removal and stacking of serviceable materials and then disposing off by spreading and neatly levelling with in all leads and lifts and making up the trenched areas to proper levels by filling with earth or earth mixed with sludge or/and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	171.50 Cubic metre	37.10	Rupees Thirty Seven And Paise Ten Only	Per Cubic metre	6,363.00
3	Supplying and stacking of good earth at site including royalty and carriage within all leads and lifts (Earth measured in stacks will be reduced by 20% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	60.00 Cubic metre	308.35	Rupees Three Hundred Eight And Paise Thirty Five Only	Per Cubic metre	18,501.00
4	Rough dressing the trenched ground including breaking clods and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	0.72	Rupees And Paise Seventy Two Only	Per Square metre	108.00
5	Fine dressing the ground and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	1.75	Rupees One And Paise Seventy Five Only	Per Square metre	263.00
6	Supply and stacking at site dung manure from approved sources (duly screened through specified sieve) including all carriage on head load and mechanical transport (manure measured in stacks will be reduced by 8% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic metre	5,740.00
7	Spreading of sludge, dung manure or/and good earth in required thickness (cost of sludge/dung manure or/and good earth to be paid seperately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	25.15	Rupees Twenty Five And Paise Fifteen Only	Per Cubic metre	444.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Mixing earth and sludge or manure in proportion specified or directed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	32.00 Cubic metre	17.25	Rupees Seventeen And Paise Twenty Five Only	Per Cubic metre	552.00
9	Providing, laying and proper rolling of Doob/ Bermuda grass/korean (Variety-Selection I) turf which is compact, evenly grown and free from weeds alongwith maintenance for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the earth shall be paid separately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	196.05 Square metre	260.00	Rupees Two Hundred Sixty Only	Per Square metre	50,973.00
10	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid seperately. In rows 7.5 cm apart in either direction and including entire carriage of material in all leads, lifts and cost of all other incidentals.	5.50 Square metre	6.34	Rupees Six And Paise Thirty Four Only	Per Square metre	35.00
	Total					99,280.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,280.00/- only.

Executive Engineer,
Dehra Division,
UPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,280.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Months.

Name of work:- Landsacping CHC Haripur Tehsil Haripur Distt. Kangra (H.P) (SH):- Providing Land Sacppng work in CHC Haripur).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in dumped stones of malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable material with in all leads and lifts, disposed material to be neatly dressed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	67.50 Cubic metre	241.50	Rupees Two Hundred Forty One And Paise Fifty Only	Per Cubic metre	16,301.00
2	Trenching in ordinary soil upto a depth of 60cm including removal and stacking of serviceable materials and then disposing off by spreading and neatly levelling with in all leads and lifts and making up the trenched areas to proper levels by filling with earth or earth mixed with sludge or/and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	171.50 Cubic metre	37.10	Rupees Thirty Seven And Paise Ten Only	Per Cubic metre	6,363.00
3	Supplying and stacking of good earth at site including royalty and carriage within all leads and lifts (Earth measured in stacks will be reduced by 20% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	60.00 Cubic metre	308.35	Rupees Three Hundred Eight And Paise Thirty Five Only	Per Cubic metre	18,501.00
4	Rough dressing the trenched ground including breaking clods and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	0.72	Rupees And Paise Seventy Two Only	Per Square metre	108.00
5	Fine dressing the ground and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	1.75	Rupees One And Paise Seventy Five Only	Per Square metre	263.00
6	Supply and stacking at site dung manure from approved sources (duly screened through specified sieve) including all carriage on head load and mechanical transport (manure measured in stacks will be reduced by 8% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic metre	5,740.00
7	Spreading of sludge, dung manure or/and good earth in required thickness (cost of sludge/dung manure or/and good earth to be paid seperately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	25.15	Rupees Twenty Five And Paise Fifteen Only	Per Cubic metre	444.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Mixing earth and sludge or manure in proportion specified or directed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	32.00 Cubic metre	17.25	Rupees Seventeen And Paise Twenty Five Only	Per Cubic metre	552.00
9	Providing, laying and proper rolling of Doob/ Bermuda grass/korean (Variety-Selection I) turf which is compact, evenly grown and free from weeds alongwith maintenance for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the earth shall be paid separately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	196.05 Square metre	260.00	Rupees Two Hundred Sixty Only	Per Square metre	50,973.00
10	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid separately. In rows 7.5 cm apart in either direction and including entire carriage of material in all leads, lifts and cost of all other incidentals.	5.50 Square metre	6.34	Rupees Six And Paise Thirty Four Only	Per Square metre	35.00
	Total					99,280.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Beltd 742424, 04/06/16
99280.00*

Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,280.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Months.

Name of work:- Landsacpping PWD Residential Colony Haripur Tehsil Haripur Distt. Kangra (H.P) (SH):- Providing Land Sacpping work in PWD Residential Colony Haripur).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in dumped stones of malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable material with in all leads and lifts, disposed material to be neatly dressed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	67.50 Cubic metre	241.50	Rupees Two Hundred Forty One And Paise Fifty Only	Per Cubic metre	16,301.00
2	Trenching in ordinary soil upto a depth of 60cm including removal and stacking of serviceable materials and then disposing off by spreading and neatly levelling with in all leads and lifts and making up the trenched areas to proper levels by filling with earth or earth mixed with sludge or/and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	171.50 Cubic metre	37.10	Rupees Thirty Seven And Paise Ten Only	Per Cubic metre	6,363.00
3	Supplying and stacking of good earth at site including royalty and carriage within all leads and lifts (Earth measured in stacks will be reduced by 20% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	60.00 Cubic metre	308.35	Rupees Three Hundred Eight And Paise Thirty Five Only	Per Cubic metre	18,501.00
4	Rough dressing the trenched ground including breaking clods and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	0.72	Rupees And Paise Seventy Two Only	Per Square metre	108.00
5	Fine dressing the ground and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	1.75	Rupees One And Paise Seventy Five Only	Per Square metre	263.00
6	Supply and stacking at site dung manure from approved sources (duly screened through specified sieve) including all carriage on head load and mechanical transport (manure measured in stacks will be reduced by 8% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic metre	5,740.00
7	Spreading of sludge, dung manure or/and good earth in required thickness (cost of sludge/dung manure or/and good earth to be paid seperately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	25.15	Rupees Twenty Five And Paise Fifteen Only	Per Cubic metre	444.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Mixing earth and sludge or manure in proportion specified or directed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	32.00 Cubic metre	17.25	Rupees Seventeen And Paise Twenty Five Only	Per Cubic metre	552.00
9	Providing, laying and proper rolling of Doob/ Bermuda grass/Korean (Variety-Selection I) turf which is compact, evenly grown and free from weeds alongwith maintenance for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the earth shall be paid separately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	196.05 Square metre	260.00	Rupees Two Hundred Sixty Only	Per Square metre	50,973.00
10	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid separately. In rows 7.5 cm apart in either direction and including entire carriage of material in all leads, lifts and cost of all other incidentals.	5.50 Square metre	6.34	Rupees Six And Paise Thirty Four Only	Per Square metre	35.00
	Total					99,280.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

By 9/12/15 to 99280/-

Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,280.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Months.

Name of work:- Landsacpping PWD Residential Colony Haripur Tehsil Haripur Distt. Kangra (H.P) (SH):- Providing Land Sapping work in PWD Residential Colony Haripur).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in dumped stones of malba including stacking of serviceable and unserviceable material separately and disposal of unserviceable material with in all leads and lifts, disposed material to be neatly dressed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	67.50 Cubic metre	241.50	Rupees Two Hundred Forty One And Paise Fifty Only	Per Cubic metre	16,301.00
2	Trenching in ordinary soil upto a depth of 60cm including removal and stacking of serviceable materials and then disposing off by spreading and neatly levelling with in all leads and lifts and making up the trenched areas to proper levels by filling with earth or earth mixed with sludge or/and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	171.50 Cubic metre	37.10	Rupees Thirty Seven And Paise Ten Only	Per Cubic metre	6,363.00
3	Supplying and stacking of good earth at site including royalty and carriage within all leads and lifts (Earth measured in stacks will be reduced by 20% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	60.00 Cubic metre	308.35	Rupees Three Hundred Eight And Paise Thirty Five Only	Per Cubic metre	18,501.00
4	Rough dressing the trenched ground including breaking clods and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	0.72	Rupees And Paise Seventy Two Only	Per Square metre	108.00
5	Fine dressing the ground and including entire carriage of material in all leads, lifts and cost of all other incidentals.	150.00 Square metre	1.75	Rupees One And Paise Seventy Five Only	Per Square metre	263.00
6	Supply and stacking at site dung manure from approved sources (duly screened through specified sieve) including all carriage on head load and mechanical transport (manure measured in stacks will be reduced by 8% for payment) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic metre	5,740.00
7	Spreading of sludge, dung manure or/and good earth in required thickness (cost of sludge/dung manure or/and good earth to be paid separately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	17.66 Cubic metre	25.15	Rupees Twenty Five And Paise Fifteen Only	Per Cubic metre	444.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Mixing earth and sludge or manure in proportion specified or directed and including entire carriage of material in all leads, lifts and cost of all other incidentals.	32.00 Cubic metre	17.25	Rupees Seventeen And Paise Twenty Five Only	Per Cubic metre	552.00
9	Providing, laying and proper rolling of Doob/ Bermuda grass/Korean (Variety-Selection 1) turf which is compact, evenly grown and free from weeds alongwith maintenance for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the earth shall be paid separately) and including entire carriage of material in all leads, lifts and cost of all other incidentals.	196.05 Square metre	260.00	Rupees Two Hundred Sixty Only	Per Square metre	50,973.00
10	Grassings with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass form a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid seperately. In rows 7.5 cm apart in either direction and including entire carriage of material in all leads, lifts and cost of all other incidentals.	5.50 Square metre	6.34	Rupees Six And Paise Thirty Four Only	Per Square metre	35.00
	Total					99,280.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Billed by 94000449212415
9/12/2017/12/2/2017

Executive Engineer,
Dehra Division,
CHPPWD Dehra.

DNIT

Estimate Cost :- Rs. 99077.00

Earnest Money :-Rs.2000.00

Time Limit :- One Month.

Name of work:- Repair & Maintenance of Type-II Qtr in PWD Colony at Dehra Tehsil Dehra District Kangra (H.P.)					
Sub Head :-C/O R/Wall , P/F ACP Sheet, Steel Work etc					
Sr. No.	Item of work	Qty.	Rate	Unit	Amount
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and lift dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per direction of Engineer in Charge.	3.51	290.00	Cum	1018.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 Sand : 10 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin: Foundation and plinth, as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	15.66	3750.00	Cum	58725.00
3	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint. as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	174.47	94.00	Kg	16400.00
4	Providing and fixing 3 mm thick ACP (Alluminium Comosite profile) including fixing with acrews and nails complete (frame work will be measured separately as per HPPWD specification and as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	15.33	832.00	Sqm	12755.00
5	Providing wood work in frames of doors, windows, clere story windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	0.08	95763.05	Cum	7722.00

6	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including all leads and lifts as per the direction of Engineer-in Charge. as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	3.78	650.00	Sqm	2457.00
	Total				99077.00
	% Above/Below				
	Quoted Amount in Figures				
	Quoted Amount in Words				

Bill of quantity checked and approved for Rs 99077.05/- only

Executive Engineer
H.P.W.D Division
Dehra - 177101

DNIT

Estimate Cost :- Rs. 99656.00

Earnest Money :-Rs.2000.00

Time Limit :- One Month.

Name of work:- Repair & Maintenance of Type-II Qtr in PWD Colony at Dehra Tehsil Dehra District Kangra (H.P.)					
Sub Head :- P/L Wall Tiles, P/F ply, Wood Work etc					
Sr. No.	Item of work	Qty.	Rate	Unit	Amount
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and lift dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per direction of Engineer in Charge.	0.54	290.00	Cum	157.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 Sand :10 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form workin: Foundation and plinth. as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana. Octroi, toll tax, sale tax or any taxes imposed by the Government	3.24	3750.00	Cum	12150.00
3	Providing wood work in frames of doors, windows, clere story windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana. Octroi, toll tax, sale tax or any taxes imposed by the Government	0.1540	95763.05	Cum	14748.00
4	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including all leads and lifts as per the direction of Engineer-in Charge. as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana. Octroi, toll tax, sale tax or any taxes imposed by the Government	8.40	650.00	Sqm	5460.00

5	Providing and laying 1200x200 mm (six hundred into Three hundred millimetre) ceramic wall tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of Orient bell/ Kazaria/ AGL/ RAK /Johnson & Johnson approved make, in all colours and shades,, in skirting, riser of steps, dado, with cement bases high polymer modified quick set tile adhesive (water based) conforming to IS:15477 in average 6mm (six millimetre) thick including grouting the joints with white cement and matching pigments etc., complete in pattern finish approved by the Engineer-in-Charge upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	32.64	1600.00	52224.00
6	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	2.10	3433.70	7211.00
7	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 35 mm thick shutters as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	2.10	3669.30	7706.00
Total				99656.00
	% Above/Below			
	Quoted Amount in Figures			
	Quoted Amount in Words			

Bill of quantity checked and approved for Rs. 99,656.00/- only

Executive Engineer
H.P.P.W.D Division
Dehra-177101

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99208.00

Earnest Money :-Rs. 2000.00

Time Limit :- One Month,

Name of work:- Construction of C/o Road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under G.P. Sherlohara (SH):- C/o

R/ward 1/350 10/355

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks, (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.07 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	2 920.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement to five sand to ten graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.41 Cubic meter	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic meter	91 538.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical to twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete including carriage of materials with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,750.00
	Total					99,208.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

all responsibility checked and approved for
Rs 99208/-

[Signature]
 Executive Engineer,
 Dehra Division,
 HPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99208.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Construction of C/o Road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under G.P. Sherlophara (SH:- C/o *Rajul 1/355-10/60*)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited), complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.07 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	2,920.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.41 Cubic meter	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic meter	91,538.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709.1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,750.00
	Total					99,208.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved by
 Rs 99,208/- only

Executive Engineer
 Dehra Division,
 UP PWD Dehra