

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-

6067-74

Dated:- 5/02/2025

To,

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in


Subject:

Publication of Tender Notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tenders on the form 6&8 are hereby invited by the Executive Engineer Fatehpur Division HPPWD., Fatehpur on behalf of the Governor of HP for the below noted works from eligible Contractors/firms registered in HPPWD in appropriate class as per revised enlistment rules. So as to reach in this office on or before 18-02-2025 up to 12:00 Noon and the same shall be opened on the same day at 12:30 PM in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 17.02.2025 upto 4:00 PM. The application for issued of tender form shall be received for 15.02-2025 up to 4:30.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/ bank in HP duly pledged in the favour of undersigned.

Conditional tenders telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Fatehpur Division HP PWD at Fatehpur reserves the right to accept or reject the tenders. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	Construction of Retaining wall near the house of Gian Chand in village Patti Under MLALAD Deposit work (SH:-Construction of retaining wall at R.D. 0/00 to 0/011)	Rs.97176/-	Rs.2000/-	One Month	350 -	Class D&C
2	Construction of Retaining wall near the house of Prahlad Singh village Kothi Under MLALAD Deposit work (SH:-Construction of retaining wall at R.D. 0/00 to 0/015.50)	Rs.95592/-	Rs.2000/-	One Month	350/-	Class D&C
3	Construction of Retaining wall near the field of Shanta Devi W/O Pawan Kumar in village Pandora Under MLALAD Deposit work (SH:-Construction of retaining wall at R.D. 0/00 to 0/010.50)	Rs.72650/-	Rs.1500/-	One Month	350/-	Class D&C
4	Construction of Path from Paploch Mohal road to Lalit Madhusudun etc. house in village Samkar (Under MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement)	Rs.97403/-	Rs.2000/-	One Month	350/-	Class D&C
5	Construction of path from slab to Sikander Singh house Ward No. 5 Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement at R.D.0/0 to 0/045).	Rs.97647/-	Rs.2000/-	One Month	350 -	Class D&C
6	Construction of Retaining wall near the house of Anil Kumar in Ward No.4 Under (MLALAD) Deposit Work (SH:-Construction of Retaining wall at R.D.0/0 to 0/025).	Rs.97320/-	Rs.2000/-	One Month	350/-	Class D&C
7	Construction of Mahila Bath Room (Snan Ghar) in village Kodu Bela (Under SDP) Deposit work.	Rs.98378/-	Rs.2000/-	One Month	350/-	Class D&C
8	Construction of Retaining wall near house of Sham Singh in village Kummi Under SDF Deposit Work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/008.50)	Rs.72841/-	Rs.1500/-	One Month	350/-	Class D &C
9	Construction of culvert near school Luthial, Kasial via Khadalhar under Deposit work (SH:- Balance work for construction of approaches for culvert in left side).	Rs.96511/-	Rs.2000/-	One Month	350 -	Class D&C
10	A/R & M/O to various roads under Rehan Sub Division (SH:- Painting , Lettering on road sign Boards and Kms stone etc.) (Under Raja ka Talab Section)	Rs.99461/-	Rs.2000/-	Two Month	350/-	Class D&C

11	A/R & M/O to various roads under Rehan Sub Division (SH:- providing and fixing informatory sign board) (Under Raja ka Talab Section)	Rs.98300/-	Rs.2000/-	Two Month	350/-	Class D&C
12	Construction of Malhari Kothi Bhartial road Km. 0/0 to 4/200 (SH:- Providing and Laying 90mm to 45mm hard broken / crushed stone soling and 63mm to 45mm size hard broken / crushed wearing (G-II) in Km. 3/180 to 3/257.50).	Rs.87261/-	Rs.1800/-	One Month	350/-	Class D&C
13	Construction of Malhari Kothi Bhartial road Km. 0/0 to 4/200 (SH:- Providing and Laying 90mm to 45mm hard broken / crushed stone soling and 63mm to 45mm size hard broken / crushed wearing (G-II) in Km. 3/257.50 to 3/335).	Rs.82238/-	Rs.1700/-	One Month	350/-	Class D&C
14	Construction of Retaining wall near the house of Som nath in village Duhag (Under SDRF) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/010.50).	Rs.97,092/-	Rs.2000/-	One Month	350/-	Class D&C
15	Construction of Retaining wall near the house of Vijay Kumar S/o late Gorkhu Ram Ward No. 4 in GP Fatehpur (Under MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/009.70).	Rs.96,468	Rs.2000/-	One Month	350/-	Class D&C
16	A/R & M/O to various roads under Rehan Sub Division (Raja ka Talab Section) (SH:- Construction of Unlined surface drains and maintenance of earthen shoulders)	Rs.98,710/-	Rs.2000/-	One Month	350/-	Class D&C
17	A/R & M/O to various roads under Dhameta Sub Division (Section Rey) (SH:-Construction of Unlined surface drains and maintenance of earthen shoulders).	Rs.98,710/-	Rs.2000/-	One Month	350/-	Class D&C
18	A/R & M/O to various roads under Rehan Sub Division (Raja ka Talab Section)(SH:- Construction of Unlined surface drains and maintenance of earthen shoulders)	Rs.98,710/-	Rs.2000/-	One Month	350/-	Class D&C
19	A/R & M/O to various roads under Dhameta Sub Division (Section Sathana) (SH:- Construction of Unlined surface drains and maintenance of earthen shoulders).	Rs.98,710/-	Rs.2000/-	One Month	350/-	Class D&C
20	Preparation of Digital Cantour plan of W.R.S Govt. PG Collage Dehri for Auditorium, Multipurpose Hall & Administrative Block at Dehri Kangra	Rs.64,800/-	1500/-	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-


1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders from will be issued to the contractor/ firms which may be noted.
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division, HPPWD,
Fatehpur

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Gian Chand in village Patti Under MLALAD Deposit work (SH:- Construction of retaining wall at R.D. 0/00 to 0/011)				Estimated cost:- Rs.97176/- only		Earnest Money : Rs.2000/- only		Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.88 Cubic meter.	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	2059.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.73 cubic meter	3580.10	Rupees Three Thousand Five Hundred Eighty And Paise Ten Only	Per cubic meter	92116.00			
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre, square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00 Numbers	300.10	Rupees Three Hundred And Paise Ten Only	Each	3001.00			
					Total:-	97176.00			
	Amount quoted by the contractor in % Above/Below								


 Engineer
 Patti Division HPPWD
 Fatehgarh Sahib, Kangra (H.P.)



SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Prahlad Singh village Kothi Under MLALAD Deposit work (SH:- Construction of retaining wall at R.D. 0/00 to 0/015.50)				Estimated cost:- Rs.95592/- only Earnest Money : Rs.2000/- only Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	7.44 Cubic meter.	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	2605.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.80 cubic meter	3580.10	Rupees Three Thousand Five Hundred Eighty And Paise Ten Only	Per cubic meter	88786.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00 Numbers	300.10	Rupees Three Hundred And Paise Ten Only	Each	4201.00
					Total:-	95592.00
	Amount quoted by the contractor in % Above/Below					


Engineer
Fatigue Division HPPWD
Fatehpur Distt. Kangra (H.P.)

3

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the field of Shanta Devi W/O Pawan Kumar in village Pandora Under MLALAD Estimated cost:- Rs.72650/- only
 Deposit work (SH):- Construction of retaining wall at R.D. 0/00 to 0/010.50) Earnest Money : Rs.1500/- only
 Time limit:- One month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.67 Cubic meter.	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	1985.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.90 cubic meter	3580.10	Rupees Three Thousand Five Hundred Eighty And Paise Ten Only	Per cubic meter	67664.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00 Numbers	300.10	Rupees Three Hundred And Paise Ten Only	Each	3001.00
					Total:-	72650.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
 Fatuapur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Path from Paploch Mohal road to Lalit Madhusudun etc. house in village Samkar (Under MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement)

Estimated cost:- Rs.97403/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters)size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	7.43 Cubic meter.	16%6.10	Rupees One Thousand Six Hundred Ninety Six And Paise Ten Only	Per cubic meter	12602.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.85 Cubic meter.	5350.20	Rupees Five Thousand Three Hundred Fifty And Paise Twenty Only	Per cubic meter	84801.00
					Total:-	97403.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

5

SCHEDULE OF QUANTITY

Name of work:- Construction of path from slab to Sikander Singh house Ward No.5 Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement at R.D.0/0 to 0/045).						
Estimated cost:- Rs.97647/- only						
Earnest Money : Rs.2000/- only						
Time limit:- One month						
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.25 Cubic meter.	5350.50	Rupees Five Thousand Three Hundred Fifty And Paise Fifty Only	Per cubic meter	97647.00
					Total:-	97647.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Rajpur Division HPPWI
Rajpur Distt. Kangra (H)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Anil Kumar in Ward No.4 Under (MLALAD) Deposit Work (SH):- Construction of Retaining wall at R.D.0/0 to 0/025).

Estimated cost:- Rs.97320/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.25 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3140.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.00 cubic meter	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic meter	89700.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.00 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	4480.00
					Total:-	97320.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
Farapur Division HPPWD

4

A SCHEDULE OF QUANTITY									
Name of work:- Construction of Mahila Bath Room (Snan Ghar) in village Kodu Bela (Under SDP) Deposit work.									
Estimated cost:- Rs.98378/- only									
Earnest money Rs.2000/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five meter) in width or 10 sqm (ten square meter) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (fifty meter) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.30 cubic meter	339.40	Rupees Three Hundred Thirty Nine And Paise Forty Only	Per cubic meter	781.00			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level cement concrete 1:5:10 (one cement isto five coarse sand isto ten graded stone aggregate) 40mm (forty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.80 cubic meter	3550.60	Rupees Three Thousand Five Hundred Fifty And Paise Sixty Only	Per cubic meter	9942.00			
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (one cement isto six coarse sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.50 cubic meter	6560.20	Rupees Six Thousand Five Hundred Sixty And Paise Twenty Only	Per cubic meter	29521.00			
4	Centering and shuttering including strutting, propping etc. and removal of form work for : Suspended floors, roofs, landings, balconies and access platform including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.62 square meter	243.65	Rupees Two Hundred Forty Three And Paise Sixty Five Only	Per square meter	1857.00			
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering and shuttering, finishing and reinforcement - All work upto plinth level cement concrete 1:2:4 (one cement isto two coarse sand isto four graded stone aggregate) 20mm (twenty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.19 cubic meter	5650.40	Rupees Five Thousand Six Hundred Fifty And Paise Forty Only	Per cubic meter	6724.00			
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild Steel and Medium Tensile steel bars including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	107.43 kilogram	90.00	Rupees Ninety Only	Per kilogram	9669.00			
7	15mm (fifteen millimeter) cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement isto six fine sand) Both side including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	45.21 square meter	165.00	Rupees One Hundred Sixty Five Only	Per square meter	7460.00			
8	6mm six millimeter) cement plaster of mix 1:3 (one cement isto three fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.54 square meter	150.00	Rupees One Hundred Fifty Only	Per square meter	1131.00			

9	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimeter) (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimeter) thick cement mortar 1:4 (one Cement into four Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.08 square meter	1120.40	Rupees One Thousand One Hundred Twenty And Paise Forty Only	Per square meter	4571.00
10	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge For doors windows and ventilators and fixing hinges/pivots and glazed partitions frames For shutters of doors windows & ventilators including providing and fixing gaskets as required and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately) Per kg. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	16.72 kilogram me	330.00	Rupees Three Hundred Thirty Only	Per kilogram me	5518.00
11	Providing and fixing glazing aluminium door, window, ventilators and partitions PVC/neoprens gasket etc. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.15 square meter	1210.00	Rupees One Thousand Two Hundred Ten Only	Per square meter	3812.00
12	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete fixed to steel windows by welding including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.56 kilogram me	105.00	Rupees One Hundred Five Only	Per kilogram me	794.00
13	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm) (three decimal eight four kilogram/ten squaremetre) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	55.21 square meter	61.21	Rupees Sixty One And Paise Twenty One Only	Per square meter	3379.00
14	Providing and fixing wash basin with C.I. brackets, 15mm (fifteen millimeter) C.P. brass pillar taps, 32 mm (thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 630x450mm (six hundred thirty into four hundred fifty millimetre) with a pair of 15mm (fifteen millimeter) C.P. brass pillar taps including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	2980.40	Rupees Two Thousand Nine Hundred Eighty And Paise Forty Only	Each	2980.00

15	Providing and fixing white vitreous china pedestal wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	1960.55	Rupees One Thousand Nine Hundred Sixty And Paise Fifty Five Only	Each	1961.00
16	Providing and fixing 32mm (thirty two millimeter) dia P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete Flexible pipe including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	101.10	Rupees One Hundred One And Paise Ten Only	Each	101.00
17	Providing and fixing PTMT soap dish holder having length of 138mm (one hundred thirty eight millimeter) breadth 102mm (one hundred two millimeter) height of 75mm (seventy five millimeter) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six gram) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.00 Number	130.50	Rupees One Hundred Thirty And Paise Fifty Only	Each	131.00
18	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450mm (four hundred fifty millimeter) long towel rail with total length of 495 mm (four hundred ninety five millimeter), width 78 mm (seventy eight millimeter) and effective height of 88 mm (eight eight millimeter), weighing not less than 170 gms (one hundred seventy gram) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2 Numbers	315.15	Rupees Three Hundred Fifteen And Paise Fifteen Only	Each	630.00
19	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931 : 15mm (fifteen millimeter) nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2 Numbers	418.95	Rupees Four Hundred Eighteen And Paise Ninety Five Only	Each	838.00
20	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour 15 mm (fifteen millimeter) nominal bore with 45 cm (forty five millimeter) length including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1 Numbers	112.45	Rupees One Hundred Twelve And Paise Forty Five Only	Each	112.00
21	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	500 Litre	8.00	Rupees Eight Only	Per litre	4000.00
22	Providing and fixing G.I. pipes complete with G.I. fittings and clamps including cutting and making good the walls etc. Internal work Exposed on wall 15mm (fifteen millimeter) dia nominal bore including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	12.00 Running meter	205.50	Rupees Two Hundred Five And Paise Fifty Only	Per Running meter	2466.00
					Total:-	98378.00

Amount quoted by the contractor in % Above/Below

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near house of Sham Singh in village Kummi Under SDF Deposit Work
(SH:- Construction of Retaining wall at R.D. 0/00 to 0/008.50)

Estimated cost:- Rs.72841/- only
Earnest Money : Rs.1500/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets ectetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	4.76 Cubic meter.	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	1666.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	19.21 cubic meter	3580.10	Rupees Three Thousand Five Hundred Eighty And Paise Ten Only	Per cubic meter	68774.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00 Numbers	300.10	Rupees Three Hundred And Paise Ten Only	Each	2401.00
					Total:-	72841.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Munir Division HPPWD
Rampur Distt. Kangra (H.P.)

9

SCHEDULE OF QUANTITY

Name of work:-Construction of culvert near School on Luthial, Kasial via Khadalahar Under Deposit work (SH:- Balance work for construction of approaches for culvert in left side)

Estimated cost:- Rs.96511/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.08 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3422.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	22.20 cubic meter	3901.30	Rupees Three Thousand Nine Hundred One And Paise Thirty Only	Per cubic meter	86609.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00 Numbers	315.00	Rupees Three Hundred Fifteen Only	Each	2520.00
4	Construction of embankment and earthen shoulders with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimeters) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical satisfaction Clause 301.5 and as per direction/specification of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	14.40 Cubic meter.	275.00	Rupees Two Hundred Seventy Five Only	Per cubic meter	3960.00
					Total:-	96511.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads under Rehan Sub Division (SH:- Painting, Lettering on road sign Boards and Kms stone etc.) (Under Raja ka Talab Section)					Estimated Cost:- Rs.	99461.00
					Earnest Money:- Rs.	4800.00
					Time limit:- Two Months	2000/-
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In words	In figures		
1	Painting steel work with Deluxe Multi Surface paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sam (Zero point ninety litre/ten square meter) over an under coat of primer @ 0.80 ltr./10 sam (Zero point eighty litre/ ten square meter) of approved brand and manufacture as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	45.00	99.20		Per square metre	4464.00
2	Painting one coat (excluding priming coat) on previously painted concrete/ masonry/ plastered surface with enamel paint of approved brands and manufacturing for use on floor to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter and sand papering as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	40.00	95.30		Per square metre	3812.00
3	Writing letters of figures on any surface with black japan paint (Stop commas, hyphens and like not to be measured and paid separately)					
	(a) Indian Letter/Figure.	15900.00	3.20		Per letter Per centi metre Height	50880.00
	(b) Block letter/Figure.	11600.00	3.30		Per letter Per centi metre Height	38280.00
4	Painting index hand normal size or arrows (up to 40cm) long on any surfaces either black japan paint including carriage of material with in all leads & lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	30.00	67.50		Per Figure	2025.00
					Total:-	99461.00
	Amount quoted by the contractor in % Above/Below					


 Engineer
 Panchpur Division HPPWD
 Panchpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads under Rehan Sub Division (SH:- Providing and fixing informatory sign board) (Under Raja Ka Talab Section)				Estimated cost:- Rs.98300/- only Earnest Money : Rs.2000/- only Time limit:- Two months		
Sr. No	Description of items	Quantity	In words	Rate		Amount
				In figures	Unit	
1	Providing and fixing of typical NABARD informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm (one point six millimeter) thick, top and middle plate duly welded with MS flat iron 25mm x 5m (twenty five millimeter into five millimeter) size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm (twenty five millimeter into twenty five millimeter into five millimeter). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm (seventy five millimeter into seventy five millimeter) of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 (M-fifteen) grade blocks of 450mm x 450mm x 600mm (four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter), 600mm (six hundred millimeter) below ground level. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing and M.O.R.D. technical specification and as per the direction of entire satisfactions of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00 Numbers	16000.00	Rupees Sixteen Thousand Only	Each	32000.00
2	Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm (two millimeter) thick with area exceeding 0.9 sqm supported on a mild steel single angle iron post 75x75x6mm (seventy five into seventy five into six millimeter) firmly to the ground by means of properly designed foundation with M-15 grade cement concrete 450mm x 450mm x 600mm (four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter), 600mm (six hundred millimeter) below ground level as per approved drawing and Technical Specification Clause 1701 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00 Numbers	4200.00	Rupees Four Thousand Two Hundred Only	Each	42000.00
3	Providing and fixing of semi reflective cautionary, mandatory and informatory sign board as per IRC:67 made of 1.5 mm thick MS Sheet duly stove white colour in front and gray colour on back with red reflective border of 65 mm (sixty five millimeter) width and required letters and figures with reflective tape engineering grade as per Clause 1701.3.9 of MORD for Rural Roads of required shade and colour supported and welded on 47mm x 47 mm x 12 (forty seven millimeter into forty seven millimeter into twelve) SWG sheet tube firmly fixed to the ground by mean of properly designed foundation with M-15 grade cement concrete 450mm x 450mm x 600mm (four hundred fifty millimeter into four hundred fifty millimeter into six hundred millimeter), 600mm (six hundred millimeter) below ground level as per approved drawing and Technical Specification Clause 1701.2.2 600mm (six hundred millimeter) circular as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.00 Numbers	2700.00	Rupees Two Thousand Seven Hundred Only	Each	24300.00
					Total:-	98300.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

12

SCHEDULE OF QUANTITY

Name of work:-Construction of Malhari Kothi Bhartial road Km. 0/0 to 4/200 (SH:- Providing and laying 90mm to 45mm size hard broken/crushed soling and 63mm to 45mm size hard broken/crushed wearing (G-II) in km. 3/180 to 3/257.50)				Estimated cost:- Rs.87261/- only	
				Earnest Money : Rs.1800/- only	
				Time limit:- One month	
Sr.No	Description of items	Quantity	Rate		Amount
			In words	In figures	
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.30 cum (zero point thirty cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -I 90mm to 45mm (Ninety millimeters to forty five millimeters)size, 100mm (One hundred millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.97 Cubic meter.	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	47803.00
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters)size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	22.45 Cubic meter.	1757.60	Rupees One Thousand Seven Hundred Fifty Seven And Paise Sixty Only	39458.00
				Total:-	87261.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

(B)

SCHEDULE OF QUANTITY

Name of work:-Construction of Malhari Kothi Bhartial road Km. 0/0 to 4/200 (SH:- Providing and laying 90mm to 45mm size hard broken/crushed soling and 63mm to 45mm size hard broken/crushed wearing (G-II) in km. 3/257.50 to 3/335)							Estimated cost:- Rs.82238/- only		Earnest Money : Rs.1700/- only	
Sr.No	Description of items	Quantity	Rate		Unit	Amount				
			In words	In figures						
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.30 cum (zero point thirty cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –I 90mm to 45mm (Ninety millimeters to forty five millimeters)size, 100mm (One hundred millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.47 Cubic meter.	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per cubic meter	45328.00				
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –II, 63mm to 45mm (sixty three millimeters to forty five millimeters)size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	21.00 Cubic meter.	1757.60	Rupees One Thousand Seven Hundred Fifty Seven And Paise Sixty Only	Per cubic meter	36910.00				
						Total:-	82238.00			
Amount quoted by the contractor in % Above/Below										

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Re-Construction of Retaining wall near the house of Som Nath in village Duhag (Under SDRF)
Deposit Work (SH:- Construction of Retaining wall at R.D.0/0 to 10/050).

Estimated cost:- Rs.97092/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	6.30 Cubic meter.	320.00	Rupees Three Hundred Twenty Only	Per cubic meter	2016.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.51 cubic meter	3450.60	Rupees Three Thousand Four Hundred Fifty And Paise Sixty Only	Per cubic meter	91475.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 Numbers	300.10	Rupees Three Hundred And Paise Ten Only	Each	3601.00
					Total:-	97092.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Solanpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Vijay Kumar S/O Late Gorkhu Ram Ward No.4 G.P. Fatehpur (Under MLALAD) Deposit Work (SH:- Construction of P.C.C. Retaining wall at R.D.0/0 to 0/009.70).

Estimated cost:- Rs.96468/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out; shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.92 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3028.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.41 cubic meter	3450.60	Rupees Three Thousand Four Hundred Fifty And Paise Sixty Only	Per cubic meter	91130.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.00 Numbers	330.00	Rupees Three Hundred Thirty Only	Each	2310.00
					Total:-	96468.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

76

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road Under Rehan Sub-Division (Section Raja-Ka-Talab) (SH:- Construction of Unlined surface drains and maintenance of earthen shoulder).									
Estimated Cost:- Rs.98710/- only									
Earnest Money:- Rs.2000/- only									
Time limit:- One Month									
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.			
			In words	In figures.					
1	Construction of unlined surface drain of average cross-sectional area 0.40 sqm (Zero point forty) Square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment at with a lift upto 3.00mtr(three metre) and lead of 50.00mtr (fifty metre) (average lead 25) as per technical specification clause 307 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	250.00 Running metre	18.00	Rupees Eighteen Only	Per Running metre	4500.00			
2	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	450.00 Square metre	35.00	Rupees Thirty Five Only	Per square meter	15750.00			
3	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	225.00 Cubic meter.	280.00	Rupees Two Hundred Eighty Only	Per cubic meter	63000.00			
4	Restoration of rain cuts with soil, moorum gravel or a mixture of these cleaning the loose soil, benching for 300mm (three hundred millimeter) width laying fresh material in layers not exceeding 250mm (two hundred fifty millimeter) and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specification clause 1902 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	50.63 Cubic meter.	175.00	Rupees One Hundred Seventy Five Only	Per cubic meter	8860.00			
5	Cutting of branches of trees shrubs and trimming of glass and weeds cutting of shrubs from the road way or with in R.O.W and disposal of shrubs to suitable locations as per technical specifications Clause 1914 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1320.00 Square metre	5.00	Rupees Five Only	Per square meter	6600.00			
Amount quoted by the contractor in % Above/Below						Total:-	98710.00		

Executive Engineer
Ratnapur Division HPPWD
Ratnapur Distt. Kangra (H.P.)

(17)


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road Under Dhameta Sub-Division (Section Key)
(SH:-Construction of Unlined surface drains and maintenance of earthen shoulder).

Estimated Cost:- Rs.98710/- only
Earnest Money:- Rs.2000/- only
Time limit:- One Month

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In words	In figures.		
1	Construction of unlined surface drain of average cross-sectional area 0.40 sqm (Zero point forty) Square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment at with a lift upto 3.00mtr(three metre) and lead of 50.00mtr (fifty metre) (average lead 25) as per technical specification clause 307 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	250.00) Running metre	18.00	Rupees Eighteen Only	Per Running metre	4500.00
2	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	450.00) Square meter	35.00	Rupees Thirty Five Only	Per square meter	15750.00
3	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	225.00) Cubic meter.	280.00	Rupees Two Hundred Eighty Only	Per cubic meter	63000.00
4	Restoration of rain cuts with soil, moorum gravel or a mixture of these cleaning the loose soil, benching for 300mm (three hundred millimeter) width laying fresh material in layers not exceeding 250mm (two hundred fifty millimeter) and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specification clause 1902 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government	50.63) Cubic meter.	175.00	Rupees One Hundred Seventy Five Only	Per cubic meter	8860.00
5	Cutting of branches of trees shrubs and trimming of glass and weeds cutting of shrubs from the road way or with in R.O.W and disposal of shrubs to suitable locations as per technical specifications Clause 1914 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1320.00) Square meter	5.00	Rupees Five Only	Per square meter	6600.00
					Total:-	98710.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatnagar Division HPPWD
Fatnagar Distt. Kangra (H.P.)

(18)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road Under Rehan Sub-Division (Section Raja-Ka-Talab)
(SHI:-Construction of Unlined surface drains and maintenance of earthen shoulder).

Estimated Cost:- Rs.98710/- only

Earnest Money:- Rs.2000/- only

Time limit:- One Month

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In words	In figures.		
1	Construction of unlined surface drain of average cross-sectional area 0.40 sqm (Zero point forty) Square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment at with a lift upto 3.00mtr(three metre) and lead of 50.00mtr (fifty metre) (average lead 25) as per technical specification clause 307 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	250.00 Running metre	18.00	Rupees Eighteen Only	Per Running metre	4500.00
2	Making up loss of materials/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	450.00 Square meter	35.00	Rupees Thirty Five Only	Per square meter	15750.00
3	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	225.00 Cubic meter.	280.00	Rupees Two Hundred Eighty Only	Per cubic meter	63000.00
4	Restoration of rain cuts with soil, moorum gravel or a mixture of these cleaning the loose soil, benching for 300mm (three hundred millimeter) width laying fresh material in layers not exceeding 250mm (two hundred fifty millimeter) and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specification clause 1902 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	50.63 Cubic meter.	175.00	Rupees One Hundred Seventy Five Only	Per cubic meter	8860.00
5	Cutting of branches of trees shrubs and trimming of glass and weeds cutting of shrubs from the road way or with in R.O.W and disposal of shrubs to suitable locations as per technical specifications Clause 1914 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1320.00 Square meter	5.00	Rupees Five Only	Per square meter	6600.00
					Total:-	98710.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Patnagar Division HPPWD
Patnagar Distt. Kangra (H.P.)

19

SCHEDULE OF QUANTITY


SCHEDULE OF QUANTITY									
Name of work:- Restoration of Rain Damages on various road Under Dhameta Sub-Division (Section <u>Satlana</u>)									
(SH):-Construction of Unlined surface drains and maintenance of earthen shoulder).									
Estimated Cost:- Rs.98710/- only									
Earnest Money:- Rs.2000/- only									
Time limit:- One Month									
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.			
			In words	In figures.					
1	Construction of unlined surface drain of average cross-sectional area 0.40 sqm (Zero point forty) Square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment at with a lift upto 3.00mtr(three metre) and lead of 50.00mtr (fifty metre) (average lead 25) as per technical specification clause 307 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	250.00 Running metre	18.00	Rupees Eighteen Only	Per Running metre	4500.00			
2	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	450.00 Square metre	35.00	Rupees Thirty Five Only	Per square meter	15750.00			
3	Construction of embankment with approved materials obtained from borrow pits, with in all lifts and leads transporting to site, spreading, grading to required slope and compacted to meet requirement of tables 300.1 and 300.2 as per MORD technical specification clause 301.5 including hauling of materials in all leads, lifts and other incidental or as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	225.00 Cubic meter.	280.00	Rupees Two Hundred Eighty Only	Per cubic meter	63000.00			
4	Restoration of rain cuts with soil, moorum gravel or a mixture of these cleaning the loose soil, benching for 300mm (three hundred millimeter) width laying fresh material in layers not exceeding 250mm (two hundred fifty millimeter) and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specification clause 1902 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana toll tax sale tax or other taxes imposed by the Government	50.63 Cubic meter.	175.00	Rupees One Hundred Seventy Five Only	Per cubic meter	8860.00			
5	Cutting of branches of trees shrubs and trimming of glass and weeds cutting of shrubs from the road way or with in R.O.W and disposal of shrubs to suitable locations as per technical specifications Clause 1914 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1320.00 Square metre	5.00	Rupees Five Only	Per square meter	6600.00			
					Total:-	98710.00			
					Amount quoted by the contractor in % Above/Below				


Executive Engineer
Lathampur Division HPPWD
Lathampur Distt. Kangra (H.P.)

20

SCHEDULE OF QUANTITY

Name of work:- Preparation of Digital Cantour plan of W.R.S. Govt. P.G.Collage Dehri for Auditorium, Multipurpose Hall & Administrative Block at Dehri Kangra.			Estimated cost:- Rs.64800/- only			
			Earnest Money : Rs.1500/- only			
			Time limit:- One month			
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In figures	In words		
1	Preparation of digital survey contour plan with drawing complete in all respect in manuscript from and submission of the same to Higher office for approval. If any correction/amendment has desired by the Head Office. This same may be corrected as desired and directed by the Engineer-in-Charge complete in all respect. After approval, the same should be submitted in two No. set of fair drawing again if any correction/ amendment as desired by Head Offices including carriage of materials within all leads and lifts and other incidental. The rate include all kind of taxes such as G.S.T, octroi, sale tax and all other taxes imposed by the Government.	72.000	900.00	Rupees Nine hundred only	Kanal	64800.00
		Kanal				
					Total:-	64800.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)