



E-Mail ID - cepwd-jha-bil@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"**

Sealed item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form

Date of issue/sale of Tender forms

Date of opening of tender

13/02/2025 upto 12:00 PM

13/02/2025 from 02:00 PM to 04:00 PM

14/02/2025 at 11:00AM

The tender shall be received up to **10:30AM on 14/02/2025** and will be opened on the same day at **11:00AM** in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on **13/02/2025 from 02:00 PM to 04:00 PM**.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Balance work of Construction of link road to Khater Km. 0/0 to 1/0 (SH: P/L Cement Concrete at RD 0/673 to 0/695) under Deposit Work.	84435.00	1700/-	350/-	Three Month
2	C/o Ghumarwin Berthin Shahtalai road MDR-116 Km. 4/0 to 31/0 (SH: C/o Edge wall at RD 6/345 to 6/375).	94235.00	1900/-	350/-	Three Month
3	C/o Ghumarwin Berthin Shahtalai road MDR-116 Km. 4/0 to 31/0 (SH: C/o Edge wall at RD 7/510 to 7/525).	92306.00	1800/-	350/-	Three Month
4	C/o Ghumarwin Berthin Shahtalai road MDR-116 Km. 4/0 to 31/0 (SH: C/o Edge wall at RD 7/525 to 7/540).	92743.00	1900/-	350/-	Three Month
5	C/o link road GTB road to Nav Durga Mata Mandir Baniyan Km. 0/0 to 1/0 (SH: C/o Edge wall at RD 0/020 to 0/035) Under OTMNP.	98134.00	2000/-	350/-	Three Month
6	C/o link road GTB road to Nav Durga Mata Mandir Baniyan Km. 0/0 to 1/0 (SH: C/o U-Shape Drain at RD 0/020 to 0/050) Under OTMNP.	93458.00	1900/-	350/-	Three Month
7	C/o Govt. Middle School at Buhad in GP Paploa (SH: C/o Balance work of one Room with Verandha all finishing work etc.) Deposit Work.	74225.00	1500/-	350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of public interest.

Terms and conditions:

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.
2. The contractors should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy Application will not be entertained.
6. Payment for the works under N.I.T. shall be made as & when sufficient funds are available with the Department.
7. Tender form shall not be issued to those contractors who have two or more work in hand.

... HIM SUCHNA AVAM JAN SAMPARK...

Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.

No. PW-JDT-CB-EA-I-Tender Notice/2024-25-

8717 - 26

Dated:- 03/02/25

Copy forwarded to following:-

1. The Engineer-in-Chief, HPPWD Shimla-2 for kind information please.
2. The Chief Engineer (HZ), HPPW., Hamirpur for kind information please.
3. The Superintending Engineer, 10th Circle, HPPWD., Bilaspur for information please.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division for information.
6. Drawing Branch.
7. Accounts Branch
8. Notice Board.

Executive Engineer,
Jhandutta Division,
HPPWD., Jhandutta.

①

Balance work

DRAFT SCHEDULE OF QUANTITY

Name of Work :-Construction of link road to Khater Km 0/00 to 1/000 (SH:- P/L Cement Concrete at RD 0/673 to 0/695). Under Deposit Wotk.		Estimated cost:- ₹84435.00		Only		
		Earnest Money:- ₹1700.00		Only		
		Time allowed:- Three Month				
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specificaation clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a all lead and lifts. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other consttruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.08	222.90	INR two Hundred twenty two point Nine zero Only	Per Cubic Meter	3138.00
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD pecification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods and Service Tax, building and other consttruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.56	1452.85	INR one thousand four hundred fifty two point eight five only	Per Cubic Meter	15342.00

3 Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:1.5:3 (one Cement isto one point five coarse sand) isto three graded, crushed stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Total:-

10.56

6245.70

INR six
Thousand two
hundred forty
five point seven
zero Only

Per Cubic
Meter

65955.00

399

84435.00

*Draft Schedule of quantity approved
for Rs 84435/- only for the year 2024-25.*

Estimate No. 399

DNT No. 399

Head of Account . Under Deposit Work.

Available Fund :-/only

Executive Engineer,
Jhandutta Division
HPPWD. Jhandutta

[Signature]

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/O Ghumarwin Berthin Shah Talai road MDR-116 Km 4/00 to 31/00 (SH:- Construction of Edge Wall at RD 6/345 to 6/375)		Estimated cost:- ₹		94235.00	Only	
		Earnest Money:- ₹		1900.00	Only	
		Time allowed:- Three Month				
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of excavated earth lead upto all lift and leads as directed by Engineer-in-charge. in Ordinary rock including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.40	216.90	INR two hundred sixteen and Paise nine zero Only	Per Cubic Meter	1822.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one Cement into five coarse sand) into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	4400.60	INR four thousand four hundred and Paise sixty Only	Per Cubic Meter	92413.00
Total:-						94235.00

*Draft Schedule of quantity No. 409 for the year 2024-25
approved for Rs- 94235/-only*

Estimate No. 409

DNIT No. 409

Head of Account .

Available Fund:-/-only

lead
Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/O Ghumarwin Berthin Shah Talai road MDR-116 Km 4/00 to 31/00 (SH:- Construction of Edge Wall at RD 7/510 to 7/525).					
			Estimated cost:- ₹ 92306.00		Only
			Earnest Money:- ₹ 1800.00		Only
			Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Rate		Amount
			Figures	words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of excavated earth lead upto all lift and leads as directed by Engineer-in-charge. in Ordinary rock including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.40	216.90	INR two hundred sixteen and Paise nine zero Only	1171.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one Cement into five coarse sand) into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.25	4400.60	INR four thousand four hundred and Paise sixty Only	89112.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	289.00	INR two hundred eighty nine and Paise zero Only	2023.00
Total:-					92306.00

*Draft Schedule of quantity No 408 for the year 2024-25
abstracted for Rs - 92306/- only*

Estimate No. 408
DNIT No. 408
Head of Account .
Available Fund:-/-only

[Signature]
Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

4

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/O Ghumarwin Berthin Shah Talai road MDR-116 Km 4/00 to 31/00 (SH:- Construction of Edge Wall at RD 7/525 to 7/540)					
			Estimated cost:- ₹	92743.00	Only
			Earnest Money:- ₹	1900.00	Only
Time allowed:- Three Month					
Sr. No.	Description of iteams	Quantity	Rate		Amount
			Figures	words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of excavated earth lead upto all lift and leads as directed by Engineer-in-charge. in Ordinary rock including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.08	216.90	INR two hundred sixteen and Paise nine zero Only	1319.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one Cement into five coarse sand) into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.25	4400.60	INR four thousand four hundred and Paise sixty Only	89112.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whats over in this respect of the same.	8.00	289.00	INR two hundred eighty nine and Paise zero zero Only	2312.00
Total:-					92743.00

Draft Schedule of Quantity Not for the year 2024-25
approved for Rs- 92743/- only

Estimate No. 407
DNIT No. 407
Head of Account .
Available Fund:-/-only

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta



DRAFT SCHEDULE OF QUANTITY.

Name of Work :- Construction of Link road GTB road to Nav Durga Mata Mandir Baniya Km 0/0 to 1/00 (SH:- Construction of Edge Wall at RD 0/020 to 0/035) Under OTMNP.				Estimated cost:- ₹ 98134.00		Only
				Earnest Money:- ₹ 2000.00		Only
				Time allowed:- Three Month		
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specifaation clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a all lead and lifts. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.88	216.90	INR Two Hundred sixteen point nine zero Only	Per Cubic Meter	1058.00
2	Providing and laying cement concrete 1:5:10 (one cement isto five sand isto ten graded, crushed stone agg. 40 mm (forty millimeter) nominal size) and curing complete work in foundation and plinth including the cost of centring & shuttering in foundation and plinth including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.60	4400.60	INR four thousand four hundred point six zero only	Per Cubic Meter	95053.00
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm (One hundred) dia PVC pipe enterding through full of width of the structure with slope of (V): 20 (H) towards drawing face complete as per HPPWD specification including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	289.00	INR Two hundred eighty Nine point zero zero only	Each	2023.00
Total:-						98134.00

Draft Schedule of quantity No 406 for the year 2022-23 approved for Rs 98134/- only

Estimate No:- 406

DNIT No:- 406

Head of account :-

Available Fund :-/-only

JHANDUTTA DIVISION,
HPPWD, Jhandutta

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta



DRAFT SCHEDULE OF QUANTITY.

DRAFT SCHEDULE OF QUANTITY.						
Name of Work :- Construction of Link road GTB road to Nav Durga Mata Mandir Baniya Km 0/0 to 1/00 (SH:- Construction of U-Shape Drain at RD 0/020 to 0/050) Under OTMNP.			Estimated cost:- ₹ 93458.00		Only	
			Earnest Money:- ₹ 1900.00		Only	
			Time allowed:- Three Month			
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, lift upto a all leads & lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead & Lifts. All kinds of soil. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.60	164.15	INR one Hundred sixty four point one five Only	Per Cubic Meter	3546.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:3:6 (one Cement isto three coarse sand) isto six graded, Crushed stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.25	5212.30	INR Five thousand two hundred twelve point three zero only	Per Cubic Meter	89912.00
Total:-						93458.00

Draft Schedule of quantity No 405 for the year 2024-25 approved for Rs- 93458/- only.

Estimate No:- 405
DNIT No:- 405
Head of account :-
Available Funds:-/-only

ent
Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Construction of Govt. Middle School at Bulhar in GP Paploa (SH:- Construction of Balance work of one Room With Verandha all finishing work etc.) Deposit Work.

Name of Work :- Construction of Govt. Middle School at Buhar in GP Paploa (SH.- Construction of Balance work of one Room With Verandha all finishing work etc.) Deposit Work.							Estimated cost:- ₹ 74225.00		Only
							Earnest Money:- ₹ 1500.00		Only
							Time allowed:- three Month		
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount			
1	Making plinth protection 50mm (fifty millimeter) thick of cement concrete 1:3:6 (one cement isto three coarse sand isto six graded, Crushed stone aggregate 20 mm (twenty millimeter) nominal size) over 75 mm (seventy five millimeter) thick bed of dry brick ballast 40 mm (forty millimeter) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.5	512.00	INR five hundred twelve point zero zero only	Per Square meter	8960.00			
2	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.48	40.95	INR forty point nine five only	Per Square meter	1781.00			
3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point nine zero liter per ten square meter) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	43.48	98.30	INR ninety eight point three zero only	Per Square meter	4274.00			

(7)

4	Providing and applying plaster of paris putty of 2 mm (Two millimeter) thickness over plastered surface to prepare the surface even and smooth complete, including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	265.10	123.50	INR one hundred twenty three point five zero only	Per Square meter	32740.00
5	Disempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	265.10	99.85	INR ninety nine point eight five only	Per Square meter	26470.00
Total:-						74225.00

*Direct Schedule of quantity approved
for Rs 74,225/- only for May/Jun 2024-25,*

Estimate No. 394
DNIT No. 394
Head of Account.
Available Fund:-/-only

red
Executive Engineer,
Jhanda Division,
HPPWD, Jhanda