

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 18690-739

Dated/ 10-2-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025.

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 19.02.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 18.02.2025 up to 4.00 P.M and the application for issue of tender form shall be received 17.02.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o link road to Gujjar Basti Lamlehar (SW:- P/L G-II & G-III and CC Pavement Road RD 0/069 to 0/098.30 (MMGSY)	Rs. 99,285.00	Rs. 2,000.00	Three Months
2	C/o road from Main road to Bhagtillu (SH:- Formation and cutting at RD 0/570 to 0/590 & Hume Pipe at RD 0/350 to 0/390 along with Toe wall (MMGSY)	Rs. 93,012.00	Rs. 1,900.00	Two Months
3	C/o road from Main road to Bhagtillu (SH:- Formation cutting at RD 0/400 to 0/560 (MMGSY)	Rs. 99,920.00	Rs. 2,000.00	Two Months
4	C/o road from Guggar Marhi to Rensu Basti (SH:- Providing and laying Interlocking Paver Block at RD 0/119 to 0/142(MMGSY)	Rs. 99,528.00	Rs. 2,000.00	Two Months
5	C/o road from Guggar Marhi to Rensu Basti (SH:- Providing and laying Interlocking Paver Block at RD 0/147 to 0/170(MMGSY)	Rs. 99,528.00	Rs. 2,000.00	Two Months
6	Improvement of Black Spot on Badsar to Jugehar via Kharti Km0/00 to 2/500 (SH:- P/F Crash at various reaches between 0/900 to 0/922)	Rs.95,172.00	Rs. 2,000.00	Two Months
7	C/o 500 mtrs road from Jia Majhethly Gopalpur road to O.P. Bhardwaj House upto Radha Krishan Mandir (SH:- P/L Interlocking Tiles at RD 0/00 to 0/33)(MNP)	Rs. 99,165.00	Rs. 2,000.00	Two Months
8	C/o CHC at Gopalpur (SH:- P/F Prepainted Sheet for Extension of Chajja (Deposit)	Rs. 99,760.00	Rs. 2,000.00	Two Months
9	C/o CHC at Gopalpur (SH:- P/F B.P Sheet for Extension portion & Wire Gauge shutter (Deposit)	Rs. 99,650.00	Rs. 2,000.00	Two Months
10	C/o link road from Rampur Rajehar Sarsawa via Kapen NeelKanthi Bhadraina N.H Road (SW:- P/L Interlocking Concrete Block Pavement at RD 9/140 to 9/162 (NABARD)	Rs. 99,428.00	Rs. 2,000.00	Three Months
11	C/o link road from Rampur Rajehar Sarsawa via Kapen NeelKanthi Bhadraina N.H Road (SW:- P/L Interlocking Concrete Block Pavement at RD to 9/162 to 9/183(NABARD)	Rs. 97,125.00	Rs. 2,000.00	Three Months
12	Minor repair work of Type-I Quarters at HP.PWD Colony Holta (Quarter No. 65 & 66) (SW:- Providing and laying vetrified tiles, Providing Fixing Wash Basin & Water Closet (European Type) etc	Rs. 36,960.00	Rs. 800.00	Three Months
13	VR & M/O Dharamshala Yol Dadli Palampur road Km 27/000 to 38/000 (SW:- Painting Steel Work)	Rs. 91,035.00	Rs. 1,900.00	Three Months

14	Improvment of Black Spot at Bhagotla Rajnali Dharer road Km 0/00 to 4/500 (SH:- P/F Crash Barrier at RD 0/230 to 0/253.50 (Black Spot)	Rs. 99,480.00	Rs. 2,000.00	Two Months
15	Improvment of Black Spot at Bhagotla Rajnali Dharer road Km 0/00 to 4/500 (SH:- P/F Crash Barrier at RD 0/280 to 0/303.50 (Black Spot)	Rs. 99,480.00	Rs. 2,000.00	Two Months
16	C/o Jeopable road from House of Smt. Koushalya Devi Towards Sh. Hari Ram Machine (SH:- C/o R/Wall at RD 0/110 to 0/122 (VKVNY)	Rs. 98,099.00	Rs. 2,000.00	Two Months
17	C/o Jeopable road from House of Smt. Koushalya Devi Towards Sh. Hari Ram Machine (SH:- C/o R/Wall at RD 0/138 to 0/173 (VKVNY)	Rs. 99,225.00	Rs. 2,000.00	Two Months
18	C/o link road from Jia to Village Fota Ward No. 4 Km 0/00 to 2/500 (SW:- C/o Wire Crate on RD 0/715 to 0/720 (MNP)	Rs. 95,017.00	Rs. 2,000.00	Two Months
19	Restoration of rain damages on Bagora Bhagotla road Km 0/00 to 2/00 (SH:- Balance work of existing 10.00 Murs Bridge at RD 1/405 (LHS)	Rs. 62,887.00	Rs. 1,300.00	Two Months
20	C/o link road from GMS Dharot to Harizan Basti via Hari Ram House in GP Lahla Km 0/00 to 1/500 (SW:- Providing and laying CC Pavement at RD 0/020 to 0/054) (MNP)	Rs. 98,028.00	Rs. 2,000.00	Two Months
21	C/o link road from GMS Dharot to Harizan Basti via Hari Ram House in GP Lahla Km 0/00 to 1/500 (SW:- Providing and laying CC Pavement at RD 0/542 to 0/574) (MNP)	Rs. 98,982.00	Rs. 2,000.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

Work No. :- C/O link road to Gujar Basti Lamiehar
S. W. :- P/L G-II, G-III & CC Pavement road RD 069 to 0/098.30 (MMGSY)

Schedule of Quantity

Work No. ①
Estimated Cost : Rs. 99,285/-
Earnest Money : 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.67	Cubic metres		Per Cubic metre.	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.67	Cubic metres		Per Cubic metre.	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	10.22	Cubic metre		Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Road from Main road to Bhagtilu. (SH:- Formation & Cutting at Rd 0/570 to 0/590 & Hume pipe at Rd 0/350 & 0/390 along with toe wall). **MMSY**

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			Time Limits			
			In Figures	In Word		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	83.75			Per cubic metre.	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	28.62			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogramme) per cubic metre in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.08			Per cubic metre	
4	Providing and laying (to level or slope) 900 mm (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipe I.S Class NP2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding the cost of excavation, protection works, backfilling, concrete and masonry work in head walls and parapets as per drawing and technical specifications clause 1101 and as per the direction of the Engineer -in-Charge including carriage of materials within all leads and lift and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	12.50			Per Running metre	
Total						


Executive Engineer,
Palampur Division
HP PWD Palampur

(3)

SCHEDULE OF QUANTITY

Name of work:- C/o Road from Main road to Bhagtilu. (SH:- Formation & Cutting at Rd 0/400 to 0/560). MMSY

Name of work:- C/o Road from Main road to Bhagtilu. (SH:- Formation & Cutting at Rd 0/400 to 0/560). MMSY							Estimated cost Rs.	99920.00
							Earnest Money Rs.	2000.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	624.50			Per cubic metre.			
	Total							


 Executive Engineer
 Palampur Division
 HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Road from Gugga Marhi to Rensu Basti. (SH:- Providing and Laying interlocking paver blocks at Rd 0/119 to 0/142). MMSY

0/142). MMSY							Estimated cost Rs.		99528.00
							Earnest Money Rs.		2000.00
							Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading, watering and rolling of binding materials moonum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	1.35			Per cubic metre				
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	2.04			Per cubic metre.				
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	69.00			Per square metre				
	Total								

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Road from Gugga Marhi to Rensu Basli. (SH:- Providing and Laying interlocking paver blocks at Rd 0/147 to 0/170). **MMSY**

		Estimated cost Rs.		99528.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Stone soling properly hand-packed filling interstices with Khariya stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moonrum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	1.35			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depts including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government	2.04			Per cubic metre.	
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	69.00			Per square metre	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black Spot on Badsar to Jugehar Via Kharti Km 0/00 to 2/500. (SH:- P/F Crash Barrier at various reaches between 0/900 to 0/922)

Name of work:- Improvement of Black Spot on Badsar to Jugehar Via Kharti Km 0/00 to 2/500. (SH:- P/F Crash Barrier at various reaches between 0/900 to 0/922)							Estimated cost Rs.	95172.00
							Earnest Money Rs.	2000.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORID technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.09			Per cubic metre			
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.09			Per cubic metre.			
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre) long complete as per clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.00			Per running metre			
Total								


 Executive Engineer
 Palampur Division
 HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o 500 mt. Road from Jia Majhelly Gopalpur road to O.P. Bhardwaj house upto Radha Krishan Mandir. (SH:- P/L interlocking tiles at Rd 0/00 to 0/33). **MNP**

Name of work:- C/O 500 mt Road from Jia Majhelly Gopalpur road to O.P. Bhardwaj house upto Radha Krishan Mandir. (SH:- P/L interlocking tiles at Rd 0/00 to 0/33). MNP						
Sr. No	Description of Item	Quantity	Estimated cost Rs.		Unit	Two Months Amount
			Earnest Money Rs.			
			Time Limits			
			Rate			
		In Figures	In Word			
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	72.60			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.99			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP, PWD Palampur

20

SCHEDULE OF QUANTITY

Name of work:- C/o CHC at Gopalpur. (SH:- P/F preprinted Sheet for extension of Chajja). Deposit

Name of work:- C/O CTC at Gopapur. (SH:- P/F preprinted Sheet for extension of Chajja). Deposit						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Two Months	
			Earnest Money Rs.		2000.00	
			Time Limits			
			Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing preprinted steel sheet roofing of Tata / Sail over steel trusses, P/F Kale metal preprinted single skin Trapezoidal profile sheeting 0.60 mm thickness having the 1060 mm cover width(overall width 1126mm) 28 mm crest depth at 353+2 c/c crest distance. There will be a two rib at the centre for stiffening for crest depth of 25 mm. The main crust width at top of 25mm at lower 81 mm base metal of cold rolled steel coil with steel cast with Zinc coating top coat with regular modified polyester coating of approved shade & balancing reverse coat with polyester paint fixed of sheet shall be of self drilling and self tapping screws of size 5.5 mm dia and 5.5 mm length with EIDPM seal. The metal supply will be accompanied by test by certificate & 20 years warranty from company against the corrosion fading of colour & manufacture defect as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.800			Per Square Metre	
	Total					


 Executive Engineer,
 Palampur Division
 HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o CHC at Gopalpur. (SH:- P/E B.P. Sheet for extension portion & wire Gauge Shutter). Deposit

Sr. No.		Description of Item	Quantity	Estimated cost Rs.			Two Months
				Earnest Money Rs.		Amount	
				Time Limits			
				Rate			
			In Figures	In Word	Unit		
1	Providing and fixing 30 mm thick Kilm seasoned selected class of sheesham wood shutters wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.49			Per square metre		
2	Providing and fixing M.S. BP Sheet 2mm (two millimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately). The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.00			Per square metre		
3	Providing and fixing35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters, including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.69			Per square metre		

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity
Name of Work :- C/O link road from Rampur Rajehar Sarsawa via Kapen NeelKanth Bhadraina N.H. road
(S. W. :- P/L Interlocking Concrete block Pavement at RD 9/140 to 9/162 (NABARD)

Work No.
Estimated Cost : Rs. 98,428/-
Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing Concrete for plain/reinforced concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802.803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.32	Cubic metre			Per Cubic metre	
3	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	70.40	Square Metre			Per square metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road from Rampur Rajehar Sarsawa via Kapen NeelKanth Bhadraina N.H. road
(S. W. :- P/L Interlocking Concrete block Pavement at RD 9/162 to 9/183 (NABARD))

Estimated Cost : Rs. 97,125/-
Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802.803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	2.19	Cubic metre			Per Cubic metre	
3	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	65.10	Square Metre			Per square metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Minor repair work of Type -I Quarters at HPPWD Colony Holta (Quarter NO. 65 & 66)

Estimated Cost : Rupees 36,960/-

Earnest Money : Rupees 800/-

Time limit : Three Months.

Sub Work :- Providing and Laying vitrified tiles, Providind/Fixing Wash Basin & Water Closet (European Type), etc.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Size of Tile 600x600 mm including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	11.40	Sqm			Per Square metre	
2	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked black solid plastic seat and lid including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.			Each	
3	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.			Each	
4	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.			Each	
	Total:-						

Executive Engineer
Palampur Division
H.P.PWD Palampur

Work No. 35-

Estimated Cost : Rs. 91,035-
Earnest Money : 1900/-

Earnest Money : 1900/-

Time limit : Three Months

S. No.	Description of Item	Quantity	Time Limit : Three Months		Amount
			Rate		
			In figure	In words	
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications ; Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1071.00	Square metres	Per Square metre	
				Total :-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Name of work:- Improvement of Blackspot at Bhagolia Rajnati Dharer road Km 0/00 to 4/500. (SH:- P/F Crash Barrier at Rd 0/230 to 0/253.50). **Blackspot**

SCHEDULE OF QUANTITY

0/230 to 0/253.50). Blackspot						
K. S.						

Executive Engineer
Palampur Division
HP, PWD Palampur

15

SCHEDULE OF QUANTITY

Name of work:- Improvement of Blackspot at Bhagolla Rajnathi Dharer road Km 0/00 to 4/500. (SIH- P/F Crash Barrier at Rd 0/280 to 0/303.50). **Blackspot**

Estimated cost Rs.	99480.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sl No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	1. All work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets, etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of silt/silt which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	1. Providing and laying concrete for plan/ reinforced concrete 1:2:4 (One Cement Two Sand Four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-1 twents) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
3	1. Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimeter) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimeter) above road/ground level, fixed on ISM series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into five millimeter) spaced 2 m (two meter) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section, 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimeter) 330 mm (three hundred thirty millimeter) long complete as per clause 810 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	23.50			Per running metre	
	Total					

Executive Engineer
Palampur Division
HP, PW-1 Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from house of Smt. Koushalya Devi towards Sh. Hari Ram Machine. (SH:- C/o R/wall at Rd 0/110 to 0/122). (VKVNY)

Estimated cost Rs.	98099.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORAD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST, or other taxes imposed by the Government time to time.	8.64			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from house of Smt. Koushalya Devi towards Sh. Hari Ram Machine. (SH:- P/L C.C. Pavement at Rd 0/138 to 0/173). (MKVNY)

Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
		In Figures	In Word			
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including cartage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75			Per cubic metre.	
Total						


 Executive Engineer
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/O link road from Jia to village Potta ward No. 4 Km 0/00 to 2/500, (SH-2 C/O Wire Gate on Rd 0/715 to 0/720).
MNP

Estimated cost Rs.	95017.00
Fairnest Money Rs.	2000.00
Time Limits	Two Months

Sr No.	Description of Item	Quantity	Rate		Unit	Amount
			In Trenches	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, cuttings, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any fill including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface (i) layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise and during dewatering of as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidents. The rate is including octroi, royalty, Malkana toll tax, CST or other taxes imposed by the Government time to time.	10.00			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia (4) wire conforming to IS-280 and IS-4826 in 100 mm x 100 mm (hundred millimeters) mesh (evenly distributed) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications Clause 2503 and as per direction of the Engineer. In (4) large including carriage of materials within all leads and lifts and other incidental. The rate includes octroi, royalty, Malkana Toll tax, CST or any other taxes imposed by the Government.	31.26			Per cubic metre	

Executive Engineer
Palampur Division
I/P PWD Palampur

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain Damages on Bagodā Bhagotla road Km 0/00 to 2/00. (SI) - Balance work of existing 10.00 mtr. Bridge at Rd 1/405 (LHS).

Estimated cost Rs.	62887.00
Earnest Money Rs.	1300.00
Time Limits	Two Months

Sr No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock cherting / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 105.1 and as per the directions of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including designing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in boxes not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Mahakana toll tax, (CS) or other taxes imposed by the Government time to time.	4.55			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M 10) nominal mix 1:3:6 (one cement, three sand, six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or hauling out water, dewatering, removal of slush as required @ site which may arise in the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications (Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Mahakana toll tax, or other taxes imposed by the government.	13.25			Per cubic metre	
	Total					


 Executive Engineer,
 Palampur Division
 JHP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GMS Dharot to Harizan Basti Via Hari Ram House in G.P. Labla Km 0/00 to 1/500. (SH:- Providing and Laying C.C. Pavement at Rd 0/020 to 0/054) MNP

Name of work:- C/O Link road from GMS Dharot to Harizan Basti Via Hari Rann House in G.P. Lahla Km 0/00 to 1/500. (SH:- Providing and Laying C.C. Pavement at Rd 0/020 to 0/054) MNP					Estimated cost Rs.	98028.00
					Earnest Money Rs.	2000.00
					Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.56			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GMS Dharot to Harizan Basti Via Hari Ram House in G.P. Lahla Km 0/00 to 1/500. (SH:- Providing and Laying C.C. Pavement at Rd 0/542 to 0/574) MNP

Estimated cost Rs. 98982.00
Earnest Money Rs. 2000.00

Time Limits

Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre.	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	14.64			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur