



Office of the
Executive Engineer
Una Division, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No.PWU/ CB//TA/Tender/2024-25/-

15165-73

Dated

06

02/25

To

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.


Subject: - Regarding publication of Tenders Notice.

Sir,

“JAI HIND”

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.


Executive Engineer,
Una, Division,
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.

Executive Engineer,
Una, Division
HPPWD, Una

Certificate

Certified that the tenders called vide this office letter
No.PWU/CB/T-I/2024-25:- 15174-86 dated-06.02.2025 emergent nature and in
Public interest.


Executive Engineer,
Una Division, HP:PWD
Una

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Sealed item rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Una Division HPPWD Una H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office or before **15.02.2025 upto 11.00 A.M.** and will be opened on the same day at **11.30 A.M.** in presence of the intending contractor s or their authorized representatives who may like to be present. If it happened be holiday on the day of opening of tender the same will be opened on next working day at the same time. The application for obtaining the tender forms will be received latest by **13.02.2025 10.00 AM upto 12.00 Noon** against cash payment (non-refundable) and the tender form can be had from this office upto **13.02.2025 12.00 PM to 4.00 PM.**

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Una Division HPPWD Una , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice. The offers of the tender (s) shall be kept open for 75 days from the date of opening the tender(s).

Sr. No.	Name of work	Estimated cost	Earnest Money	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	Repair of Restoration of Rain damages of internal road at IRB Bangarh km 0/0 to 1/600 (SH:- Retaining wall near Barrack No.2 Mohal (Phase-I)	98832/-	2,000/-	One Month	350/-	Class-C & D
2	Repair of Restoration of Rain damages of internal road at IRB Bangarh km 0/0 to 1/600 (SH:- Retaining wall near Barrack No.2 Mohal (Phase-III)	98832/-	2,000/-	One Month	350/-	Class-C & D
3	C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (under VKVNY) (SH:- P/L 60 mm thick pavers blocks & C/O V-shape drain) (Phase-I) (Deposit work)	98365/-	2000/-	One Month	350/-	Class-C & D
4	C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (under VKVNY) (SH:- P/L 60 mm thick pavers blocks & C/O V-shape drain) (Phase-II) (Deposit work)	98529/-	2,000/-	One Month	350/-	Class-C & D
5	Construction of Path & Paver block near the house of Sh. Tara Singh GP Jalgran Tabbha tehsil & Distt. Una under VKVNY scheme (D.W.) (Phase-III)	78809/-	1600/-	One Month	350/-	Class-C & D
6	Repair of Path Ram Asra House to Vidya Sagar House ward No. 5 in Lower Dehlan (GP Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/0 to 0/053) (Deposit work)	99,913/-	2,000/-	One Month	350/-	Class-C & D
7	Repair of Path Main link road to House of Des Raj ward No.7 in Lower Dehlan (G.P. Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/0 to 0/040) (Deposit work)	99,834/-	2,000/-	One Month	350/-	Class-C & D


8	Repair of Path Main link road to House of Des Raj ward No.7 in Lower Dehlan (G.P. Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/040 to 0/080) (Deposit work)	99,834/-	2,000/-	One Month	350/-	Class-C & D
9	C/O link road to Bana Beli Ram Dera to ward No.06 Lalsingi Una km 0/0 to 1/600 (SH:- C/O Brest wall at RD 0/969 to 1/0) Under OTMNP	99,894/-	2,000/-	One Month	350/-	Class-C & D
10	Repair of damages on Una Malahat road km 0/0 to 2/0 (SH:- Earthen Shoulder at RD 0/0 to 2/0) Under OFC Deposit	96,600/-	2,000/-	One Month	350/-	Class-C & D
11	Construction of path Muhalla Kalia Nichla ward No.3 GP Jakhera (SH:-P/L CC pavement, 150mm PVC pipes & MS covers etc. in RD 0/135 to 0/167) (Deposit work)	99,727/-	2,000/-	One Month	350/-	Class-C & D
12	Construction of Retaining wall and Gramin Samprak near the house of Gurcharan Muhalla Dole ward No.1, GP Rampur Tehsil & Distt. Una (HP0 (SH:- C/O R/wall at RD 0/011 to 0/014) (Scheme ID-VKV 2024/27) (Deposit work)	99,600/-	2,000/-	One Month	350/-	Class-C & D
13	Repair of damages on Rakkar Basoli road 0/0 to 2/0 (SH:- C/O R/wall along road from RD 0/059.50 to 0/070) (under OFC Deposit)	99,892/-	2,000/-	One Month	350/-	Class-C & D
14	Repair of damages on Rakkar Basoli road 0/0 to 2/0 (SH:- C/O R/wall along road from RD 0/050 to 0/059.50) (under OFC Deposit)	99,892/-	2,000/-	One Month	350/-	Class-C & D
15	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/045 to 0/060 (RHS) (Deposit work)	99,688/-	2,000/-	One Month	350/-	Class-C & D
16	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/135 to 0/150 (RHS) (Deposit work)	97,648/-	2,000/-	One Month	350/-	Class-C & D
17	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/060 to 0/075 (RHS) (Deposit work)	99,348/-	2,000/-	One Month	350/-	Class-C & D
18	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/150 to 0/165 (RHS) (Deposit work)	97,308/-	2,000/-	One Month	350/-	Class-C & D
19	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/850) under Black spot	99,899/-	2,000/-	One Month	350/-	Class-C & D
20	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/950) under Black spot	99,503/-	2,000/-	One Month	350/-	Class-C & D
21	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/220 to 1/237) (RHS) under OFC Deposit	97548/-	2,000/-	One Month	350/-	Class-C & D
22	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/271 to 1/288) (RHS) under OFC Deposit	97548/-	2,000/-	One Month	350/-	Class-C & D
23	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/220 to 1/260) (LHS) under OFC Deposit	98165/-	2,000/-	One Month	350/-	Class-C & D

6
2

24	Repair of damage on 120 mtr. span bridge at Rampur on Una Santoshgarh road at RD 1/760 (SH:- P/L bituminous concrete both side ramp) under OFC Deposit	78450/-	1600/-	One Month	350/-	Class-C & D
25	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/900) under Black spot	98,549/-	2,000/-	One Month	350/-	Class-C & D

TERM & CONDITIONS:-

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board "Men at work / work in progress" shall be placed " by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
10. The tender shall be issued to those contractors/ firms who have not more than two works in hand.
11. Work should be completed by the contractor within stipulated period.



Executive Engineer
Una Division, HP:PWD,
Una.

No. PWU/CB/T-I/2024-25:-

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. All the Assistant Engineers under this Division.
4. The Deputy Commissioner, Una.
5. The Sub Divisional Officer (C), Una.
6. The District Treasury Officer, Una.
7. The Block Development Officer, Una.
8. The Municipality, Una.
11. All the Head of the Branches in this office.
12. The Notice Board.

Dated:- 06-02-2025


Executive Engineer,
Una Division, HP:PWD,
Una

SCHEDULE OF QUANTITY						
Name of work :Repair of Restoration of Rain damages of internal road at IRB Bangarh km.0/0 to 1/600 (SH: Retaining wall near Barrack No.2 Mohal.(Phase-I)				Estimated Cost		99832/-
				Earnest Money		2000/-
				Time limit		One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT	
			Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.84	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	29.23	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental.	11.00	Each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:		
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer
Una Divn.HP.PWD.,
Una

9

SCHEDULE OF QUANTITY								
						Estimated Cost	99832/-	
	Name of work :Repair of Restoration of Rain damages of internal road at IRB Bangarh km.0/0 to 1/600 (SH: Retaining wall near Barrack No.2 Mohal.(Phase-III)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.84	Per cubic metre					
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	29.23	Per cubic metre					
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental.	11.00	Each					
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						Total:		
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								

Executive Engineer
Una Divn.HP.PWD.,
Una

196

3

Vigns Bimalan

SCHEDULE OF QUANTITY

Name of work :C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (Under VKVNY) (SH: P/L 60mm thick pavers blocks & C/O V-shape drain)(Phase-I) (Deposit work)

Estimated Cost 98365/-

Earnest Money 2000/-

Time limit one month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.31	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.88	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.15	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 200mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Per running metre			

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	61.25	Per square metre			
6	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand); 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer

Una Divn.HP.PWD

Una


197

4

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Name of work :C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (Under VKVNY) (SH: P/L 60mm thick pavers blocks & C/O V-shape drain)(Phase-II) (Deposit work)							
						Estimated Cost	98529/-
						Earnest Money	2000/-
						Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	7.05	Per cubic metre				
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.50	Per cubic metre				
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.05	Per cubic metre				
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.58	Per cubic metre				

5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.00	Per running metre			
6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	61.10	Per square metre			
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.14	Per cubic metre			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST etcetra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						


 Executive Engineer
 Una Divn. HP. PWD.,
 Una

(148)

(5)

SCHEDULE OF QUANTITY						
Name of work : Construction of Path & Paver block near the house of Sh. Tara singh GP Jalgran Tabba tehsil & Distt. Una under VKVNY scheme. (Deposit work) <i>Phase - III</i>				Estimated Cost	78809/-	
				Earnest Money	1600/-	
				Time limit	one month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.47	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.24	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	54.95	Per square metre			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total		
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer


Una Divn. HP. PWD., Una

203

6

SCHEDULE OF QUANTITY						
Name of work :Repair of Path Ram Aasra House to Vidya Sagar House Ward No.5 in Lower Dehlan(G.P.Lower Dehlan) (SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/0 to 0/053) (Deposit work)						
					Estimated Cost	₹9913/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government .	3.88	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.76	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.18	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	57.50	Per running metre			

5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.95	Per cubic metre			
6	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	37.50	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD
 Una

183

7

SCHEDULE OF QUANTITY							
Name of work :Repair of Path Main link road to House of Des Raj Ward No.7 in Lower Dehlan(G.P.Lower Dehlan) (SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/0 to 0/040) (Deposit work)							
						Estimated Cost	99834/-
						Earnest Money	2000/-
Sl. No.	Description of work	Quantity	Unit	RATE In		Time limit	one month
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	3.00	Per cubic metre				
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.01	Per cubic metre				
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.84	Per cubic metre				
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	44.50	Per running metre				


5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.40	Per cubic metre			
6	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	37.50	Per kilogramme			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer
Una Divn.HP.FWD.,
Una

184 8

SCHEDULE OF QUANTITY						
Name of work :Repair of Path Main link road to House of Des Raj Ward No.7 in Lower Dehlan(G.P.Lower Dehlan) (SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/040 to 0/080) (Deposit work)						
					Estimated Cost	99834/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.00	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.01	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.84	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	44.50	Per running metre			
5	Providing and laying in position cement concrete1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering andshuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	7.40	Per cubic metre			

6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	37.50	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

218

9

	DRAFT SCHEDULE OF QUANTITY				Estimated cost	99894/-
					Earnest money	2000/-
					Time limit	One month


Name of Work: C/O link road to Baba Beli Ram Dera to ward No.6 Lalsingi Una km.0/0 to 1/600(SH: C/O Breast wall at RD.0/969 to 1/0) Under OTMNP						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.23	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	28.25	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	34.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Kumeta
Executive Engineer ,
Una Divn.HP.PWD.,Una

222

10

SCHEDULE OF QUANTITY						
					Estimated Cost	96600/-
					Earnest Money	2000/-
					Time limit	One month
	Name of work : Repair of damages on Una Malahat road km.0/0 to 2/0 (SH: Earthen shoulder at RD.0/0 to 2/0)) Under OFC Deposit					
Sl No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Maintenance of earthen shoulder (stripping of excess soil) stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specical clause 1903 including carriage of material within all leads and lifts other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4600.00	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer,

Una Division, HPRWD.,

Una

204

(1)

SCHEDULE OF QUANTITY						
Name of work :Construction of Path Muhalla Kalia Nichla ward No.3 GP Jakhera (SH: P/L CC Pavement, 150mm PVC pipes & MS covers etc. in RD.0/135 to 0/167)(Deposit work)						
					Estimated Cost	99724/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.37	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.37	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.37	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	32.00	Per running metre			

5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.37	Per cubic metre			
6	Steel work work (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	40.50	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer

Una Divn.HP.PWD.


Una

202

19

SCHEDULE OF QUANTITY					
				Estimated Cost	99600/-
	Name of work :Construction of Retaining wall and Gramin Samprak near the house of Gurcharan Muhalla Dole ward No.1 , G.P.Rampur Tehsil & Distt.Una (HP)(SH: C/O R/wall at RD. 0/011 to 0/014))(Scheme ID-VKV 2024/27) (Deposit work)			Earnest Money	2000/-
				Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT
			Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	9.85	Per cubic metre		
2	Providing and laying cement concrete 1:5:10(one cement:five sand: ten graded stone aggregate 40mm(forty millimetre) nominal size plain/reinforced concrete in open foundations and curing complete including cost of form work on ground or under water including pumping and bailing out water,dewatering, removal of sluch as required at site which may arise at the time of laying under water complete in all heights/depths in Retaining wall and parapets etc.complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per drawing and HP.PWD., technical specification including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.10	Per cubic metre		
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	26.00	Per cubic metre		

4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax ,octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each			
5	Back filling with granular material behind abutments, wing wall, return walls and retaining walls complete as per drawings and technical specification MORD technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.25	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.
 Una

216

13

SCHEDULE OF QUANTITY					
Name of work :Repair of damages on Rakkar Basoli road RD.0/0 to 2/0 (SH: C/O R/wall along road from RD.0/059.50 to 0/070) Under OFC Deposit				Estimated Cost	99892/-
				Earnest Money	2000/-
				Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In	
				Figures	Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.35	Per cubic metre		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.36	Per cubic metre		
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	each		


4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.16	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PW
 Una

217

SCHEDULE OF QUANTITY						(14)				
Name of work :Repair of damages on Rakkar Basoli road RD.0/0 to 2/0 (SH: C/O R/wall along road from RD.0/050 to 0/059.50) Under OFC Deposit						Estimated Cost		99892/-		
						Earnest Money		2000/-		
						Time limit		one month		
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT				
				Figures	Words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.35	Per cubic metre							
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.36	Per cubic metre							
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	each							

4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.16	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PW
 Una

927

15

SCHEDULE OF QUANTITY						
				Estimated Cost		99688/-
Name of work : Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/045 to 0/060(RHS) (Deposit work)				Earnest Money		2000/-
				Time limit		One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.00	Each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:		
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						


Executive Engineer
Una Divn.HP.PWD.
Una

228

(16)

SCHEDULE OF QUANTITY

					Estimated Cost	97648/-
	Name of work : Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/135 to 0/150(RHS) (Deposit work)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.
 Una

229

17

SCHEDULE OF QUANTITY


SCHEDULE OF QUANTITY							17					
										Estimated Cost	99348/-	
Name of work :Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/060 to 0/075(RHS) (Deposit work)										Earnest Money	2000/-	
										Time limit	One month	
Sl. No.	Description of work		Unit	RATE In		AMOUNT						
				Figures	Words							
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre									
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre									
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.00	Each									
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018										Total:		
2) The rates shall be including of all types of taxes including GST ectra)												
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021												


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

230

SCHEDULE OF QUANTITY

							Estimated Cost	97308/-
							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre					
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre					
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	12.00	Each					
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						Total:		
2) The rates shall be including of all types of taxes including GST etctra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

222

19

SCHEDULE OF QUANTITY						
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, comvex mirror at RD.1/850(Deposit work) <i>under black spot</i> .				Estimated Cost	99899/-	
				Earnest Money	2000/-	
				Time limit	one month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre			
3	Providing and erecting a "W" metal weem crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm. above road/ground level , fixed on ISMC series channel vertical post 150x75x5mm speed 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fitments to be galvansed by hot dip process, all fittings to conform to IS: 1367 and IS: 1364 , mmetal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm , 330mm long complete as per clause 810including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.00	Per Running metre			
4	Providing and fixing of road safety convex(size 80 cm) made of polycarbonate and ABS body suitable for indorr/ outdoor with hood complete with mounting hardware including post as per drawing and technical specifications including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.00	each			

5	Providing and fixing of dual-directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side)provided with twp steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No.GPL-07-02 Make GREENs or equivalent as per direction of Engineer-in-charge including carriage of material within all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	each			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					G.Total
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.
 Una

228

SCHEDULE OF QUANTITY					Estimated Cost	99503/-
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, convex mirror at RD.1/950(Deposit work) <u>Under Black spot</u> .					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.91	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.91	Per cubic metre			
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70mm. above road/ground level, fixed on ISMC series channel vertical post 150x75x5mm speed 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fittings to be galvansed by hot dip process, all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Per Running metre			
4	Providing and fixing of dual-directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side) provided with two steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No.GPL-07-02 Make GREENs or equivalent as per direction of Engineer-in-charge including carriage of material within all leads and lifts.	44.00	each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST etcetra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Kadale
Executive Engineer
Una Divn.HP.PWD.,Una

221

SCHEDULE OF QUANTITY

21

Estimated cost 97548/-

Earnest money 2000/-

Time limit One month

Name of Work: Repair of damages on Behdala Jankour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/220 to 1/237)(RHS) Under OFC Deposit

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.77	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.06	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	18.03	Per cubic metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etctra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer ,
 Una Division, HPPWD.,
 Una

224

22

SCHEDULE OF QUANTITY						Estimated cost	97548/-
						Earnest money	2000/-
						Time limit	One month
Name of Work: Repair of damages on Belidala Jankour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/271 to 1/288)(RHS) Under OFC Deposit							
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.77	Per cubic metre				
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.06	Per cubic metre				
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	18.03	Per cubic metre				

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una

228

23


	SCHEDULE OF QUANTITY			Estimated cost	98165/-
--	----------------------	--	--	----------------	---------

Earnest money 2000/-
Time limit One month

Name of Work: Repair of damages on Behdala Jankour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/220 to 1/260)(LHS)
Under OFC Deposit

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	18.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.20	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	17.00	Per cubic metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out-water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una


221

24

SCHEDULE OF QUANTITY

						Estimated Cost	78450/-
						Earnest Money	2000/- 1600/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Repair Name of work : Restoration of rain damage on 120 mtr. Span bridge at Rampur on Una Santoshgarh road at RD.1/760 (SH: P/L bituminous concrete both side ramp.) Under ofc deposit	11.25	Per cubic metre				
2	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	150.00	Per square metre				
3	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty, malkana toll taxes, GST, labour cess or taxes imposed by the Government	150.00	Per Square metre				
	Providing and applying tack coat with BITUMEN emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero decimal two five to zero decimal three zero kilogram) per square metre on the prepared dry and hungry bitumenious surface cleaned with Hydraulic broom as per specifications clause No. 503 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.						

4	Providing and laying bituminous concrete 30mm (thirty millimetre) thick with 9.5mm (nine point five millimetre) nominal minimum aggregate size with 100-120 TPH (one hundred to one hundred twenty tonne per Hour) (Hot Mix Plant) producing an average output of 75 (seventy five) tonnes per hour premixed with bituminous binder VG-30 @ 5.5% (five point five per cent) minimum aggregate grading as per table 500.15 and Filler @ 2% (two per cent) of weight of aggregates as per clause No. 509.2.4.2 design mix as per clause 509.4.3.2 transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, camber, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH -2014 specification clause No. 509 complete in all respects The Hot Mix Plant should be situated with in the distance of 30Km (thirty kilometre) from work site, including carriage of material within all leads and lifts and other incidentials. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government .	4.50	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					


 Executive Engineer
 Una Divn. HP. PWD,
 Una

229

SCHEDULE OF QUANTITY										
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, convex mirror at RD.1/900(Deposit work) <i>under black spot.</i>									Estimated Cost	98549/-
									Earnest Money	2000/-
									Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT				
				Figures	Words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre							
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre							
3	Providing and erecting a " W" metal weam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm. above road/ground level , fixed on ISMC series channel vertical post 150x75x5mm spaced 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fitments to be galvansed by hot dip process. all fittings to conform to IS: 1367 and IS: 1364 . metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm , 330mm long complete as per clause 810including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.00	Per Running metre							
4	Providing and fixing of dual-directional refelctive speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side)provided with twp steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No.GPL-07-02 Make GREENs or equivalent as per direction of Engineer-in-charge including carriage of materail within all leads and lifts .	51.00	each							
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018									G.Total	
2) The rates shall be including of all types of taxes including GST ectra)										
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021										

Kumhar
Executive Engineer
Una Divn.HP.PWD.,Una