

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-

7941-57

Dated:- 27/03/2025

To,


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage rate tenders on the form 6&8 are hereby invited by the Executive Engineer Fatehpur Division HPPWD., Fatehpur on behalf of the Governor of HP for the below noted works from eligible Contractors/firms registered in HPPWD in appropriate class as per revised enlistment rules. So as to reach in this office on or before 09.04.2025 up to 12:00 Noon and the same shall be opened on the same day at 12:30 PM in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 08.04.2025 upto 4:00 PM. The application for issued of tender form shall be received for 07.04.2025 up to 4:30.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/ bank in HP duly pledged in the favour of undersigned.

Conditional tenders telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Fatehpur Division HP PWD at Fatehpur reserves the right to accept or reject the tenders. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible-class of Contractor
✓ 1	Repair of Rajasav Sadan due to rain damage at Fatehpur in Tehsil Fatehpur Distt. Kangra (H.P.) (Under SDRF) Deposit work (SH:- Providing and fixing Ceiling in 1st floor).	98896.00	2000.00	One Month	350/-	Class D&C
✓ 2	Construction and Metalling/Tarring of Maira Palli road (SH:- Providing and laying cement concrete pavement at RD 0/077 to 0/080 and 0/120 to 0/131)	96857.00	2000.00	One Month	350/-	Class D&C
✓ 3	Construction and Metalling/Tarring of Maira Palli road (SH:- Construction of U-shape drain at RD 0/085 to 0/120 LHS and down stream side Nalla 0/0 to 0/011)	91952.00	1900.00	One Month	350/-	Class D&C
✓ 4	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III , pot holes at RD 1/472 to 1/627)	97166.00	2000.00	One Month	350/-	Class D&C
✓ 5	Construction of Drainage near the house of Onkar Singh etc. village Bhatoli Pakwan in G.P Bhatian (Under MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/007) <i>HO</i>	48648.00	1000.00	One Month	350/-	Class D&C
✓ 6	Repair of Mahila Snan Ghar in village Jhikla Moch in G.P Sunet (Under MLALAD) Deposit work (SH:- Repair of plaster , steel sheet , tile in floor and walls, Distempering and sanitary item etc).	95695.00	2000.00	One Month	350/-	Class D&C
7	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III , pot holes at RD 2/102 to 2/257)	98323.00	2000.00	One Month	350/-	Class D&C
8	Repair of Rajasav Sadan due to rain damage at Fatehpur in Tehsil Fatehpur Distt. Kangra (H.P.) (Under SDRF) Deposit work (SH:- Providing and fixing steel work of prepainting CGI Sheet in 1st floor). <i>with ceiling.</i>	95427.00	2000.00	One Month	350/-	Class D&C

9	Construction of road Hans Raj Ghar se Ramswaroop ke Ghar tak village Khatta (Under MLALAD) Deposit work (SH:- Construction of Retaining wall to protect the existing road towards vilaage Khatta).	95370.00	2000.00	One Month	350/-	Class D&C
10	Construction of Retaining wall near the house of Karnail Singh in village Bari (Under MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/155 to 0/175).	97781.00	2000.00	One Month	350/-	Class D&C
11	Construction of Pucca path from Anil Restaurant to tubewell in village chamral (Under MLALAD) Deposit work (SH:- Providing and laying Cement concrete pavement at RD. 0/0 to 0/045).	95114.00	1900.00	One Month	350/-	Class D&C
12	Construction of protection work near the house of Rumila Bibi in village Duhag Tehsil Fatehpur Distt. Kangra (H.P.) (Under SDP) Deposit work (SH:- Constructin of breast wall for protection of existing house)	66666.00	1400.00	One Month	350/-	Class D&C
13	Preparation of Detailed and working estimate for the Construction of additional accommodation for HPPWD rest house at Fatehpur, Tehsil Fatehpur, Distt Kangra (H.P.) along with DNIT	50000.00	1000.00	One Month	350/-	Class D&C
14	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III , pot holes at RD 1/945 to 2/100)	97132.00	2000.00	One Month	350/-	Class D&C
15	Construction and Metalling/Tarring of Maira Palli road (SH:- Construction of U-shape drain Nalla at RD 0/011 to 0/034	92873.00	1900.00	One Month	350/-	Class D&C
16	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III , pot holes at RD 1/787 to 1/942)	97396.00	2000.00	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders from will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is **within limit of (+) 5%** of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

6

SCHEDULE OF QUANTITY

Name of work:- Repair of Rajsav Sadan due to rain damage at Fatehpur in Tehsil Fatehpur Distt. Kangra (HP) (Under SDRF)					
Deposit work (SH:- Providing and fixing 1st floor ceiling)					
Estimated cost:- Rs.98896/- only					
Earnest Money : Rs.2000/- only					
Time limit:- One month					
Sr.N o	Description of items	Quantity	Rate		Amount
			In words	In figures	
1	Providing asbestos cement corrugated sheets roofing fixed with galvanised iron J or L hooks bolts and nuts 8mm (eight millimetre) dia G.I. plain bituman washers complete excluding the cost of purlins rafters and trusses 6mm (six millimetre) thick sheet including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, sale tax, malkana and all other taxes as imposed by the Government.	137.26 square meter	720.50	Rupees Seven Hundred Twenty meter And Paise Fifty Only	98896.00
				Total:-	98896.00
	Amount quoted by the contractor in % Above/Below				

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P)

2402

SCHEDULE OF QUANTITY

Name of work:- Construction and Metalling/Tarring of Maira Palli road (SH:- Providing and laying cement concrete pavement at R.D. 0/077 to 0/080 and 0/120 to 0/131)				Estimated cost:- Rs.96857/- only	
				Earnest Money : Rs.2000/- only	
				Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Amount
			In words	In figures	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax. sale tax, GST or other taxes imposed by the Government.	17.95 Cubic meter.	5395.95	Rupees Five Thousand Three Hundred Ninety Five And Paise Ninety Five Only	96857.00
				Total:-	96857.00
	Amount quoted by the contractor in % Above/Below				


 Executive Engineer
 Fatahgaon Division HPPWD
 Fatahgaon Distt. Kangra (H.P.)

7063

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY									
Name of work:- Construction and Metalling/Tarring of Maira Palli road (SH:- Construction of U-shape drain at R.D. 8/785 to 8/820 LHS and down stream side Nalla 0/0 to 0/011).									
Estimated cost:- Rs.91952/- only									
Earnest Money : Rs.1900/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	23.21 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	7880.00			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	18.89 Cubic meter.	4450.60	Rupees Four Thousand Four Hundred Fifty And Paise Sixty Only	Per cubic meter	84072.00			
						Total:-	91952.00		
Amount quoted by the contractor in % Above/Below									


 Engineer
 Division Highway
 District, Kangra

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan to Nawar Shahar via Choumka Road km. 0/000 to 3/375 (SIH:- Providing and laying G-III, Estimated cost:- Rs.97166/- only
Pot holes at R.D. 1/472 to 1/627). Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.44 cubic meter	1705.10	Rupees One Thousand Seven Hundred Five And Paise Ten Only	Per cubic meter	16096.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	242.00 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	81070.00
					Total:-	97166.00

Amount quoted by the contractor in % Above/Below

[Handwritten signature]

2065

SCHEDULE OF QUANTITY

Name of work:-Construction of Drainage near the house of Onkar Singh etc. village Bhatoli Pakwan G.P. Bhatian (Under MLALAD)
 Deposit work (SH):- Construction of PCC Retaining wall at R.D. 0/0 to 0/007.40)

Estimated cost:- Rs.48648/- only
 Earnest Money : Rs.1000/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	5.33 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	1810.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.14 Cubic meter.	3550.40	Rupees Three Thousand Five Hundred Fifty And Paise Forty Only	Per cubic meter	36001.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6 Numbers	320.00	Rupees Three Hundred Twenty Only	Each	1920.00
4	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimeter) dia G.I. (Galvanized iron) wire conforming to IS:280 and IS:4826(IS : Two hundred eighty and IS : Four thousand eight hundred twenty six) in 100mm x 100mm mesh (one hundred into one hundred millimeter mesh) (woven diagonally) including 10 percent (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg. (Twenty five kilogramme) each as per drawings and M.O.R.D. technical specifications clause 1301 (One block of crate work should not be more than 2.50x1.25x1.25mm. (two point five zero into one point two five into one point two five millimeter) and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.91 cubic meter	2280.60	Rupees Two Thousand Two Hundred Eighty And Paise Sixty Only	Per cubic meter	8917.00
					Total:-	48648.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (P.P.)

SCHEDULE OF QUANTITY

Name of work:- Repair of Mahila Suan Ghar in village Jhikla Moch G.P. Sanet (Under MLALAD) Deposit work (SH:- Repair of plaster, repainted, steel sheet, tile in floor and walls, distemper and sanitary items etc.)

Estimated cost:- Rs.95695/- only
Earnest money Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	55.53 square meter	22.25	Rupees Twenty Two And Paise Twenty Five Only	Per square meter	1236.00
2	15mm (fifteen millimeter) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement isto six coarse sand) both side including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	55.53 square meter	208.60	Rupees Two Hundred Eight And Paise Sixty Only	Per square meter	11584.00
3	Providing and fixing 0.60mm. (zero point six zero millimeter) thick prepaainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with prepaainted iron J or L hooks, bolts and nuts 6mm (six millimeter) dia meter with prepaainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate includes royalty charges, octroi, GST, sale tax, malkhana and all other taxes as imposed by the Government.	10.00 square meter	1450.40	Rupees One Thousand Four Hundred Fifty And Paise Forty Only	Per square meter	14504.00
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	200.00 kilogram	115.00	Rupees One Hundred Fifteen Only	Per kilogram	23000.00
5	Providing and laying Rectified glazed ceramic floor tiles of size 300x300 mm (three hundred into three hundred millimeter) or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except white, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetre) thick bed of cement mortar 1:4 (one Cement isto four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etcetera complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	13.38 square meter	1150.65	Rupees One Thousand One Hundred Fifty And Paise Sixty Five Only	Per square meter	15396.00

6	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (twelve millimeter) thick bed of cement Mortar 1:3 (one cement into three coarse sand) and jointing with grey cement slurry @ 3.5kg per sqm including pointing in white cement mixed with pigment of matching shade complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	7.56 square meter	1259.70	Rupees One Thousand Two Hundred Fifty Nine And Paise Seventy Only	Per square meter	9523.00
7	Finishing walls with water proofing cement paint of required shade Old work (one or more coats applied @ 2.20 kg/10 sqm) (two decimal two zero kilogram/ten square metre) over priming coat of primer applied @ 0.80 litre/10 sqm Zero decimal eight zero litre/ ten square metre) complete including cost of Priming coat including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	23.52 square meter	69.20	Rupees Sixty Nine And Paise Twenty Only	Per square meter	1628.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level 1:3:6 (one cement into three coarse sand into six graded stone aggregate) 40mm (forty millimeter) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1.000 cubic meter	4520.95	Rupees Four Thousand Five Hundred Twenty And Paise Ninety Five Only	Per cubic meter	4521.00
9	Providing and fixing glazing in aluminium door, window, ventilator shutters and partition etc. with PVC/neoprens gasket as per the architectural drawings and the directions of Engineer-In charge (cost of aluminium snap beading shall be paid in basic item.) weight not less than 10.00 kg/sqm (ten kilogramme/square meter) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.00 square meter	1150.20	Rupees One Thousand One Hundred Fifty And Paise Twenty Only	Per square meter	3451.00
10	Providing and fixing PTMT soap dish holder having length of 158mm (one hundred thirty eight millimeter) breadth 102mm (one hundred two millimeter) height of 75mm (seventy five millimeter) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six gram) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2 Numbers	130.50	Rupees One Hundred Thirty And Paise Fifty Only	Each	261.00

11	Providing and fixing 15mm (fifteen millimetre) nominal bore brass bib cock of approved quality including carriage of materials within all 2	302.55	Rupees Three Hundred Two And Paise Fifty Five Only	Each	605.00
	by the Government.				
12	Providing and fixing 15mm (fifteen millimetre) nominal bore to wall ceiling and floor galvanised mild steel tubes (lighting grade) tube fitting and clamps including making good the wall, ceiling and floor including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	240.15	Rupees Two Hundred Forty And Paise Fifteen Only	Per running meter	2402.00
13	Providing and fixing 650x20mm (six hundred fifty two twenty millimetre) C.P. brass towel rail complete with C.P. brackets fixed to wooden plugs with C.P. brass including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	392.00	Rupees Three Hundred Ninety Two Only	Each	784.00
14	Providing and fixing water tank 500 litre (five hundred litre) including all fittings etc. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	6.80	Rupees Six And Paise Eighty Only	Per litre	6800.00
				Total:-	95695.00
	Amount quoted by the contractor in % Above/Below				


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

2067

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan to Nawar Shahar via Chounka Road km. 0/000 to 3/375 (SH:- Providing and laying G-III, Estimated cost:- Rs.98323/- only
 Pot holes at R.D. 2/102 to 2/257). Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.18 cubic meter	1696.90	Rupees One Thousand Six Hundred Ninety Six And Paise Ninety Only	Per cubic meter	15578.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	247.00 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	82745.00
					Total:-	98323.00

Amount quoted by the contractor in-% Above/Below

Executive Engineer
 Fatehpur Division HPP&ID
 Fatehpur Distt. Kangra (H.P.)

8902

SCHEDULE OF QUANTITY

Name of work:- Repair of Rajsav Sadan due to rain damage at Fatehpur in Tehsil Fatehpur Distt. Kangra (HP) (Under SDRF)			Estimated cost:- Rs.95427/- only			
Deposit work (SH):- Providing and fixing steel work of pre-painted CGI sheet in 1st floor with ceiling)			Earnest Money : Rs.2000/- only			
Description of items			Quantity	Time limit:- One month		Amount
				In words	Rate In figures	
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads, lifts and other incidental. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	321.16 Kilogram	107.90	Rupees One Hundred Seven And Paise Ninety Only	Per Kilogram	34653.00
2	Providing and fixing M.S.(mild steel) BP (Black plain) sheet 1.66mm to 2mm (one point six six millimetres to two millimetres) thick in eaves board/facia soffits/ ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-Charge (Base members of steel work shall be measured and paid separately) for (Facia and Ceiling) including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, sale tax, malkana and all other taxes as imposed by the Government.	40.24 square meter	1510.30	Rupees One Thousand Five Hundred Ten And Paise Thirty Only	Per Square meter	60774.00
					Total:-	95427.00
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of road Hans Raj Ghar se Ramswaroop Ke Ghar Tak village Khatta (Under MLALAD) Deposit work (SH):- Construction of Retaining wall to protect the existing road towards village Khatta)

Estimated cost:- Rs.95370/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental .	8.93 Cubic meter	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3032.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete for plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.03 Cubic meter	3450.40	Rupees Three Thousand Four Hundred Fifty And Paise Forty Only	Per cubic meter	89814.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilograms (four point five kilograms) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.700, 1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	315.50	Rupees Three Hundred Fifteen And Paise Fifty Only	Each	2524.00
					Total:-	95370.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

2010

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Karnail Singh in village Bari (Under MLALAD)						
Deposit work (SH:- Construction of Retaining wall at R.D. 0/155 to 0/175)						
Estimated cost:- Rs.97781/- only						
Earnest Money : Rs.2000/- only						
Time limit:- one month						
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	9.40 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3191.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.40 cubic meter	3450.90	Rupees Three Thousand Four Hundred Fifty And Paise Ninety Only	Per cubic meter	91104.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government .	12 Numbers	290.50	Rupees Two Hundred Ninety And Paise Fifty Only	Each	3486.00
					Total:-	97781.00
	Amount quoted by the contractor in % Above/Below					

Engineer

Super Division HPPWD

Fatehpur, Dist. Kangra (P.P.)

7000 11

SCHEDULE OF QUANTITY						
Name of work:- Construction of Pucca Path from Anil Resturant to Tubewell in village Chamral (Under MLALAD) Deposit work (SI:- Providing and laying cement concrete pavement at R.D. 0/00 to 0/045)				Estimated cost:- Rs.95114/- only		
				Earnest Money : Rs.1900/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interslices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.52 cubic meter	1696.50	Rupees One Thousand Six Hundred Ninety Six And Paise Fifty Only	Per cubic meter	4275.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.74 Cubic meter.	5120.60	Rupees Five Thousand One Hundred Twenty And Paise Sixty Only	Per cubic meter	90839.00
					Total:-	95114.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Kanara

SCHEDULE OF QUANTITY

Name of work:- Construction of protection work near the house of Rumila Bibi in village Duhag Tehsil Fatehpur Distt. Kangra (H.P.) Under SDP (Deposit work) (SH:- Construction of breast wall for protection of existing house)

Estimated cost:- Rs.66666/- only
Earnest Money : Rs.1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.08 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3422.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D. technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.75 cubic meter	3550.00	Rupees Three Thousand Five Hundred Fifty Only	Per cubic meter	59463.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 Numbers	315.10	Rupees Three Hundred Fifteen And Paise Ten Only	Each	3781.00
					Total:-	66666.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur-Distt. Kangra (H.P.)

20613 337 322
2024-25

PERCENTAGE BILL OF QUANTITY

ESTIMATED COST :-	Rs.50,000/-
EARNEST MONEY :-	Rs.2,000/- 1000/-
TIME LIMIT :-	One Month

NAME OF WORK: -Preparation of Detailed and working estimate for the Construction of additional accomodation for HPPWD Rest House at Fatehpur, Tehsil-Fatehpur, Distt. Kangra (H.P) along with DNT.

S.No.	Description of items	Qty.	Rate		Unit	Amount
			In figures	In words		
1.0	Additional accomodation for HPPWD Rest House at Fatehpur, Tehsil-Fatehpur, Distt. Kangra (H.P) along with DNT on prevailing market rates, abstract of cost, detail of measurements and analysis of rates complete in all respect and also providing 3 (Three) number of hard copies to the department. If any correction/amendment has desired by the head office, the same may be corrected as desired and getting approval thereof from the competent authority by getting the detailed estimate/DNT checked as and when required from Circle Office Nurpur, Chief Office Dharamshala, and as per the direction and entire satisfaction of Engineer-In-charge as per approved drawings from this office. The estimate will consists the following components:- Building Block, Water Supply & Sanitary Installation, Rainwater Harvesting Tank, Septic Tank & Soak Pit, Site development, Boundary wall.	1.00	50000.00	Rupees Fifty Thousand Only	Per Job	50,000.00
TOTAL						50,000.00
			% above/Below			
			Quoted amount in figures			
			Quoted amount in words			

as per schedule quantity checked and approved for Rs 50,000 and Rs. fifty thousand only

Terms & Condition:-

- 1.0 10% payment will be released after the submission to the Divison Office Fatehpur.
- 2.0 Next 20% payment will be released after getting detailed estimate checked from Circle Office Nurpur.
- 3.0 Next 20% payment will be released after getting detailed estimate checked from Chief Office Dharamshala.
- 4.0 Next 40% payment will be released after getting working estimate checked from Circle Office Nurpur/Chief Office Dharamshala.
- 5.0 Remaining payment will be released after getting DNT checked from Circle Office Nurpur/ Chief Office Dharamshala.

Executive Engineer,
Fatehpur Division,
HPPWD Fatehpur

20614

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan to Nawan Shahar via Chouinka Road km. 0/000 to 3/375 (SH:- Providing and laying G-III, Estimated cost:- Rs.97132/- only
Pot holes at R.D. 1/945 to 2/100), Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading - III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.49 cubic meter	1710.10	Rupees One Thousand Seven Hundred Ten And Paise Ten Only	Per cubic meter	16229.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	241.50 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	80903.00
					Total:-	97132.00

Amount quoted by the contractor in % Above/Below

Signature of Engineer
Fateh Singh
Fateh Singh Kangra (H.D.)

2015

SCHEDULE OF QUANTITY

Name of work:- Construction and Metalling/Tarring of Maira Palli road (SH:- Construction of U-shape drain/Nalla at R.D. 0/011 to 0/034).										Estimated cost:- Rs.92873/- only		Earnest Money : Rs.1900/- only		Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount									
			In words	In figures											
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	29.33 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	9958.00									
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heighis/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	18.63 Cubic meter.	4450.60	Rupees Four Thousand Four Hundred Fifty And Paise Sixty Only	Per cubic meter	82915.00									
						Total:-	92873.00								
Amount quoted by the contractor in % Above/Below															

Executive Engineer
Fatehpur Division H.P.W.D.
Fatehpur, Distt. Kangra (H.P.)

Job 18

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan to Nawar Shahar via Choukka Road km. 0/000 to 3/375 (SH:- Providing and laying G-III, Estimated cost:- Rs.97396/- only
 Pot holes at R.D. 1/787 to 1/942). Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and bronning, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading - III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.93 cubic meter	1696.90	Rupees One Thousand Six Hundred Ninety Six And Paise Ninety Only	Per cubic meter	15153.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat ' type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	245.50 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	82243.00
					Total:-	97396.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
 State Road Division H.P.W.D.
 Fatehgarh Sahib, Kangra (H.P.)