

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PWCB/CB-GA/Tender/2024-25-

18/12- 18230

Dated:- 10-3-2025

To


The Executive Engineer (IT Cell),
Nigam Bihar, Himachal Pradesh Shimla-2.
cc-pwd-hp@nic.in

Subject: - Publication of Tender Notice

Sir,

Enclosed please find herewith notice of various work as given in the tender inviting tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest. .


Your's Faithfully,


Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

DA/As above.

Copy forwarded to the following for information please :-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, Kangra Zone, HP.PWD.Dharamshala.
3. Deputy Commissioner Chamba District Chamba.
4. All the Superintending Engineers/Executive Engineer in HPPWD
5. All the Assistant Engineer under Bharmour Division.
6. Additional District Magistrate Bharmour.
7. The Superintendent of Police Chamba.
8. Labour Officer Chamba.
9. Notice Board of this office


Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS

Sealed percentage rate tenders on from 6 & 8 are hereby invited by the Executive Engineer, Bharmour Division, HP.PWD. Bharmour on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form 17.03.2025 up to 1.00 PM

Date and time of issue/Sale of tender form- 17.03.2025 at 2:00 PM to 04:30 PM

Date and time of receipt of tender form-18.03.2025 up to 11:30 AM

Date and time of opening tender form- 18.03.2025 at 3:30 PM

The tender form can be had from the office of the Executive Engineer against Cash (Non-refundable). The earnest money should be in the shape of Fixed Deposit duly pledged in favour of the Executive Engineer Bharmour Division HPPWD Bharmour must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for 75 days. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.

Sr. No.	Name of work	Estimated cost	EMD	Cost of Tender	Time Allowed	Class of Contractor
1.	Restoration of snow Damage on KSPA road Km 0/00 to 13/00 (SH:- Removal of snow at various Rds	98056/-	2000/-	Rs. 350/-	Three month	Class C & D only
2.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O E/Wall at RD 10/970 to 10/990.	96272/-	2000/-	Rs. 350/-	Three month	Class C & D only
3.	Restoration of snow Damage under Garola Sub Division at various Road (SH:- Removal of snow at various Rds	98000/-	2000/-	Rs. 350/-	Three month	Class C & D only
4	Restoration of snow Damage under Garola Sub Division at various Road (SH:- Removal of snow at various Rds	98000/-	2000/-	Rs. 350/-	Three month	Class C & D only
5	Restoration of snow Damage under Garola Sub Division at various Road (SH:- Removal of snow at various Rds	98000/-	2000/-	Rs. 350/-	Three month	Class C & D only
6	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD 0/240 to 0/245.70	99863/-	2000/-	Rs. 350/-	Three month	Class C & D only
7.	Restoration of snow damage on Dhakog to Badgram road (SH:- Removal of snow at various Rds	98056/-	2000/-	Rs. 350/-	Three month	Class C & D only
8	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD 0/257.10 to 2/262.80	99876/-	2000/-	Rs. 350/-	Three month	Class C & D only
9	Restoration of snow Damage under Garola Sub Division at various Road (SH:- Removal of snow at various Rds	98000/-	2000/-	Rs. 350/-	Three month	Class C & D only

10.	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD0/251.40 to 0/257.10)	99727/-	2000/-	Rs. 350/-	Three month	Class C & D only
11.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O E/Wall at RD 11/178.55 to 11/187.05 including toe wall)	99495/-	2000/-	Rs. 350/-	Three month	Class C & D only
12.	A/R & M/O to various road under Garola Sub Division (SH:- Removal of slips & Boulder at various Rds)	99781/-	2000/-	Rs. 350/-	Three month	Class C & D only
13.	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD 0/262.80 to 0/268.50)	99863/-	2000/-	Rs. 350/-	Three month	Class C & D only
14.	A/R & M/O to various road under Garola Sub Division (SH:- Removal of slips & Boulder at various Rds)	99550/-	2000/-	Rs. 350/-	Three month	Class C & D only
15.	A/R & M/O to various road under Garola Sub Division (SH:- Removal of slips & Boulder at various Rds)	99660/-	2000/-	Rs. 350/-	Three month	Class C & D only
16.	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD 0/360 to 0/363.95)	99130/-	2000/-	Rs. 350/-	Three month	Class C & D only
17.	A/R & M/O to various road under Garola Sub Division (SH:- Removal of slips & Boulder at various Rds)	99715/-	2000/-	Rs. 350/-	Three month	Class C & D only
18.	A/R & M/O to various road under Garola Sub Division (SH:- Removal of slips & Boulder at various Rds)	99748/-	2000/-	Rs. 350/-	Three month	Class C & D only
19.	Construction of Panhernu to Sanahan road (SH:- C/O R/wall at RD 0/530 to 0/539.50)	99455/-	2000/-	Rs. 350/-	Three month	Class C & D only
20.	Restoration of rain damage on Surge Shaft to Arki road Km 0/00 to 17/00 (SH Removal of slips at various Rds)	99120/-	2000/-	Rs. 350/-	Three month	Class C & D only
21.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O E/Wall at RD 8/220 to 8/226.75 including toe wall)	99469/-	2000/-	Rs. 350/-	Three month	Class C & D only
22.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O E/Wall at RD 8/233.45 to 8/240 including toe wall)	96507/-	2000/-	Rs. 350/-	Three month	Class C & D only
23.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O E/Wall at RD 11/178.55 to 11/187.05 including toe wall)	98936/-	2000/-	Rs. 350/-	Three month	Class C & D only
24.	A/R & M/O on various road in Holi Sub and Dalli Section (SH:- Painting and art panting of Ordinary Km stones 200mtr stones and information sign board etc)	99981/-	2000/-	Rs. 350/-	Three month	Class C & D only

25	A/R & M/O on various road in Holi Sub Division Dalli Section (SH:- Painting and art panting of Ordinary Km stones 200mtr stones and information sign board etc	99981/-	2000/-	Rs. 350/-	Three month	Class C & D only
26	Special Repair of SDM residence at Helipad Bharmour SH:- Repair of stair and Boundary wall	97868/-	2000/-	Rs. 350/-	Three month	Class C & D only
27	Special Repair of SDM residence at Helipad Bharmour SH:- Repair of stair and Boundary wall	97106/-	2000/-	Rs. 350/-	Three month	Class C & D only
28	Construction of New Hospital building at Choori, Distt Chamba, HP Preparation of DPR	99500/-	2000/-	Rs. 350/-	Three month	Class C & D only
29	1.Construction of Govt. Senior Secondary School Building at Ullansa, Tehsil Bharmour, Distt. Chamba (H.P.) Preparation of DPR 2 Construction of Doctor residence building at Choori, Distt. Chamba (H.P.) Preparation of DPR	99999/-	2000/-	Rs. 350/-	Three month	Class C & D only
30	Annual Repair and maintenance on KSPA Road Km 13/00 to 40/00 SH:-C/oSub grade and earthen shoulder C/o unlined drain cutting of bushes surface dressing etc various Rds	99388/-	2000/-	Rs. 350/-	Three month	Class C & D only
31	Annual Repair and maintenance on churi to Lylh Road SH:-C/oSub grade and earthen shoulder C/o unlined drain cutting of bushes surface dressing etc various Rds	99388/-	2000/-	Rs. 350/-	Three month	Class C & D only

Certificate: - It is certified that the tenders of above works are exlgency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ Acknowledgement of up to date filed GST Return along with Certificate of GST Registration as per Condition No. 16(iii)/ EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected. 3. The offer shall remain valid up to 75 days.
4. The contractor should not have more than two contracts within Division at a time tender. If the contractor has already two works in hand then the tender not excepted at the time of opening of tender and the same will be rejected technical evaluations.
5. If the contractors found lowest more than two works during the opened of bid then two works awarded to contractor at the one time and then opportunity will be given to next lowest bidder.
6. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.

7. The contractor /bidders must inspect the site to ascertain /famillar the site conditions, accessibility etc. before quoting the bid/tender.


8. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.

9. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.

10. The provislons of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification Issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-In-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996- 38095 dated 13.03.2023.



Executive Engineer,
Bharmour Division,
HP.PWD; Bharmour

Dated:- 7.02.2025

NO/PW/CB/GA /Tender/2024-25 - 16760-16859

Copy forwarded for Information & necessary action to:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, Kangra Zone, HP.PWD.Dharamshala.
3. Deputy Commissioner Chamba District Chamba.
4. All the Superintending Engineers/Executive Engineer in HPPWD
5. All the Assistant Engineer under Bharmour Division.
6. Additional District Magistrate Bharmour.
7. The Superintendent of Police Chamba.
8. Labour Officer Chamba.
9. Notice Board of this office


Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 98056.00
 EARNMENT MONEY :- Rs 20000
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of snow Damage on KSPA Road Km 00/00 to 13/00
 SUB-HEAD :- Removal of snow at Various fds

Sr. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig.	Words	Fig.	Words		
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sides as per MORTH and IRC specification 48-1998 as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	17510.00	Cubic metres	5.60	Rs per Five And Paise Sixty Only	per cubic metre	98056.00
Total							98056.00

quoted rate in figure
 quoted rate in words

Dr. H. T. Approved As 98056/only

Executive Engineer,
 Bhairamgarh Div. Bhairamgarh
 H.E.P.W.D. Bhairamgarh

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 96272.00
EARNEST MONEY :- Rs 1925.00
TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of KSPA road km 0/000 to 13/000

SUB-HEAD :- C/O Elwall at RD 10/970 to 10/990

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Words			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge	11.00	Cubic metres	610.10	Rupees six hundred ten and paise ten only	Per cubic metre	6711.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	2.03	Cubic metres	5332.00	Five thousands three hundred thirty two only	Per cubic metre	10824.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	24.00	Cubic metres	3280.70	Rupees three thousands two hundred eighty and paise seventy only	Per cubic metre	78737.00
GROSS TOTAL =							96272.00
Quoted rate in figure							
Quoted rate in words.							

Print Approved for Rs = 96,272/- only

Executive Engineer,
Bhamour Division,
HPPWD Bhamour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- **Rs 98000.00**
 EARNEST MONEY :- **Rs 20000**
 TIME LIMIT **THREE MONTHS**

NAME OF WORK : Restoration of snow Damage Under Garola sub Division at Various Road

SUB-HEAD :- Removal of snow at Various rds

Sr. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sides per MORTH and IRC specification 48-1998 as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17500.00	Cubic metres	5.60	Rupers Five And Paise Sixty Only	Per cubic metre	98000.00
Total							98000.00

Quoted rate in figure
 Quoted rate in words

Unit Approved Rs 98000/- only


 Executive Engineer,
 Bharmour Division,
 HPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 98000.00
 HARVEST MONEY :- Rs 20000
 THREE MONTHS
 TIME LIMIT

NAME OF WORK : Restoration of snow Damage Under Garola sub Division at Various Road
 SUB-HEAD : Removal of snow at Various rds

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sides as per MCH TH and IRC specification 48-1-978 as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	17500.00	Cubic metres	5.60	Rupess Five And Paise Sixty Only	Per cubic metre	98000.00
Total							98000.00

Quoted rate in figure
 Quoted rate in words

Price approved Rs 98000/- only

Executive Engineer,
 Bharmour Division,
 HPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of snow Damage Under Garola sub Division at Various Road
 SUB-HEAD :- Removal of snow at Various rds

ESTIMATED COST :- Rs 98000.00
 EARNEST MONEY :- Rs 20000
 TIME LIMIT THREE MONTHS

Sr. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sides per MORTH and IRC specification 48-1 208 as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17500.00	Cubic metres	5.60	Rupees Five And Paise Sixty Only	Per cubic metre	98000.00
Total							98000.00

Quoted rate in figure
 Quoted rate in words

Unit Offered Rs 9800/- only

Executive Engineer,
 Bharmour Division,
 HPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 99863.00
EARNEST MONEY :- Rs 20000.00
TIME LIMIT THREE MONTHS

NAME OF WORK :- Construction of Panheru Janni to Sanathan road
SUB-HEAD :- Construction of R.Wall at RD 0240 to 0245.70

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig.	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.C.R.D technical specification clause 305 and 1603.4 and as per direction of the Engineer. In- Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.43	259.90	Rupees Two Hundred Fifty Nine And Paise Ninety Only	Per cubic metre	3231.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1.6 12 (One cement. Six sand. Twelve graded/crushed stone aggregate 40mm (Forty millimetres) nominal size) in road work as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.14	4407.70	Rupees Four Thousand Four Hundred Seven And Paise Seventy Only	Per cubic metre	13840.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1.4 8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	4914.40	Rupees Four Thousand Nine Hundred Fourteen And Paise Forty Only	Per cubic metre	9829.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.40	3306.00	Rupees Three Thousand Three Hundred Six Only	Per cubic metre	40994.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.03	1599.80	Rupees One Thousand Five Hundred Ninety Nine And Paise Eighty Only	Per cubic metre	24043.00

6 Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and by per direction of Engineer - In-Charge including carriage of materials within all loads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.

8.38

Cubic
metres

945 60

Rupees Nine Hundred
Forty Five And Paise
Sixty Only

Per cubic
metre


7924.00

Total :- 99863.00

Quoted rate in figure

Quoted rate in words

Don't Approved Rs 99863/- only


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK : Restoration of snow Damage on Dhakog to Badgram road
SUB-HEAD :- Removal of snow at Various rds

ESTIMATED COST :- Rs 98056.00
 EARNEST MONEY :- Rs 20000
 TIME LIMIT THREE MONTHS

Sr. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sides as per MORTH and IRC specification 48-1998 as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17510.00	Cubic metres	5.60	Rupres Five And Paise Sixty Only	Per cubic metre	98056.00
					Total		98056.00

Quoted rate in figure *Draft Approved Rs 98056/- only*
Quoted rate in words


 Executive Engineer,
 Bharnagar Division,
 HPPWD Bharnour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 99876.00
EARNEST MONEY :- Rs 1000.00
TIME LIMIT THREE MONTHS

NAME OF WORK : Construction of Parkernu Janni to Sanathan road
SUB-HEAD :- Construction of R.wall at RD 0/257.10 to 2/262.80

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer - In - Change including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of silt which may arise out during dewatering as per direction of Engineer - In - Change including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.48	259.90	Rupees Two Hundred Fifty Nine And Paise Ninety Only	Per cubic metre	3244.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical M.O.R.D. specifications Clause 802, 803, 1202 & 1203 1.6 1.2 (One cement Six sand Twelve graded/crushed stone aggregate 40mm (four millimetres) nominal size) in road work as per direction of Engineer - In - Change including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.14	4407.70	Rupees Four Thousand Four Hundred Seven And Paise Seventy Only	Per cubic metre	13840.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical M.O.R.D. specifications Clause 802, 803, 1202 & 1203 1.4 8 (One cement iso four sand iso eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per direction of Engineer - In - Change including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	4914.40	Rupees Four Thousand Nine Hundred Fourteen And Paise Forty Only	Per cubic metre	9829.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement iso six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per direction of Engineer - In - Change including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.40	3306.00	Rupees Three Thousand Three Hundred Six Only	Per cubic metre	40994.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per direction of Engineer - In - Change including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.03	1599.80	Rupees One Thousand Five Hundred Ninety Nine And Paise Eighty Only	Per cubic metre	24445.00

6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M O R D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all loads and lifts and other incidental. The rate including octroi, royalty, Malhana, toll tax, sale tax or other taxes imposed by the Government.	8.38	Cubic metres	945.60	Supers Nine Hundred Forty Five And Paise Sixty Only	Per cubic metre	7924.00
Total :- 99876.00							

quoted rate in figure

quoted rate in words

Unit Approved As 99876/- only

Approved
 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 98000.00
 EARNMENT MONEY :- Rs. 20000/-
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of snow Damage Under Garola sub Division at Various Road
 SUB-HEAD :- Removal of snow at Various rds

Sr. No.	Description of work	Quantity		Fig	RATES		Unit	Amount
					Words			
1	Snow clearance from road surface by a Bulldozer 165 HP and disposing it on the velly sidesas per MORTH and IRC specification 48-1998 as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17500.00	Cubic metres	5.60	Rupess Five And Paise Sixty Only		Per cubic metre	98000.00
					Total			98000.00

quoted rate in figure
 quoted rate in words.

Shit Approved Rs 98000/-only

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 99727.80
EARNEST MONEY :- Rs 2000.00
TIME LIMIT THREE MONTHS

NAME OF WORK : Construction of Panhermu Jannu to Saraban road
SUB-HEAD :- Construction of R/wall at RD 0/251 40 to 0/257 10

SL No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any head and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during de-watering as per direction of Engineer - In- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	11.91	259.90	Rupees Two Hundred Fifty Nine And Paise Ninety Only	Per cubic metre	30995.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:6:12 (One cement, Six sand, Twelve graded/crushed stone aggregate 40mm (four millimetres) nominal size) in road work as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.14	4407.70	Rupees Four Thousand Four Hundred Seven And Paise Seventy Only	Per cubic metre	13840.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	2.00	4914.40	Rupees Four Thousand Nine Hundred Fourteen And Paise Forty Only	Per cubic metre	9829.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	12.40	3306.00	Rupees Three Thousand Three Hundred Six Only	Per cubic metre	40994.40
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	15.03	1599.80	Rupees One Thousand Five Hundred Ninety Nine And Paise Eighty Only	Per cubic metre	24045.00


Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M O R D technical specifications clause 1603 7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all heads and tails and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government

8.38	Cubic metres	945 60/Ruppes Nine Hundred Forty Five And Paise Sixty Only	Per cubic metre	7924.00
Total :- 99727.00				

Quoted rate in figures

Quoted rate in words

Unit Approved RS 99727/- only


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 2000.00
 EARNEST MONEY Rs 200.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of KSPA road km 0/000 to 13/000

SUB-HEAD :- C/O Elwalai RD 11/178.55 to 11/187.05 including Toe wall

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1/13.08 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge	Cubic metres	610.10	Rupees six hundred ten and paise ten only	Per cubic metre	7565.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1/4.8 (One cement 1st to four sand 1st to eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	Cubic metres	5332.00	Five thousands three hundred thirty two only	Per cubic metre	54795.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	Cubic metres	3280.70	Rupees three thousands two hundred eighty and paise seventy only	Per cubic metre	2885.00
GROSS TOTAL :-						65145.00
Quoted rate in figures						
Quoted rate in words.						

DMIT approved for Rs=99445/only

Executive Engineer,
 Bhavnagar Division,
 HPPMD Bhavnagar

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A.R. & M.O. to Various road under Garola Sub division

SUB-HEAD :- Removal of slips & Boulders at Various R.D.S)

ESTIMATED COST :-

RS 99781.00

EARNEST MONEY :-

RS 1996.00

TIME LIMIT :-

ONE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of slips /land slid in hilly area in all kinds of soft/te ordinary rock, not required blasting by mechanical means including cutting and trimming of slips and disposal of cut material within all leads and lifts of material as per technical specification 302.3.5 and 1611 including carriage of materials through all modes of transportation with in all leads and lift, as per direction of the Engineer-in-charge.	907.10	110.00	One Hundred ten rupees only	plcum	99781.00
Total :-						99781.00

Quoted rate in figure

Quoted rate in words

Unit Approved RS 99781/-only

Executive Engineer
Bharmour Division
HPPWD Bharmour

09/12

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 99863.00
EARNEST MONEY :- Rs 2000.00
TIME LIMIT THREE MONTHS

NAME OF WORK : Construction of Panthermu Jamni to Sanathan road
SUB-HEAD :- Cons. section of R/wall at RD 0/262.80 to 0/268.50

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig.	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification clause 305 and 1603.4 and as per direction of the Engineer - In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer - In - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	12.43	259.90	Rupees Two Hundred Fifty Nine And Paise Ninety Only	Per cubic metre	3231.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical (MORD) specifications (Clause 802, 803, 1202 & 1203 1.6 12 (One cement Six sand Twelve graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per direction of Engineer - In - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	3.14	4407.70	Rupees Four Thousand Four Hundred Seven And Paise Seventy Only	Per cubic metre	13840.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical (MORD) specifications (Clause 802, 803, 1202 & 1203 1.4 8 (One cement two four sand two eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per direction of Engineer - In - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	2.00	4914.40	Rupees Four Thousand Nine Hundred Fourteen And Paise Forty Only	Per cubic metre	9829.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement two six sand) in foundation complete as per drawing and technical specifications (Clauses 702, 704, 1202 & 1203 as per direction of Engineer - In - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	12.40	3306.00	Rupees Three Thousand Three Hundred Six Only	Per cubic metre	40994.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per direction of Engineer - In - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	15.03	1599.80	Rupees One Thousand Five Hundred Ninety Nine And Paise Eighty Only	Per cubic metre	24045.00


Block filling with granular material between abutments, wing walls, return walls and retaining walls, complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all limits and lifts and other incidental. The rate including octroi, royalty, Malgana toll tax, sale tax or other taxes imposed by the Government.

8.36	Cubic metres	945 60	Rupees Nine Hundred Forty Five And Paise Sixty Only	Per cubic metre	7924 00
Total :- 99863.00					

Quoted rate in figure

Quoted rate in words

Unit appeared Rs 99863/-only


 Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							
NAME OF WORK :-		A.R & A.O to Various road under Garola Sub division			ESTIMATED COST :-	Rs	99550.00
SUB-HEAD :-		Removal of slips & Boulders at Various RD.S)			EARNEST MONEY :-	Rs	1991.00
					TIME LIMIT :-	ONE MONTHS	
SL. No.	Description of work	Quantity	Fig	RATES Words	Unit	Amount	
1	Removal of slips /land slid in hilly area in all kinds of soil i/c ordinary rock, not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all leads and lifts of material as per technical specification 302.3.5 and 1611 including carriage of materials through all modes of transportation with in all leads and lift, as per direction of the Engineer-in-charge.	905.00	110.00	One Hundred ten rupees only	p/cum	99550.00	
Total :-						99550.00	
Quoted rate in figure							
Quoted rate in words.							

Quoted rate in figure
Quoted rate in words.

Unit Approved Rs 99550/only

Executive Engineer
Bhadrnour Division
HPPWD Bhadrnour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A.R & M.O to Various road under Garola Sub division		ESTIMATED COST :-	Rs	99660.00
SUB-HEAD :- Removal of slips & Boulders at Various RD.S).		EARNEST MONEY :-	Rs	1993.00
		TIME LIMIT :-	ONE MONTHS	

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of slips /land std in hilly area in all kinds of soil i/c ordinary rock, not required blasting by mechanical means including cutting and trimming of stops and disposal of cut material within all leads and lifts of materials through all modes of transportation 302.3.5 and 1611 including carriage of materials through all modes of transportation with in all leads and lift, as per direction of the Engineer-in-charge.	906 (10)	110.00	One Hundred ten rupees only	picum	99660.00
Total :-						99660.00

Quoted rate in figure
Quoted rate in words

Unit Approved Rs 99660/- only

Executive Engineer
Bhutanpur Division
H.P.W.D. Bhutanpur

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK : Construction of Panheru Janni to Samahan road
SUR-HEAD : Construction of R/wall at RD 0/360 to 0/363.95

ESTIMATED COST :- Rs 99130.00
EARNEST MONEY :- Rs 2000.00
TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305 and 1603.4 and as per direction of the Engineer - In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	11.06	259.90	Rupees Two Hundred Fifty Nine And Paise Ninety Only	Per cubic metre	2874.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical M.O.R.D specifications Clause 802, 803, 1202 & 1203 1 & 12 (One cement Six sand Twelve graded/crushed stone aggregate 40mm (Forty millimetres) nominal size) in road work as per direction of Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	2.53	4407.70	Rupees Four Thousand Four Hundred Seven And Paise Seventy Only	Per cubic metre	11151.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical M.O.R.D specifications Clause 802, 803, 1202 & 1203 1 & 4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per direction of Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	1.58	4914.40	Rupees Four Thousand Nine Hundred Fourteen And Paise Forty Only	Per cubic metre	7765.00
4	Ranikam Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per direction of Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	13.40	3306.00	Rupees Three Thousand Three Hundred Six Only	Per cubic metre	44300.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per direction of Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	15.54	1599.80	Rupees One Thousand Five Hundred Ninety Nine And Paise Eighty Only	Per cubic metre	24861.00

Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D technical specifications clause 1604.7 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkama, toll or, sale tax or other taxes imposed by the Government

8.65	Cubic metres	9-5.60	Rupees Nine Hundred Forty Five And Paise Sixty Only	Per cubic metre	5179.00
Total ~ 59120.60					

Quoted rate in figure

Quoted date in words

Dm1 + Approved 123 09 13/

[Signature]

Executive Engineer,
Bhartnour Division,
HPPWD Bhartnour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O to Various road under Garola Sub division

SUB-HEAD :- Removal of slips & Boulders at Various R.D.S)

ESTIMATED COST :-

RS

99715.00

EARNEST MONEY :-

RS

1994.00

TIME LIMIT :-

ONE MONTHS

Sl No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of slips /land slid in hilly area in all kinds of soil i/c ordinary rock, not required blasting by mechanical means including cutting and trimming of stops and disposal of cut material within all leads and lifts of material as per technical specification 302.3-5 and 1611 including carriage of materials through all modes of transportation with in all leads and lift, as per direction of the Engineer-in-charge.	906.50	110.00	One Hundred ten rupees only	p/cum	99715.00
Total :-						99715.00

Rate quoted in figure
Output rate in words

Unit Approved Rs 99715 only

Executive Engineer
Bharmour Division
HPTWD Bharmour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A.R. & M.O to Various road under Garola Sub division		ESTIMATED COST :-		Rs	997.48.00
SUB-HEAD :- Removal of slips & Boulders at Various R.D.S		EARNEST MONEY :-		Rs	1995.00
		TIME LIMIT :-		ONE MONTHS	
Sl. No.	Description of work	Quantity	RATES		Amount
			Fig	Words	
1	Removal of slips /land slid in hilly area in all kinds of soil i/c ordinary rock, not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all leads and lifts of material as per technical specification 302.3.5 and 1611 including carriage of materials through all modes of transportation with in all leads and lift, as per direction of the Engineer-in-charge.	906.80	110.00	One Hundred ten rupees only	997.48.00
Total :-					997.48.00

Quoted rate is figure
Quoted rate is words

Unit Approved as 99748/only

Executive Engineer
Bharatpur Division
H.P.P.A.D. Bharatpur

PROJ. SCHEDULE OF WORK

NAME OF WORK : Construction of Peshawar Tunnel to Naranhar road
 SCHEDULE : Construction of R. wall at R/O (15.50 to 17.50 m)

ESTIMATED COST : Rs. 99431.00
 EARNED MONEY : Rs. 1000.00
 TIME LIMIT

Sl. No.	Description of work	Quantity	RATES			
			Fig.	Rs. per cu. m.	Rs. per cu. m.	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets meeting in all type of combination of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (where blasting is prohibited as per drawings and N.O.R.) technical specification clause 815 and 1601.4 and as per direction of the Engineer. In - Change including setting out, shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto and upto 15% including dressing of sides and bottom and back filling in trenches with excavated material approved material to the original surface to levels not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slabs which may arise out during dewatering as per direction of Engineer - in - Change including carriage of materials within all limits and lifts and other incidental. The rate including extra, royalty, Malakana toll tax, salt tax or other taxes imposed by the Government.	13.97	Cu. m.	719.00	Rs. per cu. m.	1000.00
2	Shoring and bracing mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical N.O.R. specifications (Clause 802, 803, 1202 & 1203) 1 to 12 (One cement six sand) Twelve graded crushed stone aggregate (Twenty millimetres) nominal size) in road work as per direction of Engineer. In - Change including carriage of materials within all limits and lifts and other incidental. The rate including extra, royalty, Malakana toll tax, salt tax or other taxes imposed by the Government.	13.14	Cu. m.	440.70	Rs. per cu. m.	1000.00
3	Shoring and bracing mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical N.O.R. specifications (Clause 802, 803, 1202 & 1203) 1 to 12 (One cement six sand) Twelve graded crushed stone aggregate (Twenty millimetres) nominal size) in road work as per direction of Engineer. In - Change including carriage of materials within all limits and lifts and other incidental. The rate including extra, royalty, Malakana toll tax, salt tax or other taxes imposed by the Government.	13.13	Cu. m.	471.40	Rs. per cu. m.	1000.00
4	Shoring and bracing mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications (Clause 802, 803, 1202 & 1203) as per direction of Engineer - in - Change including carriage of materials within all limits and lifts and other incidental. The rate including extra, royalty, Malakana toll tax, salt tax or other taxes imposed by the Government.	12.16	Cu. m.	1500.00	Rs. per cu. m.	1000.00
5	Construction of dry rubble masonry for retaining walls, breast walls, abutments and parapets etc. for sub-structure and super structure complete as per drawings and technical specifications clause 704.6 & 1302.5 as per direction of Engineer. In - Change including carriage of materials within all limits and lifts and other incidental. The rate including extra, royalty, Malakana toll tax, salt tax or other taxes imposed by the Government.	16.47	Cu. m.	1500.00	Rs. per cu. m.	1000.00

Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M O R D technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all loads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	9.41	Cubic metres	945.60	Rupees Nine Hundred Forty Five And Paise Sixty Only	Per cubic metre	₹ 945.00
Total :- 945.60						
Quoted rate in figure						
Quoted rate in words						

Unit approved of Rs 945.60

[Signature]
Executive Engineer,
Baranwar Division,
MPWD Baranwar

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK : Restoration of rain Damage on Surge shaft to Arki road Km 0/00 to 17/00

SUB-HEAD :- Removal of slips at various Rds

ESTIMATED COST : Rs 99120.00
EARNEST MONEY : Rs 2000
THREE MONTHS
TIME LIMIT

Sr. No.	Description of work	Quantity		Fig	RATES		Unit	Amount
					Words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611.1 as per the direction of Engineer - in - Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	944.00	Cubic metres	105.00	Rupees One Hundred Five Only		Per cubic metre	99120.00
Total								99120.00

Quoted rate in fig.

Quoted rate in words

Esttmt approved Rs 99120/- only

Executive Engineer,
Bharatpur Division,
HPPWD Bharatpur

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 99469.00
EARNEST MONEY :- Rs 1989.00
TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of KSPA road km 0/000 to 13/000

SUB-HEAD :- C/o E/wall at RD 8/220 to 8/286.75 including Toe wall

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge	11.14 Cubic metres	610.10	Rupees six hundred ten and paise ten only	Per cubic metre	6797.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	9.72 Cubic metres	5332.00	Five thousands three hundred thirty two only	Per cubic metre	51827.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	12.45 Cubic metres	3280.70	Rupees three thousands two hundred eighty and paise seventy only	Per cubic metre	40845.00
GROSS TOTAL =						99469.00
Quoted rate in figure						
Quoted rate in words						

DMIT approved after RA = 99469/only

Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 96507.00
EARNEST MONEY :- Rs 1930.00
TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of KSPA road km 0/000 to 13/000

SUB-HEAD :- C/o Elwall at RD 8/233.45 to 8/240 including Toe wall

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge	10.81	Cubic metres	610.10	Rupees six hundred ten and paise ten only	Per cubic metre	6565.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORC specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including cartage of materials within all leads, lifts and other incidental.	9.43	Cubic metres	5332.00	Five thousands three hundred thirty two only	Per cubic metre	50281.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including cartage of materials within all leads, lifts and other incidental.	12.08	Cubic metres	3280.70	Rupees three thousands two hundred eighty and paise seventy only	Per cubic metre	39631.00
GROSS TOTAL =							96507.00
<p>Quoted rate in figure</p> <p>Quoted rate in words</p>							

DMIT approved for RA=96,507/meg

Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 98936.00
EARNEST MONEY :- Rs 1980.00
TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of KSPA road km 0/000 to 13/000

SUB-HEAD :- C/O E/wall at RD 11/178.55 to 11/187.05 including Toe wall

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and, bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge	13.01	610.10	Rupees six hundred ten and paise ten only	Per cubic metre	7937.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	10.20	5332.00	Five thousands three hundred thirty two only	Per cubic metre	54386.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	11.16	3280.70	Rupees three thousands two hundred eighty and paise seventy only	Per cubic metre	36613.00
GROSS TOTAL =						98936.00
Quoted rate in figure						
Quoted rate in words						

DNIT approved for RA = 98936/only.
Executive Engineer,
Bhamour Division,
HPPWD Bhamour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M.O on various roads in Holli Sub Division Deol and Nayagram Section

Sub Head :- Painting and art painting of Ordinary K.M stones, 200 mts stones, and information sign boards etc

ESTIMATED COST :- ₹ 99981.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Three MONTHS

Sl No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Removing old paint from steel and other metal surfaces and making the surface even with paint remover of approved brand and manufacture including the cost of material with as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	3 45.00 Square Metre	4 30.00	5 Rupees Thirty Only	6 Per Square Metre	7 1350.00
2	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper complete. With ready mixed priming paint brushing red lead, Red oxide/ zinc oxide chrome including the cost of material with as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	45.00 Square Metre	46.40	Rupees Forty Six And Paise Forty Only	Per Square Metre	2088.00
3	Painting two coats (excluding priming cost) on new steel and other metal surfaces with enamel paint brush in to give an even shade including cleaning the surface of all dirt, dust and other foreign matters enamel paint other than white including the cost of material with as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	45.00 Square Metre	98.70	Rupees Ninety Eight And Paise Seventy Only	Per Square Metre	4412.00
4	Applying priming coat on new concrete / masonry/ asbestos cement / plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with Ready mixed primer including the cost of material with as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	50.16 Square Metre	48.20	Rupees Forty Eight And Paise Twenty Only	Per Square Metre	2418.00

plying Brita white wall care putty over plaster surface after thoroughly brushing the surface free from mortar ps, dust loose materials and other foreign matters sand papered smooth to give final matter finish to the face complete including entire carriage of material within per direction of Engineer - in-Charge including range of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.

fining two coats (excluding priming cost on new concrete masonry/ plaster surfaces with ready mixed paint washing for use on floors to give and even shade including cleaning the surfaces of all dirt, dust and other foreign matter and sand papering as required with paint other than whitas per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.

Writing letters or figures on any surface with black japan paint (Stops, commas, hyphens and the like not to be measured and paid separately) Indian (letters/figures) including the coat of whitas per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.

3	4	5	6	7
50.16 Square Metre	102.60	Rupees One Hundred Two And Paise Sixty Only	Per Square Metre	5146.00
50.16 Square Metre	89.50	Rupees Eighty Nine And Paise Fifty Only	Per Square Metre	4489.00
41050.00 centimetre Height	1.95	Rupees One And Paise Ninety Five Only	Per letter per centimetre Height	80048.00
Total				99981.00

Quoted rate in figure
Quoted rate in words

DM-1 Approved As 99981/- only

Executive Engineer,
Bharmour Division,
HP.PWD., Bharmour

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/C on various roads in Holi Sub Division Holi and Dahi Sections

Sub Head :- Painting and art painting of Ordinary KM stones, 200 mts stones, and information sign boards etc.

ESTIMATED COST :- ₹ 99981.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Three MONTHS

Sl. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Removing old paint from steel and other metal surfaces and making the surface even with paint remover of approved brand and manufacture including the cost of material with per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00 Square Metre	30.00	Rupees Thirty Only	Per Square Metre	1350.00
2	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper complete. With ready mixed priming paint brushing red lead, Red oxide/ zinc oxide chrome including the cost of material with per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00 Square Metre	46.40	Rupees Forty Six And Paise Forty Only	Per Square Metre	2088.00
3	Painting two coats (excluding priming coat on new steel and other metal surfaces with enamel paint brush in to give an even shade including cleaning the surface of all dirt, dust and other foreign matters enamel paint other than white including the cost of material with per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00 Square Metre	98.70	Rupees Ninety Eight And Paise Seventy Only	Per Square Metre	4442.00
4	Applying priming coat on new concrete / masonry/ asbestos cement / plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with Ready mixed primer including the cost of material with per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	50.16 Square Metre	48.20	Rupees Forty Eight And Paise Twenty Only	Per Square Metre	2418.00

2
 Applying 13mm white wall care putty over plaster surface after thoroughly brushing the surface free from mortar lumps, dust loose materials and other foreign matters sand papered smooth to give final muller finish to the surface complete including entire carriage of material within per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.

Painting two coats (excluding priming cost on new concrete masonry/ plaster surfaces with ready mixed paint brushing for use on floors to give and even shade including cleaning the surfaces of all dirt, dust and other foreign matter and sand papering as required with paint other than whitewash per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.

Writing letters in figures on any surface with black japan paint (Stops, eunias, hyphens and the like not to be measured and paid separately) Indian (letters/figures) including the cost of whitewash per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.

	3		4	5	6	7
	50.16	Square Metre	102.60	Ruppes One Hundred Two And Paise Sixty Only	Per Square Metre	5146.00
	50.16	Square Metre	89.50	Ruppes Eighty Nine And Paise Fifty Only	Per Square Metre	4489.00
	41050.00	centimetre Height	1.95	Ruppes One And Paise Ninety Five Only	Per letter per centimetre Height	80045.00
Total						99981.00

Quoted rate in figure
 Quoted rate in words

Unit Approved Rs 99,981/- only

Executive Engineer,
 Bharmour Division,
 H.P.P.W.D., Bharmour

SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various road under Rakh Sub Division
Sub Head: Removal of slips at various RD's

E/Cost:-99750/-
E/Money:-2000/-
Time Limit:-One Month

Sr. No	Description of item	Qty	Rate	Unit	Total
1	Removal of slips in all kind of soil i/c saturated soil but excluding boulders and rocky portion requiring blasting up to a distance of 20 meters disposing of unserviceable materials, stacking serviceable materials, stacking serviceable material and neatly dressing the surface incl. all leads and lifts and as per direction of Engineer in Charge.	950	105.00	Cum	99750.00
Total=					99750.00

Quoted rate is figure
Quoted rate is words
Unit 11682000 RS 99750



30

Pharmaceutical Division
1110 P.O. Box 12000
St. Louis, MO 63143

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST : RS 97106.00
EARNEST MONEY :- RS 1942.00
TIME LIMIT THREE MONTHS

NAME OF Special repair of S.D.M. Residence at Helipad Bharmour Distt. Chamba (HP)
SUB-HEAD :- Repair of Stair, boundary wall

SL No.	Description of work	Quantity	RATES		Unit	Amount.
			Fig	Words		
1	Demolishing stone rubble masonry manually/by mechanical means including stacking of servicable material and disposal of unservicable material with 50 metres lead as per direction of Engineer-in-Charge.	5.11 Cubic metres	1011.75	Rupess one thousand eleven and paise seventy five only	Per cubic metre	5170.00
2	vibrated so as to give compressive strength corresponding to M-20 grade and curing complete excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and selves and their support balconies, beams, girders, bressumers and cantilever upto floor two level as per the direction of the Engineer-in-Charge with in all leads and lift and other incidents.	6.40 Cubic metres	8900.00	Rupess eight thousands nine hundred only	Per cubic metre	56950.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement iso four sand iso eight graded/crushed stone aggregate 20mm (twenty five millimeures) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.37 Cubic metres	5800.00	Rupess five thousands eight hundred only	Per cubic metre	7946.00
4	Providing and laying Gehra slab stone flooring 40mm thick.	15.00 Sqm	1800.00	Rupess one thousand eight hundred only	Per square metre	27000.00
Total :-						97106.00

Quoted rate in figure
Quoted rate in words

Unit Approved as 97106/- only

Executive Engineer
Bharmour Division
HPPWD Bharmour

SCHEDULE OF QUANTITY

NAME OF Special repair of S.D.M. Residence at Helipad Bharamur Dist. Chamba (HP)
SUB-HEAD :- Repair of S.D. boundary wall

ESTIMATED COST : Rs 97868.00
EARNEST MONEY : Rs 1957.00
TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig.	Words		
1	Demolishing more rubble masonry masonry including stacking of new rubble material and disposal of unworkable material with 50 metres lead as per direction of Engineer-in-Charge.	5.11	1011.75	Eighteen thousand eleven and paise seventy five only	Per cubic metres	5170.00
2	Repaired so as to give compressive strength corresponding to 14.25 grade and curing complete extending 8.00		8000.00	Eight thousand only	Per cubic metres	58800.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations 1.37		5800.00	Eight thousand only	Per cubic metres	7946.00
4	Providing and laying Guba's slab stone facing 40mm thick.	15.44	1800.00	Eighteen thousand only	Per square metres	27792.00
Total :-						97868.00

Don't Approved Rs 94868/- only

Executive Engineer
Bharamur Division
H.P.W.D. Bharamur

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99500.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT :- Three MONTHS

NAME OF WORK:- Construction of New Hospital building at Choori, Distt Chamba, HP
Preperation of DPR

Sr No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Preparation of Working estimate of whole project as per Architectural Drawing for the Construction of New Hospital building at Choori, Distt Chamba, (HP) including Building portion with W.S. & S.I, R.WHT & Site Development etc. The Job shall also include supplying detailed estimate as per analysis of rates on based on JPSR 2020 /market rates for all the items appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office / Circle office /CE office complete as per directions of Engineer-in-charge.	3 1.00 Nos	99500.00	Ruppes Ninety Nine Thousand Five Hundred Only	6 Per Nos	7 99500.00
	Quoted Rate in figure			Total		99500.00
	Quoted Rate in words					

Unit Approved of Rs 99500 only

Executive Engineer,
Bharmour Division,
H.P.P.W.D., Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST
EARNEST MONEY
TIME LIMIT

Rs 19344.00
Rs 2000.00
THREE MONTHS

NAME OF WORK :- Annual repair & Maintenance of KSPA Road KM 13/00 to 40/00
SUB-HEAD :- C/O subgrade and earthen shoulders, Construction of unlined surface drain, Cutting of bushes & Surface dressing etc. at various R.Ds.

Sl. No.	Description of work	Quantity	Fig	RATES		Unit	Amount
				Words			
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. Turfing with Sods Seeding and Mulching Construction of Subgrade as per the direction of Engineer-in-Charge.	265.50	199.25	Rupees one hundred ninety nine and paise twenty five only		Per cubic metre	52903.00
2	Construction of unlined surface drain of average cross-sectional area 0.40 square meter (Zero point forty square meter) in soil to specified lines, grade, levels and dimensions. Excavated material to be used in embankment with a lift upto 3.00 meter (Three meter) and lead of 50 meter (Fifty meter) (average lead 25 meter (Twenty meter) as per Technical specification Clause 307, with in all leads and lifts of materials and other incidentals.	349.00	50.00	Rupees fifty only		Per running metre	17450.00
3	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per Technical specification Clause 1914, with in all leads and lifts and as per the direction of Engineer-in-Charge.	377.50	8.50	Rupees eight and paise fifty only		Per cubic metre	3209.00
4	Cutting of scrubs from the road way or with in ROW and disposal of the scrubs to the suitable location as per technical specification Clause 1914, with in all leads and lifts and as per the direction of Engineer-in-Charge.	478.00	12.80	Rupees twelve and paise eighty only		Per cubic metre	6118.00
5	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil with in all leads and lifts and as per the direction of the Engineer-in-Charge.	657.00	30.00	Rupees thirty only		Per cubic metre	19710.00
Total							99388.00

Unit Approved of Rs 99388/only

Executive Engineer,
Bhamour Division,
HPPWD Bhamour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST
EARNEST MONEY
TIME LIMIT

RS
RS
THREE MONTHS

NAME OF WORK : Annual repair & Maintenance of Churi to Lyth Road
SUB-HEAD : C/O subgrade and earthen shoulders, Construction of unlined surface drain, Cutting of bushes & Surface dressing etc. at various R.Ds.

Sl. No.	Description of work	Quantity	Fig	RATES		Unit	Amount
				Words			
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. Turfing with Sods Seeding and Mulching Construction of Subgrade as per the direction of Engineer-in-Charge.	265.50	199.25	Rupees one hundred ninety nine and paise twenty five only		Per cubic metre	52901.00
2	Construction of unlined surface drain of average cross-sectional area 0.40 square meter (Zero point forty square meter) in soil to specified lines, grade, levels and dimensions. Excavated material to be used in embankment with a lift upto 3.00 meter (Three meter) and lead of 50 meter (Fifty meter) (average lead 25 meter (Twenty meter) as per Technical specification Clause 307, with in all leads and lifts of materials and other incidentals.	349.00	50.00	Rupees fifty only		Per running metre	17450.00
3	Trimming of grass and weeds from the shoulders/bermis and disposing off the same to suitable locations as per Technical specification Clause 1914, with in all leads and lifts and as per the direction of Engineer-in-Charge.	377.50	8.50	Rupees eight and paise fifty only		Per cubic metre	3209.00
4	Cutting of scrubs from the road way or with in ROW and disposal of the scrubs to the suitable location as per technical specification Clause 1914, with in all leads and lifts and as per the direction of Engineer-in-Charge.	478.00	12.80	Rupees twelve and paise eighty only		Per cubic metre	6118.00
5	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil with in all leads and lifts and as per the direction of the Engineer-in-Charge.	657.00	30.00	Rupees thirty only		Per cubic metre	19710.00
Total							99388.00

Unit Approved of Rs 99388/- only

Executive Engineer,
Bhamour Division,
HPPWD Bhamour