

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Scaled Item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 13-03-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable):- 13-03-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 15-03-2025 at 10.30 AM.
4. Date of opening of Tender:- 15-03-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O link road Chab to Mundkhar Genda road Km 0/00 to 1/00 (SH:- C/O B/wall at RD 0/336.50 to 0/343) (Under SCDP)	96141/-	2000/-	Two Months	Rs. 350/-	Class-D
2	C/O link road Chab to Mundkhar Genda road Km 0/00 to 1/00 (SH:- C/O B/wall at RD 0/330 to 0/336.50) (Under SCDP)	96141/-	2000/-	Two Months	Rs. 350/-	Class-D
3	A/R & M/O Dasmal to Kot Kangri road Km 0/00 to 3/500 (SH:- C/O R/wall at RD 1/039 to 1/045.50)	99009/-	2000/-	Two Months	Rs. 350/-	Class-D
4	A/R & M/O Dasmal to Kot Kangri road Km 0/00 to 3/500 (SH:- C/O R/wall at RD 1/045.50 to 1/052)	99009/-	2000/-	Two Months	Rs. 350/-	Class-D
5	Repair of Residential Building HPPWD Bhoranj (AE Residential Building) (SH:- P/Fixing 19mm thick Ply Board for Cup board side & shutter)	98175/-	2000/-	Two Months	Rs. 350/-	Class-D
6	C/O Una Aghar Mandi road Km 79/00 to 90/00 (II) Link road from lagmanwin Mandir to Chahab More via Samkari Km 0/00 to 3/015 Under HPPWD Sub Division Bhoranj HPPWD Bhoranj (Providing & manufacturing sign Board)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
7	C/O link road form Lagmanwin to manoh (II) link road Mundkhar Ganda Chab to Harizan Basti under HPPWD Sub-Division Bhoranj HPPWD Bhoranj (Providing & Manufacturing sign Board)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
8	Restoration of Rain damages on Ladrour Lathwan road km 0/00 to 4/00 (SH:- C/O B/wall at RD 2/745 to 2/755) Near Society Lathwan)	88567/-	2000/-	Two Months	Rs. 350/-	Class-D
9	Restoration of Rain damages on Ladrour to Lathwan road km 0/00 to 4/00 (SH:- C/O B/wall at RD 2/735 to 2/745) (Near GPS Lathwan)	90751/-	2000/-	Two Months	Rs. 350/-	Class-D

10	Restoration of rain damages on link road to village Balokhar Km 0/00 to 1/00 (SH:- C/O R/wall at RD 0/230 to 0/237) (Under SCDP	97996/-	2000/-	Two Months	Rs. 350/-	Class
11	Restoration of rain damages on link road to Village Balokhar km. 0/00 to 1/00 (SH:- C/O R/wall at RD 0/237 to 0/244) (Under SCDP)	97996/-	2000/-	Two Months	Rs. 350/-	Class
12	Restoration and repair path with retaining wall from Sh. Kartar Singh House towards village Bhebal, PO Karohra from Tikkar Manoh road . (Deposit work SDP/ 2024/199	99037/-	2000/-	Two Months	Rs. 350/-	Class
13	Restoration of rain damages on lajyani to Bhalwani via Kakrot road Km 0/00 to 6/540) (SH:- C/O R/wall at RD 4/435 to 4/440)	92494/-	2000/-	Two Months	Rs. 350/-	Class
14	Restoration of rain damages on Lajhyani to Bhalwani via Kakrot Kalyal road km 0/00 to 6/540 (SH:- C/O R/wall at RD 4/440 to 4/445)	92494/-	2000/-	Two Months	Rs. 350/-	Class-
15	R/R damages on Samirpur to Bagwara via Samlehra road km 0/00 to 2/500 (SH:- P/L interlocking paverblock pavement at RD0/335 to 0/347)	99565/-	2000/-	Two Months	Rs. 350/-	Class-C
16	Annual repair & maintenance of Sangroh to Bhuana via Bakkar Khad road 0/00 to 4/00 (SH:- Dressing and cutting , filling road side Berms/Shoulder & unlined drain at 3/00 to 3/200 , 3/400 to 3/800)	99984/-	2000/-	Two Months	Rs. 350/-	Class-D
17	Annual repair & maintenance of Sangroh to Bhuana via Bakkar Khad road 0/00 to 4/00 (SH:- Dressing and cutting , filling road side Berms/Shoulder & unlined drain at 2/00 to 2/300 , 2/400 to 2/800)	99984/-	2000/-	Two Months	Rs. 350/-	Class-D
18	R/R damages on Samirpur to Bagwara via Samlehra road Km 0/00 to 2/500 (SH:- P/L interlocking paverblock pavement at 0/359 to 0/371)	99565/-	2000/-	Two Months	Rs. 350/-	Class-D
19	Repair of Residential Building HPPWD Bhoranj (AE Residential Building) (SH:- Removing of old distemper and paint etc.)	98323/-	2000/-	Two Months	Rs. 350/-	Class-D
20	C/O link road from village Deog Negian to Panjarda (SH:- P/L GSB, WMM in Km 2/360 to 2/420)(Under SCSP)	98122/-	2000/-	Two Months	Rs. 350/-	Class-D
21	C/O link road from village Deog Negian to Panjarda (SH:- P/L GSB, WMM in Km 1/540 to 1/600) (Under SCSP)	98122/-	2000/-	Two Months	Rs. 350/-	Class-D
22	C/O link road from village Deog Negian to Panjarda (SH:- P/L GSB,WMM in Km 1/420 to 1/480) (Under SCSP)	98122/-	2000/-	Two Months	Rs. 350/-	Class-D
23	A/R & M/O various roads under Bhoranj Sub Division (SH:- Painting & writing letters of information Sign Boards , km Stone and other road side furniture etc) (Section Patt)	98203/-	2000/-	Two Months	Rs. 350/-	Class-D
24	A/R & M/O various road under Bhoranj Sub Division (SH:- Painting & writing letters of information sign boards , km stone and other road side furniture etc. (Section Jahu)	99512/-	2000/-	Two Months	Rs. 350/-	Class-D
25	R/R damages on Bhumplu Da Ghat to Katoh (	98452/-	2000/-	Two	Rs. 350/-	Class-D

	SH:- C/O R/wall at RD 3/306.50 to 3/313)			Months		
26	R/R damages on Bhumplu Da Ghat to Katoh (SH:- C/O R/wall at RD 3/300 to 3/306.50)	98452/-	2000/-	Two Months	Rs. 350/-	Class-D
27	R/R damages on Dungi Kanjian Dho road Km 5/00 to 5/050 (SH:- C/O R/wall at RD 0/056 to 0/061.50)	99255/-	2000/-	Two Months	Rs. 350/-	Class-D
28	C/O Link road from main road toward Ghari village Bajlah GP Ludder Mahadev Tehsil Bhoranj Distt Hamirpur (HP) Mohal (SH:- P/L CC pavement at RD various RDs)	99087/-	2000/-	Two Months	Rs. 350/-	Class-D
29	C/O Ambulance road Mahila Mandal Bhawan to Baba BalakNath Temple via Rajpootan Basti (SH:- P/L filling at RD 0/00 to 0/100)	98750/-	2000/-	Two Months	Rs. 350/-	Class-D
30	C/O Ambulance road Mahila Mandal Bhawan to Baba BalakNath Temple via Rajpootan Basti (SH:- P/L filling at RD 0/100 to 0/200)	2000/-	Two Months	Rs. 350/-	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).


The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case:

- (i) No Violation of social distancing.
- (ii) Mandatorily wearing of face cover by everyone.
- (iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj
 For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2024-

12345-85

Dated:- 05-03-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

WORK:- C/O Link road Chab to Mundkhar Genda Road km. 0/00 to 1/00. (SH:- C/O B/Wall at RD 0/336.50 to 0/343.) (under S.C.D.P)

Estimated Cost
Earnest Money
Time

Rs 96141/-
Rs. 2000/-
2 month

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1 Cutting in earth work for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.49	Per Cubic Meter			
2 Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.40	Per Cubic Meter			
3 Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.29	Per Cubic Meter			
4 Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
Total					
Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

(3)

SCHEDULE OF QUANTITY

WORK:- C/O Link road Chab to Mundkhar Genda Road km. 0/00 to 1/00. (SH:- C/O B/Wall at RD 0/330 to 0/336.50.) (under S.C.D.P)

Estimated Cost
Earnest Money
Time

Rs 96141/-
Rs. 2000/-
2 month

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1 Cutting in earth work for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.49	Per Cubic Meter			
2 Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.40	Per Cubic Meter			
3 Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.29	Per Cubic Meter			
4 Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
Total					
Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- A/R & M/O Dasmal to Kot Kangri road km. 0/00 to 3/500. (SH:- C/O R/Wall at RD 1/039 to 1/045.50.)

Estimated Cost
Earnest Money
Time

Rs 99009/-
Rs. 2000/-
2 month

	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.44	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Dasmal to Kot Kangri road km. 0/00 to 3/500. (SH:- C/O R/Wall at RD 1/045.50 to 1/052.)

Estimated Cost
Earnest Money
Time

Rs 99009/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.44	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand:ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls/breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg. per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair of Residential Building HPPWD Bhoranj (A.E. Residential Building JS.H):- Fixing 19mm Thick Ply Board for Cup Board side & Shutter etc.)

Estimated Cost Rs. 98,175/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing 19mm thick ply Board fro cup board side and shutter, 19mm board form box top bottom and its shelves, finished with 1mm thick lamination sheet (burnica) and 6mm thick PVC sheet fixed in back side including PVC tape (beading) and Hydraulic Hings stainless steel handle complete as per the direction of the Engineer-in-charge including entire cartage of material within all leads and fits and other incidentals. The rates are inclusive octroi, royalty, Mahana, toll tax sale tax or other taxes imposed by the Government	17.85	Per square meter			
Total						
Terms and Condition:-						

1 Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on Lathwan road km. 0/00 to 4/00. (SH:- C/O B/Wall at RD 2/745 to 2/755.) (Near Society Lathwan)

Estimated Cost
Earnest Money
Time

Rs 88567/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.40	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.60	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/linolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on Ladrour Lathwan road km. 0/00 to 4/00. (SH:- C/O B/Wall at RD 2/735 to 2/745.) (Near GPS Lathwan)

Estimated Cost
Earnest Money
Time

Rs 90751/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- Restoration of Rain damages on link road to village Balokhar km. 0/00 to 1/00. (SH:- C/O R/Wall at RD 0/230 to 0/237.) (under D.P)

Estimated Cost
Earnest Money
Time

Rs 97996/-
Rs. 20000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.82	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.20	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- Restoration of Rain damages on link road to village Balokhar km. 0/00 to 1/00. (SH:- C/O R/Wall at RD 0/237 to 0/244.) (under

Estimated Cost
Earnest Money
Time

Rs 97996/-
Rs. 2000/-
2 month

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.82	Per Cubic Meter			
2 Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.89	Per Cubic Meter			
3 Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
4 Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.20	Per Cubic Meter			
Total					
Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- Restoration and Repair path with retaining wall from Sh. Kartar Singh house towards village Bhebal, P.O. Karohta from Tikkar
anoh road. (Deposit work SDF/2024/199.)

Estimated Cost
Earnest Money
Time

Rs 99037/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.82	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.90	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.25	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on Lajhyani to Bhalwani via kakrot, kalyal road km. 0/00 to 6/540. (SH:- C/O R/Wall at RD 4/435 to 140.)

Estimated Cost
Earnest Money
Time

Rs 92494/-
Rs. 2000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.90	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.34	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- Restoration of Rain damages on Lajhyani to Bhalwani via kakrot, kalyal road km. 0/00 to 6/540. (SH:- C/O R/Wall at RD 4/440 to

Estimated Cost
Earnest Money
Time

Rs 92494/-
Rs. 2000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.90	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.34	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- R/R damages on Samirpur to Bagwara via samlehra road km . 0/0 to 2/500.
interlocking paverblock pavement at RD 0/335 to 0/347).

Estimated Cost
Earnest Money
Time

Rs 99,565/-
Rs. 2000/-
2 Months

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which anse out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
2 Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size including shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.20	Per cubic metre			
3 Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (N.T.C Tile), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	42.00	Per square meter			
4 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.80	Per Cubic Meter			
Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HSPWD Bhoranj

SCHEDULE OF QUANTITY

**OF WORK:- Annual Repair & Maintenance of Sangroh to Bhuana via Bakkar khad road 0/00 to 4/00.
Dressing and Cutting , filling road side Berms/shoulders & unlined drain at 3/00 to 3/200 , 3/400 to 3/800.)**


Estimated Cost
Earnest Money
Time

Rs 99984/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	975.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	635.00	Per Running Mtr.			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HR PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- Annual Repair & Maintenance of Sangroh to Bhuana via Bakkar khad road 0/00 to 4/00.
Grading and Cutting , filling road side Berms/shoulders & unlined drain at 2/00 to 2/300 , 2/400 to 2/800.)

Estimated Cost
 Earnest Money
 Time

Rs 99984/-
 Rs. 2000/-
 2Months

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	975.00	Per square metre			
2 Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	635.00	Per Running Mtr.			
Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 H.R. PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- R/R damages on Samirpur to Bagwara via samlehra road km . 0/0 to 2/500.
interlocking paverblock pavement at RD 0/359 to 0/371).

Estimated Cost
Earnest Money
Time

Rs 99,565/-
Rs. 2000/-
2 Months

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
2 Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size including shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.20	Per cubic metre			
3 Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (n.t.c apper 24), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	42.00	Per square meter			
4 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.80	Per Cubic Meter			
Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK :- Repair of Residential Building HPPWD Bhoranj (A.E. Residential Building (S.H):- Removing of old distemper and paint etc.)


Estimated Cost
Earnest Money
Time

Rs 98323/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	301.74	Per Squire meter			
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	301.74	Per Square Meter			
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	301.74	Per Square Meter			
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	106.59	Per Square Meter			
5	Providing and laying vitrified floor tiles in 600 600 mmt sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqmincluding grouting the joints with matching pigments etc., complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.11	Per square meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- C/O link road from village Deog negian to panjarda,
GSB, WMM in km 2/360 to 2/420). (Under SCSP)

Estimated Cost
Earnest Money
Time
Rs 98122/-
Rs. 2000/-
2 Months

Sl. No.	Description of Items	Quantity	Unit	Rate	Rates in Words	
					Amount	Amount
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.018	Per cubic Meter			
2	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of coarse aggregate watering and compacting to the required density grade-I as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.21	Per Cubic Meter			
TOTAL						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road from village Deog negian to panjarda.
SH:- P/L GSB, WMM in km 1/540 to 1/600). (Under SCSPT)

Estimated Cost
 Earnest Money
 Time

Rs 98122/-
 Rs. 2000/-
 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.018	Per cubic Meter			
2	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grade-I as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.21	Per Cubic Meter			
TOTAL						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 HR PWD Bhoranj

SCHEDULE OF QUANTITY

WORK:- C/O link road from village Deog nejan to panjarda.
GSB, WMM in km 1/420 to 1/480).(Under SCSP)

Estimated Cost
 Earnest Money
 Time

Rs 98122/-
 Rs. 2000/-
 2 Months

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.018	Per cubic Meter			
2 Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grade-I as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.21	Per Cubic Meter			
TOTAL					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 H.R. PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Various roads under Bhoranj Sub division. (SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.) (Section Patta)

Estimated Cost
Earnest Money
Time

Rs 98203/-
Rs 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13 99.1 one or more coat on old works including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55	Per sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13 62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	60	Per Sqm			
3	Wall painting road side kerv stone with acrylic cement emulsion approved brand and manufacture of required colour to give an even shade Two or more coats including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	120	Per Sqm			
4	Re-lettering with black Japan paint of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19000	Per letter. Per cm ht.			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Various roads under Bhoranj Sub division. (SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.) (Section Jahu)

**Estimated Cost
Earnest Money
Time**

**Rs 99512/-
Rs 2000/-
2Months**

Sr No	Description of Items	Quantity	Unit	Rate	Rates In Words	Amount
1	Painting with synthetic ename paint of approved brand and manufacture of required colour to give an even shade 13.99.1 one or more coat on old works including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55	Per sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55	Per Sqm			
3	Re-lettering with black Japan paint of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23500	Per letter. Per cm ht.			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.R. PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Bhumplu da Ghat to Katoh Road (SH:- C/O R/Wall at RD 3/306.50 to 3/313.)

Estimated Cost
Earrest Money
Time

Rs 98,452/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.45	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths, In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.50	Per Cubic Meter			
3	Providing weep holes in bnck/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.50	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY


NAME OF WORK:- R/R Damages on Bhumplu da Ghat to Katoh Road (SH:- C/O R/Wall at RD 3/300 to 3/306.50.)

Estimated Cost
Earnest Money
Time

Rs 98,452/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.45	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.50	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.50	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HQ PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Dungi Kanjain Dho road km 5/00 to 5/050 (SH:- C/O R/Wall at RD 0/056 to 0/061.50.)

Estimated Cost
Earnest Money
Time

Rs 99255/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.78	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand:ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
R/R PWD Bhoranj

SCHEDULE OF QUANTITY

For C/O Link road from Main Road Toward Ghari Vill. Bajlah G.P. Ludder Mahadev Teh. Bhoranj Distt. Hamirpur(HP) Mohal. (SH:- P/L)
 At RD various RD's (Deposit work)

Estimated Cost
 Earnest Money
 Time

Rs. 99087/-
 Rs. 2000/-
 2Months

Description of Items

Providing concrete for plain reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government

Quantity	Unit	Rate	Rate in words	Amount
10.35	Per cubic meter			
7.76	Per Cubic Meter			
Total				

Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:2:4 one cement: two sand: four graded crushed stone aggregate) 20mm (twenty millimeters) for plain reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803, 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government

Total

Terms and Condition:-

1. Work shall be executed as per PWD specification

Executive Engineer
 Bhoranj Division
 HP PWD Bhoranj