

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Scaled Item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. **Date of receipt of Applications for tender form a/w requisite documents:- 24-03-2025 upto 10.00 AM to 11:00 AM.)**
2. **Date of issue/Sale of tender forms against Cash payment (Non- refundable) 24-03-2025 (3:00 PM to 5.00 PM)**
3. **Date of receipt of Tender:- 25-03-2025 at 10.30 AM.**
4. **Date of opening of Tender:- 25-03-2025 at 11.30 AM.**

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O Executive Engineer office Building (PWD) Bhoranj (SH:- C/O R/wall at RD 0/039 to 0/043)	99539/-	2000/-	Two Months	Rs. 350/-	Class-D
2	C/O & M/T Jhanikar Tal to Thathwani High School km 0/00 to 1/00 ) ( SH:- P/L CC pavement at RD 0/382 to 0/393)	97632/-	2000/-	Two Months	Rs. 350/-	Class-D
3	C/O Executive Engineer office Building (PWD) Bhoranj (SH:- C/O R/wall at RD 0/035 to 0/039)	99539/-	2000/-	Two Months	Rs. 350/-	Class-D
4	C/O & M/T Jhanikar Tal to Thathwani High School( GP Amman) km 0/00 to 1/00 ) ( SH:- P/L CC pavement at RD 0/307 to 0/314)	99499/-	2000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

**TERMS AND CONDITIONS:-**

The tender form will be issued to those contractors who have relevant machinery and equipment, the list which may be attached with their applications (The proof of ownership of machinery/ legal tie arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

**Certified that the above work is of emergent nature in exigency of Public interest.**

Executive Engineer  
Bhoranj Division  
HPPWD Bhoranj  
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2024-

12940-61

Dated:-

17-3-25

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8<sup>th</sup> Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,  
Bhoranj Division,  
HPPWD, Bhoranj.

# DRAFT SCHEDULE OF QUANTITY


OF WORK:- C/O Executive Engineer Office Building (PWD) Bhoranj . (SH:- C/O R/Wall at RD 0/039 to 0/043.)

Estimated Cost  
Earnest Money  
Time

Rs 99539/-  
Rs. 2000/-  
2 month

S No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited ) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre ) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.76	Per Cubic Meter	295.00	Rupees two hundred ninety five only	3174.00
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size ) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.14	Per Cubic Meter	4300.00	Rupees four thousand three hundred only	90902.00
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square ) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each	270.00	Rupees two hundred seventy only	2160.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.67	Per Cubic Meter	900.00	Rupees Nine hundred only	3303.00
	<b>Total</b>					<b>99539.00</b>
	<b>Terms and Condition:-</b>	DNIT. NO:- 583 for the year 2024-25 recommended for approval for Rs 99539/-(Rupees ninety nine thousand five hundred thirty nine only.)				

1.Work shall be executed as per PWD specification.

  
 Executive Engineer  
 Bhoranj Division  
 Hq. PWD Bhoranj

# SCHEDULE OF QUANTITY

OF WORK:- C/O Executive Engineer Office Building (PWD) Bhoranj. (SH:- C/O RWall at RD 0/039 to 0/043.)

Estimated Cost  
Earnest Money  
Time

Rs 99539/-  
Rs. 2000/-  
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.14	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.67	Per Cubic Meter			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
Hq. PWD Bhoranj

# SCHEDULE OF QUANTITY

NAME OF WORK:- C/O & MT Jhanikar Tal to Thathwani High School km.0/00 to 1/00  
 (SH:- P/L C.C.Pavement at RD 0/382 to 0/393.)

Estimated Cost Rs 97632/-  
 Earnest Money Rs. 2000/-  
 Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M <sub>10</sub> (M- ten )nominal mix 1:3:6 ( one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	18.08	Per cubic metre			
	<b>Total</b>					

## Terms and Condition:-

1. Work shall be executed as per PWD specification.

  
 Executive Engineer  
 Bhoranj Division  
 H.P.PWD Bhoranj



# SCHEDULE OF QUANTITY

OF WORK:- C/O Executive Engineer Office Building (PWD) Bhoranj. - (SH:- C/O R/Wall at RD 0/035 to 0/039.)

Estimated Cost  
Earnest Money  
Time

Rs 99539/-  
Rs. 2000/-  
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement, five sand, ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.14	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe. De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.67	Per Cubic Meter			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
PWD Bhoranj

# SCHEDULE OF QUANTITY

OF WORK:- C/O & M/T Jhanikar Tal Road to Thathwani High School (GP Amman) km. 0/00 to 1/00 . (SH:- C/O R/Wall at RD 0/307 to 0/314.)

Estimated Cost  
Earnest Money  
Time

Rs 99499/-  
Rs. 2000/-  
2 month

Sl. No.	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.58	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of l(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each			
	<b>Total</b>					
	<b>Terms and Condition:-</b>					

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
MR PWD Bhoranj