

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

E-Mail id-ee-bil2-hp@nic.in
Phone No.01978-222550

NOTICE INVITING TENDERS

Sealed items rates tender for the following works are hereby invited by the Executive Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriate class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 19.03.2025 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on any working day upto 2.00 PM. On dated 18.03.2025. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No.etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.


The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	A/R & M/O Ghawandal to Sh.Naina Devi Ji Temple road Km.0/00 to 3/855(SH:- Maintenance of Earthen Shoulder and construction of unlined surface drain in Km.2/750 to 3/600)	Rs.78,606/-	Rs.1,600/-	Rs.350/-	One Month
2	A/R & M/O Ghawandal to Sh.Naina Devi Ji Temple road Km.0/00 to 3/855(SH:- Maintenance of Earthen Shoulder and construction of unlined surface drain in Km.1/00 to 2/600)	Rs.77,985/-	Rs.1,600/-	Rs.350/-	One Month
3	A/R & M/O Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.19/00 to 21/00)	Rs.78,480/-	Rs.1,600/-	Rs.350/-	One Month
4	A/R & M/O Sh.Naina Devi Ji Bhakra road Km.0/00 to 37/300(SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.19/00 to 21/00)	Rs.79,650/-	Rs.1,600/-	Rs.350/-	One Month
5	A/R & M/O Sh.Naina Devi Ji Toba road Km.0/00 to 9/225(SH:-Maintenance of Earthen Shoulder and Construction of unlined surface drain in Km.7/00 to 9/225)	Rs.77,733/-	Rs.1,600/-	Rs.350/-	One Month
6	A/R & M/O on link road to Village Nehla Km.0/00 to 2/500(SH:- Maintenance of Earthen Shoulder and Construcion of unlined surface drain in Km.0/500 to 2/000).	Rs.78,648/-	Rs.1,600/-	Rs.350/-	One Month

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor Firms are requested to insert the rate of each item both in words and in figures filling which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2025-


12198-207

Dated:-

15/03/2025

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HP.PWD., Hamirpur.
3. The Superintending Engineers, 10th Circle, HP. PWD., Bilaspur.
4. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through email-eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/ Notice Board.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.78,606/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O Ghawandal to Sh. Naina Devi Ji Temple road km 0/00 to 3/855 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 2/750 to 3/600)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	793.50			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	510.00			Per Cubic Meter	
Total						

Executive Engineer
Bilaspur Division
Bilaspur
Bilaspur
Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.77,985/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O Ghawandal to Sh. Naina Devi Ji Temple road km 0/00 to 3/855 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 1/00 to 2/600)

Sr No.	Description of items.	Quantity	Rates in	Unit	Amount
			Figure. Words.		
1	2	3	4	5	6
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	836.25	Cubic Meter	Per Cubic Meter	7
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	465.00	Cubic Meter	Per Cubic Meter	
Total					

Executive Engineer
Bilaspur Division M
HR PWD, Bilaspur

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.78,480/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O on Sh. Naina Devi Bhakra road km 0/00 to 37/300 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 19/00 to 21/00)

Sr No.	Description of Items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including cartage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	791.25			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including cartage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	510.00			Per Cubic Meter	
Total						

Executive Engineer,
Bilaspur Division No.
H.P. P.W.D., Bilaspur (H.)
R2

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.79,650/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O on Sh. Naina Devi Bhakra road km 0/00 to 37/300 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 23/00 to 25/00)

Sr No.	Description of Items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	776.25			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octon, malikhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	540.00			Per Cubic Meter	
Total						

Executive Engineer,
Bilaspur Division No.
HR, PWD, Bilaspur (H.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.77,733/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O Sh. Naina Devi Ji Toba road km 0/00 to 9/225 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 7/00 to 9/225)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	831.75			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	465.00			Per Cubic Meter	
Total						

Executive Engineer,
Bilaspur Division No.
HR PWD, Bilaspur (M)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.78,648/-Only.

Earnest Money :- Rs.1,600/-

Time:- One Month.

NAME OF WORK:- A/R & M/O on link road to village Nehla km 0/00 to 2/500 (SH:- Maintenance of Earthen Shoulder and Construction of unlined surface drain in km 0/500 to 2/000)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/ Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	794.25			Per Cubic Meter	
2	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	510.00			Per Cubic Meter	
Total						

Executive Engineer,
Bilaspur Division Ho
HR, PWD, Bilaspur (Jh)
(24)