

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Dal/TA/Tender /2024-25 **6721-23**  
To

Dated: - **06-03-25**


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 9 Date of receipt of application for the tender Form a/w requisite documents:- 06.03.2025 onward (between 2.00 p.m. to 4.30 p.m.)  
10 Date of issued/sale of tender form against Cash payment (non refundable).

The tender shall be received up to 3.00 PM on 17.03.2025 and will be opened on the same day at 3.30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 15.03.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

| S. No. | Name of work                                                                                                                                                                                                              | Estimated cost | Earnest Money | Cost of tender | Time Limit | Class |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|---------------|----------------|------------|-------|
| 1.     | Construction of link road to village China k.m. 0/0 to 0/750 (SH:- Formation Cutting between k.m. 0/520 to 0/615)                                                                                                         | 91410.00       | 2000.00       | 350.00         | Two Months | D & C |
| 2.     | Restoration of rain damage on Brangal Wangal Mandoh road k.m. 0/0 to 39/600 (SH:- Removal of Slips between 13/0 to 16/0)                                                                                                  | 98840.00       | 2000.00       | 350.00         | One Month  | D & C |
| 3      | Restoration of rain damage on Banikhet Dalhousie Khajjiar road under Dalhousie Sub Division (SH:- Removal of Slips/ Snow on Banikhet Dalhousie Khajjiar road at RD 15/600 to 27/00)                                       | 98793.00       | 2000.00       | 350.00         | One Month  | D & C |
| 4      | Restoration of rain damage on Banikhet Dalhousie Khajjiar road under Dalhousie Sub Division (SH:- Removal of Slips/ Snow on link road to village Ruliyani k.m. 0/0 to 2/020 & Jandrigat to Pukhri road k.m. 0/0 to 2/180) | 96863.00       | 2000.00       | 350.00         | One Month  | D & C |
| 5      | Restoration of rain damage on Banikhet Dalhousie Khajjiar road under Dalhousie Sub Division (SH:- Removal of Slips/ Snow on link road Kathlog to Bharera k.m. 0/0 to 2/180 & Cantt to Bathri road k.m. 0/0 to 4/700)      | 97594.00       | 1000.00       | 350.00         | One Month  | D & C |
| 6      | Restoration of rain damage on Lahar to Sangrain road k.m. 0/ 0 to 5/500 (SH:- Removal of Slips at R.D.0/0 to 5/500)                                                                                                       | 99365.00       | 2000.00       | 350.00         | One Month  | D & C |
| 7      | A/R & M/O Type-V Quarter (EE Residence) at Dalhousie (SH:- Painting work of (EE Residence) at Dalhousie).                                                                                                                 | 92313.00       | 2000.00       | 350.00         | Two Months | D & C |
| 8      | A/R & M/O Residential Quarters at Banikhet (SH: - Painting and Water Proofing).                                                                                                                                           | 83558.00       | 2000.00       | 350.00         | Two Months | D & C |
| 9      | A/R & M/O to Rose villa Typ-III Quarter at Dalhousie (SH:- Construction of Boundary wall at Back side of Rose villa Quarter at Dalhousie).                                                                                | 93843.00       | 2000.00       | 350.00         | Two Months | D & C |

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.

91  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Dated:- 06-03-25

No. PWD/TA/Tender /2024-25 6724-6773

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

91  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie

### Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:- 6724-73 dated, 06-03-25 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

# Schedule of Qty.

Job No. 01

Name of work: - Construction of Link road to village China Km. 0/0 to 0/750

Descriptions of Item

(SH: - Formation Cutting between Km. 0/520 to 0/615).

Estimated Cost: - Rs. 914  
Earnest Money :- Rs. 20  
Time Limit :- Two Months

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Qty.   | Rate    |          | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        | In fig. | In words |                 |        |
| 1       | Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORDE technical specification section 300 and 1600 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials for to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rates is inclusive of the octroi, royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government. | 378.98 |         |          | Per Cubic Metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        |         |          |                 |        |

Executive Engineer  
Dahousie Divis  
HPWD, Dailho

## Schedule of QTY.

Name of work: -Restoration of rain damage on Hirangal Wargal Mandok road Km. 0.9 to 39.600 (SHE : Removal of Slope between 13.09 to 16.00).

Job No. 02 TS 88  
 Estimated Cost : Rs. 988,40.00  
 Present Money : Rs. 2000.00  
 Time Limit : One Month

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                              | Qty.   | Rate    |          | Unit            | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                   |        | In Pkg. | In words |                 |        |
| 1       | Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lands and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government. | 791.48 |         |          | Per Cubic Metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                   |        |         |          |                 |        |

  
 Engineer  
 Dalhousie Division,  
 H.P.P.A.D. Dalhousie

## Schedule of Qty.

Name of work: - Restoration of rain damage on Banikhet Dalhousie Khajjiar road under Dalhousie Sub-Division (SH: - Removal of Slips/Snow on Banikhet

Job No. 03 TS 92

Estimated Cost: - Rs.

98793.00

Earnest Money :- Rs.


2000.00

Time Limit :-

One Month

Dalhousie Khajjiar road at RD. 15/600 to 27/00).

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                               | Qty.   | Rate    |          | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                    |        | In Fig. | In words |                 |        |
| 1       | Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 161 I. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government. | 791.10 |         |          | Per Cubic Metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                    |        |         |          |                 |        |

  
 Executive Engineer  
 Dalhousie Division,  
 HPWD, Dalhousie

## Schedule of Qty.

Job No. 04 TS 93

Estimated Cost: - Rs.

96863.00

Earnest Money :- Rs.


2000.00

Time Limit :-

One Month

Name of work: - Restoration of rain damage on Banikhet Dalthouse Khajjar road under Dalthouse Sub-Division (SH: - Removal of Slips/Snow on Link road to village Ruliyani Km. 0/0 to 2/020 & Jandrighat to Pakhri road Km. 0/0 to 2/180).

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                              | Qty.    | Rate    |          | Unit            | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                   |         | In fig. | In words |                 |        |
| 1       | Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government. | 775.65  |         |          | Per Cubic Metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                   | Total:- |         |          |                 |        |

  
 Executive Engineer  
 Dalthouse Division,  
 HPPWD, Dalthouse

## Schedule of Qty.

Job No. 05 TS 94

Estimated Cost :- Rs. 97594.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: - Restoration of rain damage on Banikhet Dathousie Khajjiar road under Dathousie Sub-Division (SH :- Removal of Slips/Snow on Link road Kathlog to Bhareira Km. 0/0 to 2/180 & Cantt to Bathri road Km. 0/0 to 4/700).

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                              | Qty.   | Rate    |          | Unit            | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                   |        | In Fig. | In words |                 |        |
| 1       | Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government. | 781.50 |         |          | Per Cubic Metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                   |        |         |          |                 |        |

Executive Engineer  
 Dathousie Division,  
 HPMD, Dathousie

## Schedule of Qty.

Name of work: - Restoration of ruin damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SH: - Removal of Slips at RD 0/0 to 5/500).

Job No. 06 TS 95  
Estimated Cost: - Rs. 99364.80  
Earnest Money: - Rs. 2000.00  
Time Limit: - One Month

| Sl. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                              | Qty.   | Rate    |          | Unit            | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                   |        | In fig. | In words |                 |        |
| 1       | Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611, or as directed by Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government. | 795.68 |         |          | Per Cubic Metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                   |        |         |          |                 |        |

Executive Engineer  
Dainousle Division  
HPPMD, Dainous


## Schedule of Qty.

Job No. 07 TS 96

Name of work :- A/R & M/O Type-V Quarter (EE Residence) at Dalhousie (SH: - Painting work of (EE Residence) at Dalhousie).

|                       |            |
|-----------------------|------------|
| Estimated Cost: - Rs. | 92313.00   |
| Earnest Money :- Rs.  | 2000.00    |
| Time Limit :-         | Two Months |

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Rate    | Unit             | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------|------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          | In Fig. | In Words         |        |
| 1       | Painting two coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government. | 624.17   |         | Per Square Metre |        |
| 2       | Painting two coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Deluxe Paint on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.                                                                       | 135.15   |         | Per Square Metre |        |
| 3       | Painting of G.S. Sheet (excluding Priming Coat) with synthetic enamel paint of Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.                                        | 170.30   |         | Per Square Metre |        |
|         | <b>Total:-</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |         |                  |        |

  
 Executive Engineer  
 Dalhousie Division,  
 HPBWD, Dalhousie

# Schedule of Qty.

Job No. 08 TS 97

Estimated Cost: - Rs.

83558.00

Earnest Money :- Rs.


2000.00

Time Limit :- Two Months

Name of work :- A/R & M/O Residential Quarters at Banikhet (SH: - Painting and Water Proofing).

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Rate    |          | Unit             | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------|----------|------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          | In Fig. | In Words |                  |        |
| 1       | Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                  | 27.90    |         |          | Per Square Metre |        |
| 2       | Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.                                                                                                | 84.64    |         |          | Per Square Metre |        |
| 3       | Painting one coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Delux Paint on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.                                                                                                                                                                       | 17.84    |         |          | Per Square Metre |        |
| 4       | Providing and fixing white vitreous China Pedestal type water closet (European type W.C. Pan) (of approved brand like Hindware, cera, Jagaur etc.) with seat and lid, 10 litre (ten liter) low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (Handle Lever), conforming to IS: 7231, with all fittings and fixture complete, including cutting and making good the walls and floors wherever required as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government. | 2.00     |         |          | Each             |        |
| 5       | Providing and fixing vitreous china wash basin with single hole for pillar tap with CI or MS brackets painted white including cutting holes and making good the same but excluding fittings 550 mm x 400 mm (five hundred millimetre into four hundred millimetre) within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.                                                                                                                                                                                                              | 1        |         |          | Each             |        |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |  |  |                  |  |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--|--|------------------|--|
| 6 | Providing and laying water proofing treatment with Dr. Fixit-FASTFLEX, Polymer, Bitumen, Vinyl-Ester-Resin or equivalent with two components polymer modified cementitious coating consisting of cementitious powder and a polymer liquid in two coats for first coat:- clean and saturate surface and then applying a coat of Dr. Fixit-FASTFLEX by maintaining a coverage of 6-7 square foot per kg to achieve one mm thickness and the same process shall extend upto 300 mm (three hundred millimeter) vertically. The second coat shall be applied in opposite direction after four six-hours of application of first coat then sprinkle sand on top surface of applied Dr. Fixit-FASTFLEX while still tacky over the second coat. Then apply cement mortar 1:4 (1 cement :m 4 sand) admixed with 200 ml (two hundred Millimeter) of pidiproof L.W @ 200ml per 50 kg (fifty kilogram) bag of cement over the floor with the suitable gradient towards drain pipe, while the second coat of Dr. Fixit is still tacky as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government. | 26.73 |  |  | Per Square Metre |  |
| 7 | Dismantling tile work in floors and roofs laid in cement mortar manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 (fifty) meter lead as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 9.16  |  |  | Per Square Metre |  |
| 8 | Providing and fixing 10 mm (ten millimetre) thick antiskid water proof stain and impet resistant heavy duty verified tiles Niteco, Kajaria, Orient Bell or equivalent 600mmx600mmx10mm (six hundred millimetre into six hundred millimetre into ten millimetre) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12 mm (twelve millimetre) thick cement mortar 1:4 (one cement isto four sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 9.16  |  |  | Per Square Metre |  |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |  |  | Total:-          |  |

  
 Executive Engineer,  
 Dalhousie Division,  
 HPWD, Dalhousie

# Schedule of Qty.

Job No. 09 TS 98

Estimated Cost: - Rs. 93843.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: - A/R & M/O to Rose villa Type-III Quarter at Dalthousie (SH: - Construction of Boundary wall at Back side of Rose villa Quarter at

Dalthousie).

| Sr. No. | Descriptions of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Qty.  | Rate    |          | Unit             | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------|----------|------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       | In fig. | In words |                  |        |
| 1       | Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes | 6.48  |         |          | Per Cubic Metre  |        |
| 2       | Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size) and curing complete, in or under water, including pumping or bailing out water/dewatering, removal of slush which may arise at the time of laying under water complete excluding the cost of form work in foundation and plinth in all depths/heights as per HPPWD specifications and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts. The is rate inclusive of Malkhana, royalty, octroi, toll tax, GST or any taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 1.08  |         |          | Per Cubic Metre  |        |
| 3       | Brick work Second class common burnt clay building bricks in super structure above plinth level upto floor to all level in cement mortar 1:6 (one cement isto six sand) as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkhana, toll tax sale tax GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 0.95  |         |          | Per Cubic Metre  |        |
| 4       | Half Brick work Second class common burnt clay building bricks in super structure above plinth level upto floor to all level upto all height/floor level in cement mortar 1:4 (one cement isto four sand) shall be provided with hoop iron and curing complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkhana, toll tax sale tax GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 32.40 |         |          | Per Square Metre |        |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |  |  |  |                  |  |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--|--|--|------------------|--|
| 5        | 15mm cement plaster in single coat on Rough side of brick/concrete/stone walls for interior plastering upto floor all level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (1 cement: 6 sand), within all leads and lift and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.                                        | 75.60  |  |  |  | Per Square Meter |  |
| 6        | Applying Birla white/J.K. white two or more coats wall care putty over plaster surfaces after thoroughly brushing the surface free from mortar drops dust, loose material and other foreign matter sand papered smooth to give final matter finished to the surface complete upto all floor level within all leads and lifts and as per HP PWD specification and per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.                                                                     | 100.80 |  |  |  | Per Square Metre |  |
| 7        | Wall painting with two coat Acrylic emulsion of Asian Paints/Neerolac surksha Paints/Berger Paints/DeLux Paint on undecorated wall having interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams / litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government. | 100.80 |  |  |  | Per Square Metre |  |
| Total: - |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |  |  |  |                  |  |

  
 Executive Engineer  
 Dalhousie Division  
 HPBWD, Dalhousie