

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

13501-10

DATED:

19/3/25

✓ The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President NAC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

Exigency Certificate

It is certified that the tenders invited vide this office NIT
No.....13501-10.....dated....19-03-25 are of emergent nature of work and in
public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:-

- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 26.03.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 27.03.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 28.03.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 28.03.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Preparation of Forest Diversion Case under FRA-2006 for the construction of various Roads under HPPWD Sub Division Dehra (1) L/R from Beehan to Machkund Mahadev Mandir via Baddan and Panjbehar KM 0/0 to 2/496).	Rs. 52,480.00	Rs.2,000/-	One Month	Rs.350/-
02	Preparation of Forest Diversion Case under FRA-2006 for the construction of various roads under HPPWD Sub Division Haripur (1) L/R from Ranjeet Singh House, G.P. Gher KM 0/0 to 0/574 (2) L/R from Jondu Ram House to Subhash Chand House, G.P. Gher KM 0/0 to 0/796 (SH: Preparation of Forest Diversion Case under FRA-2006).	Rs. 95,295.00	Rs.2,000/-	One Month	Rs.350/-
03	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace Road KM 9/00 to 22/200 (SH: P/L Interlocking Paver Block 80mm thick at RD 18/756 to 18/761 & Drain at RD 18/830 to 18/846).	Rs. 99,134.00	Rs.2,000/-	One Month	Rs.350/-
04	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace Road KM 9/00 to 22/200 (SH: C/o Drain at RD 18/846 to 18/895).	Rs. 99,507.00	Rs.2,000/-	One Month	Rs.350/-
05	Construction of Administrative-Cum-Academic Block at GDC Dhaliara (SH: C/o U-Shape Drain near College Gate at RD 0/0 to 0/049).	Rs. 99,507.00	Rs.2,000/-	One Month	Rs.350/-
06	Construction of Administrative-Cum-Academic Block at GDC Dhaliara (SH: P/L 60mm Interlocking Paver Block at RD 0/0 to 0/023.50).	Rs. 99,704.00	Rs.2,000/-	One Month	Rs.350/-
07	Construction of link road from GSSS Sera Bari to Dehra Jawali Road via Dhiman Basti, Choudhary Basti, Harizan Basti in KM 0/0 to 1/345 (SH: P/L 900mm dia HPC, Toe Wall & Catchpit at RD 1/250).	Rs. 99,905.00	Rs.2,000/-	One Month	Rs.350/-
08	Restoration of Rain Damages on Kundlihar to Kathog via Panjla Basti KM 0/0 to 2/600 (SH: C/o R/Wall at RD 2/020 to 2/024, Toe Wall, Abutment & P/L GSB at RD 2/00 to 2/070).	Rs. 99,505.00	Rs.2,000/-	One Month	Rs.350/-
09	Restoration of Rain Damages on Kundlihar to Kathog via Panjla Basti KM 0/0 to 2/600 (SH: C/o R/Wall at RD 2/010 to 2/018.40).	Rs. 99,919.00	Rs.2,000/-	One Month	Rs.350/-
10	Construction of Jawalamukhi Dehra Jawali Raja-Ka-Talab Road in KM 4/00 to 39/180 (SH:P/L Granite Stone for C/o Ashok Stambh, Rain Shelter, Water Booth).	Rs. 98,900.00	Rs.2,000/-	One Month	Rs.350/-
11	Construction of link road from Sapru to Haripur via Koda Gharna in KM 0/0 to 6/00	Rs. 99,990.00	Rs.2,000/-	One Month	Rs.350/-

12	Construction of link road from Sapru to Haripur via Koda Gharna in KM 0/0 to 6/00 (SH: Removal of Formation Deficiencies from KM 2/685 to 2/835).	Rs. 99,017.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P.

on behalf of Governor of Himachal Pradesh

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs52480.00

Earnest Money :-Rs.2000.00

Time Limit :- One Month

Name of work:- Preparation of forest diversion case under FRA, 2006 for the construction of various roads in Dehra Sub Division 1. Link Road from Beehan to Muchkund Mahadev Mandir via Baddan and Panjbehar Km 0/00 to 2/496 Km

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Preparation of KML File, Topo Sheet Map, Alternative Map and Geo Referenced Digital map of proposed land. Preparation of 3 number of proposal folders including Reclamation Plan, Cost Benefit Analysis, Muck Management complete in all respect. Assistance to User Agency to attend the queries and clarification sought by Forest Department. The Rates are inclusive of all equipment within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1.00 Number	40000.00	Rupees Forty Thousand Only	Each	40,000.00
2	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.496 Kilometre	5000.00	Rupees Five Thousand Only	Per Kilometre	12,480.00
Total						52,480.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Billed quantity checked and approved
for Rs 52480/-

Executive Engineer,
Dehra Division,
HPPWD DEHRA

Estimate Cost :- Rs.95295.00
Earnest Money :-Rs.2000.00
Time Limit :- One Month

Name of work:-

Total

Executive Engineer,
Dehra Division,
HPPWD DEHRA

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99134.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Kaloha Pargpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace road in Km.9/00 to 22/200 (SH:- P/L Interlocking Paver Block 80mm thick 18/756 to 18/761 & Drain at Rd 18/830 to 18/846)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	13.60 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,944.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.00 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	16,200.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.80 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	10,440.00
4	Providing and laying ISI marked factory made, chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	37.00 Square metre	1050.00	Rupees One Thousand Fifty Only	Per Square metre	38,850.00
5	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/ dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	6.00 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	29,700.00
	Total					99,134.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Qty Quantity checked & approved as per 79134

Executive Engineer,
Dehra Division,
HPPWD Dehra

490

Name of work:-	Restoration of Rain Damages on Kaiona Pa
	Construction of drain at Rd. 18/846 to 18/895)

Time Limit:- One month.
Office road in Km.9/00 to 22/200 (SH:-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom of excavations necessary for placing the foundations, trimming, leveling ramming and watering of obstructions and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	29.40 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	8,526.00
2	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/ dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	18.38 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	90,981.00
	Total					99,507.00

Bigger quantity checked & approved for

Buddy Bryant Executive Engineer
76086 9508

Executive Engineer,
Dehra Division,
UPPWD Dehra

484

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,507.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- C/o Administrative Cum Academic Block at GDC Dhaliara. (SH:- Construction of U-Shape Drain Near College Gate at RD 0/0 to 0/049).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	29.40 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	8,526.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	18.38 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	90,981.00
	TOTAL					99,507.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,507.00/- only.

Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,704.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- Construction of Administrative Cum Academic Block at GDC Dhaliara (SH:- Providing and laying 60mm Interlocking Paver Block at RD 0/0 to 0/023.50).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	7.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,030.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	7.00 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	28,350.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in open foundation Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in open foundation etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, Toll tax or any other taxes imposed by the Government.	2.05 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	11,890.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm (Sixty millimetre) of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	61.10 Square metre	940.00	Rupees Nine Hundred Forty Only	Per Square metre	57,434.00
	Total					99,704.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved
for Rs. 99,704.00/- only


Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,905.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

me of work:- C/o link road GSSS Sera Bari to Dehra Jawali road via Dhiman Basti, Choudhary Basti, Harizan Basti in Km 0/0 to 1/345. (SH:- Providing and laying 900mm dia Hume Pipe Culvert, Toewall & Catchpit at RD 1/250).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	20.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	5,800.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	0.70 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	2,835.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, in Toe wall and parapets etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	7.80 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	40,560.00
4	Providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement isto two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	12.50 Running metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per Running metre	47,500.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the	0.70 Cubic metre	3300.00	Rupees Three Thousand Three Hundred Only	Per Cubic metre	2,310.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	1.20 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	900.00
	TOTAL					99,905.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99905.00/only.

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99505.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damages on Kundlihar to kathog via Panjla Basti in Km. 0/00 to 2/600 (SH:- C/o R/wall at RD. 2/020 to 2/024, Toe wall, Abutment & P/L GSB at RD. 2/000 to 2/070)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.40 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	696.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	5.76 Cubic meter	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic meter	21,600.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of Gravel/Granular sub base/base 100mm (one hundred twenty five millimeter) compacted thickness by providing well graded material of nominal maximum size 80mm (eighty millimeter) Type 'A' conforming to table 2.3 of IRC- SP-77 -2008 and spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with tractor mount appropriate rotavator at OMC and compacting with three wheel 80-100 (Eighty-Hundred) kN static roller to achieve the desired density, complete as per MORD Technical specification clause 401 and as per the direction and entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	34.30 Cubic meter	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic meter	46,305.00
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, in Toe wall and abutment etcetera including cost of form work and curing complete as per MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	5.27 Cubic meter	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic meter	27,404.00
5	Back filling behind abutment Retaining wall/Breast wall. Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	2,250.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
6	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204 3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	1,250.00
	Total					99,505.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bluey 94cm 144 checked 18
 11/12/2017 for Rs 99505/-

Executive Engineer,
 Dehra Division,
 MPPWD Dehra

9

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99919.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damages on Kundlihar to kathog via Panjla Basti in Km. 0/00 to 2/600 (SH):- C/o R/wall at RD. 2/010 to 2/018,40).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.09 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	2,636.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	23.58 Cubic meter	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic meter	88,425.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.81 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	7,358.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	1,500.00
	Total					99,919.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & approved for Rs 99919/-

Executive Engineer,
Dehra Division,
UPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98,900.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One months.

Name of work:- Improvement of Blackspot on Jawalamukhi- Dehra- Jawali- Raja ka Talab road km 4/00 to 39/180. (S.H.:- P/L Granite stone in Construction of Ashok Stanbh, Water Booth & Rain Shelter)

Sr. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figures	words		
1	Providing and laying granite stone/black granite/Red Lakha/Sadar Ali in flooring 20mm average thickness base of cementmortar 1:3 (1cement : 3 sand) laid over and jointed with grey cement slury mixed with pigment to match the shade of granite stone i/c rubbing and polishing, double/single moulding ,16-20 mm thick complete including carriage of material with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	21.50	4600.00	Rupees Four Thousand Six Hundred Only	Per Square Meter	98900.00
	Total					98900.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

18000 quantity checked & approved for Rs. 98,900/- only.

[Signature]
 Executive Engineer
 Dehra Division
 H.P.PWD. Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,990.00
Earnest Money :- Rs. 2000.00

Time Limit :- One Months.

Name of work:- Construction of Link road from Sapru to Haripur via Koda Sharna in Km 0/0 to 6/000 (SH:- Removal of Formation Deficiencies from Km 2/500 to 2/650).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels as shown in the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 30.00 cubic meter quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	303.00 Cubic metre	330.00	Rupees Three Hundred Thirty Only	Per Cubic metre	99,990.00
	Total					99,990.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,990.00 only.

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,017.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Months.

Name of work:- Construction of Link road from Sapru to Haripur via Koda Sharna in Km 0/0 to 6/000 (SH:- Removal of Formation Deficiencies from Km 2/685 to 2/835).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels as shown in the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification section 300 & 1600 and sorting out and stacking of useful materials with in all leads and lifts in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 30.00 cubic meter quantity at the rate of Rs. 300/- only (Rupees three hundred only) per cubic meter shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	300.05 Cubic metre	330.00	Rupees Three Hundred Thirty Only	Per Cubic metre	99,017.00
	Total					99,017.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 99,017.00/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra.