

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2024-25- 24951-75

Dated:- 26-03-2025

To

✓ The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) A (3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dharni on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **05-04-2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **04.04.2025 up to 5:00 PM** and the application for issue of tender form shall be received on **03.04.2025 up to 4:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dharni must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. **The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons.** If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/O 16 Mile Sedan road Km. 0/00 to 2/660 (SH: C/O R/Wall at Rd. 2/422.10 to 2/424.20).	96250/-	2000/-	One month	Rs.350/-
2	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00(SH: C/O R/Wall at Rd. 1/528 to 1/533.50).	99963/-	2000/-	One month	Rs.350/-
3	Special repair to Judicial Court Complex at Chakkar Shimla (SH: Providing & fixing aluminium windows frames, paneled shutter and wire gauge shutter in POCOSO gallery at court chakkar at Shimla).	99584/-	2000/-	One Month	Rs.350/-
4	Special repair to Govt. S.S.S. at Kaina-1 Teh. & Dist. Shimla (SH: C/O B/Wall in school campus) Deposit work.	99117/-	2000/-	One month	Rs.350/-
5	A/R & M/O on Shimla Mandi road Km. 22/00 to 33/200 (SH: C/O R/Wall at Rd. 32/600.20 to 32/601).	45211/-	1000/-	One Month	Rs.350/-
6	C/O link road from Daud to Neen Km. 0/00 to 1/00 (SH: Formation cutting 5/7 mtr. Wide at Rd. 0/445 to 0/490).	99982/-	2000/-	One Month	Rs.350/-
7	Construction of Veterinary Hospital building at Deola Tehsil Sunni Dist. Shimla (H.P.) (SH: Providing and laying interlocking paver thereof).	99750/-	2000/-	One Month	Rs.350/-
8	C/O Ambulance road to Uparli Fathachi Km. 0/00 to 0/750 (SH: C/O R/Wall at Rd. 0/095 to 0/097.50).	96993/-	2000/-	One Month	Rs.350/-
9	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 1/544 to 1/548).	99532/-	2000/-	One Month	Rs.350/-
10	Special repair to Govt. S.S.S. at Kaina-1Teh. & Dist. Shimla (SH: P/L stone soling and cement concrete 1:2:4 in school campus) Deposit work.	99122/-	2000/-	One month	Rs.350/-
11	Special repair to Judicial Court Complex at Chakkar Shimla (SH: Providing & fixing Aluminium door frame & shutter in ADJ-01 & covering below window in POCOSO gallery at Chakkar Shimla).	94997/-	2000/-	One Month	Rs.350/-

12	A/R & M/O on Chanawag Dawaroo road Km. 0/00 to 1/700 (SH: C/O B/Wall in between Km. 0/580 to 0/587.50).	94939/-	2000/-	One Month	Rs.350/-
13	Improvement on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: Cutting in Km. 8/910 to 8/940) Balance work.	97091/-	2000/-	One Month	Rs.350/-
14	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: C/O R/Wall at Rd. 6/411 to 6/413 and 6/419 to 6/421).	98260/-	2000/-	One Month	Rs.350/-
15	A/R & M/O Bainsh Bangera road Km. 0/00 to 3/00 (SH: Maintenance of erathern road surface and construction of unlined drain in Km. 0/00 to 3/00).	94535/-	2000/-	One month	Rs.350/-
16	Annual repair to Director residence at Judicial Academy ghandal (SH: P & F Jaffari on back side, Aluminium work, interlocking tiles and painting etc.)	95865/-	2000/-	One Month	Rs.350/-
17	C/O Jawahar Lal govt. College of fine Arts at Loharav, Distt. Shimla (SH: Providing fixing glazing & Granite work for canteen for students).	96912/-	2000/-	Three months	Rs.350/-
18	A/R & M/O Tutikandi Sheelgaon via Kiari road Km. 0/00 to 3/870 (SH: C/O B/Wall at Rd. 2/522 to 2/527).	98246/-	2000/-	One month	Rs.350/-
19	A/R & M/O Tutikandi Sheelgaon via Kiari road Km. 0/00 to 3/870 (SH: C/O B/Wall at Rd. 2/512 to 2/517).	98208/-	2000/-	One month	Rs.350/-
20	A/R & M/O Totu Taradevi road Km. 0/00 to 4/105 (SH: C/O R/Wall at Rd. 3/950 to 3/965) Balance work.	83483/-	2000/-	One month	Rs.350/-
21	C/O link road from Daud to Neen Km. 0/00 to 1/00 (SH: Formation cutting 5/7 mtr. Wide at Rd. 0/580 to 0/620).	99774/-	2000/-	One Month	Rs.350/-
22	C/O Shara Nallah to village Nallah road Km. 0/00 to 2/300 & C/O Shara Nallah to village Nadoth road Km. 0/000 to 2/700 (SH: Providing & fixing of village board and reflectorized cautionary, mandatory and informatory sign board and RCC Km. stone/local stone).	90000/-	2000/-	One Month	Rs.350/-
23	R/R damages on Jathiadevi Rampuri road Km. 0/00 to 6/300 (SH: C/O R/Wall at Rd. 3/563.70 to 3/567.40).	97276/-	2000/-	One Month	Rs.350/-
24	R/R damages on Shal Chanog road Km. 0/00 to 7/330 and Majthai Bharyal road Km. 0/00 to 2/600 under Badhari section (SH: Hiring of JCB for removal of snow/slips).	98550/-	2000/-	One Month	Rs.350/-
25	Geological investigation for construction of Liabrary at Hanuman Parisar at Suni Tehsil Suni, Distt. Shimla H.P.	98550/-	2000/-	One Month	Rs.350/-
27	Geological investigation for construction of bridge at Khaira on Slapper Tatapani Suni Luhri road Km. 72/00 to 86/000.	97038/-	2000/-	One Month	Rs.350/-
28	Special repair to residential accommodation of govt. Ayurvedic health Centre at thaila Tehsil Duni Distt. Shimla H.P (SH: Providing fixing G.I. Sheet for roofing & Marval work, distemperng thereof).				
29	Special repair to residential accommodation of govt. Ayurvedic health Centre at thaila Tehsil Duni Distt. Shimla H.P (SH: Cement Plaster, Cement sheet Ceiling thereof).	99966/-	2000/-	One Month	Rs.350/-
30	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: C/O R/Wall at Rd. 6/407 to 6/409 and 6/415 to 6/417).	98256/-	2000/-	One Month	Rs.350/-
31	Improvement on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: Cutting in Km. 9/070 to 9/100) Balance work.	98226/-	2000/-	One Month	Rs.350/-
32	Construction of Veterinary Hospital building at Deola Tehsil Sumi Distt. Shimla (H.P.) (SH: Providing and laying interlocking paver thereof).	95765/-	2000/-	One Month	Rs.350/-

33	C/O link road from Jalog Gadheri to Harijan basti Tharu Km. 0/00 to 1/00 (SH: Providing & fixing of village board and reflectorized cautionary, mandatory and informatory sign board).	91000/-	2000/-	One Month	Rs.350/-
34	Annual repair to Director residence at Judicial Academy ghandal (SH: P & F Jaffari on back side, Aluminium work, interlocking tiles and painting etc.)	98843/-	2000/-	One Month	Rs.350/-
35	C/O Jawahar Lal govt. College of fine Arts at Loharav, Distt. Shimla (SH: Providing fixing aluminium door, window for providing canteen for students).	97797/-	2000/-	Three months	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the percentage rates both in figures and in word failing which tender is likely to be rejected.

**Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhamsi.**

Certificate

Certified that the tenders called vide this notice inviting tender for 35 (Thirty five) jobs are due to exigencies/emergency of works in the larger public interest.

**Executive Engineer,
Shimla Rural Division,
H.P.P.W.D. Dhamsi.**

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

Note : (i) All the material will procured by the contractor him self.

Name of Work:- Construction of 16 Mile Sedan Road Km. 0/00 to 2/660 (Sh: Construction of R-wall at Rd. 2/422.10 to 2/424.20)									
SCHEDULE OF QUANTITY									
S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount	Time -	
			figures					One Month	
								Earnest Money - Rs 2000 /-only	
Estimated Cost - Rs 96250 /- only									
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	7.09	Cum	233.40		Rupees Two Hundred Thirty Four Only	Per cubic metre	1655.00	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	4.83	Cum	356.50		Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1722.00	
3	Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering in all work upto plinth level :- 1:5:10 (1 cement: 5 sand : 10 graded stone aggregate 40 mm nominal size) including the carriage of material upto all leads and lifts as per thed direction of Engineer in Charge.	26.02	Cum	3450.00		Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	89769.00	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	1.83	Cum	841.80		Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1540.00	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v).20(H) towards drawing face complete as per drawing and technical specification including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	9.20	Rmt.	170.00		Rupees One Hundred Seventy Only	Per Running Metre	1564.00	
0							Total:	96250.00	
Amount Quoted by the Contractor in Percentage									
Rs.									

Schedule Of Quantity

Name Of Work :- Construction of Nehra via Keru km. 0/00 to 3/00 (SH:- C/O Retaining wall at Rd. 1/528 to 1/533.50)

Estimated Cost:- 99,963.00

Earnest Money:- 2,000.00


Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	3	4	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	8
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6.12	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2182
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 10mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. Including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.40	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93840
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v) 20(h) towards drawing face complete as per drawing and technical specification clauses 614.709, 1204.3.7	5.45	Rmt.	170.00	Rupees One Hundred Seventy Only	Per running Metre	927
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP, PWD, specifications of 1990 volume-I, including carriage of material within all leads and lifts.	2.45	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2062
Total Rs.							99963
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhamsi. *Bm*

Schedule Of Quantity						Estimated Cost:- 99,584.00	
Name Of Work :- Special repair to Judicial Court Complex at Chakkar Shimla (SH:- Providing and fixing aluminium Widnow frames , Panelled shutter & wire gauge shutter in Pocso Gallery at Chakker Court Shimla)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	65.50	Kg.	680.00	Rupees Six Hundred Eighty Only	Per killogram	44540
2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	54.76	Kg.	690.00	Rupees Six Hundred Ninety Only	Per killogram	37784
3	Providing and Fixing shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	9.47	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square metre	11838
4	Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.50mm dia wire and 1.4 mm wide aperture with matching wood beading including carriage of material within all leads and lifts.	2.15	Sqm	550.00	Rupees Five Hundred Fifty Only	Per Square metre	1183
5	Providing and fixing 100x58x1.90 mm size M. S. pressed butt hinges bright finished with necessary screws etc complete including carriage of materials within all leads and lifts.	24.00	No.	70.00	Rupees Seventy Only	Each	1680
6	Providing and fixing bright finished hard drawn hooks and eyes as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	8.00	No	70.00	Rupees Seventy Only	Each	560

6	Providing and fixing oxidised M.S hooks and eyes 150mm complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge	8.00	No	70.00	Rupees Seventy Only	Each	560
7	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :150mm.	8.00	No	70.00	Rupees Seventy Only	Each	560
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :200mm x 10mm.	16.00	No	90.00	Rupees Ninety Only	Each	1440
Total Rs.							99584
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. 

SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Govt. Sr.Sec.School at Kaina-I The. & District Shimla, H.P. (Sh: Construction of B-wall in School Campus) Deposit Work Job No. 2

Estimated Cost: - Rs 99117 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
			4	5		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	13.00 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	4635.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	20.00 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	92000.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	14.60 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	2482.00
0					Total:	99117.00

Amount Quoted by the Contractor in Percentage	Rs.
------------------------------------------------------	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

ti Schedule Of Quantity						Estimated Cost:- 45,211.00	
Name Of Work :- A/R & M/O on Shimla Mandi Road km. 22/000 to 33/200 (SH:- C/O R/wall at Rd. 32/600.20 to 32/601) Job No.5						Earnest Money:- 1,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	0.72	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	168
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	1.15	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	410
3	Providing and laying cement concrete drain with cement concrete 1:3:6 (one cement : 3 sand : 6 graded stone aggregate 20 mm nominal size) mechanically mixed in open surface drain with plinth protection having internal size 20x15 cm & with side wall of 10 cm thick & inside plastering with CM. 1:3 including earthwork & finished with floating coat of neat cement complete as per standard design as per HPPWD specification 1990 volume - I including carriage of all labour equipments and materials to various location through complete including carriage of material in all leads and lifts as per direction of Engineer in Charge.	8.08	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	42016
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	5.00	Rmt.	180.00	Rupees One Hundred Eighty Only	Per running Metre	900
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2.04	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1717
Total Rs.							45211
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
UPPWD Dhami

Schedule Of Quantity						Estimated Cost:- 99,982.00	
Name of Work :- C/o Link road from Daud to Neen km. 0/00 to 1/00 (SH:- Formation Cutting 5/7 mtr wide at Rd. 0/445 to 0/490)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	6	7
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones , shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 40.01 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	399.13	Cum	250.50	Rupees Two Hundred Fifty and Paise Fifty Only	Per cubic metre	99982
Total Rs.							99982
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhanni.

Schedule Of Quantity						Estimated Cost:- 99,750.00	
Name Of Work :- Construction of Veterinary Hospital building at Deola Tehsil Sunni Distt. Shimla (HP) (SH:- Providing and Laying interlocking Paver thereof)						Earnest Money:- 2,000.00	
						Time:- One Months.	
						Unit	Amount
S.No	Description of Work	No. of Qty.		Rate			
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge:- 60mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.including carriage of material in all leads and lifts as per direction of the Engineer in Charge	75.00	Sqm	1330.00	Rupees One Thousand Three Hundred Thirty Only	Per Square metre	99750
	Total Rs.						99750
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama

Name of Work:- Construction of Ambulance Road to Uparli Fatechi Km. 0/00 to 0/750 (Sh: Construction of R-wall at Rd. 0/095 to 0/097.50)

SCHEDULE OF QUANTITY

Estimated Cost - Rs 96993 /- only
Earnest Money - Rs. 2000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3.60 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 840.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	4.88 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 1740.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.89 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 91494.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	3.80 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 646.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.70 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 2273.00
0				Total:	96993.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 99,532.00	
Name Of Work :- Construction of Nehra via Keru km. 0/00 to 3/00 (SH:- C/O Retaining wall at Rd. 1/544 to 1/548)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	405 ३१	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	945
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6248 ३१	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2310
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20130 ३१	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	93380
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	5145 ३१	Rmt.	170.00	Rupees One Hundred Seventy Only	Per running Metre	927
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2384 ३१	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	1970
Total Rs.							99532
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama.

SCHEDULE OF QUANTITY						
Name of Work:- Special Repair to Govt. Senior Sec. School at Kaina-I Tehsil & District Shimla (Sh: Providing & Laying Stone Soling and Cement Concrete 1:2:4 in School Campus) Deposit Work Job No. 3				Estimated Cost: - Rs 99122 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month		
S. No.	Sub head and items of work	Qty.	Rate figures		Unit	Amount
1	2	3	4	5	6	7
1	Providing and laying compacting stone soling of specific size to properly hand packed tightly in under flooring as per drawing complete and technical specification by manual means (i) 100 mm thickness including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	16.35 Cum	1400.00	Rupees One Thousand Four Hundred Only	Per cubic metre	22890.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	13.04 Cum	5846.00	Rupees Five Thousand Eight Hundred Forty Six Only	Per Cubic Metre	76232.00
0					Total:	99122.00


Amount Quoted by the Contractor in Percentage	Rs.
------------------------------------------------------	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 94,997.00	
Name Of Work :- Special repair to Judicial Court Complex at Chakkar Shimla (SH:- Providing and fixing aluminium door frame and shutter in ADJ - 01& Covering below window in Pocso Gallery at Chakker Court Shimla)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	73.82	Kg.	680.00	Rupees Six Hundred Eighty Only	Per killogram	50198
2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material within all leads and lifts	36.74	Kg.	690.00	Rupees Six Hundred Ninety Only	Per killogram	25351
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm	5.86	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square metre	7325
4	Providing and fixing Plain/coloured polycarbonate transparent sheet 1.20 mm thick in foofing and lining with self drilling screws along with washers etc. complete with all accessories as required to complete the work in all leads and lifts as per direction of Engineer-in-charge	4.31	Sqm	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per killogram	7543
5	Providing and fixing bright finished hydraulic door closer of Godraj make or equivalent with screws etc. complete including carriage of materials in all leads and lifts.	2.00	No.	1850.00	Rupees One Thousand Eight Hundred Fifty	Each	3700

6	Providing and fixing 100x58x1.90 mm size M. S. pressed butt hinges bright finished with necessary screws etc complete including carriage of materials within all leads and lifts.	6.00	No.	70.00	Rupees Seventy Only	Each	420
7	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :200mm x 10mm.	2.00	No	90.00	Rupees Ninety Only	Each	180
8	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :150mm.	4.00	No	70.00	Rupees Seventy Only	Each	280
							94997
Total Rs.							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi 

SCHEDULE OF QUANTITY
Name of Work:- Annual Repair & Maintenance of Chanawag Dawaroo Road Km. 0/00 to 1/700 (Sh: Construction of Breast Wall in Between Km. 0/580 to 0/587.50)

Estimated Cost : - Rs 94939 /- only
 Earnest Money : - Rs. 2000 /- only
 Time : One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	7.50 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 1751.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	5.25 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre 1872.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.43 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 89378.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	11.40 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre 1938.00
0				Total:	94939.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 97,091.00	
Name of Work :- Improvement on Galog Nehra Okhroo road km. 0/00 to 11/135 (SH:- Cutting in km. 8/910 to 8/940) Balance work Job No. 3						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 41.18.00 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	247.05	Cum	393.00	Rupees Three Hundred Ninety Three Only	Per Cubic metre	97091
Total Rs.							97091
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 98,260.00	
Name of Work :- Restoration of Rain Damages on Galog Nehra Okhroo Road km. 0/00 to 11/135 (SH:- Constuction of Retaining wall at Rd. 6/411 to 6/413 and 6/419 to 6/421)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried, out true tolines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	3.46	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	808
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6.94	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2474
3	Providing and laying lean cement concrete 1:4:8 (one cement :four sand :eight graded stone aggregate 20mm nominal size)(Twenty millimetre) and curing complete excluding cost of form work with pidilite or Dr.fixit water proofing treatment as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts.	19.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	89884
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 Including carriage of material within all leads and lifts.	16.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	2720
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I.Including carriage of material within all leads and lifts.	2.82	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2374
Total Rs							98260
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhama

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Bainsh Bangera Road Km. 0/00 to 3/00 (Sh: Maintenance of erthen road surface and construction of unlined drain in Km. 0/00 to 3/00)

Estimated Cost: - Rs 94535 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Removal of land slides slip clearance Removalof land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	353.00 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	33535.00
2	Maintenance of Earhen road surface (stripping of excess soil) , Stripping excess soil from the earthen surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	1400.00 Sqm	10.00	Rupees Ten Only	Per Square Meter	14000.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with all leads and lifts as per technical specifications as per the directions of Engineer-in-Charge including carriage of material upto all leads and lifts. .	1175.00 Rmt.	40.00	Rupees Forty Only	Per Running Meter	47000.00
0					Total:	94535.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dhama

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Repair to Repair to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc.) Job No. 2				Estimated Cost: - Rs 95865 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month		
Sr. No.	Sub head and items of work	Qty.	Rate in figures		Unit	Amount
			4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.15 Cum	5846.00	Rupees Five Thousand Eight Hundred Forty Six Only	Per Cubic Metre	6723.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	938.34 Kg.	95.00	Rupees Ninety Five Only	Per Kilogramme	89142.00
					Total:	95865.00

Draft Schedule of Quantity approved for Rs.95865/- only (Rupees Ninety Five Thousand Eight Hundred Sixty Five Only) At Sr. No. 870, year 2024-25

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Name of Work:- Construction of Jawahar Lal Govt. College of Fine Arts at Loharav, District Shimla (Sh: Providing fixing glazing & Granite work for canteen for students)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 96912 /- only

Earnest Money : - Rs. 2000 /-only

Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3		4	5	6	7
1	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with 5mm thick float glass etc. complete as per the detailed drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm) including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	50.76	Sqm	1129.79	Rupees One Thousand One Hundred Twenty Nine and Paise Seventy Only	Per Square Meter	57344.00
2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels: Granite of any colour and shade including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	7.56	Sqm	4862.00	Rupees Four Thousand Eight Hundred Sixty Two Only	Per Square Meter	36757.00
3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge including carriage of material in all leads and lifts as per direction of the Engineer in Charge. Granite work.	10.60	Rmt	265.15	Rupees Two Hundred Sixty Five and Paise Fifteen Only	Per Running Meter	2811.00
0						Total:	96912.00


Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhani


Schedule Of Quantity						Estimated Cost:- 98,246.00	
Name of Work :- A/R & M/O Tutikandi Sheelgaon via Kiari Road km. 0/00 to 3/870. (C/O Breast wall at Rd. 2/522 to 2/527)						Earnest Money:- 2,000.00	
						Time:- One Months.	
						Unit	Amount
S.No	Description of Work	No. of Qty.		Rate			
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	7.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1680
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	7.76	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2766
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.44	Cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	91368
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	12.80	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running metre	2432
Total Rs.							98246
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama. 

Schedule Of Quantity						Estimated Cost:- 98,208.00	
Name of Work :- A/R & M/O Tutuikandi Sheelgaon via Kiari Road km. 0/00 to 3/870. (C/o Breast wall at Rd. 2/512 to 2/517)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	7.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1680
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	7.76	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2766
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.44	Cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	91368
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	12.60	Rmt.	190.00	Rupees One Hundred Ninety Only	Per running Metre	2394
Total Rs.							98208
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 83,483.00	
Name of Work :- A/R & M/O on Totu Tara Devi road km. 0/00 to 4/105 (SH:- Construction of Retaining wall at Rds. 3/950 to 3/965) Job No.2 (Balance work)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	8.14	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2902
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand :8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.16	Cum	4700.00	Rupees Four Thousand Seven Hundred Only	Per cubic metre	75952
3	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2.70	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2273
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	12.40	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2356
	Total Rs.						83483
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhama. 

Schedule Of Quantity						Estimated Cost:- 99,774.00	
Name of Work :- C/o Link road from Daud to Neen km. 0/00 to 1/00 (SH:- Formation Cutting 5/7 mtr wide at Rd. 0/580 to 0/620)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones , shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 39.80 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	398.30	Cum	250.50	Rupees Two Hundred Fifty and Paise Fifty Only	Per cubic metre	99774
Total Rs.							99774
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharm

Schedule Of Quantity						Estimated Cost:- 90,000.00	
Name of Work :-Construction of Shara Nallah to Village Nallah road km. 0/00 to 2/300 & C/O Shara Nallah to Village Nadoth road km. 0/00 to 2/700 (SH:- Providing and fixing of village board and reflectorized cautionary , mandatory and informatory sign board and RCC Km. stone/local stone)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6 7	8
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over MS sheeting 1.5 mm thick supported on a mild steel angle iron post 75x40 Lc firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 450mm x 450mm x 600mm below ground level as per drawings and Technical Specification Clause 801. (identification sign with size 1200x900 (informatory sign board)	4.00	No	7000.00	Rupees Seven Thousand Only	Each	28000
2	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over MS sheeting 1.5 mm thick supported on a mild steel angle iron post 75x40 Lc firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 450mm x 450mm x 600mm below ground level as per drawings and Technical Specification Clause 801. (identification sign with size 750x600 (Village board)	1.00	No	5000.00	Rupees Five Thousand Only	Each	5000
3	Reinforced cement concrete M15 grade KM stone/local stone and standard design as per IRC 8 fixed in position including and printing etc. (5th)	2.00	No	6000.00	Rupees Six Thousand Only	Each	12000
4	Reinforced cement concrete M15 grade KM stone/local stone and standard design as per IRC 8 fixed in position including and printing etc.	10.00	No	4500.00	Rupees Four Thousand Five Hundred Only	Each	45000
Total Rs.							90000
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi

Name of Work:- Restoration of rain damages on Jathia Devi Rampuri Road Km. 0/00 to 6/300 (Sh: Construction of Retaining wall at R.D. 3/563.70 to 3/567.40)				Estimated Cost: - Rs 97276 /- only Earnest Money : - Rs. 2000 /-only Time: - One Month	
SCHEDULE OF QUANTITY					
S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	6.66 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	6.96 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.57 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (I) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	2.37 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	7.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre
0					Total: 97276.00

Amount Quoted by the Contractor in Percentage	Rs.
-----------------------------------------------	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhani

Name of Work:- Restoration of rain damages on Shal Chanog Road Km. 0/00 to 7/330 and Majthai Bharyal Road Km. 0/00 to 2/600 under Badheri Section (Sh: Hiring of JCB for removal of snow / Slips)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 98550 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Hiring of Excavator-cum-Loader for removal of slips including cost of fuel oil lubricants wages of operational staff any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor & including all leads and lifts & work shall be executed as per the direction of Engineer -in-Charge.	90.00 Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour
0					98550.00
Total:					98550.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhani

Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- Geological Investigation for Construction of Library at Hanuman Parisar at Suni Tehsil Suni, Distt Shimla . HP. Job No.1						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
I	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.50	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Perrunning metre	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm.

Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- Geological Investigation for Construction of bridge at Khaira on Slapper Tatapani Suni Luhri road km. 72/000 to 86/000 (Job No.1)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and demobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.50	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Schedule Of Quantity						Estimated Cost:- 97,038.00	
Name Of Work :- Special Repair to Residential accomodation of Govt. Ayurvedic Health Centre at Thaila Tehsil Suni Distt Shimla HP.(SH:- Providing Fixing G.I Sheet for roofing & Marval work, Distemping Thereof)						Earnest Money:- 2,000.00	
						Time:- One Months.	
						Unit	Amount
S.No	Description of Work	No.of Qty.		Rate			
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing corrugated G.I. sheet roofing including vertical/curved surface fixed with polymer coated J or L. hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.63 mm thick.	30.24	Sqm	1053.43	Rupees One Thousand Fifty Three and Paise Forty Three Only	Per Sqaure metre	31856
2	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm thick glass panes	1.89	Sqm	996.51	Rupees Nine Hundred Ninety Six and Paise Fifty One Only	Per Sqaure metre	1883
3	Providing and laying marble work with baroda green marble having semi round noising (table rubbed and polished) in flooring 20 mm thick base in cement mortar 1:3 (1 cement: 3 coarse sand), including jointing with white cement mortar 1:2 (1 white cement: 2 marble dust) with an admixture of pigment to match the marble shade of the marble 20 mm thick baroda green marble including carriage of materials upto all leads and lifts.	4.86	Sqm	3345.00	Rupees Three Thousand Three Hundred Forty Five Only	Per Sqaure metre	16257
4	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with Alkali-resistance primer of approved brand and manufacture after throughly brushing the surface free from mortar drooping and other foreign matter and also including preparing the surface even and sand papered smooth.	333.75	Sqm	140.95	Rupees One Hundred Forty and Paise Ninety Five Only	Per Sqaure metre	47042
Total Rs.							97038
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 99,966.00	
Name of Work :- Special Repair to Residential accomodation of Govt. Ayurvedic Health Centre at Thaila Tehsil Suni Distt Shimla HP.(SH:- Cement Plaster ,Cement sheet Ceiling thereof)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate	Unit	Amount	
				In figures			
1	2	3	4	5	6	7	8
1	Providing and fixing plain asbestos cement sheet ceiling of approved quality with butt jointing and wood screws (frame work and fillets to be measured and paid for separately	40.16	Sqm	614.89	Rupees Six Hundred Fourteen and Paise Eighty Nine Only	Per Square metre	24694
	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement 4 fine sand	183.47	Sqm	410.27	Rupees Four Hundred Ten and Paise Twenty Seven Only	Per Square metre	75272
	Total Rs.						99966
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. *Som*

Schedule Of Quantity						Estimated Cost:- 98,256.00	
Name of Work :- Restoration of Rain Damages on Galog Nehra Okhroo Road km. 0/00 to 11/135 (SH:- Constuction of Retaining wall at Rd. 6/407 to 6/409 and 6/415 to 6/417)						Earnest Money:- 2000.00	
						Time:- One Months.	
						Unit	Amount
S.No	Description of Work	No. of Qty.		Rate			
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	3.46	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	808
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	6.94	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2474
3	Providing and laying lean cement concrete 1:4:8 (one cement :four sand :eight graded stone aggregate 20mm nominal size)(Twenty milimetre) and curing complete excluding cost of form work with pidilite or Dr.fixit water proofing treatment as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts.	19.54	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	89884
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full with of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 Including carriage of material within all leads and lifts.	15.98	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	2717
5	Back filling filling behind abutment wing wall and retaning wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2.82	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2374
Total Rs							98256
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 98,226.00	
Name of Work :- Improvement on Galog Nehra Okhroo road km. 0/00 to 11/135 (SH:- Cutting in km. 9/070 to 9/100) Balance work Job No. 9						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones , shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 41.65 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	249.94	Cum	393.00	Rupees Three Hundred Ninety Three Only	Per Cubic metre	98226
	Total Rs.						98226
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 95,765.00	
Name Of Work :- Construction of Veterinary Hospital building at Deola Tehsil Sunni Distt. Shimla (HP) (SH:- Providing and Laying interlocking Paver thereof)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	0.64	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic Metre	228
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) M-10	9.79	Cum	5300.00	Rupees Five Thousand Three Hundred Only	Per Cubic Metre	51887
3	Steel work welded in built up sections/ framed work, including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. As per required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in charges.	330.00	Kg.	120.00	Rupees One Hundred Twenty Only	Per Kilogram	39600
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture. including carriage of materials with in all leads, lifts and other incidentals.	30.00	Sqm	135.00	Rupees One Hundred Thirty Five Only	Per Square Metre	4050
Total Rs.							95765
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. *Sam*

Schedule Of Quantity						Estimated Cost:- 91,000.00	
Name of Work :- Construction of Link road from Jalog Gadheri road to Harijan Basti Tharu km. 0/00 to 1/00 (SH:- Providing and Fixing of village board and reflectorized cautionary, mandatory and information sign board)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over M S sheeting, 1.5 mm thick supported on a mild steel angle iron post 75x40 Le firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 801. i) Direction and place in nification sign with size 1200x900 (informatory sign board)	13.00	No	7000.00	Rupees Seven Thousand Only	Each	91000
Total Rs.							91000
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi

DRAFT SCHEDULE OF QUANTITY


Name of Work:- Annual Repair to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc.) Job No. 1

Estimated Cost: - Rs 98843 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

Sr. No.	Sub head and items of work	Qty.	Rate in figures		Unit	Amount
			4	5		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within all lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	27.07 Cum	619.05	Rupees Six Hundred Nineteen and Paise Five Only	Per Cubic Metre	16758.00
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 40 mm (Forty milimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	8.13 Cum	4955.20	Rupees Four Thousand Nine Hundred Fifty Five and Paise Twenty Only	Per Cubic Metre	40286.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	7.15 Cum	5846.00	Rupees Five Thousand Eight Hundred Forty Six Only	Per cubic metre	41799.00
					Total:	98843.00

Draft Schedule of Quantity approved for Rs.98843/- only (Rupees Ninety Eight Thousand Eight Hundred Forty Three Only) At Sr. No. 869 year 2024-25

Note : (i) All the material will procured by the contractor him self.


Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

SCHEDULE OF QUANTITY

Name of Work:- Construction of Jawahar Lal Govt. College of Fine Arts at Loharav, District Shimla (Sh: Providing fixing aluminium door, window for providing canteen for students)

Estimated Cost: - Rs 97797 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material upto all leads & lifts as per the direction of Engineer in Charge.	232.60 kg.	420.45	Rupees Four Hundred Twenty and Paise Forty Five Only	Per Kilogramme	97797.00
0					Total:	97797.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division,
HPPWD, Dhami