

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-
To,

7470-80

Dated:- 13/3/2025


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: Publication of Tender Notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed percentage rate tenders on the form 6&8 are hereby invited by the Executive Engineer Fatehpur Division HPPWD., Fatehpur on behalf of the Governor of HP for the below noted works from eligible Contractors/firms registered in HPPWD in appropriate class as per revised enlistment rules. So as to reach in this office on or before 25-03-2025 up to 12:00 Noon and the same shall be opened on the same day at 12:30 PM in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 24-03-2025 upto 4:00 PM. The application for issued of tender form shall be received for 22-03-2025 up to 4:30.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/ bank in HP duly pledged in the favour of undersigned.


Conditional tenders telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Fatehpur Division HP PWD at Fatehpur reserves the right to accept or reject the tenders. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III, pot holes at RD 2/260 to 2/415)	97151.00	2000.00	One Month	350/-	Class D&C
2	Construction of Sunhara Khadow Nangal road Km. 0/0 to 8/850 under SCDP (SH:- Removal of Formation deficiency in Km. 2/600 to 2/720 & 4/040 to 4/100).	97247.00	1900.00	One Month	350/-	Class D&C
3	A/R & M/O Golwan to Nawan Shahar via Chounka road km 0/0 to 3/375 (SH:- Providing and laying G-III, pot holes at RD 1/315 to 1/470)	97819.00	2000.00	One Month	350/-	Class D&C
4	Construction of Sunhara Khadow Nangal road Km. 0/0 to 8/850 under SCDP (SH:- Removal of Formation deficiency in Km. 1/785 to 1/915 & 4/100 to 4/200).	95913.00	1900.00	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders from will be issued to the contractor/ firms which may be noted.
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.
On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- A/P&M/O on Golwan to Nawan Shahr via Choukna Road km. 0/000 to 3/375 (SH:- Providing and laying G-III, Estimated cost:- Rs.97151/- only
For holes at R.D. 2/260 to 2/415).
Earliest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.05 cubic meter	1700.10	Rupees One Thousand Seven Hundred And Paise Ten Only	Per cubic meter	17086.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	239.00 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	80065.00
					Total:-	97151.00

Amount quoted by the contractor in % Above/Below

[Handwritten signature]
[Handwritten signature]
 Division Engineer
 Public Works Department
 Fatehgarh Sahib
 Punjab

SCHEDULE OF QUANTITY

Name of work:- Construction of Sunhara Khadlow Bhatoli Baroh Nangal road Km. 0/0 to 8/850 Under SCDP (SH:- Removal of formation deficiency in Km. 2/600 to 2/720 and 4/000 to 4/100)					Estimated cost:- Rs.97247/- only	
					Earnest Money : Rs.2000/- only	
					Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Excavation in hilly area for road ways in all heights and depths and in all kind of soil by mannual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chieselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 1600 and 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material in required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of machineries, materials, tools, equipment and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty. Malkana, Toll Tax, Sale tax, GST, or any other taxes imposed by the Government.	553.800	175.60	Rupees One Hundred Seventy Five And Paise Sixty Only	Per cubic meter	97247.00
					Total:-	97247.00
	Amount quoted by the contractor in % Above/Below					


 Engineer
 Fatehpur Division HPPWD
 Fatehgarh Distt. Kangra (P.B.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan to Nawar Shahar via Chounka Road km. 0/000 to 3/375 (SH:- Providing and laying G-III, Estimated cost:- Rs.97819/- only
Pot holes at R.D. 1/315 to 1/470). Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.91 cubic meter	1696.90	Rupees One Thousand Six Hundred Ninety Six And Paise Ninety Only	Per cubic meter	16816.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	241.80 Square meter	335.00	Rupees Three Hundred Thirty Five Only	Per square meter	81003.00
					Total:-	97819.00

Amount quoted by the contractor in % Above/Below


 Engineer
 Fatehpur District
 Fatehpur

SCHEDULE OF QUANTITY

Name of work:- Construction of Sunhara Khadlow Bhatoli Baroh Nangal road Km. 0/0 to 8/850 Under SCDP
(SH:- Removal of formation deficiency in Km. 1/785 to 1/915 and 4/100 to 4/200)

Estimated cost:- Rs.95913/- only

Earnest Money : Rs.1900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Excavation in hilly area for road ways in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chieselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 1600 and 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material in required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of machineries, materials, tools, equipment and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, Toll Tax, Sale tax, GST, or any other taxes imposed by the Government.	546.200 Cubic meter.	175.60	Rupees One Hundred Seventy Five And Paise Sixty Only	Per cubic meter	95913.00
					Total:-	95913.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)