

Himachal Pradesh  
Public Works Department.

Through mail

No. PWH/HD/CB/T-I/2024-25  
To

\*\*\*\*

10062-64

Dated: -

12/03/2025

The Executive Engineer (IT Cell)  
Nirman Bhawan, Nigam Vihar,  
Shimla-2

Subject: - **Publication of Notice inviting tender.**

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

  
Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15<sup>th</sup> Circle, HP: PWD, Una.
2. Copy to Notice board.

  
Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una HP).

### Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-25-10062-64 dated 17/08/2025 are required to be carried out immediately being emergent nature of work in public interest.

  
Executive Engineer,  
HPPWD Division, Una,  
Distt. Una HP).

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
“ NOTICE INVITING TENDERS ”**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 19.03.2025 up to 10.30 (Non).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 19.03.2025 up to 3.00 PM
3. Date of receipt of tenders: - 20.03.2025 up to 10.30 AM
4. Date of opening of tenders: - 20.03.2025 at 11.00 AM

| Sr. No. | Name of work                                                                                                                                                                                        | Estimated cost | EMD    | Time Limit | Cost of tender | Eligible class of contractor |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|--------|------------|----------------|------------------------------|
| 1       | 2                                                                                                                                                                                                   | 3              | 4      | 5          | 6              | 7                            |
| 1       | Improvement of black spots on Panjavar Bathri road Km 0/0 to 34/00 (SH: P/L Thermoplastic rumble strips & P/F cat eye in RD 1/00 to 9/00)                                                           | 99,361/-       | 2000/- | One month  | 350/-          | Class- C & D                 |
| 2       | A/R & M/O on Panjavar Bathri to Lalhri Kungrat Dhillwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/550 to 1/580)                                                                           | 99,920/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 3       | C/o link road Sehtoot Bagh Khad Harijan Basti to National Highway Pandoga Km 0/0 to 2/600 (SH: C/o R/wall at RD 0/166 to 0/182 RHS) under OTMNP                                                     | 99,688/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 4       | A/R & M/O on link road Upper Karampura to Swan Border Km 0/0 to 2/650 (SH: P/L Paver block at RD 1/725 to 1/750)                                                                                    | 99,432/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 5       | A/R & M/O on Ajouli Santokhgarh Polian road Km 0/0 to 13/400 (SH: P/F delineators at RD 5/00 to 7/500)                                                                                              | 99,550/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 6       | A/R & M/O link road to village Nagnoli Km 0/0 to 5/560 (SH: C/o Toe wall for U-shape drain at RD 0/017 upto disposal point) RHS (Balance work)                                                      | 99,599/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 7       | Balance work for the C/o link road Nagnoli Chaproh Chotti Khad to H?o Sh.Jeevan via Sidh Charno WNo.2 GP Nagnoli (SH: C/o Embankment, GSB,R/wall & P/L CC pavement in RD 0/033 to 0/050) under MMSY | 99,756/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 8       | A/R & M/O on link road Gurplah to Gondpur Km 0/0 to 10/500 (SHJ: Repair of berms at various RDs from Km 2/00 to 5/500)                                                                              | 99,528/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 9       | A/R & M/O on L/R Gondpur Baliwal to Nayian Basti Km 0/0 to 1/500 (SH: C/o B/wall along with drain at RD 0/737.60 to 0/751.40)                                                                       | 99,543/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 10      | C/o link road Swarn Dass Chowk to Dalit Basti Dulehar WNo.6 via Ravidas Mandir to Kangoo Wala Mandir Km 0/0 to 1/00 (SH: C/o R/wall at RD 0/710 to 0/724 RHS)(under SCDP)                           | 99,638/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 11      | A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00 (SH: Painting work on bridge at RD 22/200 & parpaets at various RDs etc) Section Haroli                                                           | 99,473/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 12      | A/R & M/O on Panjavar Bathri to Lalhri Kungrat Dhillwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/580 to 1/610)                                                                           | 99,919/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 13      | A/R & M/O on Ajouli Santokhgarh Polian road Km 0/0 to 13/400 (SH: P/F delineators at RD 2/500 to 5/00)                                                                                              | 99,550/-       | 2000/- | One Month  | 350/-          | Class- C & D                 |

|    |                                                                                                                                                                                                         |          |        |           |       |              |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|--------|-----------|-------|--------------|
| 14 | A/R & M/O on link road Upper Karampura to Swan Border Km 0/0 to 2/650 (SH: P/L Paver block at RD 1/700 to 1/725)                                                                                        | 99,601/- | 2000/- | One Month | 350/- | Class- C & D |
| 15 | Restoration of Gramin Sampark from H/o Sh.Subhash S/o Pritam Singh to H/o Sh.Gurbaksh S/O Sh.Thadu Ram to Jasmer Singh S/o Sh.Dharam Singh WNo.3 G.P.Bathu Phase-I (Deposit work)                       | 99,814/- | 2000/- | One Month | 350/- | Class- C & D |
| 16 | Balance work for the C/o link road Nagnoli Chaproh Chotti Khad to H/o Sh.Jeevan via Sidh Charno WNo.2 GP Nagnoli (SH: C/o Embankment, GSB,R/wall & P/L CC pavement in RD 0/016.50 to 0/0333) under MMSY | 99,866/- | 2000/- | One Month | 350/- | Class- C & D |
| 17 | A/R & M/O on Panjawar Bathri road Km 0/0 to 34/00 (SH: Painting work on bridge at RD 22/200 & parpaets at various RDs etc) Section Ghaluwal                                                             | 99,647/- | 2000/- | One Month | 350/- | Class- C & D |
| 18 | C/o link road Pritam Ki Nehali to Mohalla Loharan Chak Khad GP Khad Km 0/0 to 1/00 (SH: C/o embankment for left hand side slope RD 0/010 to 0/210) under OTMNP                                          | 99,725/- | 2000/- | One month | 350/- | Class- C & D |
| 19 | A/R & M/O on link road Old Haroli Gugga Mandir upto Pajjal Yojna Haroli Km 0/0 to 2/240 (SH: C/O U-shape drain at RD 2/040 to 2/065)                                                                    | 99,464/- | 2000/- | One month | 350/- | Class- C & D |
| 20 | C/o link road Swarn Dass Chowk to Dalit Basti Dulehar WNo.6 via Ravidas Mandir to Kangoo Wala Mandir Km 0/0 to 1/00 (SH: C/o R/wall at RD 0/724 to 0/738 RHS)(under SCDP)                               | 99,488/- | 2000/- | One month | 350/- | Class- C & D |
| 21 | A/R & M/O on Ajouli Santokhgarh Polian road Km 0/0 to 13/400 (SH: P/F delineators at RD 0/00 to 2/500)                                                                                                  | 99,000/- | 2000/- | One month | 350/- | Class- C & D |
| 22 | Restoration of Gramin Sampark from H/o Sh.Subhash S/o Pritam Singh to H/o Sh.Gurbaksh S/O Sh.Thadu Ram to Jasmer Singh S/o Sh.Dharam Singh WNo.3 G.P.Bathu Phase-IV (Deposit work)                      | 99,679/- | 2000/- | One Month | 350/- | Class- C & D |
| 23 | A/R & M/O on Panjawar Bathri to Lalhri Kungrat Dhilwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/520 to 1/550)                                                                                | 98,918/- | 2000/- | One Month | 350/- | Class- C & D |
| 24 | A/R & M/O on Ajouli Santokhgarh Polian Jaijon road Km 0/0 to 17/400 (SH: Repair of RCC railing of various bridges)                                                                                      | 99,625/- | 2000/- | One Month | 350/- | Class- C & D |
| 25 | A/R & M/O on link road Gurplah to Gondpur Km 0/0 to 10/500 (SHJ: Repair of berms at various RDs from Km 6/00 to 9/500)                                                                                  | 99,385/- | 2000/- | One Month | 350/- | Class- C & D |
| 26 | A/R & M/O on link road Upper Karampura to Swan Border Km 0/0 to 2/650 (SH: P/L Paver block at RD 1/630 to 1/645)                                                                                        | 99,263/- | 2000/- | One Month | 350/- | Class- C & D |
| 27 | A/R & M/O on L/R Gondpur Baliwal to Nayian Basti Km 0/0 to 1/500 (SH: C/o B/wall along with drain at RD 0/723.80 to 0/737.60)                                                                           | 99,703/- | 2000/- | One Month | 350/- | Class- C & D |
| 28 | C/o link road Shahtoog Bagh Khad Harijan Basti to National Highway Pandoga Km 0/0 to 2/600 (SH: C/o R.wall at RD 0/150 to 0/166 RHS) under OTMNP                                                        | 99,528/- | 2000/- | One Month | 350/- | Class- C & D |
| 29 | C/o link road Swarn Dass Chowk to Dalit Basti Dulehar WNo.6 via Ravidas Mandir to Kangoo Wala Mandir Km 0/0 to 1/00 (SH: C/o R/wall at RD 0/738 to 0/752RHS)(under SCDP)                                | 99,338/- | 2000/- | One Month | 350/- | Class- C & D |
| 30 | A/R & M/O link road to village Nagnoli Km 0/0 to 5/560 (SH: C/o Toe wall for U-shape drain at RD 0/032.50 to 0/080 LHS) RHS (Balance work)                                                              | 99,288/- | 2000/- | One Month | 350/- | Class- C & D |
| 31 | Balance work for the C/o link road Nagnoli Chaproh Chotti Khad to H/o Sh.Jeevan via Sidh Charno WNo.2                                                                                                   | 99,917/- | 2000/- | One Month | 350/- | Class- C & D |

|    |                                                                                                                                                                                     |           |        |           |       |              |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----------|-------|--------------|
|    | GP Nagnoli (SH: C/o Embankment, GSB,R/wall & P/33L CC pavement in RD 0/0 to 0/016.50) under MM34SY                                                                                  |           |        |           |       |              |
| 32 | A/R & M/O on link road Umrli Singa road Km 0/00 to 6/550 (SH: P/F delineators at RD 0/0 to 3/00)                                                                                    | 99,550/-  | 2000/- | One Month | 350/- | Class- C & D |
| 33 | Restoration of Gramin Sampark from H/o Sh.Subhash S/o Pritam Singh to H/o Sh.Gurbaksh S/O Sh.Thadu Ram to Jasmer Singh S/o Sh.Dharam Singh WNo.3 G.P.Bathu Phase-III (Deposit work) | 99,694/-  | 2000/- | One Month | 350/- | Class- C & D |
| 34 | A/R & M/O on Panjavar Bathri to Lalhri Kungrat Dhillwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/520 to 1/550)                                                           | 99,921/-  | 2000/- | One Month | 350/- | Class- C & D |
| 35 | Improvement of black spots on Panjavar Bathri road Km 0/0 to 34/00 (SH: P/L Thermoplastic rumble strips & P/F cat eye, delinator & Sign board in RD 0/300 to 1/00)                  | 99,636/-  | 2000/- | One Month | 350/- | Class- C & D |
| 36 | C/o link road from H.B. to Ward No.1 via Bhatti Sahib Panjavar Tehsil Haroli Distt.Una Km 0/0 to 2/00 (SH: C/o Rwall in RD 0/705 to 0/721 RHS) under SCCP                           | 99,863/-  | 2000/- | One Month | 350/- | Class- C & D |
| 37 | A/R & M/O on link road Upper Karampura to Swan Border Km 0/0 to 2/650 (SH: P/L 900mm dia hume pipe culvert at RD 1/640)                                                             | 98,984/-  | 2000/- | One Month | 350/- | Class- C & D |
| 38 | C/o link road Swarn Dass Chowk to Dalit Basti Dulehar WNo.6 via Ravidas Mandir to Kangoo Wala Mandir Km 0/0 to 1/00 (SH: C/o R/wall at RD 0/752 to 0/766 RHS)(under SCDP)           | 99,788/-  | 2000/- | One Month | 350/- | Class- C & D |
| 39 | A/R & M/O on L/R Gondpur Baliwal to Nayian Basti Km 0/0 to 1/500 (SH: C/o B/wall along with drain at RD 0/710 to 0/723.80)                                                          | 99,863/-  | 2000/- | One Month | 350/- | Class- C & D |
| 40 | Restoration of Gramin Sampark from H/o Sh.Subhash S/o Pritam Singh to H/o Sh.Gurbaksh S/O Sh.Thadu Ram to Jasmer Singh S/o Sh.Dharam Singh WNo.3 G.P.Bathu Phase-II (Deposit work)  | 99,854/-  | 2000/- | One Month | 350/- | Class- C & D |
| 41 | C/o Gramin Sampark to the H/o Sh.Ram Lal S/o Sh.Tarsem Lal WNo.2 GP Beetan (SH: C/o CC pavement at RD 0/134 to 0/148) under MMSY                                                    | 99,372 /- | 2000/- | One Month | 350/- | Class- C & D |
| 42 | A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00 (SH: P/L 80mm thick paver block in berms RD 22/524.80 to 22/549.50)                                                               | 98,882/-  | 2000/- | One Month | 350/- | Class- C & D |
| 43 | A/R & M/O on Umrli Singan road Km 0/0 to 4/350 (SH: Maintenance of Earthen shoulder RD 0/0 to 2/00)                                                                                 | 99,572 /- | 2000/- | One Month | 350/- | Class- C & D |
| 44 | Restoration of Gramin Sampark from Panjavar Bathri to Patka Temple Haroli WNO.8 GP Haroli (SH: C/o CC pavement RD 0/198 to 0/222) Deposit work                                      | 99,642/-  | 2000/- | One Month | 350/- | Class- C & D |
| 45 | A/R & M/O Non-residential bldg. HPPWD Haroli (SH: Painting work for Rest House for Rest House at Haroli) Phase-II                                                                   | 99,544/-  | 2000/- | One Month | 350/- | Class- C & D |
| 46 | C/o link road Sehtoot Bagh Khad Harijan Basti to NH Pandoga Km 0/0 to 2/600 (SH: C/o R/wall at RD 0/090 to 0/120 LHS) under OTMNP                                                   | 99,578 /- | 2000/- | One Month | 350/- | Class- C & D |
| 47 | C/o Gramin Sampark to the H/o Sh.Ram Lal S/o Sh.Tarsem Lal WNo.2 GP Beetan (SH: C/o CC pavement at RD 0/106 to 0/120) under MMSY                                                    | 99,874/-  | 2000/- | One Month | 350/- | Class- C & D |
| 48 | A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00 (SH: P/L 80mm thick paver block in berms RD 22/500 to 22/524.80)                                                                  | 99,282 /- | 2000/- | One Month | 350/- | Class- C & D |
| 49 | Restoration of Gramin Sampark from Panjavar Bathri to Patka Temple Haroli WNO.8 GP Haroli (SH: C/o CC pavement RD 0/150 to 0/174) Deposit work                                      | 99,669 /- | 2000/- | One Month | 350/- | Class- C & D |

|    |                                                                                                                                                                                                                   |           |        |           |       |              |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----------|-------|--------------|
| 50 | A/R & M/O on Ajouli Santokhgarh Polian road Km 0/0 to 13/400 (SH: P/F delineators at RD 7/500 to 10/00)                                                                                                           | 99,550 /- | 2000/- | One Month | 350/- | Class- C & D |
| 51 | A/R & M/O on link road Subowana road to vill.Baliwal Km 0/0 to 5/00 (SH: Maintenance of Earthen shoulder RD 0/0 to 3/00)                                                                                          | 99,638 /- | 2000/- | One Month | 350/- | Class- C & D |
| 52 | C/o Gramin Sampark to the H/o Sh.Ram Lal S/o Sh.Tarsem Lal WNo.2 GP Beetan (SH: C/o CC pavement at RD 0/092 to 0/104) under MMSY                                                                                  | 99,372 /- | 2000/- | One Month | 350/- | Class- C & D |
| 53 | A/R & M/O Non-residential bldg. HPPWD Haroli (SH: Painting work for Rest House for Rest House at Haroli) Phase-III                                                                                                | 99,688 /- | 2000/- | One Month | 350/- | Class- C & D |
| 54 | C/o link road Sehtoot Bagh Khad Harijan Basti to NH Pandoga Km 0/0 to 2/600 (SH: C/o R/wall at RD 0/170 to 0/200 LHS) under OTMNP                                                                                 | 99,876 /- | 2000/- | One Month | 350/- | Class- C & D |
| 55 | Restoration of Gramin Sampark from Panjavar Bathri road to Patka Temple Haroli WNO.8 GP Haroli (SH: C/o R/wall at RD 0/100 to 0/120 LHS) Deposit work                                                             | 99,865 /- | 2000/- | One Month | 350/- | Class- C & D |
| 56 | A/R & M/O on Umrli Singan road Km 0/0 to 4/350 (SH: Maintenance of earthen shoulder RD 2/00 to 4/100)                                                                                                             | 99,740 /- | 2000/- | One Month | 350/- | Class- C & D |
| 57 | A/R & M/o on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: C/o R/wall at RD 10/220.10 to 10/236.80 LHS)                                                                                           | 99,156 /- | 2000/- | One Month | 350/- | Class- C & D |
| 58 | A/R & M/o on PWD NR Rest House bldg. Haroli (SH: Landscaping & Plantation work at Rest House Haroli)                                                                                                              | 99,950 /- | 2000/- | One Month | 350/- | Class- C & D |
| 59 | Restoration of Gramin Sampark from Panjavar Bathri road to Patka Temple Haroli WNO.8 GP Haroli (SH: C/o R/wall at RD 0/174 to 0/198 LHS) Deposit work                                                             | 99,498 /- | 2000/- | One Month | 350/- | Class- C & D |
| 60 | A/R & M/O Non-residential bldg. HPPWD Haroli (SH: Painting work for Rest House for Rest House at Haroli) Phase-I                                                                                                  | 99,860 /- | 2000/- | One Month | 350/- | Class- C & D |
| 61 | A/R & M/o on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: C/o R/wall at RD 10/203.40 to 10/220.10 LHS)                                                                                           | 99,606 /- | 2000/- | One Month | 350/- | Class- C & D |
| 62 | A/R & M/O on Ajouli Santokhgarh Polian road Km 0/0 to 13/400 (SH: P/F delineators at RD 10/00 to 12/500)                                                                                                          | 99,550 /- | 2000/- | One Month | 350/- | Class- C & D |
| 63 | A/R & M/o on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: C/o R/wall at RD 10/170 to 10/186.70 LHS)                                                                                              | 99,456 /- | 2000/- | One Month | 350/- | Class- C & D |
| 64 | C/o Gramin Sampark to the H/o Sh.Ram Lal S/o Sh.Tarsem Lal WNo.2 GP Beetan (SH: C/o CC pavement at RD 0/120 to 0/134) under MMSY                                                                                  | 99,568 /- | 2000/- | One Month | 350/- | Class- C & D |
| 65 | A/R & M/o on Ajouli Santokhgarh Tahliwal Polian road Km 0/0 to 13/400 (SH: C/o R/wall at RD 10/186.70 to 10/203.40 LHS)                                                                                           | 99,306 /- | 2000/- | One Month | 350/- | Class- C & D |
| 66 | A/R & M/O HPPWD NR bldg. Haroli Division HPPWD (SH: Supplying and Commissioning of 1.00 Tonne (Cold & Hot) split up air conditioner in Accountant Room and 1.50 Tonne split up air conditioner in Drawing Branch) | 91,000 /- | 2000/- | One Month | 350/- | Class- C & D |
| 67 | A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00 (SH: Balance work C/o Rain Shelter at RD 29/600, C/o R/wall for site development) Phase-I                                                                       | 99,942/-  | 2000/- | One Month | 350/- | Class- C & D |
| 68 | A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00 (SH: C/o U-shape drain at RD 18/432 to 18/448)                                                                                                                  | 99,241 /- | 2000/- | One Month | 350/- | Class- C & D |
| 69 | A/R & M/O on Panjavar Bathri road Km 0/0 tom 34/00 (SH: C/o U-shape drain with RCC slab etc.in RD 1/479 to 1/496 LHS)                                                                                             | 99,706/-  | 2000/- | One Month | 350/- | Class- C & D |

|    |                                                                                                                                              |           |        |           |       |              |
|----|----------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|-----------|-------|--------------|
| 70 | A/R & M/O on link road Old Haroli road Gugga Mandir upto Pajal Yojna Haroli Km 0/0 to 2/240 (SH: C/o shape drain at RD 2/065 to 2/090)       | 99,387 /- | 2000/- | One Month | 350/- | Class- C & D |
| 71 | A/R & M/O on Panjawar Bathri road Km 0/0 to 34/00 (SH: Balance work C/o Rain Shelter at RD 29/600, C/o R/wall for site development) Phase-II | 99,455 /- | 2000/- | One Month | 350/- | Class- C & D |
| 72 | A/R & M/O on Panjawar Bathri road Km 0/0 tom 34/00 (SH: C/o U-shape drain with RCC slab etc.in RD 1/415 to 1/450 RHS)                        | 99,206/-  | 2000/- | One Month | 350/- | Class- C & D |
| 73 | A/R & M/O on Panjawar Bathri road Km 0/0 tom 34/00 (SH: C/o U-shape drain with RCC slab etc.in RD 1/445 to 1/462 LHS)                        | 99,372/-  | 2000/- | One Month | 350/- | Class- C & D |
| 74 | A/R & M/O on Panjawar Bathri road Km 0/0 tom 34/00 (SH: C/o U-shape drain with RCC slab etc.in RD 1/462 to 1/479 LHS)                        | 99045/-   | 2000/- | One Month | 350/- | Class- C & D |

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

**SPECIAL CONDITION: -**

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer  
HPPWD Division Haroli  
Distt.Una(HP).Pin Code-177220  
Email: [ee-haroli-hp@hp.gov.in](mailto:ee-haroli-hp@hp.gov.in)  
On behalf of Governor of Himachal Pradesh.

### Schedule of Quantity

Name of work :- Improvement of black spots on Panjagar Bathri road Km 0/0 to 34/00  
(SH: P/L Thermoplastic rumble strips & P/F cat eye in RD 1/0 to 9/00)

Estimated Cost :- Rs. 99361.00  
Earnest Money :- Rs. 2000.00  
Time limit :- One Month

| Sr. No. | Sub Head & Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Rates  |                  |                        | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------------------|------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty.   | Unit             | In figures<br>In words |        |
| 1       | Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre )thick including reflectorising glass beads @ 250 gms ( at the rate of two hundred fifty gram per square metre )per sqm area, thickness of 2.5 mm(two point five millimetre ) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                           | 134.07 | Per Square metre |                        |        |
| 2       | Providing and fixing cat eye make(3M) of size 100x100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretrite ) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 72.00  | Each             |                        |        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |        |                  |                        |        |

Note: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of H.P. vide letter No. PBW©(17)2/0212 dated 7.8.2018.  
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of H.P. vide letter No. PBW(B)A(3)1/2020 dated 22.07.2020.

  
Executive Engineer  
Haroli Division  
HP.PWD. Haroli.

568

**SCHEDULE OF QUANTITY**

| SCHEDULE OF QUANTITY                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 |         |       |                |  |           |  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|-------|----------------|--|-----------|--|
| Name of work : A/R & M/O on Panjawar Bathri to Lalhri Kungrat Dhilwan road km.0/0 to 5/500 (SH: C/O U-shape drain in km. 1460 to 1490) 1/550 to 1/580 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 |         |       | Estimated Cost |  | 99920/-   |  |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 |         |       | Earnest Money  |  | 2000/-    |  |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 |         |       | Time limit     |  | One month |  |
| Sl. No.                                                                                                                                               | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Unit            | RATE In |       |                |  | AMOUNT    |  |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 | Figures | Words |                |  |           |  |
| 1                                                                                                                                                     | Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                             | 12.00    | Per cubic metre |         |       |                |  |           |  |
| 2                                                                                                                                                     | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. | 7.30     | Per cubic metre |         |       |                |  |           |  |
| 3                                                                                                                                                     | Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                              | 20.70    | Per cubic metre |         |       |                |  |           |  |
| 4                                                                                                                                                     | Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                              | 1.20     | Per Cubic metre |         |       |                |  |           |  |
| 5                                                                                                                                                     | Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                     | 71.74    | Per Kilogram me |         |       |                |  |           |  |

SSG

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                   |        |   |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|--------|---|
| 6 | Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm(two hundred millimetre ) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,GST ,labour cess or other taxes imposed by the Government. | 7.50 | Per Running metre |        |   |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                              |      |                   | Total: | 0 |
|   | 2) The rates shall be including of all types of taxes including GST ectetra)                                                                                                                                                                                                                                                                                                                                                                                                                          |      |                   |        |   |
|   | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                              |      |                   |        |   |

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

SS9

**SCHEDULE OF QUANTITY**

**Name of work:** C/O link road Shahtoot Bagh Khad Harijan Basti to National Highway Pandoga km. 0/00 to 2/600 (SH: C/O R/wall at RD 0/166 to 0/182) - under OTMNP

Estimated Cost 99688  
Earnest Money 2000/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit            | RATE In |        | AMOUNT |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|--------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                 | Figures | Words  |        |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                   | 10.08    | Per cubic metre |         |        |        |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 26.83    | Per cubic metre |         |        |        |
| 3       | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                  | 20.00    | Each            |         |        |        |
| 4       | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 11.52    | Per cubic metre |         |        |        |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                 |         | Total: | 0      |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                 |         |        |        |

  
Executive Engineer,  
Haroli Division,  
HPPWD

590

**Schedule of quantity**

| Name of work :- A/R & M/O on link road Upper Karampur to swan Border Km. 0/000 to 2/650 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        |               | Estimated Cost: Rs | ₹ 99,432  |
|-----------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|---------------|--------------------|-----------|
| (SH: P/L Paver block at Rd. 1/725 to 1/750)                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        |               | Time:-             | One month |
| DESCRIPTION                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        |               | Earnest Money:-    | 2000      |
| S.NO                                                                                    | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty   | Unit | T.Rate | Rate in words | Amount             |           |
| 1                                                                                       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..   | 22.50 | Cum. |        |               |                    |           |
| 2                                                                                       | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 5.63  | Cum. |        |               |                    |           |
| 3                                                                                       | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                           | 7.50  | Cum. |        |               |                    |           |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                             |       |     |  |  |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|--|--|
| 4 | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                     | 75.00 | Sqm |  |  |
| 5 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 1.09  | Cum |  |  |
|   | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                |       |     |  |  |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)**

586

**Schedule of quantity**

| Name of work: - A/R & M/O on Ajouli Santoshgarh Polian Road Km. 0/00 to 13/400 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |                    |               |           |
|--------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------------------|---------------|-----------|
| (SH: Providing and fixing delineators at Rd. 5/00 to 7/500)                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |                    |               |           |
|                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      | Estimated Cost: Rs |               | ₹ 99,550  |
|                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      | Time:-             |               | One month |
|                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      | Earnest Money:-    |               | 2000      |
| S.NO                                                                           | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate             | Rate in words | Amount    |
| 1                                                                              | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centi metre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 (IRC - seventy nine) and the drawings as per MORD Technical specification Clause 1707. The rate shall including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 53.00 | Each |                    |               |           |
| 2                                                                              | Providing & fixing dual directional warnner/edge markerof episodal shape of 1.0 mtr.(One point metre long with 3 (Three) members retro-reflectorised device of 15 cm on both side as per IRC:79.2019 specification complete in all respect fixed in M-15 grade size300mmx300mmx450mm including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                | 64.00 | Each |                    |               |           |
| <b>Total</b>                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |                    |               |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

*S76*

# SCHEDULE OF QUANTITY

Estimated cost 99599  
Earnest money 2000  
Time limit One month

Name of work: A/R & M/O link Road to Village Nagnoli Km 0/0 to 5/560 (SH:- C/o Toe Wall for U-shape drain at Rd 0/0/17 upto dyabara) point) RYS (Balance work)

| S.No | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Qty   | Unit | RATE In |       | Amount |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------|--------|
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      | Figures | Words |        |
| 1    | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 5.40  | cum  |         |       |        |
| 2    | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                        | 30.38 | cum  |         |       |        |
|      | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         | Total | 0      |
|      | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                        |       |      |         |       |        |

549

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

# SCHEDULE OF QUANTITY

Estimated cost 99756  
Earnest money 2000  
Time limit One month  
W.No -2 G.P. Nagnoli

| Name of Work: Balance work for the C/O Link road Nagnoli Chaproh Chotti Khad to the H/O Sh. Jeevan via Sidh Charno W.No -2 G.P. Nagnoli (SH:C/o Embankment, GSB, R/wall & P/L CC Pavement in RD 0/033 to 0/050 )- Under MMGSY |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                 |         |       |                  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|-------|------------------|
| S. No.                                                                                                                                                                                                                        | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit            | Rates   |       | Amount (in. Rs.) |
|                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                 | Figures | Words |                  |
| 1                                                                                                                                                                                                                             | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. | 2.68     | Per cubic metre |         |       |                  |
| 2                                                                                                                                                                                                                             | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                     | 13.10    | Per cubic metre |         |       |                  |
| 3                                                                                                                                                                                                                             | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax ,octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..        | 7.00     | Each            |         |       |                  |
| 4                                                                                                                                                                                                                             | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                             | 2.60     | Per cubic metre |         |       |                  |
| 5                                                                                                                                                                                                                             | Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                              | 15.30    | Per cubic metre |         |       |                  |

598

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                 |         |   |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----------------|---------|---|
| 6 | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                       | 2.30 | Per cubic metre |         |   |
| 7 | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 8.72 | Per cubic metre |         |   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                 | G.Total | 0 |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |      |                 |         |   |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |      |                 |         |   |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

Sgd

(8)

## Schedule of quantity

| Name of work: -A/R & M/O on Link Road Gurplah to Gondpur km 0/00 to 10/500 |                                                                                                                                                                                                                                                                                                                                                         |         |      |        |               | Estimated Cost: Rs | ₹ 99,528  |
|----------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|--------|---------------|--------------------|-----------|
| (SH: Repair of Berms at Various RDs from km. 2/00 to 5/500)                |                                                                                                                                                                                                                                                                                                                                                         |         |      |        |               | Time:-             | One month |
|                                                                            |                                                                                                                                                                                                                                                                                                                                                         |         |      |        |               | Earnest Money:-    | 2000      |
| S.NO                                                                       | DESCRIPTION                                                                                                                                                                                                                                                                                                                                             | Qty     | Unit | T.Rate | Rate in words | Amount             |           |
| 1                                                                          | Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 1809.60 | Sqm  |        |               |                    |           |
| Total                                                                      |                                                                                                                                                                                                                                                                                                                                                         |         |      |        |               |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

  
Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

573

# SCHEDULE OF QUANTITY

Name of work: A/R & M/O on link road Gondpur Baliwal To Nayian Basti Km 0/00 to 1/500 (SH:C/O breast wall alongwith drain RD 0/737.60 to Earnest Money 2000/-

99543

Estimated Cost

2000/-

Earnest Money

One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit             | RATE In |       |            | AMOUNT |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                  | Figures | Words | Time limit |        |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                  | 24.22    | Per cubic metre  |         |       |            |        |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 26.98    | Per cubic metre  |         |       |            |        |
| 3       | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                         | 15.00    | Each             |         |       |            |        |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..  | 1.45     | Per Cubic metre. |         |       |            |        |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                  |         |       |            |        |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       |            |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                  |         |       | Total:     | 0      |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

Sgt

**Schedule of quantity**

| Name of work:- C/O link road Swarn Dass Chowk to Dalit Basti Dulehar Ward No. 6 via Ravidas Mandir to Kangoo wala Mandir km. 0/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |        | Estimated Cost: Rs               | ₹ 99,638  |
|-----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|----------------------------------|-----------|
| (SH: C/O Retaining wall at Rd. 0/710 to 0/724 Rhs)                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |        | Time:-                           | One month |
| S.NO                                                                                                                              | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T.Rate | Earnest Money:-<br>Rate in words | Amount    |
| 1                                                                                                                                 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 9.03  | Cum. |        |                                  |           |
| 2                                                                                                                                 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.18 | Cum. |        |                                  |           |
| 3                                                                                                                                 | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 24.00 | Nos  |        |                                  |           |
| 4                                                                                                                                 | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 6.72  | Cum. |        |                                  |           |
| <b>Total</b>                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |        |                                  |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

S78

**SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O on Panjaware Bathri road Km 0/00 to 34/00  
Painting work on bridge at RD 22/200 & parapets at various RDs etc)- (Section Haroli)**

**( SH: Estimated Cost 99473  
Earnest Money 2000  
Time limit One month**

| S<br>No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit             | RATE In |       | AMOUNT |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|--------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | Figures | Words |        |
| 1        | Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt. | 755.48   | Per square metre |         |       |        |
|          | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                             |          |                  |         | Total | 0      |
|          | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                   |          |                  |         |       |        |

  
Executive Engineer  
Haroli Division  
HPPWD

593

| SCHEDULE OF QUANTITY |  |  |  |  |  |  |  |  |  |
|----------------------|--|--|--|--|--|--|--|--|--|
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |
|                      |  |  |  |  |  |  |  |  |  |

557

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |                   |  |          |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|--|----------|
| 6 | Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm (two hundred millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government. | 7.50 | Per Running metre |  |          |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                               |      |                   |  | Total: 0 |
|   | 2) The rates shall be including of all types of taxes including GST etcetra)                                                                                                                                                                                                                                                                                                                                                                                                                               |      |                   |  |          |
|   | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                               |      |                   |  |          |

Executive Engineer  
Haroli Division  
HP.PWD., Haroli

SSA

(13)

## Schedule of quantity

| Name of work: - A/R & M/O on Ajouli Santoshgarh Polian Road Km. 0/00 to 13/400 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               |        |
|--------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|---------------|--------|
| [SH: Providing and fixing delineators at Rd. 2/500 to 5/00]                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               |        |
| Estimated Cost: Rs                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | ₹ 99,550      |        |
| Time:-                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | One month     |        |
| Earnest Money:-                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | 2000          |        |
| S.NO                                                                           | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate | Rate in words | Amount |
| 1                                                                              | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centi metre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 (IRC - seventy nine) and the drawings as per MOKID Technical specification Clause 1707. The rate shall including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 51.00 | Each |        |               |        |
| 2                                                                              | Providing & fixing dual directional warnner/edge markerof episodal shape of 1.0 mtr.(One point metre long with 3 (Three) members retro-reflectorised device of 15 cm on both side as per IRC:79:2019 specification complete in all respect fixed in M-15 grade size300mmx300mmx450mm including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                 | 65.00 | Each |        |               |        |
| Total                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               |        |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

  
**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**  
*SAS*

(14)

Schedule of quantity

| Name of work :- A/R & M/O on link road Upper Karampur to swan Border Km. 0/000 to 2/650 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Estimated Cost: Rs | ₹ 99,601  |
|-----------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|--------------------|-----------|
| (SH: P/L Paver block at Rd. 1/700 to 1/725)                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Time:-             | One month |
| DESCRIPTION                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Earnest Money:-    | 2000      |
| S.NO                                                                                    | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate | Rate in words      | Amount    |
| 1                                                                                       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..   | 22.50 | Cum. |        |                    |           |
| 2                                                                                       | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 5.63  | Cum. |        |                    |           |
| 3                                                                                       | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                           | 7.50  | Cum. |        |                    |           |

582

|              |                                                                                                                                                                                                                                                                                                                                                                                                                             |       |     |  |  |
|--------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|--|--|
| 4            | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                     | 75.00 | Sqm |  |  |
| 5            | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 1.13  | Cum |  |  |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                             |       |     |  |  |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

  
Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

587

## SCHEDULE OF QUANTITY

Estimated cost 99814  
Earnest money 2000  
Time limit One month

Name of Work: Restoration of Gramin Sampark from the H/O Sh. Subash S/O Pritam Singh to the H/o Gurbaksh S/O Sh. Thadu Ram to Jasmer Singh S/O Sh. Daram Singh Ward No 3 G.P Bathu - Phase -I ( Deposit work)

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit             | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                  | Figures         | Words   |                  |
| 1      | Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP.PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi ,royalty, malkhana, toll tax, sale tax, or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                           | 14.78    | Per cubic metre  |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                          | 5.10     | Per cubic metre  |                 |         |                  |
| 3      | Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                            | 7.05     | Per cubic metre  |                 |         |                  |
| 4      | Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 70.50    | Per square metre |                 |         |                  |
| 5      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand : four graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 2.76     | Per cubic metre  |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  |                 |         |                  |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                  |                 |         |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                  |                 | G.Total | 0                |

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

594

(16)

# SCHEDULE OF QUANTITY

Estimated cost 99866  
Earnest money 2000  
Time limit One month

Name of Work: Balance work for the C/O Link road Nagnoli Chaproh Chotti Khad to the H/O Sh. Jeevan via Sidh Charno W.No -2 G.P. Nagnoli (SH:C/O Embankment, GSB, R/wall & P/L CC Pavement in RD 0/016.50 to 0/033 )- Under MMGSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit            | Rates (in. Rs.) |       | Amount (in. Rs.) |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|-------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |                 | Figures         | Words |                  |
| 1      | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 2.68     | Per cubic metre |                 |       |                  |
| 2      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                     | 13.10    | Per cubic metre |                 |       |                  |
| 3      | Providing weepholes in brick masonry/ stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..        | 7.00     | Each            |                 |       |                  |
| 4      | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                               | 2.80     | Per cubic metre |                 |       |                  |
| 5      | Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                               | 15.30    | Per cubic metre |                 |       |                  |

597

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |                 |         |   |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----------------|---------|---|
| 6 | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                      | 2.30 | Per cubic metre |         |   |
| 7 | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 8.72 | Per cubic metre |         |   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |                 | G.Total | 0 |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |                 |         |   |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |                 |         |   |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

597

(17)

**SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O on Panjawar Bathri road Km 0/00 to 34/00  
( SH: Painting work on bridges at RD 11/122, 17/468 , 19/617 )- (Section Ghaluwal )**

Estimated Cost 99647  
Earnest Money 2000  
Time limit One month

| S<br>No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit             | RATE In |       | AMOUNT |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|--------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | Figures | Words |        |
| 1        | Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt. | 754.90   | Per square metre |         |       |        |
|          | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                   |          |                  |         | Total | 0      |
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  |         |       |        |

  
 Executive Engineer  
 Haroli Division  
 HPPWD

594

12

# SCHEDULE OF QUANTITY

Estimated Cost 99725  
Earnest Money 2000/-  
Time limit One month

Name of work:- C/O link road Pritam ki Nehali to Mohalla Loharan Chak Khad GP Khad Km 0/00 to 1/00 (SH:-C/O embankement for left hand side slope RD 0/010 to 0/210)- under OTMNP

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit            | RATE In |       | AMOUNT |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|-------|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                 | Figures | Words |        |
| 1      | Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 398.90   | Per cubic metre |         |       |        |
|        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                   |          |                 |         | Total | 0      |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                        |          |                 |         |       |        |

Executive Engineer  
Haroli Division  
HPPWD

585

**SCHEDULE OF QUANTITY**

Estimates cost:- Rs. 99464  
Earnest Money:- Rs. 2000/-  
Time Limit:- One Month.

Name of work :- A/R & M/O on link road Old Haroli road Gugga Mandir upto Patil Vojna Haroli Km 0/00 to 2/240( SH:- C/O U shape drain at RD 2/040 to 2/065)

| S. No.        | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit             | RATE In |       | AMOUNT   |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|----------|
|               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | Figures | Words |          |
| 1             | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                        | 34.48    | Per Cubic metre. |         |       |          |
| 2             | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 19.22    | Per Cubic metre. |         |       |          |
| 3             | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                          | 1.20     | Per cubic metre  |         |       |          |
| 4             | Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                            | 0.150    | Per Tonne        |         |       |          |
|               | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  |         |       | <b>0</b> |
| <b>Note:-</b> | 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/C(17)/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |                  |         |       |          |
|               | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |                  |         |       |          |

  
Executive Engineer,  
Haroli Division,  
HPPWD

*SH*

Schedule of quantity

Name of work:- C/O link road Swarn Dass Chowk to Dalit Basti Dulehar Ward No. 6 via Ravidas Mandir to Kangoo wala Mandir km. 0/00 to 1/00. Under SCSP.

(SH: C/O Retaining wall at Rd. 0/724 to 0/738 Rhs)

|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Estimated Cost: Rs |      | One month |               |
|--------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|------|-----------|---------------|
|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Time:-             |      | 2000      |               |
|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Earnest Money:-    |      | Amount    |               |
| S.NO         | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty                | Unit | T. Rate   | Rate in words |
| 1            | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 9.03               | Cum. |           |               |
| 2            | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.18              | Cum. |           |               |
| 3            | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 23.00              | Nos  |           |               |
| 4            | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 6.72               | Cum. |           |               |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                    |      |           |               |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

579

**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

(21)

## Schedule of quantity

| Name of work: - A/R & M/O on Ajouli Santoshgarh Polian Road Km. 0/00 to 13/400 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |               | Estimated Cost: Rs |  |
|--------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------|--------------------|--|
| (SH: Providing and fixing delineators at Rd. 0/00 to 2/500)                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |               | One month          |  |
|                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |               | 2000               |  |
| S.NO                                                                           | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty   | Unit | T. Rate | Rate in words | Amount             |  |
| 1                                                                              | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centi metre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 (IRC - seventy nine) and the drawings as per MORD Technical specification Clause 1707. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 50.00 | Each |         |               |                    |  |
| 2                                                                              | Providing & fixing dual directional warning edge marker of episodal shape of 1.0 mtr. (One point metre long with 3 (Three) members retro-reflectorisised device of 15 cm on both side as per IRC-79:2019 specification complete in all respect fixed in M-15 grade size 300mmx300mmx450mm including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                               | 65.00 | Each |         |               |                    |  |
| <b>Total</b>                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |               |                    |  |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

S74

# **SCHEDULE OF QUANTITY**

Name of Work: Restoration of Gramin Sampark from the H/O Sh. Subash S/O Pritam Singh to the H/o Gurbaksh S/O Sh. Thadu Ram to Jasmer Singh S/O Sh. Daram Singh Ward No 3 G.P Bathu - Phase -IV ( Deposit work)

Estimated cost 99679  
Earnest money 2000  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit             | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | Figures         | Words   |                  |
| 1      | Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP.PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                               | 16.20    | Per cubic metre  |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading-I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                             | 5.16     | Per cubic metre  |                 |         |                  |
| 3      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                            | 7.05     | Per cubic metre  |                 |         |                  |
| 4      | Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 70.50    | Per square metre |                 |         |                  |
| 5      | Providing and laying mechanically mixed and vibrated concrete for plant/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand : four graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in- charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 2.70     | Per cubic metre  |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                  |                 | G.Total | 0                |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(31/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                  |                 |         |                  |

  
 Executive Engineer  
 Haroli Division  
 HP.PWD., Haroli

600

23

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY                                                                                                                    |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |  |          |                 |                |  |           |  |
|-----------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------|-----------------|----------------|--|-----------|--|
| Name of work :A/R & M/O on Panjawar Bathri to Lahri Kungrat Dhillwan road km.0/0 to 5/500 (SH: C/O U-shape drain in km. 1/520 to 1/550) |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |  |          |                 | Estimated Cost |  | 99918/-   |  |
|                                                                                                                                         |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |  |          |                 | Earnest Money  |  | 2000/-    |  |
| Sl. No.                                                                                                                                 |  | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |  | Unit     |                 | RATE In        |  | One month |  |
|                                                                                                                                         |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |  | Quantity |                 | Figures        |  | Words     |  |
| 1                                                                                                                                       |  | Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                              |  | 12.00    | Per cubic metre |                |  |           |  |
| 2                                                                                                                                       |  | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax, sale tax, GST,labour cess or other taxes imposed by the Government. |  | 7.30     | Per cubic metre |                |  |           |  |
| 3                                                                                                                                       |  | Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..                                                                                              |  | 20.70    | Per cubic metre |                |  |           |  |
| 4                                                                                                                                       |  | Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax, sale tax, GST,labour cess or other taxes imposed by the Government.                                             |  | 1.20     | Per Cubic metre |                |  |           |  |
| 5                                                                                                                                       |  | Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax, sale tax, GST,labour cess or other taxes imposed by the Government.                                                    |  | 71.72    | Per Kilogram me |                |  |           |  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                   |  |        |   |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|--|--------|---|
| 6 | Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm(two hundred millimetre ) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST ,labour cess or other taxes imposed by the Government. | 7.50 | Per Running metre |  |        |   |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                             |      |                   |  | Total: | 0 |
|   | 2) The rates shall be including of all types of taxes including GST ectra)                                                                                                                                                                                                                                                                                                                                                                                                                            |      |                   |  |        |   |
|   | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                             |      |                   |  |        |   |


  
 Executive Engineer  
 Haroli Division  
 HP.PWD., Haroli

558

**Schedule of quantity**

| Name of work: A/R & M/O on Ajouli Santoshgarh Polian Jaijon road km. 0/00 to 17/400 ( SH: Repair of RCC railing of various bridges) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |                   |        |               | Estimated Cost: Rs | ₹ 99,625  |
|-------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------------------|--------|---------------|--------------------|-----------|
|                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |                   |        |               | Time:-             | One month |
|                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |                   |        |               | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit              | T.Rate | Rate in words | Amount             |           |
| 1                                                                                                                                   | Construction of RCC railing of M-30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, centre to centre spacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                            | 49.00 | Per Running metre |        |               |                    |           |
| 2                                                                                                                                   | Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts,struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:1:1½:3 (1 cement : 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                               | 2.03  | Cum               |        |               |                    |           |
| 3                                                                                                                                   | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with minimum cement content not less than 250Kg ( Two hundred fifty kilogram) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical MORD specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge. including carriage of materials within all leads and lifts and other incidentals. .The rates are inclusive octroi, royalty,malkhana ,toll tax sale tax,,GST,labour cess or other taxes imposed by the Government | 2.90  | Cum               |        |               |                    |           |
|                                                                                                                                     | 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |                   |        |               |                    | 0         |
|                                                                                                                                     | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |                   |        |               |                    |           |

592

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

Schedule of quantity

| Name of work: -A/R & M/O on Link Road Gurplah to Gondpur km 0/00 to 10/500 |                                                                                                                                                                                                                                                                                                                                                          |         |      |        | Estimated Cost: Rs | ₹ 99,385  |
|----------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|--------|--------------------|-----------|
| (SH: Repair of Berms at Various RDs from km. 6/00 to 9/500)                |                                                                                                                                                                                                                                                                                                                                                          |         |      |        | Time:-             | One month |
|                                                                            |                                                                                                                                                                                                                                                                                                                                                          |         |      |        | Earnest Money:-    | 2000      |
| S.NO                                                                       | DESCRIPTION                                                                                                                                                                                                                                                                                                                                              | Qty     | Unit | T.Rate | Rate in words      | Amount    |
| 1                                                                          | Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 1807.00 | Sqm  |        |                    |           |
| Total                                                                      |                                                                                                                                                                                                                                                                                                                                                          |         |      |        |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

S12

Schedule of quantity

| Name of work :- A/R & M/O on link road Upper Karampur to swan Border Km. 0/000 to 2/650 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        | Estimated Cost: Rs | ₹ 99,263  |
|-----------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|--------------------|-----------|
| (SH: P/L Paver block at Rd. 1/630 to 1/645)                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        | Time:-             | One month |
| S.NO                                                                                    | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty   | Unit | T.Rate | Earnest Money:-    | 2000      |
|                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |        | Rate in words      | Amount    |
| 1                                                                                       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..   | 22.50 | Cum. |        |                    |           |
| 2                                                                                       | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 5.63  | Cum. |        |                    |           |
| 3                                                                                       | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 .including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                            | 7.50  | Cum. |        |                    |           |

398

|              |                                                                                                                                                                                                                                                                                                                                                                                                                             |       |     |  |  |
|--------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|--|--|
| 4            | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                     | 75.00 | Sqm |  |  |
| 5            | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 1.05  | Cum |  |  |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                             |       |     |  |  |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

*Handwritten signature*

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

588

**SCHEDULE OF QUANTITY**

**Name of work:** A/R & M/O on link road Gondpur Baliwal To Nayian Basti Km 0/00 to 1/500 (SH:C/O breast wall alongwith drainat RD 0/723.80 to 0/737.60)

Estimated Cost 99703  
Earnest Money 2000/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Unit             | RATE In |               | AMOUNT   |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|---------------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                  | Figures | Words         |          |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                       | 24.22    | Per cubic metre  |         |               |          |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 26.98    | Per cubic metre  |         |               |          |
| 3       | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                       | 16.00    | Each             |         |               |          |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement :three sand:six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.   | 1.45     | Per Cubic metre. |         |               |          |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                  |         |               |          |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |                  |         |               |          |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                  |         | <b>Total:</b> | <b>0</b> |

S83



**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

# SCHEDULE OF QUANTITY

Name of work: C/O link road Shahitoot Bagh Khad Harijan Basti to National Highway Pandoga km. 0/00 to 2/600 (SH: (SH:C/O R/wall at RD 0/150 to 0/166) - under OTMNP

Estimated Cost 99528  
Earnest Money 2000/-

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity | Unit            | Time limit |               | One month |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|------------|---------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                 | Figures    | RATE In Words |           |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                       | 10.08    | Per cubic metre |            |               |           |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 26.83    | Per cubic metre |            |               |           |
| 3       | Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                     | 19.00    | Each            |            |               |           |
| 4       | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 11.52    | Per cubic metre |            |               |           |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                 |            | Total:        | 0         |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                 |            |               |           |

Executive Engineer,  
Haroli Division,  
HPPWD

591

29

**Schedule of quantity**

| Name of work:- C/O link road Swarn Dass Chowk to Dalit Basti Dulehar Ward No. 6 via Ravidas Mandir to Kangoo wala Mandir km. 0/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Estimated Cost: Rs               | ₹ 99,338                    |
|-----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------|-----------------------------|
| (SH: C/O Retaining wall at Rd. 0/738 to 0/752 Rhs)                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                  |                             |
| S NO                                                                                                                              | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T. Rate | Earnest Money:-<br>Rate in words | One month<br>2000<br>Amount |
| 1                                                                                                                                 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 9.03  | Cum. |         |                                  |                             |
| 2                                                                                                                                 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.18 | Cum. |         |                                  |                             |
| 3                                                                                                                                 | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 22.00 | Nos  |         |                                  |                             |
| 4                                                                                                                                 | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 6.72  | Cum. |         |                                  |                             |
| <b>Total</b>                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                  |                             |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

S80

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

# SCHEDULE OF QUANTITY

Estimated cost 99288  
Earnest money 2000  
Time limit One month

Name of work: A/R & M/O link Road to Village Nagnoli Km 0/0 to 5/560 (SH:- C/o Toe Wall for U-shape drain at RD 0/0) 32.50 to 0/080 LHS C Balance work

| S.No | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Qty   | Unit | RATE In |       | Amount |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------|--------|
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      | Figures | Words |        |
| 1    | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 6.30  | cum  |         |       |        |
| 2    | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                        | 30.24 | cum  |         |       |        |
|      | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         | Total | 0      |
|      | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                       |       |      |         |       |        |

Executive Engineer  
Haroli Division  
HP.PWD., Haroli

550

# **SCHEDULE OF QUANTITY**

Estimated cost 99917  
Earnest money 2000  
Time limit One month

Name of Work: Balance work for the C/O Link road Nagnoli Chaproh Chotti Khad to the H/O Sh. Jeevan via Sidh Charno W.No -2 G.P. Nagnoli  
(SH:C/o Embanliment, GSB, R/wall & P/L CC Pavement in RD 0/0 to 0/016.50 )- Under MMGSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit            | Rates (in. Rs.) |       | Amount (in. Rs.) |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|-------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |                 | Figures         | Words |                  |
| 1      | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 2.68     | Per cubic metre |                 |       |                  |
| 2      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                     | 13.11    | Per cubic metre |                 |       |                  |
| 3      | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax ,octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..             | 6.00     | Each            |                 |       |                  |
| 4      | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                | 2.80     | Per cubic metre |                 |       |                  |
| 5      | Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government.                                                                                                                                | 15.30    | Per cubic metre |                 |       |                  |

596

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                 |          |   |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----------------|----------|---|
| 6 | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                        | 2.30 | Per cubic metre |          |   |
| 7 | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 8.75 | Per cubic metre |          |   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |                 | G. Total | 0 |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |                 |          |   |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |                 |          |   |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.R.)

Sg6

Schedule of quantity

Name of work: - A/R & M/O on link road Umralli- Singah road RD 0/00 to 6/550

(SH: Providing and fixing delineators at Rd. 0/00 to 3/00)

|                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |      |           |               |        |
|------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|------|-----------|---------------|--------|
| (SH: Providing and fixing delineators at Rd. 0/00 to 3/00) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Estimated Cost: Rs |      | ₹ 99,550  |               |        |
|                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Time:-             |      | One month |               |        |
|                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Earnest Money:-    |      | 2000      |               |        |
| S.NO                                                       | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty                | Unit | T.Rate    | Rate in words | Amount |
| 1                                                          | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centi metre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 (IRC - seventy nine) and the drawings as per MORD Technical specification Clause 1707. The rate shall including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 71.00              | Each |           |               |        |
| 2                                                          | Providing & fixing dual directional warner/edge markerof episodal shape of 1.0 mtr.(One point metre long with 3 (Three) members retro-reflectorised device of 15 cm on both side as per IRC:79:2019 specification complete in all respect fixed in M-15 grade size300mmx300mmx450mm including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.this contract.                                                                                                                                                                                                                                                                   | 55.00              | Each |           |               |        |
| Total                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                    |      |           |               |        |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

577

# **DRAFT SCHEDULE OF QUANTITY**

Estimated cost 99694  
Earnest money 2000  
Time limit One month

Name of Work: Restoration of Gramin Sampark from the H/O Sh. Subash S/O Pritam Singh to the H/o Gurbaksh S/O Sh. Thadu Ram to Jasmer Singh S/O Sh. Daram Singh Ward No 3 G.P Bathu - Phase -III ( Deposit work)

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit             | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  | Figures         | Words   |                  |
| 1      | Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP PWD, technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                              | 15.60    | Per cubic metre  |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                               | 5.20     | Per cubic metre  |                 |         |                  |
| 3      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                          | 7.05     | Per cubic metre  |                 |         |                  |
| 4      | Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 70.50    | Per square metre |                 |         |                  |
| 5      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement: two sand: four graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 2.70     | Per cubic metre  |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                  |                 | G.Total | 0                |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(31)/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  |                 |         |                  |

Executive Engineer  
Haroli Division  
HP.PWD., Haroli

601

**SCHEDULE OF QUANTITY**

| SCHEDULE OF QUANTITY                                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                |                 |           |       |        |  |  |  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----------------|-----------|-------|--------|--|--|--|
| Name of work : A/R & M/O on Panjawan Bathri to Lahri Kungrat Dhillwan road km.0/0 to 5/500 (SH: C/O U-shape drain in km. 4/400 to 4/460) 1/52.5 to 1/550 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Estimated Cost |                 | 99921/-   |       |        |  |  |  |
|                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Earnest Money  |                 | 2000/-    |       |        |  |  |  |
|                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Time limit     |                 | One month |       |        |  |  |  |
| Sl. No.                                                                                                                                                  | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity       | Unit            | RATE In   |       | AMOUNT |  |  |  |
|                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                |                 | Figures   | Words |        |  |  |  |
| 1                                                                                                                                                        | Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                             | 12.00          | Per cubic metre |           |       | 0      |  |  |  |
| 2                                                                                                                                                        | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. | 7.30           | Per cubic metre |           |       |        |  |  |  |
| 3                                                                                                                                                        | Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                             | 20.70          | Per cubic metre |           |       |        |  |  |  |
| 4                                                                                                                                                        | Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                             | 1.20           | Per Cubic metre |           |       |        |  |  |  |
| 5                                                                                                                                                        | Steel reinforcement (Sail/RINIL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                   | 71.75          | Per Kilogram me |           |       |        |  |  |  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      |                   |        |   |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------------|--------|---|
| 6 | Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm(two hundred millimetre ) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty, malkana , toll tax, GST, labour cess or other taxes imposed by the Government. | 7.50 | Per Running metre |        |   |
|   | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                |      |                   | Total: | 0 |
|   | 2) The rates shall be including of all types of taxes including GST etcetra)                                                                                                                                                                                                                                                                                                                                                                                                                              |      |                   |        |   |
|   | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                |      |                   |        |   |

  
 Executive Engineer  
 Haroli Division  
 HP.PWD., Haroli

566

### Schedule of Quantity

Name of work :- Improvement of black spots on Panjavar Bathri road Km 0/0 to 34/00  
(SH: P/L Thermoplastic rumble strips, P/F cat eye, delineator & Sign boards in RD 0/300 to 1/00)

Estimated Cost :- Rs. 99636.00

Earnest Money :- Rs. 2000.00

Time limit :- One Month

| Sr. No. | Sub Head & Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Qty. | Unit             | Rates      |          |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------------|------------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |      |                  | In figures | In words |
| 1       | Providing and fixing direction and place identification <b>retro-reflectoris</b> sign board as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium composite panel sheeting, 3.00 mm thick with area exceeding 0.90 Sqm supported on 50 mm dia G.I. pipe firmly fixed as per approved drawing and technical specification clause 1701 fixed in M-15 grade including carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 4.32 | Per Square metre |            |          |
| 2       | Providing and fixing <b>800 mm x 600 mm rectangular of retro reflectoris</b> cautionary, <b>mandatory and</b> <b>informatory</b> sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801                                                                                                      | 2.00 | Each             |            |          |
| 3       | Providing and fixing <b>600 mm equilateral triangle of retro reflectoris</b> cautionary, <b>mandatory and</b> <b>informatory</b> sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801                                                                                                      | 4.00 | Each             |            |          |
| 4       | Providing and fixing <b>600 mm circular</b> of retro reflectoris cautionary, <b>mandatory and</b> <b>informatory</b> sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801                                                                                                                  | 2.00 | Each             |            |          |

\$69

| Sr. No. | Sub Head & Items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty.  | Unit             | In figures | In words | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|------------|----------|--------|
| 5       | Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre )thick including reflectorising glass beads @ 250 gms ( at the rate of two hundred fifty gram per square metre )per sqm area, thickness of 2.5 mm(two point five millimetre ) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                          | 19.58 | Per Square metre |            |          |        |
| 6       | Providing and fixing cat eye make(3M) of size 100x100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretite ) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 16.00 | Each             |            |          |        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |                  |            |          |        |

Note: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of H.P. vide letter No. PBW©(17)2/0212 dated 7.8.2018.

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of H.P. vide letter No. PBW(B)A(3)1/2020 dated 22.07.2020.

  
Executive Engineer  
Haroli Division  
HP.PWD. Haroli .

569

# SCHEDULE OF QUANTITY

Estimated cost 99863  
Earnest money 2000  
Time limit One month

Name of work :- Construction of link road from Harijan Basti to Ward No. 1 via Bhatti Sahib Panjavar Tehsil Haroli Distt. Una km. 0/00 to 2/00 (SH:- C/O R/wall in Rd 0/705 to 0/721 ) RHS (Under SCCP)

| SCHEDULE OF WORK / ITEM(S)                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         |       |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------|
| S.No                                                                                                                                                                                                                                      | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Qty   | Unit | RATE In |       |
|                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      | Figures | Words |
| 1                                                                                                                                                                                                                                         | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                | 13.20 | Cum  |         |       |
| 2                                                                                                                                                                                                                                         | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                           | 28.19 | Cum  |         |       |
| 3                                                                                                                                                                                                                                         | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg/cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 12.00 | Each |         |       |
| 4                                                                                                                                                                                                                                         | Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                      | 9.63  | Cum  |         |       |
| NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      | Total   | 0     |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt.of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         |       |

S/S

Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

**Draft Schedule of quantity**

| Name of work :- A/R & M/O on link road Upper Karampur to swan Border Km. 0/000 to 2/650<br>(SH: P/L 900 mm dia hume pipe culvert at RD. 1/640). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |        |         |               |        | Estimated Cost: Rs | ₹ 98,984  |
|-------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|---------|---------------|--------|--------------------|-----------|
|                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |        |         |               |        | Time:-             | One month |
|                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |        |         |               |        | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                            | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty   | Unit   | T. Rate | Rate in words | Amount |                    |           |
| 1                                                                                                                                               | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..   | 26.96 | Cum.   |         |               |        |                    |           |
| 2                                                                                                                                               | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                             | 5.22  | Cum.   |         |               |        |                    |           |
| 3                                                                                                                                               | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size), including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                             | 11.26 | Cum.   |         |               |        |                    |           |
| 4                                                                                                                                               | Providing and laying Non Pressure NP-2 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia RCC pipes. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                 | 5.00  | R/Mtr. |         |               |        |                    |           |
| 5                                                                                                                                               | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 8.25  | Cum.   |         |               |        |                    |           |
| Total                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |        |         |               |        |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP wide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

529

**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**

**Schedule of quantity**

Name of work:- C/O link road Swarn Dass Chowk to Dalit Basti Dulehar Ward No. 6 via Ravidas Mandir to Kangoo wala Mandir km. 0/00  
to 1/00. Under SCSP.  
(SH: C/O Retaining wall at Rd. 0/752 to 0/766 Rhs)

| Estimated Cost: Rs |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |        | One month     |
|--------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|---------------|
| Time:-             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |        | 2000          |
| Earnest Money:-    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |        | Amount        |
| S.NO               | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Qty   | Unit | T.Rate | Rate in words |
| 1                  | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                      | 9.03  | Cum. |        |               |
| 2                  | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                | 28.18 | Cum. |        |               |
| 3                  | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 25.00 | Nos  |        |               |
| 4                  | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                  | 6.72  | Cum. |        |               |
| <b>Total</b>       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |        |               |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

581

**Executive Engineer,  
H.P.P.W.D. Division Haroli,  
Distt. Una (H.P.)**

**SCHEDULE OF QUANTITY**

**Name of work:** A/R & M/O on link road Gondpur Baliwal To Nayian Basti Km 0/00 to 1/500 (SH:C/O breast wall alongwith drain at RD 0/710 to 0/723.80)

Estimated Cost 99863  
Earnest Money 2000/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | Unit             | RATE In |               | AMOUNT   |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|---------------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  | Figures | Words         |          |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                        | 24.22    | Per cubic metre  |         |               |          |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 26.98    | Per cubic metre  |         |               |          |
| 3       | Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                       | 17.00    | Each             |         |               |          |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement :three sand: six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..  | 1.45     | Per Cubic metre. |         |               |          |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                  |         |               |          |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                  |         |               |          |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  |         | <b>Total:</b> | <b>0</b> |

  
**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

582

# SCHEDULE OF QUANTITY

Estimated cost 99854  
Earnest money 2000  
Time limit One month

Name of Work: Restoration of Gramin Sampark from the H/O Sh. Subash S/O Pritam Singh to the H/o Gurbaksh S/O Sh. Thadu Ram to Jasmer Singh S/O Sh. Daram Singh Ward No 3 G.P Bathu - Phase -II ( Deposit work)

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit             | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                  | Figures         | Words   |                  |
| 1      | Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP.PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi ,royalty, malkhana, toll tax, sale tax, or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                         | 15.60    | Per cubic metre  |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                        | 5.10     | Per cubic metre  |                 |         |                  |
| 3      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                          | 7.05     | Per cubic metre  |                 |         |                  |
| 4      | Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 70.50    | Per square metre |                 |         |                  |
| 5      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 2.76     | Per cubic metre  |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/9(17)/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                  |                 | G.Total | 0                |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  |                 |         |                  |

  
Executive Engineer  
Haroli Division  
HP.PWD.,Haroli

602

# SCHEDULE OF QUANTITY

Estimated cost 99372  
Earnest money 2000  
Time limit One month

4

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No 2 GP Beetan  
(SH: C/o C.C Pavement at P.D 0/134 to 0/148) - Under MMSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit            | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | Figures         | Words   |                  |
| 1      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                         | 7.94     | Per cubic metre |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                         | 7.94     | Per cubic metre |                 |         |                  |
| 3      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 11.86    | Per cubic metre |                 |         |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 |                 | G.Total | 0                |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(31/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                 |                 |         |                  |

Executive Engineer,  
HPPWD Dehra Dun

507

**Schedule of quantity**

| Name of work :- A/R & M/O on Panjawaar Bathri road km. 0/00 to 34/00)  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               | Estimated Cost: Rs | ₹ 98,882  |
|------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|---------------|--------------------|-----------|
| (SH: P/L 80 mm thick paver blocks in berm Rd. 22/524.80 to 22/549.50 ) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               | Time:-             | One month |
|                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               | Earnest Money:-    | 2000      |
| S.NO                                                                   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate | Rate in words | Amount             |           |
| 1                                                                      | Loosening of the ground upto a level of 300 mm below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                        | 22.23 | Cum. |        |               |                    |           |
| 2                                                                      | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 6.42  | cum  |        |               |                    |           |
| 3                                                                      | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                      | 6.42  | cum  |        |               |                    |           |
| 4                                                                      | Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                   | 64.22 | Sqm  |        |               |                    |           |
| 5                                                                      | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                | 1.98  | Cum  |        |               |                    |           |
| <b>Total</b>                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |               |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)**

(43)

| SCHEDULE OF QUANTITY |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          |                |
|----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------|---------|----------|----------------|
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          | Estimated Cost |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          | Earnest Money  |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          | Time limit     |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          | One Month      |
| S/<br>No.            | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit             | Figures | RATE In |          | AMOUNT         |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         | Words   |          |                |
| 1                    | Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903..including carriage of material within all leads and lifts . The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.<br>NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018<br>2) The Bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP Vide letter No. PBW(B) A(3) 1/2020 dated 22.07.20220 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 07.10.2021. | Per Square metre | 1810.40 |         |          |                |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         | G Total: | 0              |
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |         |         |          |                |


  
Executive Engineer
   
Haroli Division
   
HPPWD

619

**SCHEDULE OF QUANTITY**

Name of work : Restoration of Gramin Sampark from Panjavar Bathri road to Patka Temple Haroli ward No 8 G P Haroli (SH: C/O  
C.C. pavement RD 0/198 to 0/222 )-Deposit work

Estimated Cost 99642  
Earnest Money 2000/-  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit            | RATE In |        |  | AMOUNT |
|--------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|--------|--|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                 | Figures | Words  |  |        |
| 1      | Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                | 60.50    | Per cubic metre |         |        |  |        |
| 2      | Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                             | 17.40    | Per cubic metre |         |        |  |        |
| 3      | Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount roller on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 5.40     | Per Cubic metre |         |        |  |        |
| 4      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed broken stone aggregate 20mm (twenty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 7.20     | Per cubic metre |         |        |  |        |
| 5      | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                        | 10.80    | Per cubic metre |         |        |  |        |
|        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)/20212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |                 |         |        |  |        |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                 |         | Total: |  | 0      |

Executive Engineer  
Haroli Division  
HPPWD

6/6

# **SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O PWD Non- Residential Building HPPWD Division Haroli ( SH: Painting work for Rest House building at Haroli)-**  
**Phase-II**

Estimated Cost 99544  
Earnest Money 2000/-  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit             | RATE In |       | AMOUNT   |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |                  | Figures | Words |          |
| 1      | Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                           | 402.06   | Per Square metre |         |       |          |
| 2      | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                    | 138.20   | Per Square metre |         |       |          |
| 3      | Applying one coat of water thinnable cement primer of approved brand and manufacture surfacWater thinnable cement primer in any floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                | 230.40   | Per Square metre |         |       |          |
| 4      | Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 402.06   | Per Square metre |         |       |          |
| 5      | Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                          | 83.95    | Per Square metre |         |       |          |
| 6      | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                  | 61.44    | Per Square metre |         |       |          |
| 7      | Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                      | 488.90   | Per Square metre |         |       |          |
|        | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |       | <b>0</b> |
|        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                |          |                  |         |       |          |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                    |          |                  |         |       |          |

Executive Engineer  
Haroli Division  
HPPWD

612

**SCHEDULE OF QUANTITY**

Name of work: C/O link road Shahtoot Bagh Khad harijahn Basti to National Highway Pandoga Km 0/00 to 2/600( SH:C/O R/wall at RD 0/090 to Estimated Cost 99578  
0/120- LHS )- under OTMNP Earnest Money 2000/- One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit            | RATE In |       | AMOUNT |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|-------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 | Figures | Words |        |
| 1       | Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                               | 10.08    | Per cubic metre |         |       |        |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 26.80    | Per cubic metre |         |       |        |
| 3       | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                    | 20.00    | Each            |         |       |        |
| 4       | Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 11.50    | Per cubic metre |         |       |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 | Total:  |       | 0      |

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(1712/0212 dated 7.8.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20

  
Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

# SCHEDULE OF QUANTITY

2

Estimated cost 99874

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No 2 GP Beetan  
SH: C/o C.C Pavement at RD 0/106 to 0/120 )- Under MMSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit            | Rates (in. Rs.) |       | Amount (in. Rs.) |
|--------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|-------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                 | Figures         | Words |                  |
| 1      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                         | 7.98     | Per cubic metre |                 |       |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.                                                                         | 7.98     | Per cubic metre |                 |       |                  |
| 3      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government. | 11.92    | Per cubic metre |                 |       |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/@/17/20212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                 |                 |       |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                 | G.Total         |       | 0                |

Executive Engineer,  
H.P.P.W.D. Division Haroli

604

# SCHEDULE OF QUANTITY

Estimated cost 99874  
Earnest money 2000  
Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No 2 GP Beetan  
SH: C/o C.C Pavement at RD 0/106 to 0/120 )- Under MMSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit            | Rates   |       | Amount (in. Rs.) |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|-------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | Figures | Words |                  |
| 1      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                         | 7.98     | Per cubic metre |         |       |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                        | 7.98     | Per cubic metre |         |       |                  |
| 3      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg.(four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 11.92    | Per cubic metre |         |       |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                 |         |       |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | G.Total |       | 0                |

Executive Engineer,  
H.P.PWD Division Haroli

604

**SCHEDULE OF QUANTITY**

Estimated Cost 99669  
Earnest Money 2000/-  
Time limit One month

(SH: C/O

Haroli

No 8 G P

Patka Temple

Bathri road to

Panjawar

Sampark from

Gramin

Restoration of

Gramin

Sampark from

Gramin

Restoration of

Name of work : Restoration of Gramin Sampark from Panjawar Bathri road to Patka Temple Haroli ward No 8 G P Haroli (SH: C/O Haroli Division HPPWD)

C.C. pavement RD 0/150 to 0/174 )-Deposit work

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit            | RATE IN |        | AMOUNT |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|--------|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |                 | Figures | Words  |        |
| 1      | Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chieselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and firming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                 | 60.40    | Per cubic metre |         |        |        |
| 2      | Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                              | 17.80    | Per cubic metre |         |        |        |
| 3      | Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                          | 5.40     | Per Cubic metre |         |        |        |
| 4      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 7.20     | Per cubic metre |         |        |        |
| 5      | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg. (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..                        | 10.80    | Per cubic metre |         |        |        |
|        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                 |         | Total: | 0      |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                 |         |        |        |

Executive Engineer  
Haroli Division  
HPPWD

6/5

50

Schedule of quantity

| Name of work: - A/R & M/O on Ajouli Santoshgarh, Polian Road Km. 0/00 to 13/400        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |               | Estimated Cost: Rs. | ₹ 99,550  |
|----------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------|---------------------|-----------|
| (SH: Providing and fixing delineators at Rd. <del>7/500 to 10/00</del> 7/500 to 10/00) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |               | Time:-              | One month |
|                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |               | Earnest Money:-     | 2000      |
| S.NO                                                                                   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Qty   | Unit | T. Rate | Rate in words | Amount              |           |
| 1                                                                                      | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centimetre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC-79 (IRC - seventy nine) and the drawings as per MORTD Technical specification Clause 1707. The rate shall including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government. | 53.00 | Each |         |               |                     |           |
| 2                                                                                      | Providing & fixing dual directional warner/edge marker of episodal shape of 150 mm (One point metre long with 3 (Three) members retro-reflectorised device of 15 cm on both side as per IRC-79) 2019 specification complete in all respect fixed in M-15 grade size 300mmx300mmx150mm including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                               | 64.00 | Each |         |               |                     |           |
| Total                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |               |                     |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

(51)

**SCHEDULE OF QUANTITY**

| SCHEDULE OF QUANTITY                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                  |         |       |                |               |            |           |        |
|-------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------|-------|----------------|---------------|------------|-----------|--------|
| Name of work: A/R & M/O on link road Subowana road to vill. Baliwal Km 0/00 to 5/00( SH: Maintenance of Earthen shoulder RD 0/00 to 3/00) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                  |         |       |                |               |            |           |        |
| S/ No.                                                                                                                                    | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Unit             | RATE In |       | Estimated Cost | Earnest Money | Time limit | One Month | AMOUNT |
|                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                  | Figures | Words |                |               |            |           |        |
| 1                                                                                                                                         | Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903..including carriage of material within all leads and lifts . The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government. | Per Square metre | 1811.60 |       |                |               |            |           |        |
|                                                                                                                                           | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                     |                  |         |       |                |               |            |           | 0      |
|                                                                                                                                           | 2) The Bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP Vide letter No. PBW(B) A(3) 1/2020 dated 22.07.20220 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 07.10.2021.                                                                                                                                                                                                                                            |                  |         |       |                |               |            |           |        |
|                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                  |         |       |                |               |            |           |        |

  
 Executive Engineer  
 Haroli Division  
 HPPWD

# SCHEDULE OF QUANTITY

Estimated cost 99788

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No 2 GP Beetan  
(SH: C/o C.C Pavement at RD 0/092 to 0/004) -under MMSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit            | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 | Figures         | Words   |                  |
| 1      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                        | 7.96     | Per cubic metre |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                        | 7.96     | Per cubic metre |                 |         |                  |
| 3      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 11.92    | Per cubic metre |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                 |                 |         | 0                |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                 |                 |         |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 |                 | G.Total |                  |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

605

**SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O PWD Non- Residential Building HPPWD Division Haroli ( SH: Painting work for Rest House building at Haroli)- Phase-III**

Estimated Cost 99688  
Earnest Money 2000/-  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit             | RATE In |       | AMOUNT   |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                  | Figures | Words |          |
| 1      | Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                          | 402.06   | Per Square metre |         |       |          |
| 2      | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                   | 136.40   | Per Square metre |         |       |          |
| 3      | Applying one coat of water thinnable cement primer of approved brand and manufacturer surfac Water thinnable cement primer in any floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                             | 236.40   | Per Square metre |         |       |          |
| 4      | Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 402.06   | Per Square metre |         |       |          |
| 5      | Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                        | 83.95    | Per Square metre |         |       |          |
| 6      | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                 | 61.44    | Per Square metre |         |       |          |
| 7      | Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                     | 488.90   | Per Square metre |         |       |          |
|        | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                  |         |       | <b>0</b> |
|        | <b>NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(172/0212 dated 7.8.2018</b>                                                                                                                                                                                                                                                                                                                                                                         |          |                  |         |       |          |
|        | <b>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20</b>                                                                                                                                                                                                                                                                                                                                                                            |          |                  |         |       |          |

Executive Engineer  
Haroli Division  
HPPWD

613

**DRAFT SCHEDULE OF QUANTITY**

99876  
Estimated Cost  
2000/-  
Earnest Money  
One month

RD  
SH:C/O C.C. Pavement

Name of work: C/O link road Shahtoot Bagh Khad harijan Basti to National Highway Pandoga Km 0/00 to 2/600( 0/170 to 0/200 - Balance work ) - under OTMNP

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit            | RATE In |        | AMOUNT |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|--------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                 | Figures | Words  |        |
| 1       | Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305, 1 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                            | 7.40     | Per cubic metre |         |        |        |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                              | 4.94     | Per cubic metre |         |        |        |
| 3       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 14.98    | Per cubic metre |         |        |        |
|         | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2 /0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                 |         | Total: | 0      |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |                 |         |        |        |

Responsible Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

**Schedule of quantity**

| Name of work :- Restoration of Gramin Sampark from Panjavar Bathri road to Patka Temple Haroli Ward No.8 GP Haroli. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |               | Estimated Cost: Rs | ₹ 99,865  |
|---------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------|--------------------|-----------|
| (SH: C/O Retaining wall at Rd. 0/100 to 0/120 Lhs) - <i>Deposit work</i>                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |               | Time:-             | One month |
|                                                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |               | Earnest Money:-    | 2000      |
| S.NO                                                                                                                | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty   | Unit | T. Rate | Rate in words | Amount             |           |
| 1                                                                                                                   | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 7.63  | Cum. |         |               |                    |           |
| 2                                                                                                                   | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 ( CC 1:4:8). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                         | 28.58 | Cum  |         |               |                    |           |
| 3                                                                                                                   | PProviding weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                              | 18.00 | Nos  |         |               |                    |           |
| 4                                                                                                                   | Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                            | 6.82  | Cum  |         |               |                    |           |
| <b>Total</b>                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |               |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

*Handwritten mark*

*Handwritten signature*

36

| SCHEDULE OF QUANTITY                                                                                                   |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  |                |  |           |  |
|------------------------------------------------------------------------------------------------------------------------|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|------------------|--|----------------|--|-----------|--|
| Name of work: A/R & M/O on Umralli Singan road Km 0/00 to 4/350( SH: Maintenance of Earthen shoulder RD 2/00 to 4/100) |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  | Estimated Cost |  | 99,740    |  |
|                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  | Earnest Money  |  | 2000      |  |
|                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  | Time limit     |  | One Month |  |
| S/ No.                                                                                                                 |  | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |  | Unit             |  | RATE In        |  | AMOUNT    |  |
|                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  | Figures        |  | Words     |  |
| 1                                                                                                                      |  | Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903..including carriage of material within all leads and lifts . The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.<br>NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018<br>2) The Bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP Vide letter No. PBW(B) A(3) 1/2020 dated 22.07.20220 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 07.10.2021. |  | Per Square metre |  | 1813.45        |  |           |  |
|                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |                  |  | G Total:       |  | 0         |  |

Executive Engineer  
Haroli Division  
HPPWD

618

**Schedule of quantity**

| Name of work :- A/R & M/O on Ajouli Santoshgarh Tahliwal Polian road km. 0/00 to 13/400. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Estimated Cost: Rs | ₹ 99,156  |
|------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|--------------------|-----------|
| (SH: C/O Retaining wall at Rd. 10/220.10 to 10/236.80 Lhs)                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Time:-             | One month |
|                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Earnest Money:-    | 2000      |
| S.NO                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T. Rate | Rate in words      | Amount    |
| 1                                                                                        | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.02 | Cum. |         |                    |           |
| 2                                                                                        | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.31 | Cum. |         |                    |           |
| 3                                                                                        | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 13.00 | Nos  |         |                    |           |
| 4                                                                                        | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 8.02  | Cum. |         |                    |           |
| <b>Total</b>                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,**  
**W.D. Division Haridwar**  
**Chait. Una (H.P.)**

SR

## Schedule of quantity

| Name of work: - A/R & M/O on PWD Non-Residential Rest House Building Haroli Tehsil Haroli Distt. Una (HP) |                                                                                                                                                                                                                                                        |        |      |        | Estimated Cost: Rs | ₹ 99,960  |
|-----------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|--------------------|-----------|
| (SH: Landscaping & Plantation work at Rest House Haroli )                                                 |                                                                                                                                                                                                                                                        |        |      |        | Time:-             | One month |
|                                                                                                           |                                                                                                                                                                                                                                                        |        |      |        | Earnest Money:-    | 2000      |
| S.NO                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                            | Qty    | Unit | T.Rate | Rate in words      | Amount    |
| 1                                                                                                         | Medium ornamental Flawring periniul Plant.Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octori.royalty,malkhana, toll tax, GST.labour cess or other taxes imposed bythe Government.        | 12.00  | Each |        |                    |           |
| 2                                                                                                         | Ornamental Large Plant.Including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octori.royalty,malkhana, toll tax, GST.labour cess or other taxes imposed bythe Government.                           | 12.00  | Each |        |                    |           |
| 3                                                                                                         | Truffing of lown grass, including weeding chiseling the grass, for king the ground, top dressing with mixture menome, watering .The rate includes sale tax octori.royalty,malkhana, toll tax, GST.labour cess or other taxes imposed bythe Government. | 300.00 | Sqm  |        |                    |           |
|                                                                                                           | <b>Total</b>                                                                                                                                                                                                                                           |        |      |        |                    |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,**  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

# SCHEDULE OF QUANTITY

Name of work : Restoration of Gramin Sampark from Panjavar Bathri road to Patka Temple Haroli ward No 8 G P Haroli (SH: C/O Estimated Cost 99498  
C.C. pavement RD 0/174 to 0/198 )-Deposit work Earnest Money 2000/-  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity | Unit            | RATE In |        | AMOUNT |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|---------|--------|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |                 | Figures | Words  |        |
| 1      | Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chieselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                            | 59.64    | Per cubic metre |         |        |        |
| 2      | Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                          | 17.26    | Per cubic metre |         |        |        |
| 3      | Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                      | 5.40     | Per Cubic metre |         |        |        |
| 4      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand-eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 7.20     | Per cubic metre |         |        |        |
| 5      | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                     | 10.80    | Per cubic metre |         |        |        |
|        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |                 |         | Total: | 0      |
|        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                 |         |        |        |

Executive Engineer  
Haroli Division  
HPPWD

619

# **SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O PWD Non- Residential Building HPPWD Division Haroli ( SH: Painting work for Rest House building at Haroli)- Phase-I**

Estimated Cost 99850  
Earnest Money 2000/-  
Time limit One month

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit             | RATE In |       | AMOUNT   |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|----------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  | Figures | Words |          |
| 1      | Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                                                                           | 402.06   | Per Square metre |         |       |          |
| 2      | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth completeincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                                     | 140.72   | Per Square metre |         |       |          |
| 3      | Applying one coat of water thinnable cement primer of approved brand and manufacture surfacWater thinnable cement primer in any floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                                                                                | 234.10   | Per Square metre |         |       |          |
| 4      | Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government . | 402.06   | Per Square metre |         |       |          |
| 5      | Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                          | 83.95    | Per Square metre |         |       |          |
| 6      | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                  | 61.44    | Per Square metre |         |       |          |
| 7      | Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surfaceincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .                                                                                                                       | 488.90   | Per Square metre |         |       |          |
|        | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |                  |         |       | <b>0</b> |
|        | <b>NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018</b>                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       |          |
|        | <b>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20</b>                                                                                                                                                                                                                                                                                                                                                                          |          |                  |         |       |          |

Executive Engineer  
Haroli Division  
HPPWD

611

**Schedule of quantity**

| Name of work :- A/R & M/O on Ajouli Santoshgarh Tahliwal Polian road km. 0/00 to 13/400. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Estimated Cost: Rs |        | ₹ 99,606  |
|------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|--------------------|--------|-----------|
| (SH: C/O Retaining wall at Rd. 10/203.40 to 10/220.10 Lhs)                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Time:-             |        | One month |
|                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Earnest Money:-    |        | 2000      |
| S.NO                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Qty   | Unit | T.Rate | Rate in words      | Amount |           |
| 1                                                                                        | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 10.02 | Cum. |        |                    |        |           |
| 2                                                                                        | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.31 | Cum. |        |                    |        |           |
| 3                                                                                        | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                              | 16.00 | Nos  |        |                    |        |           |
| 4                                                                                        | Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                   | 8.02  | Cum. |        |                    |        |           |
| <b>Total</b>                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        |                    |        |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,**  
**Haryana D. Division Haroli**  
**Chait. Uma (M.P.)**

62

Schedule of quantity

| Name of work: - A/R & M/O on Ajouli Santoshgarh, Pollan Road Km. 0/00 to 13/400       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |      | Estimated Cost: Rs |               | ₹ 99,550  |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------------------|---------------|-----------|
| (SH: Providing and fixing delineators at Rd. <del>5/00 to 10/00</del> 10/00 to 12/500 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |      | Time:-             |               | One month |
|                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |      | Earnest Money:-    |               | 2000      |
| S.NO                                                                                  | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Qty   | Unit | T Rate             | Rate in words | Amount    |
| 1                                                                                     | Supplying and installation of delineators (road way indicators, hazard markers, object markers), 80-100 cm (eighty to one hundred centimetre) high above ground level, painted black and white in 15 cm (fifteen centimetre) wide strips, fitted with 80 x 100 mm (eighty to one hundred millimetre) rectangular or 75 mm (seventy five millimetre) dia circular reflectorised panels at the top, buried or pressed into the ground and conforming to IRC -79 (IRC - seventy nine) and the drawings as per MORTD Technical specification Clause 1707. The rate shall including entire carriage of materials within all leads, lifts and other incidentals and per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts, and other incidental. The rate includes sale tax octroi, royalty, malkhama toll tax, GST labour cess or other taxes imposed by the Government. | 53.00 | Each |                    |               |           |
| 2                                                                                     | Providing & fixing dual directional warning/edge marker of episodal shape of 1.0 mtr. (One point metre long with 3 (Three) members retro-reflectorised device of 15 cm on both side as per IRC -79, 2019 specification complete in all respect fixed in M-15 grade size 300mm x 300mm x 150mm including entire carriage of materials within all leads, lifts and other incidentals and per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhama toll tax, GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                         | 64.00 | Each |                    |               |           |
| Total                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |      |                    |               |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

(63)

## Schedule of quantity

| Name of work :- A/R & M/O on Ajouli Santoshgarh Tahliwal Polian road km. 0/00 to 13/400. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Estimated Cost: Rs |  | ₹ 99,456  |
|------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|--------------------|--|-----------|
| (SH: C/O Retaining wall at Rd. 10/170 to 10/186.70 Lhs)                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Time:-             |  | One month |
| DESCRIPTION                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        | Earnest Money:-    |  | 2000      |
| S.NO                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Qty   | Unit | T.Rate | Rate in words      |  | Amount    |
| 1                                                                                        | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 10.02 | Cum. |        |                    |  |           |
| 2                                                                                        | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.31 | Cum. |        |                    |  |           |
| 3                                                                                        | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                              | 15.00 | Nos  |        |                    |  |           |
| 4                                                                                        | Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                   | 8.02  | Cum. |        |                    |  |           |
| <b>Total</b>                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |        |                    |  |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,**  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

606

3

## SCHEDULE OF QUANTITY

Estimated cost 99568

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No 2 GP Beetan  
 SH: C/o C.C Pavement at PD 0/120 to 0/134 - Under MMSY

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit            | Rates (in. Rs.) |         | Amount (in. Rs.) |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|-----------------|---------|------------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 | Figures         | Words   |                  |
| 1      | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                     | 7.96     | Per cubic metre |                 |         |                  |
| 2      | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading - I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                       | 7.96     | Per cubic metre |                 |         |                  |
| 3      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 11.88    | Per cubic metre |                 |         |                  |
|        | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)/(17)2/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |                 |                 |         |                  |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                 |                 | G.Total | 0                |

606

Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Jammu (U.D.)

(659)

## Schedule of quantity

| Name of work :- A/R & M/O on Ajouli Santoshgarh Tahliwal Polian road km. 0/00 to 13/400. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Estimated Cost: Rs |        | ₹ 99,306  |
|------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|--------------------|--------|-----------|
| {SH: C/O Retaining wall at Rd. 10/186.70 to 10/203.40 Lhs}                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Time:-             |        | One month |
|                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Earnest Money:-    |        | 2000      |
| S.NO                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T. Rate | Rate in words      | Amount |           |
| 1                                                                                        | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.02 | Cum. |         |                    |        |           |
| 2                                                                                        | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 28.31 | Cum. |         |                    |        |           |
| 3                                                                                        | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 14.00 | Nos  |         |                    |        |           |
| 4                                                                                        | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 8.02  | Cum. |         |                    |        |           |
| <b>Total</b>                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                    |        |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

Estimated cost:- Rs. :- 91000  
 Earnest money:- Rs. :- 1900  
 Time limit :- One Month

### SCHEDULE OF QUANTITY

Name of work:- A/R & M/O HP.PWD., Non-Residential building, Haroli Division HPPWD (SH: Supplying and Commissioning of 1.00 Tonne ( Cold & Hot) split up air conditioner in Accountant Room and 1.50 tonne split up air conditioner in Drawing Branch)

| Sr. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty  | Unit | Rate in Words | Rate in Figures | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|---------------|-----------------|--------|
| 1       | Supplying and commissioning of 1.00 tonne inverter (copper) split air conditioner ( Cold & Hot) of blue star (3star) or its equivalent make conforming to IS :1391 part 1992 fitted with hermetically shielded air conditioner with installation testing and commissioning etc. As required split type AC unit including voltage stabilizer 4 KVA whirlpool/godrej and out door unit stand complete with one year warranty in all respect. including carriage of material with in all lead and lift .The rates includes sale tax octroi ,royalty malikhana toll tax GST ,labour cessor or other taxes imposed by the Government. | 1.00 | each |               |                 |        |
| 2       | Supplying and commissioning of 1.50 tonne inverter (copper) split air conditioner of blue star (3star) or its equivalent make conforming to IS :1391 part 1992 fitted with hermetically shielded air conditioner with installation testing and commissioning etc. As required split type AC unit including voltage stabilizer 4 KVA whirlpool/godrej and out door unit stand complete with one year warranty in all respect. including carriage of material with in all lead and lift .The rates includes sale tax octroi ,royalty malikhana toll tax GST ,labour cessor or other taxes imposed by the Government.               | 1.00 | each |               |                 |        |
|         | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |      |               | Total:          | 0      |
|         | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                        |      |      |               |                 |        |

Executive Engineer  
 Haroli Division  
 H.P.P.W.D.

623

67

Ripper

Schedule of quantity

| Name of work :- A/R & M/O on Panjawar Bathri road Km. 0/00 to 34/00                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Estimated Cost: Rs |        | ₹ 99,942  |
|---------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------|--------------------|--------|-----------|
| (SH: Balance work C/O Rain Shelter at Rd. 29/600, C/O Retaining wall for site devolpment) Phase-1 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Time:-             |        | One month |
|                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        | Earnest Money:-    |        |           |
| S.NO                                                                                              | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate | Rate in words      | Amount |           |
| 1                                                                                                 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil Upto 3 m depth. including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 12.21 | Cum. |        |                    |        |           |
| 2                                                                                                 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                      | 30.15 | cum  |        |                    |        |           |
| Total                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |        |                    |        |           |

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

  
Executive Engineer,  
H.P.P.W.D. Division Haridwar  
Distt. Una (H.P.)

621

# SCHEDULE OF QUANTITY

Estimates cost: 99241  
Earnest Money: Rs. 2000/-  
Time Limit: One Month.

Name of work :- A/R & M/O on Panjavar Bathri road Km 0/00 to 34/00 ( SH:C/O U-shape drain at RD 18/432 to 18/448)

| S. No.        | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity | Unit             | RATE In |       | AMOUNT   |
|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|----------|
|               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                  | Figures | Words |          |
| 1             | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                       | 24.30    | Per Cubic metre. |         |       |          |
| 2             | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 12.98    | Per Cubic metre. |         |       |          |
| 3             | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                         | 2.36     | Per cubic metre  |         |       |          |
| 4             | Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                 | 0.360    | Per Tonne        |         |       |          |
|               | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |                  |         |       | <b>0</b> |
| <b>Note:-</b> | 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |                  |         |       |          |
|               | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                  |         |       |          |

Executive Engineer,  
Haroli Division,  
HPPWD

624

# SCHEDULE OF QUANTITY

Estimates cost:- 99387  
Earnest Money:- Rs. 2000/-  
Time Limit:- One Month.

Name of work :- A/R & M/O on link road Old Haroli road Gugga Mandir upto Pajal Yojna Haroli Km 0/00 to 2/240 SH:- C/O U shape drain at RD 2/065 to 2/090)

| S. No.                                                                                                                                                                  | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit             | RATE IN |       | AMOUNT |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-------|--------|
|                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  | Figures | Words |        |
| 1                                                                                                                                                                       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                      | 34.48    | Per Cubic metre. |         |       |        |
| 2                                                                                                                                                                       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under waterlor ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 19.20    | Per Cubic metre. |         |       |        |
| 3                                                                                                                                                                       | Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                        | 1.20     | Per cubic metre  |         |       |        |
| 4                                                                                                                                                                       | Providing and laying mild steel medium tensite steel bars for steel (approved make) reinforcement for reinforced cement concrete work including ,bending binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                | 0.150    | Per Tonne        |         |       |        |
| <b>Total</b>                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       | 0      |
| <b>Note:-</b>                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       |        |
| 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)/1712/0212 dated 7.8.2018     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       |        |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  |         |       |        |

Executive Engineer,  
Haroli Division,  
HPPWD

570

70

Schedule of quantity

| Name of work :- A/R & M/O on Panjawar Bathri road Km. 0/00 to 34/00                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |      |        | Estimated Cost: Rs |        | ₹ 98,455  |
|---------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|--------|--------------------|--------|-----------|
| (SH: Balance work C/O Rain Shelter at Rd. 29/600, C/O Retaining wall for site devolpment & flooring CC pavement) Phase-II |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |      |        | Time:-             |        | One month |
|                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |      |        | Earnest Money:-    |        |           |
| S.NO                                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty  | Unit | T.Rate | Rate in words      | Amount |           |
| 1                                                                                                                         | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil Upto 3 m depth. includind carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 2.73 | Cum. |        |                    |        |           |
| 2                                                                                                                         | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                                      | 5.46 | cum  |        |                    |        |           |

622

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

|                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |      |  |  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--|--|
| 3                                                                                                                                                                               | Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 17.47  | Cum. |  |  |
| 4                                                                                                                                                                               | Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundationsof cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                               | 4.80   | Cum. |  |  |
| 5                                                                                                                                                                               | Steel work welded in built up sections/ framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder,railings, brackets, gates and similar works. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                             | 552.00 | Kg   |  |  |
|                                                                                                                                                                                 | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |        |      |  |  |
| Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |      |  |  |

622

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

# DNIT/Schedule of Quantity

Name of Work/ A/E & M/O on Panjagar Bathri road Km 0/0 to 34/00  
(SI: C) U-shape drain with R.C.C. slabs etc. in RD 1/415 to 1/450.) RHS

Estimated Cost :- Rs.  
Earnest Money :- Rs.  
Time limit :-

99206.00  
2000.00  
One Month

## Item of work

| Sr. No. | Quantity | Unit | In Figures | In Words                                                      | Amount |
|---------|----------|------|------------|---------------------------------------------------------------|--------|
|         |          |      |            |                                                               |        |
| 1       | 0.90     | Cum  | 800.00     | Rupees Eight Hundred Fifty and Paise Zero Only                | 720    |
| 2       | 0.36     | Cum  | 1000.00    | Rupees One Thousand and Paise Zero Only                       | 360    |
| 3       | 1.80     | Cum  | 160.00     | Rupees One Hundred Sixty and Paise Zero Only                  | 288    |
| 4       | 5.08     | Cum  | 3850.00    | Rupees Three Thousand Eight Hundred Fifty and Paise Zero Only | 19558  |
| 5       | 0.30     | Cum  | 3250.00    | Rupees Three Thousand Two Hundred Fifty and Paise Zero Only   | 975    |

1. Providing and placing concrete manually/ by mechanical means including disposal of material within all leads as per Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) as directed by Engineer - in - charge including carriage of material within all leads and lifts and other incidentals. The rate includes royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.

2. R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of material within all leads as per direction of Engineer - in - charge as directed by Engineer-in-charge of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.

3. Excavation in work and hard blasting work in dry or saturated condition upto any depth and lift including pumping out water where required including stacking the serviceable and unserviceable material separately as per Engineer - in - charge and returning the stacked soil in 15cm (fifteen centimeter) layers when required into plinth and sides of foundation trenches etc. each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed by the Engineer in charge including entire carriage of material and disposal of unserviceable excavated/bored out earth within all leads and lifts and other incidentals. Any loss to the public /private property during the course of execution shall be absolute responsibility to the contractor which shall have to be duly compensated to him in all cases as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.

4. Providing and placing in position cement concrete of specified grade including the cost of centering and shuttering - All work upto and including level 1:3:6 (one Cement : three coarse sand): six crushed graded stone aggregate 40 mm (forty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.

5. Providing and placing cement concrete 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        |     |         |                                                       |              |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----|---------|-------------------------------------------------------|--------------|
| 6 | Providing and laying reinforcement cement concrete work of grade M-25(M-twenty five )design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square ) with minimum cement content of 400 kg (Four hundred kilogramme ) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams,girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. | 4.05   | Cum | 5500.00 | Rupees Five Thousand Five Hundred and Paise Zero Only | 22275        |
| 7 | Providing and laying mild steel medium tansite steel bars tor steel (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) reinforcement for reinforced cement concrete work including ,bending binding,streightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                          | 486.00 | Kg. | 90.00   | Rupees Ninety and Paise Zero Only                     | 43740        |
| 8 | Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .                                                                                                                                                                                                                                 | 115.20 | Kg. | 98.00   | Rupees Ninety Eight and Paise Zero Only               | 11290        |
|   | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |        |     |         |                                                       | <b>99206</b> |

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(172/0212 dated 7.8.2018

2) The rates shall be inclusive of all types of taxes including GST etcetera)

Executive Engineer  
HPPWD Division Haroli  
Distt. Una (HP)

### Schedule of Quantity

Name of Work:- A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00  
(SH: C/O U-Shape Drain with R.C.C slabs etc. in RD 1/445 to 1/462.) LHS

Estimated Cost :- Rs.  
Earnest Money :- Rs.  
Time limit :-

99372.00  
2000.00  
One Month

| Sr. No. | Item of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit | Rate       |          | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|------------|----------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |      | In Figures | In Words |        |
| 1       | Excavation in foundation trenches etcetera in all classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work in dry or saturated condition upto any depth and lift including pumping and bailing out water where required including stacking the serviceable and unserviceable material separately as directed and then returning the stacked soil in 15cm(fifteen centimeter) layers when required into plinth and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as directed by the Engineer in charge including entire carriage of material and disposal all surplus excavated/bored out earth within all leads and lifts and other incidentals. Any loss to the public/private property during the course of execution shall be absolute responsibility to the contractor which shall have to be duly compensated by him in all cases as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 14.28    | Cum  |            |          |        |
| 2       | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement : three coarse sand) six crushed graded stone aggregate 40 mm (forty millimetre) (twenty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 10.54    | Cum  |            |          |        |
| 3       | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm( forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 2.04     | Cum  |            |          |        |
| 4       | Providing and laying reinforcement cement concrete work of grade M-25(M-twenty five) design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square ) with minimum cement content of 400 kg (Four hundred kilogramme ) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams, girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                        | 3.06     | Cum  |            |          |        |
| 5       | Providing and laying mild steel medium tensile steel bars for steel (Sail/RINI/Shyam steel Tisco, Jindal panther (JSPL) make) reinforcement for reinforced cement concrete work including, bending binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 367.20   | Kg.  |            |          |        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      |            |          |        |

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17/20212 dated 7.8.2018  
2) The rates shall be inclusive of all types of taxes including GST etcetera)

Executive Engineer  
HPPWD Division Haroli  
Distt. Una (HP)

### Schedule of Quantity

Name of Work:- A/R & M/O on Panjavar Bathri road Km 0/0 to 34/00  
(SH: C/O U-Shape Drain with R.C.C slabs etc. in RD 1/462 to 1/479.) LHS

Estimated Cost :- Rs.

99045.00

Earnest Money :- Rs.

2000.00

Time limit :- One Month

| Sr. No. | Item of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit | Rate       |          | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|------------|----------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |      | In Figures | In Words |        |
| 1       | Excavation in foundation trenches etcetera in all classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work in dry or saturated condition upto any depth and lift including pumping and bailing out water where required including stacking the serviceable and unserviceable material separately as directed and then returning the stacked soil in 15cm(fifteen centimeter) layers when required into plinth and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as directed by the Engineer in charge including entire carriage of material and disposal all surplus excavated/bored out earth within all leads and lifts and other incidentals. Any loss to the public/private property during the course of execution shall be absolute responsibility to the contractor which shall have to be duly compensated by him in all cases as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. | 12.24    | Cum  |            |          |        |
| 2       | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3.6 (one Cement : three coarse sand): six crushed graded stone aggregate 40 mm (forty millimetre) (twenty millimetre) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 10.54    | Cum  |            |          |        |
| 3       | Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 2.04     | Cum  |            |          |        |
| 4       | Providing and laying reinforcement cement concrete work of grade M-25(M-twenty five design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square ) with minimum cement content of 400 kg (Four hundred kilogramme ) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams, girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                         | 3.06     | Cum  |            |          |        |
| 5       | Providing and laying mild steel medium tensile steel bars for steel (Sail/RINI/Shyam steel Tisco, Jindal panther (JSPL) make) reinforcement for reinforced cement concrete work including bending, binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 367.20   | Kg   |            |          |        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      |            |          |        |

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt.

of HP vide letter No.PBW(B)(17/20212 dated 7.8.2018

2) The rates shall be inclusive of all types of taxes including GST etcetera)

Executive Engineer  
HPPWD Division Haroli  
Distt. Una (HP)