

**Office of the Executive Engineer, HPPWD., Division Kangra
Himachal Pradesh Public works Department Kangra-176001
Phone No. & Fax No. 01892.265028 e-mail:- ee-kan-hp@nic.in
NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **07.04.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **05.04.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **04.04.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	C/O NIFT Complex at Chheb Kangra(HP)(SH- P/L Six Course Water Proofing Treatment Over Cats Block(Balance work)(Deposit work)	99680/-	2000/-	350/-	One Month
2.	C/O NIFT Complex at Chheb Kangra(HP)(SH- P/L Six Course Water Proofing Treatment Over Toilet Block(Balance work)(Deposit work)	99787/-	2000/-	350/-	One Month
3.	A/C of Pucca Path from Link road to S.C. Basti ward No. 02 and Banbari Lal House to the Shop of Sh. Desh Raj Mashand (SH- Cement Concrete Pavement)(Deposit work)(Balance work)	99918/-	2000/-	350/-	Three Month
4.	Repair & Restoration of various road under Kangra Sub Division(SH- Supplying and stacking of G-III)	43830/-	1000/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.).

(On behalf of Governor of Himachal Pradesh)


Endst:- No.PW/KD/CB/Tenders/2024-25-
Copy is forwarded to:-

10213-22

Dated:-

29/3/25

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. Tife Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.).

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF NIFT COMPLEX AT CHIEB KANGRA.(H.P) SUB HEAD:- PROVIDING AND LAYING SIX COURSES WATER PROOFING TREATMENT OVER CATS BLOCK. (Balance waste disposal work)					ESTIMATED COST. EARNEST MONEY	99680/- 2000/-
					TIME LIMIT	ONE MONTH
Sr. N	DESCRIPTION OF WORK	QTY.	UNIT	RATES		AMOUNT
				IN FIGURES	IN WORDS	
1	Providing and laying in situ six courses water proofing treatment with using two component fibre reinforced acrylic polymer coating i.e 1st coat of two component Acrylic polymer (water proofing compound) at the rate of 0.400 litter/ Sqm, 2nd coat of two component acrylic coat polymer over laying fibre mesh at the rate of 0.500 kg/sqm, 3rd and 4th coat of with two component -acrylic polymer at the rate of 0.450 grams/Sqm in each coat and 5th coat of two component acrylic polymer at the rate of 0.500 grams/sqm and 6th teh top Most layer protective course (layer) of cement ,sand and SBR based polymer on entire surface to make the treatment protected from damages caused by foot traffic, uv rays and other factors, also giving a proper slope to roof for rainwater to flow through drain pipes effectively complete the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	111.83	Per Square metres	891.35	Rupees Eight Hundred & Ninety One - Paise Thirty Five Only	99680.00
		TOTAL				99680.00

EXCESS = %

LESS = %


 EXECUTIVE ENGINEER
 KANGRA DIVISION
 H.P.P.W.D. KANGRA

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF NIFT COMPLEX AT CHHEB KANGRA.(H.P) SUB HEAD:- PROVIDING AND LAYING SIX COURSES WATER PROOFING TREATMENT OVER TOILET BLOCK. <i>Before work (Before to work)</i>					ESTIMATED COST.	99787.00
					EARNEST MONEY	2000/-
					TIME LIMIT	ONE MONTH
Sr.	DESCRIPTION OF WORK	QTY.	UNIT	RATES		AMOUNT
				IN FIGURES	IN WORDS	
N 1	Providing and laying in situ six courses water proofing treatment with using two component fibre reinforced acrylic polymer coating i.e 1st coat of two component Acrylic polymer (water proofing compound) at the rate of 0.400 liter/ Sqm, 2nd coat of two component acrylic coat polymer over laying fibre mesh at the rate of 0.500 kg/sqm, 3rd and 4th coat of with two component -acrylic polymer at the rate of 0.450 grams/Sqm in each coat and 5th coat of two component acrylic polymer at the rate of 0.500 grams/sqm and 6th teh top Most layer protective course (layer) of cement ,sand and SBR based polymer on entire surface to make the treatment protected from damages caused by foot traffic, uv rays and other factors, also giving a proper slope to roof for rainwater to flow through drain pipes effectively complete the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	111.95	Per Square metres	891.35	Rupees Eight Hundred & Ninety One Paise Thirty Five Only	99787.00
		TOTAL				99787.00

EXCESS = %

LESS = %

EXECUTIVE ENGINEER
KANGRA DIVISION
H.P.PWD KANGRA

SCHEDULE OF QUANTITY

Name of Work :- A/C of Pucca Path From Link road to S.C basti ward No. 02 and Bankari Lal house to the Shop of sh. Desh raj Mashand. (Sub Head :- Cement Concrete Pavement. (deposit Work) (*Badhaye kaam*)

ESTIMATED COST : 99918./

EARNEST MONEY : 2000./

TIME LIMIT: THREE MONTHS

S. N	Description	Qty.	Unit	Rates IN		Amount
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 40mm (forty millimetre) nominal size with cement contents not less than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty millimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.38	Per Rmt	6100.00	Rupees Six Thousand One Hundred Only	99918.00
					Total	99918.00

Excess -	%
Less -	%


 Executive Engineer,
 Kangra Division
 HPPWD, Kangra

SCHEDULE OF QUANTITY					Estimate cost-	
NAME OF WORK:- Repair & Restoration of various road under Kangra Sub					Earnest money-	
Division. (Sh:- Supplying and stacking of G-III).					Time limit-	
Sr.N o.	Sub-Head and items of work	Quantity	Unit		Rates in	
					Figures	Words
1	Supplying & Stacking stone aggregate size 53mm to 22.4 mm (fifty three millimetre to twenty two point four millimetre) Grading-III (75mm) (seventy five millimetre) consolidated thick) to water bound Macadam, specification including spreading in uniform thickness using template, hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18 cum (zero point eighteen cubic metre) per ten squared metres and to fill up the interstices of coarse aggregate watering and compacting to the required density as per MORD technical specifications clause No. 405 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi royalty Malkhana toll tax sale tax or other taxes imposed by the Government	25.00	Each		1753.20	Rupees One Thousand Seven Hundred & Fifty Three - Paise Twenty Only
Total						
						43830.00

EXCESS = %

LESS = %

Executive Engineer
HP_PWD, Division
Kangra Division