

Office of the Executive Engineer, HPPWD., Division Kangra
Himachal Pradesh Public works Department Kangra-176001
Phone No. & Fax No. 01892.265028 e-mail:- ee-kan-hp@nic.in
NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **12.03.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **11.03.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **10.03.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Repair of Guest House at NIFT Campus at Chheb Kangra (SH- Providing and Fixing Towel Rail, Soap Dish, PVC Connection, Mixture and Floor Trap etc.)(Deposit work)	99490/-	2000/-	350/-	Two Month
2.	Repair of Guest House at NIFT Campus at Chheb Kangra (SH- Demolishing of Cement Concrete Flooring/Stone Masonry and Providing and Fixing Wash Basin with Pedestal and PVC Pipe etc.)(Deposit work)	81742/-	1700/-	350/-	Two Month
3.	C/O link road Sanour Lahar to Tarkahankar road km. 0/00 to 3/360(Under SCSP)(SH- C/O R/Wall at RD 0/850 to 0/856.65)	99971/-	2000/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P).

(On behalf of Governor of Himachal Pradesh)

Endst:- No.PW/KD/CB/Tenders/2024-25- **9455-9500** Dated:- **3/3/2025**
Copy is forwarded to:-

1. The Engineer-in-Chief, HPPWD., Shimla for information please.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. All the Contractor's.
6. All Head of Branches.
7. Notice Board.
8. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P).

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR OF GUEST HOUSE AT NIFT CAMPUS AT CHIEB KANGRA(SH) PROVIDING AND FIXING TOWEL RAIL SOAP DISH,PVC CONNECTION ,MIXURE AND FLOOR TRAP ETC.) deposite work .									
SCHEDULE OF QUANTITY									
Sr. No.	Description of work	Qty	Unit	Rates		Estimated Cost- Earnest Money:- Time Limit:-	99430.00 2000/- TWO MONTH		
				In Figures	In Words			AMOUNT	
1	Providing and fixing 100mm sand cast iron grating for gully trap, as per direction of Engineer in charge..including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malikhana, toll tax, GST or any other taxes imposed by the Government	4.00	Each	120.00	Rupees One Hundred & Twenty Only		480.00		
2	Providing and fixing flat back 600x20mm (Six hundred into twenty millimetres) Towel rail of complete fitting Prayag/ Hindware/Cera I.S. marked complete with C.P (Chromium Plated) brass brackets fixed to wooden plugs with Chromium Plated brass screws, as per specification, approved drawing, design including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	4.00	Each	415.15	Rupees Four Hundred & Fifteen - Paise Fifteen Only		1661.00		
3	Providing and fixing 15mm (Fifteen millimetre) nominal bore PVC connection pipe with brass union 30 cm (Thirty Centimetre) length complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	8.00	Each	106.85	Rupees One Hundred & Six - Paise Eighty Five Only		855.00		
4	Providing and fixing chromium plated brass soap dish ofGem/Parko/ESS/JAL with C.P (Chromium plated) brass brackets fixed to wooden cleats with C.P (Chromium plated) brass screws etcetra complete as per specification, approved drawing, design including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Toll tax, GST or any other taxes imposed by the Government.	8.00	Each	875.00	Rupees Eight Hundred & Seventy Five Only		7000.00		
5	Providing and fixing 15mm (Fifteen millimetres) diametres brass angle valve without nuts IS marked No. 8934 of Jai/ESS ESS Finolex/Hindware/Cera including entire carriage of material within all leads, lifts and other incidentals as per specification approved drawing, design and as directed by the Engineer-In-charge. The rate inclusive of octroi, royalty, Malkana. Toll tax, sale tax, GST and any other taxes imposed by the Government.	32.00	Each	921.05	Rupees Nine Hundred & Twenty One - Paise Five Only		29474.00		
6	Providing and fixing hydraulic Auto hinges of approved quality (ISI) marked with necessary screws etc. Complete as per specification approved drawing, design and as directed by the Engineer-Incharge. The rate inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	68.00	Each	415.00	Rupees Four Hundred & Fifteen Only		28220.00		
7	Providing and fixing Hot and cold water mixture of Hindware/Jacar of approved brand completeas per specification approved drawing, design and as directed by the Engineer-In-charge. The rate inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	4.00	Each	7200.00	Rupees Seven Thousand Two Hundred Only		28800.00		

8	Providing and fixing 50mm (Fifty millimetre) (Confirming to ISI No.14735-99 PVC Supreme/ Kishan/ Astral or equivalent floor trap including filling the joints with approved adhesive complete, as per specification, approved drawing, design as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malikana, toll tax, GST or any other taxes imposed by the Government.	12.00	Each	250.00	Rupees Two Hundred & Fifty Only	3000.00
		Total:				99490.00

EXCESS = %

LESS = %

Executive Engineer,
HPPWD Kangra
Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR OF GUEST HOUSE AT NIFT CAMPUS AT CHIEF KANGRA/SHI-DEMOLISHING OF CEMENT CONCRETE FLOORING/STONE MASONARY AND PROVIDING AND FIXING WASHBASIN WITH PEDESTAL AND PVC PIPE ETC.)									
Estimated Cost:- 81742.00									
Earnest Money:- 17000/-									
Time Limit:- TWO MONTH									
Sr. No.	Description of work	Qty	Unit	Rates		In Figures	In Words	AMOUNT	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material with in 50 metres lead as per direction of Engineer -in- Charge.Nominal concrete 1:3:6. or richer mix/(ic equivalent design mix) including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	13.12	Per Cubic metres	1250.00			Rupees One Thousand Two Hundred & Fifty Only	16400.00	
2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material with in 50 metres lead as per direction of Engineer in charge, direction of Engineer -in- Charge including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	17.48	Per Cubic metres	1240.00			Rupees One Thousand Two Hundred & Forty Only	21675.00	
3	dismantling doors and windows and clerestory windows(steel or wood) shutter including chowkhats, architrave, hold fasts etc.complete and stacking with in 50 metres lead of area beyond 3 square metres. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	16.00	Each	80.45			Rupees Eighty - Paise Forty Five Only	1287.00	
4	Providing and fixing flat back 550x480 mm (Five hundred fifty into Four hundred millimetre) vitreous china wash basin with single hole No. 10072 (ten thousand Seventy two) Cera or Hindware/Jaquar of star white/Snow white for pillar tap with C.I. (Cast Iron) or M.S. (Mild Steel) brackets painted white including cutting holes and making good the same but excluding fittings, as per specification including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.00	Each	3258.20			Rupees Three Thousand Two Hundred & Fifty Eight - Paise Twenty Only	13033.00	
5	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings as per direction of Engineer in charge. including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	4.00	Each	3086.85			Rupees Three Thousand & Eighty Six - Paise Eighty Five Only	12347.00	
6	Providing and fixing 8mm dia C.P.V.S. Jet with flexible tube up to 1metre long with S.S triangular plate to European type W.C of quality and make as approved Hindware/ Jaquar by Engineer-in-Charge including carriage of material with in all leads, and other incidentals. The rate is inclusive of octroi,royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	4.00	Each	414.80			Rupees Four Hundred & Fourteen - Paise Eighty Only	1659.00	

7	Providing and fixing on wall face 75mm (Seventy five millimetres) diameter P.V.C. polyvinyl chloride pipe D-plant or equivalent rain water pipes of working pressure not less than 4.50 kg (Four point five zero kilograms) per Square Centimetre including filling the joints with approved adhesive including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, malkana and all other taxes as imposed by the Government.	48.00	Per running metre	319.60	Rupees Three Hundred & Nineteen - Paise Sixty Only	15341.00
		Total:				81742.00

EXCESS = %

LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK : C/O Link road Sanour Lahar to Tarkhankar road Km. 0/00 to 3/360 (Under SCSP).

(SH:- C/O R/wall at RD 0/850 to 0/862.20):- of 856.65

NAME OF WORK : C/O Link road Sanour Lahar to Tarkhankar road Km. 0/00 to 3/360 (Under SCSP).						
(SH:- C/O R/wall at RD 0/850 to 0/862.20):- of 856.65						
Sr. No.	Description of work	Qty	Unit	Estimated Cost:-		99971.00
				In Figures	In Words	2000.00
Time Limit:- One Month						
AMOUNT						
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3 m depth. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	7.95	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	3889.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure using plain cement concrete nominal mix 1: 4: 8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeters) nominal size including curing complete including the cost of form work in or under water including pumping or baffling out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths as per drawing and MORD technical specification section 800, 900 and 1200 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkhama, toll tax, GST or other taxes imposed by the Government.	12.35	Per Cubic metres	5468.10	Rupees Five Thousand Four Hundred & Sixty Eight - Paise Ten Only	67531.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1:(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental.	6.00	Each	427.50	Rupees Four Hundred & Twenty Two - Paise Fifty Only	2535.00
4	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and to the entire satisfaction of the Engineer- in-CHARGE. The rate including of octroi, royalty, Malkhama, toll tax, GST or other taxes imposed by the government, rate	2.45	Per Cubic metres	1428.00	Rupees One Thousand Four Hundred & Twenty Eight Only	3499.00
5	Providing and Laying cement concrete for plain/ reinforced concrete in open foundation complete as per drawing and technical specification clauses 802, 804, 805, 806, 807, 1202, 1204 PCC Grade M-15, in 1:2.5:5 sand as per the direction of Engineer- in -charge including carriage of material with in all leads and lifts and other incidentals. The rate including of octroi, malkhama, tolltax, sale Tax or other taxes imposed by the government.	3.85	Per Cubic metres	5848.70	Rupees Five Thousand Eight Hundred & Forty Eight - Paise Seventy Only	22517.00
		Total:				99971.00

EXCESS=	%
LESS=	%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.