

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
No.PW-Ksl-CB Tender-A/2024-25- 19656-61

Dated:- 04/03/2025

To

The Executive Engineer (IT Cell),  
Nigam Vihar, Nirman Bhawan,  
HPPWD, Shimla-2.  
Email ID:eeict-pwd-shi@hp.gov.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2024 dated: 03.01.2025. As the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - DA Above

Executive Engineer,  
Kasauli Division,  
HP.PWD, Kasauli

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (SZ), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3<sup>rd</sup> HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,  
Kasauli Division,  
HP.PWD, Kasauli

### Exigency Certificate

It is Certified that the tenders which were invited vide this office NIT NO.PW/Ksli/CB-Tenders/2024-25..19656-6 / dated 04/03/25 are of emergent nature of work and in public interest.

Dated:-

Place:- Kasauli

  
Executive Engineer,  
Kasauli Division  
HPPWD Kasauli



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

**(Exigency)**

hereby invited by the **Executive Engineer Kasauli Division, HPPWD, Kasauli** for the following works on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in HPPWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

Sr.No.	Tender Schedule	Date	Time
1.	Receipt of application for tender forms	11.03.2025	Upto 3.00 PM
2.	Issue of Tender Forms	12.03.2025	Upto 5.00 PM
3.	Receipt of Tenders	13.03.2025	Upto 11:00 AM
4.	Opening of Tenders	13.03.2025	At 11.30 AM

The tender shall be received upto 11.00AM on 13.03.2025, and will be opened on the same day at 11.30AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDR/Account/Saving account in any of the post office/Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of Executive Engineer, (B&R) Division, HPPWD, Kasauli must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Job No.	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	A/R & M/O to HPPWD Circuit House at Parwanoo Distt Solan (SH:- P/F Curtain in Set No. 5,6)	99,982/-	2000/-	Two Month	350/-
2	A/R & M/O to HPPWD Circuit House at Parwanoo Distt Solan (SH:- P/F Curtain in Set No. 7 and repair to Chairs)	96,163/-	1900/-	Two Months	350/-
3	A/R & M/O to HPPWD Circuit House at Parwanoo Distt Solan (SH:- Repair to Sofa sets in Circuit House Parwanoo)	96,761/-	1900/-	Two Months	350/-
4	A/R & M/O to HPPWD Circuit House at Parwanoo Distt Solan (SH:- P/F Curtain in Set No. 3,4)	99,982/-	2000/-	Two Month	350/-
5	C/O link road from Rakhog to Village Paptol in Km. 0/00 to 4/540. (SH:- C/O road from Jeepable standard to 5/7 mtr. Wide in Km. 0/120 to 0/210) Under SCDP.	98,857/-	2000/-	Two Month	350/-
6	C/O link road from Petrol Pump to Kakkarhatti in Km. 0/00 to 1/400. (SH:- P/L WBM G-I & G-II in Km. 1/715 to 1/795) Under SCDP.	88,646/-	2000/-	Two Month	350/-
7	C/O link road from Petrol Pump to Kakkarhatti in Km. 0/00 to 1/800. (SH:- Hiring of JCB/loader cum-excavator for removal of slips & clearance of drain and hiring of Tipper for shifting of earth and debris) Under SCDP.	99,500/-	2000/-	One Month	350/-
8	C/O ITI building at Patta Mehlog Distt Solan HP. (SH:- P/L cement concrete 1:2:4 work in approach road to backside of the building in Km. 0/00 to 0/035) Deposit	99,358/-	2000/-	One Month	350/-
9	C/O ITI building at Patta Mehlog Distt Solan HP. (SH:- P/L Kharanja stone soling work in approach road to backside of the building in Km. 0/00 to 0/035 and C/O U shape drain near main gate of ITI) Deposit.	99,336/-	2000/-	One Month	350/-
10	C/O link road from Dhillon to Barog Tunnel in Km. 0/00 to 1/300. (SH:- ROFD in Km. 0/330 to 0/465) Under MNP.	97,662/-	2000/-	Two Months	350/-
11	C/O link road from Dhillon to Barog Tunnel in Km. 0/00 to 1/300. (SH:- ROFD in Km. 0/915 to 1/030) Under MNP.	99,198/-	2000/-	Two Months	350/-

12	R/R damages on Badurighatti to Raupul road in Km. 0/00 to 3/500 and link road to Village Algra Km. 0/00 to 3/00.(SH:- Hiring of JCB/loader Cum-Excavator for removal of slips & clearance of drain)	97,900/-	2000/-	One Month	350/-
13	R/R damages to Jadli Grownghatti Badurighatti road in Km. 0/00 to 9/100.(SH:- Hiring of JCB/loader Cum-Excavator for removal of slips & clearance of drain)	99,000/-	2000/-	One Months	350/-
14	C/O link road from Gahi to Jabli in Km. 0/00 to 2/405.(SH:- Formation Cutting in Km. 1/720 to 1/825)Under MMGSY.	96,721/-	1900/-	Two Month	350/-
15	C/O link road from Gahi to Jabli in Km. 0/00 to 2/405.(SH:- Formation Cutting in Km. 1/585 to 1/630)Under MMGSY	90045	1800/-	Two Months	350/-
16	Preparation of FRA Case for the work C/O Trashadi to Banaghat road Km. 0/00 to 1/600 Under Subathu Sub-Division.	75,000/-	1500/-	Three Months	350/-
17	Preparation of FRA Case for the work C/O of Link road from Jwala Mata Mandir to House of Kapuriya Ram Km. 0/00 to 1/00 Under HPPWD Sub-Division Subathu)	75,000/-	1500/-	Three Months	350/-

#### TERMS & CONDITIONS:-

1. The tender from will not be issued to those contractor whose performance has been found unsatisfactory
2. The contractor should have submitted the proof of registration No, EPF No. & GST No. At the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Executive Engineer,  
Kasauli Division,  
HPPWD Kasauli  
On behalf of the Governor of HP

①

## DRAFT SCHEDULE OF QUANTITY

		Estimated Cost:-		99982.00	
		Earnest Money:-		2000.00	
		Time:-		Two Months	
Name of Work :- A/R & M/O to HPPWD Circuit House at Parwanoo Distt. Solan (SH:- Providing and Fixing Curtain in Set No 5, 6)					
Sr. No	Description of work	Qty	Unit	Rate in Figures Words	Amount
1	Providing and fixing curtain including stitching and fixing in which curtain cloth & lining complete having size of 0.50 metre in width complete as per HP.PWD specification. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.00	Each	3570.80 Rupees Three Thousand Five Hundred & Seventy - Paise Eighty Only	99982.00
Total:-					99982.00
Rupees Ninety Nine Thousand Nine Hundred & Eighty Two Only					

T/S No. 369 for the year 2024-2025  
Sr. No. 595 for the year 2024-2025

Executive Engineer  
B&R Division, H.P.W.D. Kasauli

Job No.

## DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	96163.00
Earnest Money:-	1900.00
Time:-	Two Months

Name of Work :- A/R & M/O to HPPWD Circuit House at Parwanoo Distt. Solan (SH:- Providing and Fixing Curtain in Set No 7 and repair to chairs)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and fixing curtain including stitching and fixing in which curtain cloth & lining complete having size of 0.50 metre in width complete as per HP.PWD specification. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	Each	3570.80	Rupees Three Thousand Five Hundred & Seventy - Paice Eighty Only	14283.00
2	Upholstering sofa chair and back with making of lapestry cloth cutting to shape stitching and fixing etc. including properly scuring speings in position with twins U hooks and cane stick etc. fixing padding with coir and cotton / latex foam rubber of approved quality in the seat and back all complete including the cost of material in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Each	4094.00	Rupees Four Thousand & Ninety Four Only	81880.00
Total:-						96163.00
Rupees Ninety Six Thousand One Hundred & Sixty Three Only						

T/S No. 370 for the year 2024-2025  
Sr. No. 596 for the year 2024-2025

Executive Engineer  
B&R Division, HPPWD, Kasauli

Job No.

## DRAFT SCHEDULE OF QUANTITY

		Estimated Cost :-		96761.00	
		Earnest Money:-		1900.00	
		Time:-		Two Months	
Name of Work :- A/R & M/O to HPFWD Circuit House at Parwanoo Distt. Solan (SH:- Repair to Sofa sets in Circuit House Parwanoo)					
Sr. No	Description of work	Qty	Unit	Rate in	Amount
1	Upholstering resitting of sofa set/seats/ using 2 thick sleep well with quality foam sheets and back fixing padding with calia and latest with superior quality trans try cloth in proper position including cost of stitching material and sets sleep well 40 density complete as per HP.PWD specification. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Each	Figures 6911.50 Rupees Six Thousand Nine Hundred & Eleven - Paise Fifty Only	96761.00
	Total:-				96761.00
Rupees Ninety Six Thousand Seven Hundred & Sixty One Only					

T/S No. 871 for the year 2024-2025  
Sr.No. 597 for the year 2024-2025

Executive Engineer  
B&R Division, HPFWD Kasauli



Job No.

## DRAFT SCHEDULE OF QUANTITY

(4)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and fixing curtain including stitching and fixing in which curtain cloth & lining complete having size of 0.50 metre in width complete as per H.P.PWD specification including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.00	Each	3570.80	Ruppes Three Thousand Five Hundred & Seventy - Paise Eighty Only	99982.00
Total:-						99982.00
		Rupees Ninety Nine Thousand Nine Hundred & Eighty Two Only				

Name of Work:- A/R & M/O to HPPWD Circuit House at Parwanoo Distt. Solan (SH:- Providing and Fixing Curtain in Set No 3, 4)

Estimated Cost:- 99982.00  
 Earnest Money:- 2000.00  
 Time:- Two Months

T/S No. ~~368~~ for the year 2024-2025  
 Sr. No. ~~894~~ for the year 2024-2025

Executive Engineer  
 B&R Division, HP PWD, Kasauli

11.11.24

Job No. :- **DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :-	98857.00
Earnest Money :-	2000.00
Time limit :-	Two Month
Name of Work :- C/O link road from Rakhog to village Paprol in Km. 0/00 to 4/540. (SH :- C/O road from jeepable standard to 5/7 mtr. Wide in Km. 0/120 to 0/210). Under SCDP.	

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. ( one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited). All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of	510.23 m3	Per cubic meter.	193.75	Rupees One Hundred & Ninety Three - Paise Seventy Five Only	98857.00
Total :-						98857.00
Rupees Ninety Eight Thousand Eight Hundred & Fifty Seven Only						
1 in Words		% above/below to the DNT amount i.e. Rs.				

T/S No. 308 for the year 2024-25  
DNT/No. 530 for the year 2024-25

Draft Schedule of Quantity approved for Rs. 98857.00 only

Executive Engineer  
B&R Division HP PWD.  
Kasauli

# DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o link road from Petrol pump to Kakharhadi in Km. 0/00 to 1/400. (SH:- P/L WBM G-I & G-II in Km. 1/715 to 1/795). Under SCDD.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 90mm to 45mm (ninety millimetre to forty five millimetre ) Grading-1 100 mm (One hundred millimetre) consolidated thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (eighty to hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 13.2mm(thirteen point two millimetre) nominal size at the rate 0.27 cum (zero point twenty seven cubic metre) and binding materials at the rate 0.06 cum (zero point zero six cubic metre) per 10 square metre (ten) and to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 by mechanical means as per direction of Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	24.020	m3	2022.00	Rupees Two Thousand & Twenty Two Only	48668.00

Estimated Cost:- 88646.00  
 Earnest Money:- 2000.00  
 Time limit:- Two Month

2	Providing and laying, spreading by mechanical means and compacting stone aggregates of WBM Grading-II i.e. 63mm to 45mm (sixty three millimeters to forty five millimeters) size @ 0.91cum (point nine one cubic meters to ten) square meters upto compacted thickness of 75mm (seventy five millimeters) including spreading in uniform thickness of 10 per 10 with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two) cubic meters per ten square meters and binding materials @ 0.060cum (point zero six cubic meter) per 10 (ten) square meters to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD Technical Specification Clause 405 (Four hundred five) upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	17.610	m <sup>3</sup>	Per Cubic metre	2275.85	Rupees Two Thousand Two Hundred & Seventy Five - Paise Eighty Five Only	40078.00
	Total :-						
1 in Words	% above/below to the DNT amount i.e. Rs.	Rupees Eighty Eight Thousand Six Hundred & Forty Six Only					88646.00

T/S No. 348 for the year 2024-25  
DNT No. 535 for the year 2024-25

Draft Schedule of Quantity approved for Rs. 88646.00 only

Executive Engineer  
B&R Division, HP.PWD.  
Kasauli

Sl. No.

# Draft SCHEDULE OF QUANTITY

(7)

Name of Work :- C/O link road from Petrol pump to Kakarhati KM 0/00 to 1/800 (SH. SH. :- Hiring of JCB / loader cum-excavator for Removal of slips & clearance of drain and hiring of Tipper for shifting of earth and debris ~~under SCDP~~ under SCDP.)

Estimated Cost :-	99500.00
Estimated Manpower :-	3064.420440
Time limit :-	One month

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
	Hire charges should include expenses on account of establishment POL Major and minor repairs / over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents. The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one. The machinery should be of latest model not older than 1999, quantity of excavated / removed material should not be less than 28 cum / per hour.	65.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	71500.00
2	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge, including carriage of all labour equipment and material to various locations through all modes of transport in all leads and lifts and all incidental charges.	7.00	Per day	4000.00	Rupees two thousands two hundred and sixteen only	28000.00
Total :-						99500.00

Total in Words

Rupees Ninety Nine Thousand Five Hundred Only  
Draft Schedule of Quantity Recommended for approval for Rs. 99500.00 only.

Sr. No. 537 for the year 24-25  
Draft Schedule of Quantity approved for Rs. 99500.00 only.

Assigned Engineer.  
B&R Sub Division HP PWD, Subanhu

Executive Engineer  
B&R Division HP PWD, Kasauli.

DRAFT SCHEDULE OF QUANTITY									
Job No. :-									
Name of Work :- C/o ITI building at Patta Mehlog Dist. Solan H.P. (SH- P) cement concrete 1:2:4 work in approach road to backside of the building in Km. 0/00 to 0/035). Deposit.					Estimated Cost :-		99358.00		
					Earnest Money :-		2000.00		
					Time limit :-		One Month		
Sr.No	Description of work		Qty.	Unit	Rate in		Amount		
			Figures	Words					
1	Providing and laying cement concrete work 1:2:4 (one cement two sand :four graded crust hard stone aggregate twenty millimetre nominal size/mechanically mixed and vibrated for compacting concrete required strength and curing complete including cost of form work and reinforcement for reinforced cement concrete work as per HPPWD specification 1990 (one thousand Nine hundred Ninety ) volume-1 including carriage of materials in all leads and lifts and as per the direction of Engineer in Charge. Foundations, and plinth in all depths and levels.		17.530 m3	Per cubic meter	5667.90	Rupees Five Thousand Six Hundred & Sixty Seven Paise Ninety Only	99358.00		
Total :-							99358.00		
Rupees Ninety Nine Thousand Three Hundred & Fifty Eight Only									
in Words									
% above/below to the DNT amount i.e. Rs.									

TS No. 330 for the year 2024-25  
DNTNo. 54) for the year 2024-25

Draft Schedule of Quantity approved for Rs. 99358.00 only

Executive Engineer  
B&R Division, HP PWD.  
Bansauli

Job No. :-

## DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o ITI building at Patta Mehlog Distt. Solan H.P. (SH:- P1 Kharanja stone soling work in approach road to backside of the building in Km. 0/00 to 0/035 and do u shape drain near main gate of ITI). Deposit.		Estimated Cost :-		Earnest Money:-		Time limit :-	One Month
		99336.00		2000.00			
Sr.No	Description of work						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesing / wedging cut rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	Qty:	Unit	Rate in		Amount	
		53.360 m <sup>3</sup>	Per Cubic Meter	Figures 277.50	Words Rupees Two Hundred & Seventy Seven - Paise Fifty Only	14807.00	
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per H.P.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. Foundations, and plinth in all depths and levels.	21.040 m <sup>3</sup>	Per cubic meter	2007.90	Rupess Two Thousand & Seven - Paise Ninety Only	42246.00	

3	Providing and laying cement concrete work 1:2:4 (one cement two sand four graded crust hard stone aggregate twenty millimetre nominal size) mechanically mixed and vibrated for compacting concrete required strength and curing complete including cost of form work and reinforcement for reinforced cement concrete work as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. Foundations, and plinth in all depths and levels.	7.460 m <sup>3</sup>	Per cubic meter	5667.90	Rupees Five Thousand Six Hundred & Sixty Seven Paise Ninety Only	42283.00
Total :-						99336.00
1 in Words	Rupees Ninety Nine Thousand Three Hundred & Thirty Six Only					
	% above/below to the DNT amount i.e. Rs.					

T.S.M. 331 for the year 2024-25  
DNT No. 543 for the year 2024-25

Draft Schedule of Quantity approved for Rs. 99336.00 only

Executive Engineer  
R&R Division, HP.PWD.  
Basantpur

Job No.

## DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	97662.00
Earnest Money:-	2000.00
Time:-	Two Months

Name of Work :- Construction of link road from Dhillion to Barog Tunnel in km 0/00 to 1/300 (SH:- ROFD in km 0/330 to 0/465) Under MNP.

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. ( one six zero three point one) and MORD specification including carriage of all labour, equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited). All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	397.15	Per Cubic Metre	193.75	Rupess One Hundred & Ninety Three Paise Seventy Five Only	76948.00



2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.2 and MORD specification modes of transportation in all lead, lift and all incidental charges. All earth work in cutting/ excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004, and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner,trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 6.519 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	65.19	Per Cubic Metre	317.75	Rupees Three Hundred & Seventeen - Paise Seventy Five Only	20714.00
	Total:-					97662.00
	Rupees Ninety Seven Thousand Six Hundred & Sixty Two Only					

T/S No. 345 for the year 2024-2025  
Sr.No. 561 for the year 2024-2025

Executive Engineer  
B&R Division, HP, MWD, Kasauli

Job No.

## DRAFT SCHEDULE OF QUANTITY

(11)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. (one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc, and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited) All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, hailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	431.71	Per Cubic Metre	193.75	Ruppes One Hundred & Ninety Three Paise Seventy Five Only	83644.00

Name of Work :- Construction of Link road from Dhillion to Barog Tunnel in km 0/00 to 1/300 (SH:- ROFD in km 0/915 to 1/030) Under MNP.

Estimated Cost:- 99198.00

Earnest Money:- 2000.00

Time:- Two Months



2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.2 and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportation in all lead, lift and all incidental charges. All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charge. in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in - Charge for smooth riding. The recovery of useful stone that is 4.895 cubic meter in all cases falling which recovery @ Rupees 310/- only (Rupees three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	42.95	Per Cubic Metre	317.75	Rupees Three Hundred & Seventeen - Paise Seventy Five Only	15554.00
Total:-						99198.00
Rupees Ninety Nine Thousand One Hundred & Ninety Eight Only						

T/S No. **346** for the year 2024-2025  
 Sr. No. **562** for the year 2024-2025

Executive Engineer  
 B&R Division, Kasauli

# Draft SCHEDULE OF QUANTITY

Name of Work :- R/R damages on Badurighatti to Raupul road in Km.0/00 to 3/500 and Link road to village Algra KM 0/00 to 3/00 (SH. SH :- Hiring of JCB / loader cum-excavator for Removal of slips & clearance of drain.)

Estimated Cost:-	AMOUNT
Earnest Money:-	97900.00
Time Limit:-	2000-01-2000.00
	One month.

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
	<b>Hiring of JCB / loader cum-excavator.</b>					
	<b>Terms and Conditions :-</b>					
	Hire charges should include expenses on account of establishment POL Major and minor repairs / over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents. The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one. The machinery should be of latest model not older than 1999. quantity of excavated / removed material should not be less than 28 cum / per hour.	89.00	Per hour.	1100.00	Ruppes One Thousand One Hundred Only	97900.00
<b>Total :-</b>						97900.00

Total in Words  
Draft Schedule of Quantity Recommended for approval for Rs. **97900.00** only.  
Ruppes Ninety Seven Thousand Nine Hundred Only

Assistant Engineer,  
B&R Sub Division, HP PWD, Subathu

Sr. No. **564** for the year 24-25  
Draft Schedule of Quantity approved for Rs. **97900.00** only.

Executive Engineer  
B&R Division, HP PWD, Kasauli.


## Draft SCHEDULE OF QUANTITY

AMOUNT	
Estimated Cost: -	99000.00
Earnest Money: -	2000.00 <del>4234.40</del>
Time Limit: -	One month.

Name of Work : R/R damages on Jaddi Grownghatti Badurghatti road in Km.0/00 to 9/100 (SH: SH : Hiring of JCB / loader cum-excavator for Removal of slips & clearance of drain.)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :- Hire charges should include expenses on account of establishment POL Major and minor repairs / over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents. The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one. The machinery should be of latest model not older than 1999. quantity of excavated / removed material should not be less than 28 cum / per hour.	90.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	99000.00
Total :-						99000.00
Total in Words					Rupees Ninety Nine Thousand Only	

Draft Schedule of Quantity Recommended for approval for Rs. **99000.00** only.

  
Assistant Engineer,  
R&R Sub Division, IIP (P.W.D), Subailm

Sr. No. **565** for the year 24-25

Draft Schedule of Quantity approved for Rs. **99000.00** only.

  
Executive Engineer,  
R&R Division, IIP (P.W.D), Kasauli.

Job No.

## DRAFT SCHEDULE OF QUANTITY

(14)

Name of Work :- Construction of Link road from Gahi to Jabli in km 0/00 to 2/405 (SH:- Formation Cutting in km 1/720 to 1/825) Under MMGSY.		Estimated Cost :-		Earnest Money :-		Time :-	Two Months
		96721.00		1900.00			
Sr. No	Description of work	Qty	Unit	Rate in		Amount	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. ( one six zero three point one) and MCRD specification including carriage of all labour equipment and materials to various location of site through all modes of Transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited) All earth work in excavation including rock excavations shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and sale disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	360.25	Per Cubic Metre	Figures	Words	69798.00	
				193.75	Rupees One Hundred & Ninety Three Paise Seventy Five Only		



Excavation in hilly area in ordinary rock not requiring blasting, by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.2 and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. All earth work in cutting / excavation, including rock excavation shall be carried out true to lines grades, side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material inspected manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding. The recovery of useful stone that is 8.473 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.

84.73	Per Cubic Metre	317.75	Rupees Three Hundred & Seventeen - Paise Seventy Five Only	26923.00
Total:-				
Rupees Ninety Six Thousand Seven Hundred & Twenty One Only				
96721.00				

T/S No. 866 for the year 2024-2025  
Sr. No. 592 for the year 2024-2025

Executive Engineer  
B&R Division, Kasauli

Job No.

## DRAFT SCHEDULE OF QUANTITY

(15)

Name of Work :- Construction of Link road from Gahi to Jabli in km 0/00 to 2/405 (SH:- Formation Cutting in km 1/585 to 1/630) Under MMGSY.

Estimated Cost:-	90045.00
Earnest Money:-	1800.00
Time:-	Two Months

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. ( one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited). All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	366.99	Per Cubic Metre	193.75	Rupees One Hundred & Ninety Three Paise Seventy Five Only	71104.00

2	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mtr. And a lead upto 20.00 mtr. as per technical specification Clause 1603.2 and MOHD specification including carriage of all labour equipment and materials to various location of site through all modes of transportation in all lead, lift and all incidental charges. All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding. The recovery of useful stone that is 5.961 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundreded only) per cubic meter shall be effected on pro-rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	59.61	Per Cubic Metre	31775	Rupees Three hundred & Seventeen Paise Seventy Five Only	18941.00
	Total:-					90045.00
	Rupees Ninety Thousand & Fourty Five Only					

T/S No. 865 for the year 2024-2025  
Sr.No. 591 for the year 2024-2025

Executive Engineer  
B&R Division, H. P. M. D. Kasauli

# SCHEDULE OF QUANTITY

Estimated Cost	75,000
Earnest Money Rs	1500
Time: -	3 Months

Name of Work : Preparation of FRA Case for the work C/o Trashadi to Banaghat road Km 0/00 to 1/600 under Subbathu Sub Division.

S.No.	Description of item	No.	Rate. (Inclusive of GST)	Unit	Amount(Inclusive of GST)
1	Preparation of FRA Case with all relevant check lists, Digital Map, Toposheet and Layout Plan as per the latest guidelines of MoEF&CC of Proposed Road with G.P.S. Coordinates @ 100 meter interval with collecting the data from site including preparation of KML files/SHP file as per the direction of Engineer- in- charge alongwith preparation of 03 No. of proposal folders alongwith Monitoring with concerned forest department for early processing of the proposed forest case including compliances of the observations raised in the forest case till In-Principle/Final Approval.	1	75000	Per Case	75,000
Total					75,000

## SCHEDULE OF PAYMENT

Sr. No.	Scope	Rates (In Percentage)
1	After Site Inspection of the Proposed Road including collection of data with G.P.S. Coordinates @ 100 meter interval, including collection of revenue records from the site, collection of data from Gram Panchayat i.e. VLC proceedings, Van Adhikar Samiti & necessary NOCs.	35%
2	After Joint Inspection & preparation of FRA case with all relevant check lists, KML File, Digital Map, Toposheet and Layout Plan, 03 No. of Proposal Folders and signed by authorized User Agency.	35%

Assistant Engineer  
B & R Sub-Division  
H.P.P.W.D. Subbathu

After submission of Proposal Folder to DFO Office alongwith attending the observations raised including	20%
enumeration of trees in coordination with concerned Forest Department Officials (i.e. Forest Guard, Range Officer etc.)	
4 Final Approval	10%

Total in Words

Rupees Seventy Five Thousand only  
Draft Schedule of Quantity Recommended for approval for Rs. 75,000

Sr. No. <sup>528</sup> for the year 2024-2025

Draft Schedule of Quantity approved for Rs. 75000.00

only.

Assistant Engineer,  
B&R Sub Division, HP.PWD, Subathu

Executive Engineer  
B&R Division, HP.PWD, Kasauli

# DRAFT SCHEDULE OF QUANTITY

17

Estimated Cost	75,000
Earnest Money Rs	1500
Time:-	3 Months

Name of Work : Preparation of FRA Case for the work C/o of Link Road from Jwala Mata Mandir to House of Kapruriya Ram Km 0/00 to 1/00 under HPPWD Sub-Division Subathu.

S.No.	Description of item	No.	Rate. (Exclusive of GST)	Unit	Amount(Inclusive of GST)
1	Preparation of FRA Case with all relevant check lists, Digital Map, Toposheet and Layout Plan as per the latest guidelines of MoEF&CC of Proposed Road with G.P.S. Coordinates @ 100 meter interval with collecting the data from site including preparation of KML files/SHP file as per the direction of Engineer- in- charge alongwith preparation of 03 No. of proposal folders alongwith Monitoring with concerned forest department for early processing of the proposed forest case including compliances of the observations raised in the forest case till In-Principle/Final Approval.	1	75000	Per Case	75,000
	<b>Total</b>				<b>75,000</b>

## SCHEDULE OF PAYMENT

Sr. No.	Scope	Rates (In Percentage)
1	After Site Inspection of the Proposed Road including collection of data with G.P.S. Coordinates @ 100 meter interval including collection of revenue records from the site, collection of data from Granth Pandayat i.e. VLC proceedings, Van Adhikar Samiti & necessary NOCs.	35%
2	After Joint Inspection & preparation of FRA case with all relevant check lists, KML File, Digital Map, Toposheet and Layout Plan, 03 No. of Proposal Folders and signed by authorized User Agency.	35%

Assistant Engineer  
B & R Sub-Division  
H.P.P.W.D. Subathu

3	After submission of Proposal Folder to DFO Office alongwith attending the observations raised including enumeration of trees in coordination with concerned Forest Department Officials (i.e. Forest Guard, Range Officer etc.)	20%
4	Final Approval	10%

Total in Words

Rupees Seventy Five Thousand only  
Draft Schedule of Quantity Recommended for approval for Rs. 75,000

Sr. No. <sup>526</sup> for the year 2024-2025

Draft Schedule of Quantity approved for Rs. 75000.00

Assistant Engineer,  
B&R Sub Division, H.P. PWD, Subathu

Executive Engineer  
B&R Division, H.P. PWD, Kasauli