

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.TH.D/CB/TENDER/Tender Notice/2024

7218-28

Dated:- 3/3/2025

To

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.

Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2024 dated 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Sealed Percent rates tender form No 7 & 8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

- 1 Date of receipt of Applications for tender forms: 07.03.2025 upto 12:00 PM
- 2 Date of issue/sale of Tender forms:- 07.03.2025 upto 4:00 PM
- 3 Date of receipt of Tender:- 10.03.2025 upto 10:30 AM
- 4 Date of opening of Tender 10.03.2025 upto 11:00 AM

Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	R/R Damages on Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 .(SH:- Removal of slip Between RD 159/ 180 to 159/202).	98879	2000	350/-	2 Months
2	2	Maintenance on Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 .(SH:- C/O B/Wall At RD 159/180 to 159/183.00)	99817	2000	350/-	2 Months
3	3	Maintenance on Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 .(SH:- C/O B/Wall At RD 159/183 to 159/185.95)	98126	2000	350/-	2 Months
4	4	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O R/Wall At RD 13/620 to 13/623.70)	98804	2000	350/-	2 Months
5	5	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O R/Wall between RD 13/623.70 to 13/627.42)	99351	2000	350/-	2 Months
6	6	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Clearance of hillside chocked drain between K.M. 18/00 to 18/750)	97500	2000	350/-	1 Month
7	7	Maintenance on Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:-Repair Of Store At RD. 159/820	95786	2000	350/-	2 Months
8	8	Maintenance on Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:-Repair Of Store At RD. 159/820	97306	2000	350/-	2 Months
9	9	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Clearance of hillside chocked drain between K.M. 18/750 to 19/510)	98800	2000	350/-	1 Month
10	10	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Removal of slip Between RD 14/ 700 to 15/200).	98438	2000	350	2 Months
11	11	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Removal of slip Between RD 15/ 640 to 15/900).	96525	2000	350	2 Months
12	12	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O U Shape drain At RD 21/350 to 21/450).	95720	2000	350	2 Months
13	13	R/R Damages on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O U Shape drain At RD 21/540 to 21/616).	96997	2000	350	2 Months
14	14	A/R & M/O Theog Kotkhair Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/090 to 16/105)	98946	2000	350	2 Months

15	15	A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Demolition of B/Wall in P.C.C. and Widening of Road at R.D. 16/105 to 16/120)	84068	2000	350	2 Months
16	16	A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- C/O R/Wall at R.D. 3/700 to 3/703.50)	99585	2000	350	2 Months
17	17	A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- C/O R/Wall at R.D. 3/703.50 to 3/707)	99735	2000	350	2 Months
18	18	A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/075 to 16/090)	98598	2000	350	2 Months
19	19	A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/060 to 16/75)	96926	2000	350	2 Months

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.
- 12 Works should be completed by the contractor within the stipulated period.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog
Dated 31/3/2024

No/PW/NH/CB/Tender/2024:- 7216-17

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar Shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Superintending Engineer NH Circle HP PWD Shimla .
- 4 All the Assistant Engineer working under this Division
- 5 The Drawing Branch/Account Branch in this office.
- 6 Notice Board.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog



NATIONAL HIGHWAY (NH-05)
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT
DIVISION THEOG

Certificate

Certified that the tenders of works as called vide this office NIT No/PW/NH/CB/Tender/2023- **7210-17** Dated **3/3/2025** are urgent nature and public interest.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Rs:- 98879
Cost:

Earnest Rs:- 2000.00
Money

Time. 2 Month.

Name of work:- R/R Damages on Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 (SH:- Removal of slip Between RD 159/ 180 to 159/202).

Sr. No	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Removal of landslide /unserviceable soil in all type of rock, including hard rock and opening of catchpits for choked culverts including cutting by a hydraulic excavator , loading and disposal upto 10 km lead as per MORTH specification 2019 clause 3000 . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	219.73	Per Cum.	450.00	Rupees Four Hundred Fifty Only	98879
	Total					98879
	(Quoted Rates in Figures)(+/-)			(Quoted Rates in Figures)(+/-)		
	(Quoted Rates in words)(+/-)			(Quoted Rates in words)(+/-)		

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:- 9981.7

Earnest Money:- 2000

Time:- 2 Month.

Name of work:- Maintenance on Kalka Shimla Wangtoo road NH- 05 km. 153/180 to 236/00 (SH:- C/O B/Wall At RD 159/180 to 159/183.00)

Sr. No.	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	3.24	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	989.04
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500, 1700, 2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.38	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	93503.40
3	Providing weep holes in Brick masonry/plain/reinforced concrete abutment/wing wall/return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	19.50	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	5325.45
Total						99817
(Quoted Rates in Figures) (+/-)				%		
(Quoted Rates in words) (+/-)				%		

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:-

98126

Earnest Money:-

2000

Time:- 2 Month.

Name of work:- Maintenance on Kalka Shimla Wangtoo road NH- 05 k.m. 153/180 to 236/00 (SH:- C/O B/Wall At RD 159/183 to 159/185.95)

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	3.19	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	973.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100. in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.15	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	91915.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment, wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slope of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	19.18	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	5238.00
	Total					98126.00
	(Quoted Rates in Figures)(+/-)			(Total Rate in Figures)	(Total Rate in Words)	
	(Quoted Rates in Words)(+/-)					

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:-

98804

Earnest Money:-

2000

Time:- 2 Month.

Name of work:- R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (SH:- C/O R/Wall At RD 13/620 to 13/623.70)

Sr. No.	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge	3.66	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	1116.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.32	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	85636.00
3	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment, wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.00	Per Cum.	2170.50	Rupees Two Thousand One Hundred Seventy and Paise Fifty Only	8682.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment, wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	12.34	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	3370.00
Total						98804.00
		(Quoted Rates in Figures)(+/-)		(Quoted Rates in words)(+/-)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer
NH Division HPPWD
Theog

SCHEDULE OF QUANTITY

Estimated Cost:-

99351

Earnest Money:-

2000

Time:- 2 Month.

Name of work:- R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (SH:- C/O RAWal between RD 13/623.70 to 13/627.42)

Sr. No.	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	3.68	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	1122.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.38	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	86090.00
3	Providing and laying of filter media with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetres) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment, wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge In all leads and lifts and carriage of materials by all means of transport etc.	4.02	Per Cum.	2170.50	Rupees Two Thousand One Hundred Seventy and Paise Fifty Only	8725.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment, wing wall/return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	12.50	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	3414.00
Total						99351.00

(Quoted Rates in Figures) (+/-)

(Quoted Rates in Figures) (+/-)

(Quoted Rates in words) (+/-)

(Quoted Rates in words) (+/-)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

DRAFT SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	97500
				Earnest Money	Rs:-	Rs:-2000 only.
				Time.	1 Month.	
Name of work:-R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Clearance of hillside choked drain between K.M. 18/00 to 18/750)						
Sr. N	Description of item	Quantity	Unit	Rate	Rate in words	Amount
1	Removal of earth from the choked hill side drain and disposing it on the valley side manually	750	Rmt	130	Rupees One Hundred Thirty Only	97500
	Total					97500
				(Quoted Rates in Figures)/(+/-)		(%)
				(Quoted Rates in words)/(+/-)		(%)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

			Estimated Cost:	Rs:-	95786
			Earnest Money	Rs:-	Rs:-2000 only.
			Time.	2 Month.	

Name of work:-Maintenance on Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:-Repair Of Store At RD. 159/820)

Sr.	Description of Item	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	0.22	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	67.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	0.22	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sody Five Only	1664.00
1	Steel work welded in built up sections/ framed work, Including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	760.96	K.G	123.6	Rupees One Hundred Twenty Three and Paise Sixty Only	94055
Total						95786
(Quoted Rates in Figures)(+/-)				%		
(Quoted Rates in words)(+/-)				%		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

**Executive Engineer,
NH Division HPPWD,
Theog.**

SCHEDULE OF QUANTITY

				Estimated Cost	Rs:-	97306
				Earnest Money	Rs:-	Rs:-2000 only.
				Time.	2 Month.	
Name of work:-Maintenance on Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:-Repair Of Store At RD. 159/820						
Sr.	Description of Item	Quantity	Unit	Rate	Rate in words	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	787.27	K.G	123.60	Rupees One Hundred Twenty Three and Paise Sixty Only	97306
	Total					97306
	(Quoted Rates in Figures)(+/-)				(%)	
	(Quoted Rates in words)(+/-)				(%)	

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Tfreog.

SCHEDULE OF QUANTITY

Estimated Cost Rs:- 98800

Earnest Money Rs:- Rs:-2000 only.

Time 1 Month.

Name of work:- R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Clearance of hillside choked drain between K.M. 18/750 to 19/510)

Sr.	Description of item	Quantity	Unit	Rate	Rate in words	Amount
1	Removal of earth from the choked hill side drain and disposing it on the valley side manually	760	Rmt	130	Rupees One Hundred Thirty Only	98800
	Total					98800
	(Quoted Rates in Figures)(+/-)				(%)	
	(Quoted Rates in words)(+/-)				(%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Rs:-	98438	
				Cost:		
				Earnest Money	2000.00	
				Time. 2 Month.		
Name of work:-R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Removal of slip Between RD 14/ 700 to 15/200).						
Sr. No	Description of item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Removal of landslide /unserviceable soil in all type of rock, including hard rock and opening of catchpits for choked culverts including cutting by a hydraulic excavator , loading and disposal upto10 km lead as per MORTH specification 2019 clause 3000 . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	218.75	Per Cum.	450.00	Rupees Four Hundred Fifty Only	98438
Total						98438
		(Quoted Rates in Figures)(+/ -)		(Quoted Rates in Figures)(+/ -) %		
		(Quoted Rates in words)(+/ -)		(Quoted Rates in words)(+/ -) %		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

			Estimated Cost	Rs:-	96525
			Earnest Money	Rs:-	2000.00
			Time.	2 Month.	

Name of work:-R/R Damages on Shimla Bye pass road km 13/00 to 24/250 (S.H:- Removal of slip Between RD 16/ 640 to 15/900).

Sr. No	Description of Item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Removal of landslide /unserviceable soil in all type of rock, including hard rock and opening of catchpits for choked culverts including cutting by a hydraulic excavator , loading and disposal upto 10 km lead as per MORTH specification 2019 clause 3000 . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	214.50	Per Cum.	450.00	Rupees Four Hundred Fifty Only	96525
	Total					96525
	(Quoted Rates in Figures)(+/-)			(Quoted Rates in Figures)(+/-)		
	(Quoted Rates in words)(+/-)			(Quoted Rates in words)(+/-)		

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

			Estimated Rs:-	95720
			Cost	
			Earnest Rs:-	2000
			Money	
			Time.	2 Month.

Name of work:- Maintenance on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O U-Shape drain between RD 21/350 to 21/450)

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	16.20	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	4940.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.00	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	90780.00
	Total					95720.00
				(Quoted Rates in Figures %/-)	(Quoted Rates in words %/-)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

13

Estimated Cost:	Rs:-	96997
Earnest Money	Rs:-	2000
Time.	2 Month.	

Name of work: Maintenance on Shimla Bye pass road km 13/00 to 24/250 .(SH:- C/O U-Shape drain between RD 21/540 to 21/616)

Sr. No.	Description of Item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	16.42	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	5007.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.16	Per Cum.	7565.00	Rupees Seven Thousand Five Hundred Sixty Five Only	91990.00
Total						96997.00
(Quoted Rates in Figures)(+/-)				(Percentage of increase/decrease over the estimated rates)(+/-) %		
(Quoted Rates in words)(+/-)				(Percentage of increase/decrease over the estimated rates)(+/-) %		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

**Executive Engineer,
NH Division HPPWD,
Theog.**

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	98946
				Earnest Money	Rs:-	2000
				Time.	2 Month.	
Name of work :- A/R & M/O Theog Kotkhal Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/090 to 16/105)						
Sr. No.	Description of item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.1 including all leads and lifts as per the direction of Engineer - in Charge	147.00	Per Cum.	185.60	Rupees One Hundred Eighty Five and Paise Sixty Only	27283.00
2	Excavation in soil in Hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut material with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.2 including all leads and lifts as per the direction of Engineer - in Charge	220.50	Per Cum.	325.00	Rupees Three Hundred Twenty Five Only	71683.00
	Total					98946.00
				(Quoted Rates in Figures)(+/-)		(+/-)
				(Quoted Rates in words)(+/-)		(+/-)

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

15 16

Estimated Cost:-	54068
Earnest Money:-	2000
Time:-	2 Month.

Name of work :- A/R & M/O Theog Kotkhal Hartkoti Road NH 705 Km 0/0 to 69/000 (SH:- Demolition of B/Wall in P.C.C. and Widening of Road at R.D. 16/105 to 16/120)

Sr. No.	Description of Item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge	58.40	Per Cum.	185.60	Rupees One Hundred Eighty Five and Paise Sixty Only	10839.00
2	Excavation in soil in Hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut material with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.2 including all leads and lifts or as per the direction of Engineer - in Cha	87.60	Per Cum.	325.00	Rupees Three Hundred Twenty Five Only	28470.00
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres	43.92	Per Cum.	1019.10	Rupees One Thousand Nineteen and Paise Ten Only	44759.00
	Total					54068.00
	(Quoted Rates in Figures) (++)			(++)		
	(Quoted Rates in words) (++)			(++)		

Conditions

1. Rates shall be Quoted for all heights including all leads and lifts.
2. The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY						
				Estimated Cost:-	99585	
				Earnest Money:-	2000	
				Time:- 2 Month.		
Name of work :- A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- C/O R/Wall at R.D. 3/700 to 3/703.50)						
Sr. No.	Description of item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing, removal of slumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	1.08	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	329.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	13.09	Per Cum.	7520.00	Rupees Seven Thousand Five Hundred Twenty Only	98437.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment/wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	3.00	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	819.00
Total						99585.00
(Quoted Rates In Figures)(+/-)				(Quoted Rates In words)(+/-)		
(Quoted Rates In Figures)(+/-)				(Quoted Rates In words)(+/-)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

			Estimated Cost:-		99735	
			Earnest Money:-		2000	
			Time:- 2 Month.			
Name of work :- AJR & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- C/O R/Wall at R.D. 3/7/03.50 to 3/7/07.00)						
Sr. No.	Description of item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	1.57	Per Cum.	304.95	Rupees Three Hundred Four and Paise Ninety Five Only	479.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	13.09	Per Cum.	7520.00	Rupees Seven Thousand Five Hundred Twenty Only	98437.00
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge,etc.	3.00	Per Rmt.	273.10	Rupees Two Hundred Seventy Three and Paise Ten Only	819.00
Total						99735.00
			(Quoted Rates in Figures)/(+/-)		(Quoted Rates in words)/(+/-)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Rs:-	98598	
				Cost:		
				Earnest Rs:-	2000	
				Money		
				Time.	2 Month.	
Name of work :- A/R & M/O Theog Kotkhai Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/075 to 16/90)						
Sr. No	Description of item	Quantity	Unit	Rate		Amount
				In figure	In words	
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge	146.00	Per Cum.	185.60	Rupees One Hundred Eighty Five and Paise Sixty Only	27098.00
2	Excavation in soil in Hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut material with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.2 including all leads and lifts or as per the direction of Engineer - in Cha	220.00	Per Cum.	325.00	Rupees Three Hundred Twenty Five Only	71500.00
	Total					98598.00
	(Quoted Rates in Figures)(+/-)			(Quoted Rates in Figures)(+/-) %		
	(Quoted Rates in words)(+/-)			(Quoted Rates in words)(+/-) %		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
				Estimated Rs:-	96926	
				Cost:		
				Earnest Money	Rs:-	2000
				Time.	2 Month.	
Name of work :- A/R & M/O Theog Kotkhal Hatkoti Road NH 705 Km 0/0 to 69/000 (SH:- Widening of Road at R.D. 16/060 to 16/075)						
Sr. No	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.1 including all leads and lifts or as per the direction of Engineer - in Charge	144.00	Per Cum.	185.60	Rupees One Hundred Eighty Five and Paise Sixty Only	26726.00
2	Excavation in soil in Hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of cut material with a lift upto 1.50 m and a lead upto 20 m as per technical specification clause 1603.2 including all leads and lifts or as per the direction of Engineer - in Cha	218.00	Per Cum.	325.00	Rupees Three Hundred Twenty Five Only	70200.00
	Total					96926.00
				(Quoted Rates in Figures) (+/-)	(Quoted Rates in Figures) (+/-) %	
				(Quoted Rates in words) (+/-)	(Quoted Rates in words) (+/-) %	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost

Executive Engineer,
NH Division HPPWD,
Theog.