

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWN-CB-Tender/2024-25- 13397-13405
To


Dated:- 13-03-2025

The Executive Engineer (IT Cell),
Nigam Vihar, H.P.P.W.D., Shimla-2.
cc-pwd-hp@nic.in

Subject:- Publication of Tender Notice.


Enclosed please find herewith the Notice Inviting Tender to be opened on 20.3.2025 for uploading on department website as per notification Secy.(PW) to the Govt. of H.P. No.PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the notice is urgent nature and public interest.

Encl:- As above.


Executive Engineer,
B & R Division,
HPPWD, Nahan

Copy forwarded to the following for information & n/a to:-

1. The Engineer-in-Chief, HP.PWD., Shimla.
2. The Chief Engineer (SZ), HP.PWD., Shimla.
3. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
4. All the Assistant Engineers under this division.
5. All Head of Branches of this office.
6. The Notice Board.


Executive Engineer,
B & R Division,
HPPWD, Nahan

**Himachal Pradesh
Public Works Department
Short term Notice inviting Tender**

Sealed percentage rate tender on form PWD 6 & 7 are invited by the Executive Engineer Nahan, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD, so as to reach in this office as per time schedule given below.

- | | |
|---|-------------------------|
| 1. Date of receipt of application of tenders forms.:- | 18.3.2025 upto 11:00 AM |
| 2. Date of issue/ sale of tender Forms.:- | 20.3.2025 upto 10.30 AM |
| 3. Date of receipt of tender | 20.3.2025 at 11:00 AM |
| 4. Date of opening of tender:- | 20.3.2025 at 12:00 Noon |


Sr. No	Name of Work	Estimated Cost (in ₹)	Earnest Money (in ₹)	Time Limit	Cost of Tender Form (in ₹)
1	A/R & M/O Division office PWD at Nahan (SH:- Providing Almirah (Rack) in office and other misc. work).	99665/-	2000/-	01 Month	350/-
2	R/R damages to Sainwala Burma Papri Road km 0/00 to 11/00 (SH:- C/O Wire crate R/Wall at RD 4/743 to 4/757.40 2 nd and third step step)(Balance work)	98805/-	2000/-	02 Month	350/-
3	R/R damages to Sainwala Burma Papri Road km 0/00 to 11/00 (SH:- C/O Wire crate R/Wall at RD 4/738 to 4/749.50 IV step)(Balance work)	51210/-	1500/-	02 Month	350/-
4	R/R damages to Shambhuwala to Matter Bhedon road km 0/0 to 7/120 (SH:- C/Wire crate R/Wall at RD 2/225 to 2/235 towards Matter)	96544/-	2000/-	02 Month	350/-
5	R/R damages to Shambhuwala to Matter Bhedon road km 0/0 to 7.120 (SH:- C/O Wire crate R/Wall at RD 2/255 to 2/265 towards Matter.)	96544/-	2000/-	02 Month	350/-
6	R/R damages to Kaulanwala Bhod Panchyat at nahan (SH:- Removal of slips)	97488/-	2000/-	02 Month	350/-
7	R/R damages to Various road of Burma Papri Panchyat, Jangla Bhod Ambulance road (SH:- Removal of slips km. 0/0 to 0/360)	99943/-	2000/-	02 Month	350/-
8	R/R damage to Various road of Ambwala Sainwala Panchyat (SH:- Removal of slips)	98868/-	2000/-	02 Month	350/-
9	A/R & M/O various HPPWD schemes in 12 th circle HPPWD Nahan Distt. Sirmour H.P. (SH:- Binding of old record files of 12 th circle Nahan) Phase-I	99750/-	2000/-	02 Months	350/-
10	A/R & M/O various HPPWD schemes in 12 th circle HPPWD Nahan Distt. Sirmour H.P. (SH:- Binding of old record files of 12 th circle Nahan) Phase-II	99750/-	2000/-	02 Months	350/-
11	R/R damages to Khajurna Bikram Bagh Suketi Kala amb road 0/0 to 15/0. (SH:- C/O wire crate R/Wall at Rd. 14/500 to 14/505.80)	96823/-	2000/-	02 Months	350/-
12	R/R damages to Khajurna Bikram Bagh Suketi Kala amb road 0/0 to 15/0. (SH:- C/O wire crate R/Wall at Rd. 14/506 to 14/511.80)	96823/-	2000/-	02 Months	350/-
13	C/O L/R from Banethi to Dagjar Km. 0/0 to 6/500(SH:- Wing wall of 4mtr. Span RCC slab culvert at Rd. 4/200)	99460/-	2000/-	02 Months	350/-
14	C/O L/R from Banethi to Dagjar Km. 0/0 to 6/500(SH:- Tor Steel, Slab Culvert at Rd. 4/200)	98020/-	2000/-	02 Months	350/-
15	C/O L/R from Banethi to Dagjar Km. 0/0 to 6/500(SH:- RCC slab of 4mtr. Span slab culvert at Rd. 4/200)	99688/-	2000/-	02 Months	350/-

CERTIFICATE:- It is certified that the tenders of above works are of exigency/ emergent nature in public interest.

Terms & Conditions:-

- The Contractors/ Bidders must submit copy of their Permanent Income Tax Account Number/ GST Number/ EPF No. along with the application for tender.
- The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
- The Contractors/Firms should attach copy of the Registration/ Renewal with the

5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The tender documents shall be issued to only those contractors who do not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 Crore each or above.
7. The offer shall remain valid up to 75 days.
8. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW(B)A(3)1/2020 dated Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
9. The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reasons.


Executive Engineer,
Nahan Division,
HPPWD Nahan.

①

SCHEDULE OF QUANTITY

of work:-A/R & M/O Division office PWD at Nahan (SH :- Providing Almirah (Rack) in office and other misc. work).

Estimated Cost Rs.99665/-

Earnest money: Rs. 2000/-

Time:- One Month

Sub Head and item of work	Qty	Unit	Rate		Amount
			Figure	Words	
Steel work welded in built up sections, trusses and framed work , including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings, framed, guard bar, ladder, railings, brackets and similar works as directed by Engineer-in-Charge including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	3.30	Per Quintal	10000.00	Rs. Ten Thousand and Paise nil only	33000.00
Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge.	35.99	Per Square metre	1350.00	Rs. One Thousand Three Hundred Fifty & Paise Nil Only.	48587.00
Providing and fixing expandable fasteners of specified size with necessary plastic sleeves & galvanised mild steel screw including drilling holes in necessary work/ cement concrete/ reinforced cement concrete & making good etc complete 40 mm long including all leads lift, carriage of material & to the entire satisfaction of the Engineer-in-charge.	125	Each	25.40	Rs. Twenty Five & Paise Forty only	3175.00
Providing and fixing M.S. BP sheet 1.66mm one point sixty six millimetres) to 2mm (two millimetres) thick in eaves boards/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (base members of steel work shall be measured paid separately) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10.50	Per Square metre	1277.00	Rs. One Thousand Two Hundred Seventy seven and Paise Nil Only	13409.00
Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter With white readymixed paint including carriage of materials with in all leads, lifts and other incidentals charges complete as per entire satisfaction of the Engineer-in-charge.	14.99	Per Square metre	92.00	Rs. Ninety two and paise Nil only	1379.00
Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete. 125 mm	2.00	Each	57.55	Rs. Fifty Seven & Paise Fifty Five Only	115.00
					99665.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

e of work:-R/R damages to Sainwala Burma Papri Road Km 0/00 to 11/00 (SH:- C/O Wire crate R/Wall at RD 4/743 to 7.40 2nd and third step) (Balance work)

Estimated Cost Rs.98805/-			
Earnest money: Rs. 2000/-			
Time:- Two Months			
Sub Head and item of work	Qty	Unit	Rate
			Figure Words
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 & IS :4826 in 100mm x 100 mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 40 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.	33.34	Per Cubic Metre	2,963.55 Rs Two Thousand Nine Hundred Sixty Three & Paise Fifty Five Only.
Total:			98805.00

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
 Nahan Division,
 HP PWD, Nahan

SCHEDULE OF QUANTITY

Particulars of work:- R/R damages to Sainwala Burma Papri Road Km 0/00 to 11/00 (SH:- C/O Wire crate R/Wall at RD 4/738 to 11/50 (1/4 step) (Balance work)				Estimated Cost Rs. 51210/-	
				Earnest money: Rs. 1500/-	
				Time:- Two Months	
Sub Head and item of work	Qty	Unit	Rate	Figure	Words
				Figure	Words
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 & IS 4826 in 100mm x 100 mm mesh (waved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 40 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges	17.28	Per Cubic Metre		2,963.55	Rs. Two Thousand Nine Hundred Sixty Three & Paise Fifty Five Only.
Total:					
					51210.00
					51210.00

Quoted Rate in Figure (+/-) (.....%)
 Quoted Rate in Words (+/-) (.....%)

Condition :-
 Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
 Nahan Division,
 HP PWD, Nahan

SCHEDULE OF QUANTITY

Work:- R/R damages to Shambuwalla to Matter Bhedon road Km 0/0 to 7/120 (SH:- C/O Wire crate R/Wall at RD

2/235 towards Matter)

Estimated Cost Rs.96544/-			
Earnest money: Rs. 2000/-			
Time:- Two Months			
Sub Head and item of work	Qty	Unit	Rate
			Figure Words Amount
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	14.25	Per cubic metre	295.00 Rs. Two Hundred Ninety Five & Paise Nil only 4204.00
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 & IS :4826 in 100mm x 100 mm mesh (waved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 40 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.	32.40	Per Cubic Metre	2,850.00 Rs. Two Thousand Eight Hundred Fifty & Paise Nil Only. 92340.00
Total:			96544.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

Estimated Cost Rs.96544/-
Earnest money: Rs. 2000/-
Time:- Two Months

of work:-R/R damages to Shambuwalla to Matter Bhedon road Km 0/0 to 7/120 (SH:- C/O Wire crate R/Wall at RD to 2/265 towards Matter.)

Sub Head and item of work	Qty	Unit	Rate			Amount
			Figure	Words		
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	14.25	Per cubic metre	295.00	Rs. Two Hundred Ninety Five & Paise Nil only		4204.00
Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS :280 & IS :4826 in 100mm x 100 mm mesh (weaved diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 40 kg each as per drawings and technical specifications clause 1301 in all leads and lifts, including all incidental charges.	32.40	Per Cubic Metre	2,850.00	Rs. Two Thousand Eight Hundred Fifty & Paise Nil Only		92340.00
Total:						96544.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-
Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

ie of work: -R/R damage to Kaulanwala Bhood Panchyat at Nahan(SH :- Removal of slips)

				Estimated Cost Rs.97488/-	
				Earnest money: Rs. 2000/-	
				Time:- Two Months	
	Sub Head and item of work	Qty	Unit	Rate	
				Figure	Words
	Hiring of Excavator cum loader for formation cutting/excavation of earth work in all kinds of soil/removal of slips in all depths and heights including statrated soil and disposal of surplus oil with in all leads and lifts as per direction of the Engineer-in-Charge and making surface smooth including P.O.L. charges and other expences etc. also including carriage of machinery and labour upto all leads, lifts etc.	1218.60	Per cubic metre	80.00	Rs. Eighty & Paise Nil only
Total:					
					97488.00
					97488.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift
The contractor shall procure all the materials conforming to the specifications
of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

7

SCHEDULE OF QUANTITY

me of work:-R/R damage to Various road of Burma Papri Panchyat, Jangla bhood Ambulance road (SH :- Removal of
ps Km. 0/0 to 0/360)

				Estimated Cost Rs.99943/-		
				Earnest money: Rs. 2000/-		
				Time:- Two Months		
Sl. No.	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Hiring of Excavator cum loader for formation cutting/excavation of earth work in all kinds of soil/removal of slips in all depths and heights including saturated soil and disposal of surplus soil with in all leads and lifts as per direction of the Engineer-in-Charge and making surface smooth including P.O.L. charges and other expences etc. also including carriage of machinery and labour upto all leads. lifts etc.	1242.91	Per cubic metre	80.00	Rs. Eighty & Paise Nil only	99433.00
Total:						99433.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) {-----%}

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP PWD, Nahan

8

SCHEDULE OF QUANTITY
me of work:-R/R damage to Various road of Ambwala Sainwala Panchyat (SH :- Removal of Slips).

				Estimated Cost Rs.98868/-	
				Earnest money: Rs. 2000/-	
				Time:- Two Months	
Sl. No	Sub Head and item of work	Qty	Unit	Rate	
				Figure	Words
1	Hiring of Excavator cum loader for formation cutting/excavation of earth work in all kinds of soil/removal of slips in all depths and heights including saturated soil and disposal of surplus oil with in all leads and lifts as per direction of the Engineer-in-Charge and making surface smooth including P.O.L. charges and other expences etc. also including carriage of machinery and labour upto all leads, lifts etc.	1235.85	Per cubic metre	80.00	Rs Eighty & Paise Nil only
Total:					98868.00

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP.PWD, Nahan

SCHEDULE OF QUANTITY

e of work:- A/R & M/O various HPPWD Schemes in 12th Circle HPPWD Nahan: Distt. Sirmour H.P.(SH:- Binding of record files of 12th Circle Nahan) Phase-I

Sub Head and item of work				Estimated Cost Rs.99,750/- Earnest money: Rs.2,000/- Time:- Two Months		
	Qty	Unit		Rate		Amount
				Figure	Words	
Binding of office file record file with card board of both side of file, fixing binding cloth on one edge of the file and Abar paper on the face of the card board with proper adhesive material like fevicol glue etc. and sewing the file with double and hard thread of suitable size including labour of as to make it in good condition in all respect as per direction of Engineer-in-Charge with all leads and lifts.	399.00	Per each		250.00	Rs. Two hundred fifty & Paise nil only	99750.00
Total:						99750.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Terms & Condition :-

- 1 Work shall be carried out as per HPPWD Specifications and as per direction of Engineer Incharge
- 2 Security, Labour cess, income tax/GST shall be deducted as per norms
- 3 The site clearance will be done wherever required by the contractor at his own cost and nothing extra is payable on this account.
- 4 Nothing shall be paid for sub standard work/material.
- 5 The contractor shall be responsible for watch and ward of the material/office record file to him and in case of any theft/loss the recovery shall be imposed as per department regulation.

Executive Engineer
Nahan Division,
HP PWD, Nahan

SCHEDULE OF QUANTITY

Part of work:- A/R & M/O various HPPWD Schemes in 12th Circle HPPWD Nahan Distt. Sirmour H.P.(SH):- Binding of record files of 12th Circle Nahan) Phase-II

				Estimated Cost Rs.99,750/-	
				Earnest money: Rs.2,000/-	
				Time:- Two Months	
Sub Head and item of work	Qty	Unit		Figure	Words
				Rate	Amount
Binding of office file record file with card board of both side of file, fixing binding cloth on one edge of the file and Abary paper on the face of the card board with proper adhesive material like fevicol glue etc. and sewing the file with double and hard thread of suitable size including labour of as to make it in good condition in all respect as per direction of Engineer-in-Charge with all leads and lifts.	399.00	Per each		250.00	Rs. Two hundred fifty & Paise nil only
Total:					99750.00

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (.....%)

Terms & Condition :-

- 1 Work shall be carried out as per HPPWD Specifications and as per direction of Engineer Incharge
- 2 Security, Labour cess, income tax/GST shall be deducted as per norms
- 3 The site clearance will be done wherever required by the contractor at his own cost and nothing extra is payable on this account
- 4 Nothing shall be paid for sub standard work/material.
- 5 The contractor shall be responsible for watch and ward of the material/office record file to him and in case of any theft/or loss the recovery shall be imposed as per department regulation

Executive Engineer
 Nahan Division,
 HP PWD, Nahan

17

SCHEDULE OF QUANTITY

ie of Work:- R/R damages to Khajurna Bikram Bag Suketi Kala Amb Road 0/0 to 15/0. (SH:- C/o Wire Crate R/wall at 14/500 to 14/505.80)

				Estimated Cost Rs.96,823/- Earnest money: Rs.2,000/- Time:- Two Months		
o	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	20.94	Per Cubic metre	295.00	Rs. Two Hundred Ninety Five & Paise nil only	6177.00
	Providing and laying of builder apron laid in wire crates with 4 mm dia GI wire conforming to IS-280 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	31.32	Per Running metre	2850.00	Rs. Two Thousand Eight Hundred Fifty & Paise Nil Only	89262.00
	Construction of Embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5	14.04	Per Cubic metre	98.60	Rs. Ninty Eight & Paise Sixty Only	1384.00
	Total:					96823.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (-----%)

Terms & Condition :-

- 1 Work shall be carried out as per HPPWD Specifications and as per direction of Engineer Incharge
- 2 Security, Labour cess, income tax/GST shall be deducted as per norms
- 3 The site clearance will be done wherever required by the contractor at his own cost and nothing extra is payable on this account
- 4 Nothing shall be paid for sub standard work/material.
- 5 The contractor shall be responsible for watch and ward of the material/office record file to him and in case of any theft/loss the recovery shall be imposed as per department regulation


Executive Engineer
Nahan Division,
HP PWD, Nahan

12

SCHEDULE OF QUANTITY

of Work:- R/R damages to Khajurna Bikram Bag Suketi Kala Amb Road 0/0 to 15/0. (SH:- C/o Wire Crate R/wall at /506 to 14/511.80)

Sub Head and item of work				Estimated Cost Rs.96,823/- Earnest money: Rs.2,000/- Time:- Two Months		
	Qty	Unit		Rate		Amount
				Figure	Words	
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	20.94	Per Cubic metre		295 00	Rs. Two Hundred Ninety Five & Paise nil only	6177.00
Providing and laying of builder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	31.32	Per Running metre		2850 00	Rs. Two Thousand Eight Hundred Fifty & Paise Nil Only	89262.00
Construction of Embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5	14.04	Per Cubic metre		98 60	Rs. Ninety Eight & Paise Sixty Only	1384.00
Total:						96823.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Terms & Condition :-

- 1 Work shall be carried out as per HPPWD Specifications and as per direction of Engineer Incharge
- 2 Security, Labour cess, income tax/GST shall be deducted as per norms
- 3 The site clearance will be done wherever required by the contractor at his own cost and nothing extra is payable on this account.
- 4 Nothing shall be paid for sub standard work/material.
- 5 The contractor shall be responsible for watch and ward of the material/office record file to him and in case of any theft/or loss the recovery shall be imposed as per department regulation.


Executive Engineer
Nahan Division,
HP, PWD, Nahan

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Banethi to Dagjar Km 0/0 to 6/500(SH :- Wing Wall of 4 mtr Span RCC Slab Culvert at RD 4/200)					Estimated Cost Rs.99,460/- Earnest Money: Rs.2000/- only Time:- Two Months		
Sr.No	Sub Head and item of work	Qty	Unit	Rate		Amount	
				Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge	14.19	Per cubic metre	300.00	Rs. Three Hundred & Paise Nil Only	4257.00	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specification Clause 802,803,1202 & 1203 nominal mix C.C 1:4:8 (One cement : four sand : eight crushed stone aggregate) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	21.00	Per Cubic Metre	4,261.30	Rs. Four Thousand Two Hundred Sixty One & Paise Thirty Only.	89487.00	
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material as per HPPWD specification 1990 of Volume-1 (one) including carriage of all labour equipment & material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-charge	2.52	Per cubic metre	1149.04	Rs. One thousand one hundred forty nine & Paise four only	2896.00	
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204.3.7, including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	10	Each	282.00	Rs. Two Hundred Eighty Two & Paise Nil Only	2820.00	
Total:						99460.00	

Quoted Rate in Figure(+/-) (.....%)

Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Nahan Division,
HP PWD, Nahan

13

147

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Banethi to Dagjar Km 0/0 to 6/500(SH :- Tor Steel, Slab Culvert at RD 4/200)

Name of work:- C/O Link road from Banethi to Dagjar Km 0/0 to 6/500(SH :- Tor Steel, Slab Culvert at RD 4/200)				Estimated Cost Rs.98,020/-		
				Earnest Money: Rs.2000/- only		
				Time:- Two Months		
Sr.N	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	Supplying fitting and placing TMT bar reinforcement in superstructure complete as per drawing and technical specification clauses 1002, 1010 and 1202 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge	1.30	Per Tonne	75,400.00	Rs. Seventy Five Thousand Four Hundred & Paise Nil Only.	98020.00
Total:						98020.00

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Nahan Division,
HP PWD, Nahan

15

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Banethi to Dagjar Km 0/0 to 6/500(SH :- RCC Slab of 4 mtr span slab culvert at RD 4/200)					Estimated Cost Rs.99,688/-		
					Earnest Money: Rs.2000/- only		
					Time:- Two Months		
Sr. No	Sub Head and item of work	Qty	Unit		Rate		Amount
					Figure	Words	
1	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specification clauses 800, 1205.4 and 1205.5 RCC M 25 (1:1.5:3) upto 5m Height including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	14.66	Per Cubic Metre		6,800.00	Rs. Six Thousand Eight Hundred & Paise Nil Only.	99688.00
Total:							99688.00

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost

Executive Engineer
 Nahar Division,
 HP.PWD, Nahar