

Himachal Pradesh
Public Works Department.

Through mail

No. PWH/HD/CB/T-I/2024-25
To

8955-57

Dated: - 27.02.2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - **Publication of Notice inviting tender.**

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,
HPPWD Division Haroli,
Distt.Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-


1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,
HPPWD Division Haroli,
Distt.Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-25-8955-57 dated 27.02.2025 are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
HPPWD Division, Una,
Distt (Una HP).



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 05.03.2025 up to 10.30 (Non).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 06.03.2025 up to 3.00 PM
3. Date of receipt of tenders: - 07.03.2025 up to 10.30 AM
4. Date of opening of tenders: - 07.03.2025 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	Construction of boundary wall at PM Shri GUSSS Kangar Distt.Una (SH: C/o Boundary wall) Deposit work Phase-V	99,467/-	2000/-	One month	350/-	Class- C & D
2	Painting of ITI Pubowal building Tehsil Haroli Distt.Una (SH: Painting work to old building) Phase-IV		2000/-	One Month	350/-	Class- C & D
3	C/o link road Nangal Khurd mohalla Thai Lower Manuwal Km 0/0 to 1/00 (SH: C/o Retaining wall at RD 0/660 to 0/672 RHS) near GSSS Nangal Khurd Deposit work	98,987/-	2000/-	One Month	350/-	Class- C & D
4	C/o Gramin Sampark from the H/o Sh.Sanjeev Kumar to Tahlilwal road via H/o Sh.Davinder Singh to Madya Marg WNO.2 GP Palkwah (SH: C/o CC pavement RD 0/256 to 0/281) under MMSY Balance work	99,971/-	2000/-	One month	350/-	Class- C & D
5	C/o Gramin Sampark alongwith R/wall from the H/o Sh.Ram Krishan to the H/o Sh.Ramesh GP Badhera (SH: C/o R/wall RD 0/010 to 0/014.45) under MMSY Balance work	99,703/-	2000/-	One Month	350/-	Class- C & D
6	A/R & M/O on link road Sarubag to Pandoga Km 0/0 to 2/640 (SH: C/o Retaining wall at RD 2/086.70 to 2/109.00 LHS)	99,003/-	2000/-	One month	350/-	Class- C & D
7	C/o Gramin Sampark from the house of Smt. Miondo Devi to Poultry farm of Sh.,Dalvir Singh WNo.4 GP Bathri (SH: P/L paver block RD 0/254 to 0/278)m under MMSY (Balance work)	99,410/-	2000/-	One Month	350/-	Class- C & D
8	A/R & M/O Non building Rest House HPPWD Haroli (SH: P/L 60mm thick interlocking paver in back side of building)	99,238/-	2000/-	One month	350/-	Class- C & D
9	A/R & M/O on link road to harijan basti Kuthar Beet Km 0/0 to 3/400 (SH: C/o CC pavement RD 0/490 to 0/506)	98,535/-	2000/-	One Month	350/-	Class- C & D
10	A/R & M/O PWD Non PWD Residentail building at Haroli (SH: P/F All in one HP-PC with 15.12h Gen Processor 8 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-87500D) in Junior Engineer	98,300/-	2000/-	One month	350/-	Class- C & D

	Section office at Laluwal under Tahliwal Sub Division					
11	C/o Gramin Sampark from the house of Smt. Miondo Devi to Poultry farm of Sh. Dalvir Singh WNo.4 GP Bathri (SH: P/L paver block RD 0/230 to 0/254)m under MMSY (Balance work	99,565/-	2000/-	One Month	350/-	Class- C & D
12	Restoration work of link road from main road upto community Centre WNo.7 GP Heeran Thara (SH: C/o edge wall at RD 0/068 to 0/080.20)	99,808/-	2000/-	One Month	350/-	Class- C & D
13	C/o link road Nangal Khurd mohalla Thai Lower Manuwal Km 0/0 to 1/00 (SH: C/o Retaining wall at RD 0/648 to 0/660 RHS) near GSSS Nangal Khurd Deposit work	99,137/-	2000/-	One Month	350/-	Class- C & D
14	C/o Gramin Sampark alongwith R/wall from the H/o Sh.Ram Krishan to the H/o Sh.Ramesh GP Badhera (SH: C/o R/wall RD 0/024 to 0/028) under MMSY Balance work	82,204/-	2000/-	One month	350/-	Class- C & D
15	C/o Model Health Research Centre at Haroli Distt Una (SH: P/S Revolving Chairs for Conference Hall) Deposit work	96,600/-	2000/-	One Month	350/-	Class- C & D
16	Restoration work for link road from main road upto community centre WNo.7 GP Heeran Thara (SH: C/o edge wall at RD 0/080.20 to 0/092.40)	99,728/-	2000/-	One Month	350/-	Class- C & D
17	A/R & M/O on link road Sarubag to Pandoga Km 0/0 to 2/640 (SH: C/o Retaining wall at RD 2/070.20 to 2/086.70 & CC in berm RD 2/050 to 2/080 LHS)	99,242/-	2000/-	One Month	350/-	Class- C & D
18	C/o Gramin Sampark from the H/o Sh.Sanjeev Kumar to Tahliwal road via H/o Sh.Davinder Singh to Madya Marg WNO.2 GP Palkwah (SH: C/o CC pavement RD 0/281 to 0/305) under MMSY Balance work	99,831/-	2000/-	One month	350/-	Class- C & D
19	Construction of boundary wall at PM Shri GUSSS Kangar DisttUna (SH: C/o Boundary wall) Deposit work Phase-III	99,574/-	2000/-	One Month	350/-	Class- C & D
20	Balance work for the C/o road from link road to Sati Mata Mandir GP Hiran Nagar (SH: C/o CC Pavement RD 0/234 to 0/256) under MMSY	99789	2000/-	One Month	350/-	Class- C & D
21	C/o Gramin Sampark alongwith R/wall from the H/o Sh.Ram Krishan to the H/o Sh.Ramesh GP Badhera (SH: C/o R/wall RD 0/015 to 0/019.45) under MMSY Balance work	99,532/-	2000/-	One Month	350/-	Class- C & D
22	A/R & M/O on link road from Umrli to Dulehar via Gahua Km 0/0 to 3/200 (SH: C/o Retaining wall at RD 0/870 to 0/899.50 LHS)	99,441/-	2000/-	One Month	350/-	Class- C & D
23	C/o link road Nangal Khurd mohalla Thai Lower Manuwal Km 0/0 to 1/00 (SH: C/o Retaining wall at RD 0/636 to 0/648 RHS) near GSSS Nangal Khurd Deposit work	99,287/-	2000/-	One month	350/-	Class- C & D
24	Construction of boundary wall at PM Shri GUSSS Kangar DisttUna (SH: C/o Boundary wall) Deposit work Phase-IV	99,542/-	2000/-	One Month	350/-	Class- C & D
25	Restoration of rain damages on Panjavar Bathri to Lalhri Kungrat Dhillwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/460 to 1/490)	99,920/-	2000/-	One Month	350/-	Class- C & D

26	A/R & M/O PWD Non PWD Residentail building at Haroli (SH: P/F All in one HP-PC with 15.12h Gen Processor 8 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-87500D) in Junior Engineer Section office at Laluwal under Tahliwal Sub Division	98,300/-	2000/-	One month	350/-	Class- C & D
27	C/o Gramin Sampark alongwith R/wall from the H/o Sh.Ram Krishan to the H/o Sh.Ramesh GP Badhera (SH: C/o R/wall RD 0/020 to 0/024.45) under MMSY Balance work	99,557/-	2000/-	One Month	350/-	Class- C & D
28	Restoration work of link road from main road upto community Centre WNo.7 GP Heeran Thara (SH: C/o edge wall at RD 0/111 to 0/143)	99,200/-	2000/-	One Month	350/-	Class- C & D
29	Construction of boundary wall at PM Shri GUSSS Kangar Distt.Una (SH: C/o Boundary wall) Deposit work Phase-II	99,638/-	2000/-	One Month	350/-	Class- C & D
30	A/R & M/O Panjavar Bathri road Km 0/0 to 34/00 (SH: Maintenance of earthen shoulder at RD 18/00 to 20/500)	99,268/-	2000/-	One Month	350/-	Class- C & D
31	A/R & M/O link road to village Nagnoli Km 0/0 to 5/560 (SH: C/o Toe wall for U-shape drain at RD 0/160 to 0/180 LHSD(Balance work)	99,834/-	2000/-	One month	350/-	Class- C & D
32	Balance work for the C/o road from link road to Sati Mata Mandir GP Hiran Nagar (SH: C/o CC Pavement RD 0/256 to 0/278) under MMSY	99727	2000/-	One Month	350/-	Class- C & D
33	Balance work for C/o Gramin Sampark to the House of Sh.Ram Lal S/o Sh.Tarsem Lal WNo.2 GP Beetan (SH: C/o CC pavement at RD 0/094 to 0/108) under MMSY	99458	2000/-	One Month	350/-	Class- C & D
34	A/R & M/O on link road from Umruli to Dulchar via Gahua Km 0/0 to 3/200 (SH: C/o Retaining wall at RD 1/800 to 1/829.40 LHS)	99,104/-	2000/-	One Month	350/-	Class- C & D
35	Restoration work of link road from main road upto community Centre WNo.7 GP Heeran Thara (SH: C/o edge wall at RD 0/099 to 0/111)	99,403/-	2000/-	One Month	350/-	Class- C & D
36	A/R & M/O link road to village Nagnoli Km 0/0 to 5/560 (SH: C/o Toe wall for U-shape drain at RD 0/080 to 0/122 LHS (Balance work)	99,624/-	2000/-	One month	350/-	Class- C & D
37	Restoration of rain damages on Panjavar Bathri to Lalhri Kungrat Dhillwan road Km 0/0 to 5/500 (SH: C/o U-shape drain in Km 1/430 to 1/460)	99,921/-	2000/-	One Month	350/-	Class- C & D
48	Balance work for the C/o road from link road to Sati Mata Mandir GP Hiran Nagar (SH: C/o CC Pavement RD 0/278 to 0/300) under MMSY	99661/-	2000/-	One Month	350/-	Class- C & D
39	Restoration work of link road from main road upto community Centre WNo.7 GP Heeran Thara (SH: C/o edge wall at RD 0/143 to 0/175)	99110/-	2000/-	One Month	350/-	Class- C & D
40	Construction of boundary wall at PM Shri GUSSS Kangar Distt.Una (SH: C/o Boundary wall) Deposit work Phase-I	99,655/-	2000/-	One month	350/-	Class- C & D
41	A/R & M/O PWD Non PWD Residentail building at Haroli (SH: P/F All in one HP-PC with 15.12h Gen Processor 8 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-87500D) in Surveyor room	98,300/-	2000/-	One month	350/-	Class- C & D

office at newly created Khad Sub Division Division Office)					
---	--	--	--	--	--

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh.

SCHEDULE OF QUANTITY

Estimated cost 99467

Earnest money 2000

Time limit One month

Name of work: Construction of boundary wall at PM Shri GUSS Kangar Distt Una (C/O boundary wall)- phase-V (D/work)

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.39	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (one Cement : three coarse sand) : six graded crushed stone aggregate 20 mm (twenty millimeter) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.00	Per cubic metre			
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty five millimeter) size so as to give a fair finish including centering shuttering and propping etcetera with wooden battens and battens for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	28.06	Per square metre			
5	Providing and laying damp proof course 30mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand four graded crushed stone aggregate 12.5mm (twelve point five millimeter) nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
6	Applying a coat of hot bitumen (mexphalt 80/100 (eighty/hundred) or equivalent using 1.70 kg (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
7	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level (height in all shapes and size cement mortar 1:6) (one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.50	Per cubic metre			

537

8	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm/ eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.54	Per square metre		
9	Providing and laying cement concrete work grade M-20(M-twenty twenty) in retaining walls, return walls, walls(any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, fillets, sunken floor etc. upto floor all level and curing curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.20	Per cubic metre		
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.57	Per Square metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)A(3)17/2020 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B) A(3)17/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 17/2020-1 dated 7.10.2021			Total	0

Executive Engineer
Haroli Division
HP PWD, Haroli

537

SCHEDULE OF QUANTITY

Estimated Cost
20000-
Earnest Money
Time limit
One month

Name of work :- Painting of ITI Pubowal building Tehsil Haroli Distt Una (Sh: Painting work to old building)- Phase-IV

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Removal of old paint by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches, complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	524.60	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	170.40	Per Square metre			
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coats including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	524.60	Per Square metre			
4	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade One or more coats on old work including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	429.74	Per Square metre			
5	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coats applied @ 1.67 lit/10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	190.40	Per Square metre			0
	Total					

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PWS/H/5412/2021 dated 7.8.2018
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PWS/H/5412/2020 dated 22.07.20

Executive Engineer
Haroli Distt Una
Haryana

522

(3)

Draft Schedule of quantity

Name of work : Name of Work:- C/O of link road Nanjal Khurd Mohalla Thal Lower Mannuwar 11 km. 0/00 to 0/01						
S/N						
DESCRIPTION						
S NO	DESCRIPTION	Qty	Unit	T Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.45	Cum.			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.65	Cum.			
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.00	nos			
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.76	Cum.			
Total						

Note: All type of material shall be arranged by the contractor vide Notification by Additional Secy to Govt. of HP vide letter No. P&W (B) 1771/202012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

(S 19)

SCHEDULE OF QUANTITY

Estimated cost 99971

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark from the H/O Sh Sanjeev Kumar to Tahliwal road via H/O Sh Davinder Singh to Madya Marg ward No -2 G.P. Palkwah (SH: C/O C.C. pavement RD 0/256 to 0/281)-under MMGOY (Balance work)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP.PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	24.30	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	6.08	Per cubic metre			

3	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.98	Per cubic metre		
4	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads, and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	12.02	Per cubic metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)X(17)20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			G.Total	0


 Executive Engineer
 Haroli Division
 HP,PWD,,Haroli

SCHEDULE OF QUANTITY

Estimated cost 99703

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark alongwith R/wall from the H/O Sh. Ram Krishan to the H/O Sh. Ramesh G.P. Badehra (SH: C/O R/wall RD 0/010 to 0/014.45)- Under MMSY (Balance work)

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and raiming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax sale tax, GST labour cess or other taxes imposed by the Government.	6.23	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm) (forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkhana, toll tax sale tax, GST labour cess or other taxes imposed by the Government.	29.30	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100mm/hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 814, 709, 1204 3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	10.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	3.42	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. HPW(B)/17/20212 dated 7.8.2018				G.Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No. HPW(B) A(3) 1/2020 dated 22.7.2020 & Govt. of HP vide letter No. HPW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HPWD

526

6

HP & W.D. Draft Schedule of quantity

Name of work:- Restoration of rain damages on link road Saruabag to Pandoga km. 0/00 to 2/640

[SH: C/O Retaining wall at Rd. 2/086.70 to 2/109.00 Lhs.]

		Estimated Cost: Rs		One month	
		Time:-		2000	
		Earnest Money:-		Amount	
S.NO	DESCRIPTION	Qty	Unit	T Rate	Rate in words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.27	Cum.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.38	Cum.		
3	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.70	Cum.		
Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) 10 (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division
Distt. Una (H.P.)

SA

SCHEDULE OF QUANTITY

Estimated cost 99410

Earnest money 2000

Time limit One month

Name of Work: C/O Gramin Sampark from the house of Smt. Mindo Devi to th Poultry farm of Sh. Dalvir Singh Ward No 4
G.P. Eathil (SH; P/L paver block RD 8234 8238) Under MMSY (Balance work)

S. No.	Description of work	Quantity	Unit	Rates		Amount (in. Rs.)
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP PWD, technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	20.12	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.38	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.18	Per cubic metre			

4	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	72.00	Per square metre			
5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement, two sand, four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.64	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020-1 dated 7.8.2021 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021				G.Total	0


 Executive Engineer
 Haroli Division
 HP.PWD., Haroli

Schedule of quantity

Name of work : A/R & M/O Non Building Rest house HPPWD at Haroli.					Estimated Cost: Rs	
(Sh. P/I 60mm thick interlocking paver in back side of building)					One month 2000	
S NO	DESCRIPTION	Qty	Unit	T Rate	Earnest Money:- Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all loads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, 30% tax, GST, labour cess or other taxes imposed by the Government.	23.48	cum			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 202 & 203 P.C.C. grade M 10 Nominal Mix 1 : 1.5 : 8 including carriage of materials within all loads and lifts and other incidentals. The rate is including of octroi, royalty, Malikana, toll tax, sale tax or other taxes imposed by the Government.	7.83	cum			
3	Providing and laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 including carriage of materials within all loads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, 30% tax, GST, labour cess or other taxes imposed by the Government.	78.28	cum			
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 202 & 203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all loads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, 30% tax, GST, labour cess or other taxes imposed by the Government.	1.65	sqm			
	Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) 117/2/2012 dated 07.08.2018

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

428

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on link road to harijan basti Kuthar Beet Km 0/00 to 3/400 (SH: C/O C.C. pavement RD 0/490 to 0/506) Estimated Cost 98535
 Earnest Money 2000/-
 Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling (wedging out rocks) (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etc. as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty mukhiana Jol tax, GST labour cess or other taxes imposed by the Government.	2.95	Per cubic metre			
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty mukhiana Jol tax, GST labour cess or other taxes imposed by the Government.	8.36	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundations for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed broken stone aggregate 20mm (twenty millimeter) nominal size in or under water or ground complete including pumping or baling out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty mukhiana Jol tax, GST labour cess or other taxes imposed by the Government.	10.62	Per cubic metre			
4	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain reinforced concrete in open foundations for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilograms) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/depths including the cost of form work with steel plates as per drawings and technical specification MCHQ 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty mukhiana Jol tax, GST labour cess or other taxes imposed by the Government.	9.84	Per cubic metre			
					Total:	0

Executive Engineer
 Haroli Division
 HPPWD

556

Schedule of quantity

Name of work:- A/R & M/O PWD Non PWD Residential building at Haroli (SH: P/F All in one HP-PC with 15. 12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-87500D) in Junior Engineer Section office at <u>Laluwal</u> under Tahliwal Sub Division.					Estimated Cost: Rs	
					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing commercial) All in one HP make computer system with inspron 24 Intel i5.12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & Window 11/12 Wi, fi, & Bluetooth 4.0 M.2/keyboard & optical mouse (3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
2	Providing and fixing Intex UPS 600 VA Gamma including entire camage of maternal within all leads and lifts and other incidentals and as per the direction by the Engineer-in charge. The rates are inclusive octroi, royalty malkana, toll tax sale tax, GST labour cess or other taxes imposed by the Government	1.00	Each			

456

3	Providing and fixing Brother printer DCP-87500D including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octori royalty.malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each			
	Total					

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

2) The rates shall be including of all types of taxes including GST etcetra)

4 B

456

SCHEDULE OF QUANTITY

Name of Work: C/O Gramin Sampark from the house of Smt. Mindo Devi to th Poultry farm of Sh. Dalvir Singh Ward No 4
G.P. Bathri (SH: P/L paver block RD 0/230 to 0/254)- Under MMSY (Balance work)

Estimated cost 99565
Earnest money 2000
Time limit One month

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, or other taxes imposed by the Government.	21.60	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.40	Per cubic metre			

3	Providing and laying cement concrete 1:4:8 (one cement, four sand, eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.20	Per cubic metre			
4	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	72.00	Per square metre			
5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement, two sand, four graded crushed / broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.64	Per cubic metre			
					G.Total	0
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/Q/17/2021 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP.PWD., Haroli

(12)

SCHEDULE OF QUANTITY

Estimated Cost 99808
Earnest Money 2000/-
Time limit One month

Name of work: Restoration work for link road from Main road upto Community Centre ward No 7 G.P. Heeran Thara (SH: C/O edge wall at RD

0/068 to 0/080.20)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.32	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement: three sand: six graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	25.62	Per cubic metre			
					Total:	0
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(C)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)(A)(31)/2020 dated 22.07.20					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

S.S.

Draft Schedule of quantity

Name of work : Name of Work:- C/O of link road Nangal Khurd Mohalla Thal Lower Mannuwal km. 0/00 to km. 0/00 to					Estimated Cost: Rs.	₹ 99,137
1/00. (SH) C/O Retaining wall at Rd. 0/648 to 0/660 Rhs. - GSS Near Mangal Khurd - 0/660					Time:-	One month
S NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lease of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.45	Cum.			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.65	Cum.			
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.00	nos			
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.76	Cum.			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. 199W (a) D (17) 2/02012 dated 07.08.2018.

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

520

SCHEDULE OF QUANTITY

Estimated cost 82204

Earnest money 1600

Time limit One month

Name of Work: C/O Gramin Sampark alongwith R/wall from the H/O Sh. Ram Krishan to the H/O Sh. Ramesh G.P. Badohra (SH: C/O R/wall RD 0024 to 0028)- Under MMSY (Balance work)

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. Lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax sale tax, GST labour cess or other taxes imposed by the Government.	4.90	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm, forty millimeter nominal size), mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	23.90	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	12.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	3.20	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/A(3)/17/2020 dated 7.8.2018				G. Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B)/A(3)/17/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B)/A(3)/17/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP PWD, Haroli

525

15

Phase-IV

Schedule of quantity

Name of work:- C/O Model Health Research Centre at Haroli Tehsil Haroli Distt. Una .					Estimated Cost: Rs	₹ 96,600
(SH:- Providing and supply Revolving Chairs for Confrence Hall)- Deposit work					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and Supplying Revolving Chair heavy hydraulic Tilting, place chrome base with adjustable handle including carriage of material within all lead and lifts and other incidental. The rate includes sale tax, octroi,royalty,malkhana, toll tax, GST labour cess or other taxes imposed bythe Government.	7.00	Each		*	
Total						
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PSW (B) © (17) 2/02012 dated 07.08.2018						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated Cost 99728
Earnest Money 2000/-
Time limit One month

Name of work: Restoration work for link road from Main road upto Community Centre ward No 7 G.P. Heeran Thara (SH: C/O edge wall at RD 0/080.20 to 0/092.40)

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax sale tax, GST labour cess or other taxes imposed by the Government.	7.30	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	25.60	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/EC(17)/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/2020 dated 22.07.20				Total:	0

Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Eng. (H.P.)

SS3

Schedule of quantity

Name of work:- Repair and widening of road on link road Saruabag to Pandoga km. 0/00 to 2/640		Estimated Cost: Rs		₹ 99,242	
(SH: C/O Retaining wall at Rd. 2/070.20 to 2/086.70 & CC in berm Rd 2/050 to 2/080 Lhs.)		Time:-		One month	
S. NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.08	Cum.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Cum.		
3	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.92	Cum.		
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.75	Cum.		
Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) 10 11/71 2/02012 dated 07.08.2018

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

S28

SCHEDULE OF QUANTITY

Estimated cost 99831
 Earnest money 2000
 Time limit One month

Name of Work: C/O Gramin Sampark from the H/O Sh Sanjeev Kumar to Tahlwal road via H/O Sh Davinder Singh to Madya Marg ward No -2 G.P. Palkwah (SH: C/O C.C. pavement RD 0/281 to 0/305)-under MMESY (Balance work)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Loosening of the ground upto a level of 300mm(three hundred millimetre) below the sub grade level, watered graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub grade construction as per technical specification clause 303.5.2 as per drawing and HP.PWD., technical specification clause 303.5.2 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	24.10	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.08	Per cubic metre			

3	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.94	Per cubic metre		
4	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.02	Per cubic metre		
				G.Total	0
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)X(17)20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021				


 Executive Engineer
 Haroli Division
 HP.PWD., Haroli

SCHEDULE OF QUANTITY

Estimated cost 99574

Earnest money 2000

Time limit One month

Name of work: Construction of boundary wall at PM Shri GUSS Kangar Distt Una (C/O boundary wall)- phase-III (D/work)

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	Figures	Words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	1.39	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand: six graded crushed stone aggregate 20 mm/ twenty millimeter) (twenty millimeter) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST labour cess or other taxes imposed by the Government.	7.01	Per cubic metre			
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	28.06	Per square metre			
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand four graded crushed stone aggregate 12.5mm (twelve point five millimeter nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	3.51	Per square metre			
6	Applying a coat of hot bitumen (mexghait 60/100 (eighty/hundred) or equivalent using 1.70 kg (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	3.51	Per square metre			
7	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level height in all shapes and size cement mortar 1:6 (one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	6.51	Per cubic metre			

535

8	15mm (fifteen millimetre)/cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor levels/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.54	Per square metre		
9	Providing and laying cement concrete work grade M-20 (M-twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, fillets, sunken floor etc. upto floor all level and curing curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.20	Per cubic metre		
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.57	Per Square metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/C/17/20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No. PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021			Total	0

Executive Engineer
Haroli Division
HP.PWD, Hq.

535

SCHEDULE OF QUANTITY

Estimated cost 99789
Earnest money 2000
Time limit One month

Name of Work: Balance work for the C/O road from link road to Sati Mata Mandir G.P. Hiran Nagar (SH: C/O C.C. pavement RD 0/234 to 0/256)-under MMSY						
S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150mm and disposal of scarified material within all lift and lead as per technical specification 301.4 as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	80.00	Per square metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	5.96	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm/forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	11.82	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018				G. Total	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3)1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP PWD, Haroli

546

SCHEDULE OF QUANTITY

Name of Work: C/O Gramin Sampark alongwith R/wall from the H/O Sh. Ram Krishan to the H/O Sh Ramesh G.P. Badehra (SH: C/O R/wall RD 0015 to 0019.45)- Under MMSY (Balance work)

Estimated cost 99532
 Earnest money 2000
 Time limit One month

S. No.	Description of work.	Quantity	Unit	Rate (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax sale tax, GST labour cess or other taxes imposed by the Government.	6.23	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm) (forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	29.30	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malikana, toll tax, GST labour cess or other taxes imposed by the Government.	9.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST labour cess or other taxes imposed by the Government.	3.40	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/C(17/20212 dated 7.8.2018				G.Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)/12020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)/ 12020-1 dated 7.10.2021					

Executive Engineer
 Haroli Division
 HP PWD, Haroli

523

Schedule of quantity

Name of work:- A/R & M/O on link road from Umralli to Dulehar via Goua km. km. 0/00 to 3/200					
(SH: C/O Retaining wall at Rd. 0/870 to 0/899.50 Lhs)					
Estimated Cost: Rs					
Time:-					
One month					
2000					
Amount					
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.80	Cum.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.02	Cum.		
Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.W.D. Division, Haroli
Distt. Una (H.P.)

Draft Schedule of quantity

Name of work: C/O of link road Nangal Khurd Mohalla Thal Lower Mannuwal near GSSS Nangal Khurd km. D/00 to 100					Estimated Cost: Rs		₹ 99,287
1/00.					Time:-		One month
(SH: C/O Retaining wall at Rd. 0/536 to 0/648 Rhs)					Earnest Money:-		2000
S NO	DESCRIPTION	Qty	Unit	T Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.45	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10. Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.65	Cum.				
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.00	nos				
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.76	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Sery to the Govt. of HP vide letter No. PBW (B) 10 (17) 2/2021.2 dated 07/08/2018

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

S21

SCHEDULE OF QUANTITY

Estimated cost 99542

Earnest money 2000

Time limit One month

Name of work: Construction of boundary wall at PM Shri GUSS Kangar Distt Una (C/O boundary wall)- phase-IV (D/work)

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
2	Providing and laying cement concrete 1:4:6 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.38	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement : three coarse sand) six graded crushed stone aggregate 20 mm/ twenty millimeter) (twenty millimeter) nominal size) as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.01	Per cubic metre			
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and batties for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	28.06	Per square metre			
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand four graded crushed stone aggregate 12.5mm (twelve point five millimeter nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
6	Applying a coat of hot bitumen (mexphalt 80/100(eighty/hundred) or equivalent using 1.70 kg (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
7	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level height in all shapes and size cement mortar 1:6 (one cement, six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.51	Per cubic metre			

S36

9	Providing and laying cement concrete work grade M-20 (Twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, fillets, sunken floor etc. upto floor all level and curing curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	Per square metre	49.54		
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	0.20		
		Per Square metre	49.57		
			Total		
					0

Executive Engineer
Haroli Division
HP.PWD, Haroli

536

SCHEDULE OF QUANTITY									
Sl. No.	Description of work	Quantity	Unit	RATE		Estimated Cost	99920/-		
				Figures	Words				
								In	
									Time limit
Name of work : Restoration of rain damages on Panjajwar Bathri to Lalhri Kungrat Dhillwan road km.0/0 to 5/500 (SH: C/O U-shape drain in km. 1/460 to 1/490)							2000/-	One month	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malikana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	12.00	Per cubic metre						
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana ,toll tax,sale tax,GST ,labour cess or other taxes imposed by the Government.	7.30	Per cubic metre						
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	20.70	Per cubic metre						
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana ,toll tax,sale tax,GST ,labour cess or other taxes imposed by the Government.	1.20	Per Cubic metre						
5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana ,toll tax,sale tax,GST ,labour cess or other taxes imposed by the Government.	71.74	Per Kilogramme						

6	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm(two hundred millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malkana ,toll tax, GST, labour cess or other taxes imposed by the Government.	7.50	Per Running metre	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)dc(17)2/0212 dated 7.8.2018			
	2) The rates shall be including of all types of taxes including GST etcetra)			
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

Schedule of quantity

Name of work:- A/R & M/O PWD Non PWD Residential building at Haroli (SH: P/F All in one HP-PC with 15. 12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-87500D) in Junior Engineer Room at Tahliwal Sub Division office.					Estimated Cost: Rs	
					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing commercial) All in one HP make computer system with inspron 24 Intel i5.12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & Window 11/12 Wi, fi, & Bluetooth 4.0 M.2/keyboard & optical mouse (3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
2	Providing and fixing Intex UPS 600 VA Gamma including entire camage of maternal within all leads and lifts and other incidentals and as per the direction by the Engineer-in charge. The rates are inclusive octroi, royalty malkana, toll tax sale tax, GST labour cess or other taxes imposed by the Government	1.00	Each			

457

3	Providing and fixing Brother printer DCP-87500D including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octori royalty.malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each		
	Total				

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

2) The rates shall be including of all types of taxes including GST etetra)

[Handwritten signature]
[Handwritten initials]

457

SCHEDULE OF QUANTITY

Estimated cost 99557
 Earnest money 2000
 Time limit One month
 Name of Work: C/O Gramin Sampark alongwith R/wall from the H/O Sh. Ram Krishan to the H/O Sh. Ramesh G.P. Badehra (SH: C/O R/wall RD 0/020 to 0/024.45)- Under MMSY (Balance work)

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana toll tax sale tax GST labour cess or other taxes imposed by the Government.	6.20	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded crushed stone aggregate 40mm/forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana toll tax sale tax GST labour cess or other taxes imposed by the Government.	29.26	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malikana toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malikana toll tax, GST, labour cess or other taxes imposed by the Government.	3.40	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/17/20212 dated 7.8.2018				G.Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No. PBW(B)/A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B)/A(3)/1/2020-1 dated 7.10.2021					

Executive Engineer
 Haroli Division
 HP PWD, Haroli

524

SCHEDULE OF QUANTITY

Name of work: Restoration work for link road from Main road upto Community Centre ward No 7 G.P. Heeran Thara (SH: P/L paver block at RD 0/111 to 0/143)

Estimated Cost 99200
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all loads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	102.40	Per square metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundations for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement, two sand, four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all loads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	3.84	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/C(17)2/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)/A(3)1/2020 dated 22.07.20					

954

Executive Engineer,
M.P.P.W.D. Division Harohi
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99638

Earnest money 2000

Time limit One month

Name of work: Construction of boundary wall at PM Shri GUSS Kangar Distt Una (C/O boundary wall)- phase-II (D/work)

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	1.40	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level: 1:3:6 (one Cement: three coarse sand): six graded crushed stone aggregate 20 mm (twenty millimeter) (twenty millimeter) nominal size as directed by Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering and propping etcetera with wooden battens and battens for all heights of propping and centering below supporting floor to ceiling and removal of the same for extra reinforcement and plain concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	28.04	Per square metre			
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand four graded crushed stone aggregate 12.5mm (twelve point five millimeter nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	3.51	Per square metre			
6	Applying a coat of hot bitumen (mexphalt 80/100 (eighty/hundred) or equivalent using 170 kg (one point seventy kilogram) per square meter on damp proof course after clearing the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	3.51	Per square metre			
7	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level height in all shapes and size cement mortar 1:6 (one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	6.51	Per cubic metre			

539

8	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arisises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all loads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.54	Per square metre			
9	Providing and laying cement concrete work grade M-20 (M-twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, sills or facing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, fillets, sunken floor etc. upto floor all level and curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all loads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.20	Per cubic metre			
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all loads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.56	Per Square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/A(3)/17/2020 dated 7.8.2018. 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B)/A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B)/A(3)/1/2020-1 dated 7.10.2021			Total		0

Executive Engineer
Haroli Division
HP, PWD, Haroli

534

30

SCHEDULE OF QUANTITY									
Name of work: A/R & M/O Panjavar Bathri road Km 0/00 to 34/00 (SH: Maintenance of earthen shoulder at RD 18/00 to 20/500)				Estimated Cost		99,268			
				Earnest Money		2000			
				Time limit		One Month			
Sl/No.	Description of work	Unit	Figures	RATE In		AMOUNT			
				Words					
1	Maintenance of Earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including carriage of material within all leads and lifts .The rates are inclusive of octrol, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	Per Square metre	2836.22						
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/A(3)/17/20212 dated 7.8.2018				G Total:		0			
2) The Bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP Vide letter No. PBW(B) A(3) 1/2020 dated 22.07.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 07.10.2021									

Executive Engineer
Haroli Division
HPPWD Haroli

SCHEDULE OF QUANTITY

Estimated cost 99834
Earnest money 2000
Time limit One month

Name of work: A/R & M/O link Road to Village Nagnoli Km 0/0 to 5/560 (SH:- C/o Toe Wall for U-shape drain at RD of 16070 0/180 LHS (B/wall)

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	Figures	Words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.40	cum			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	30.60	cum			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/G(17/2/0212 dated 7.8.2018					0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP, PWD., Haroli

552

SCHEDULE OF QUANTITY

Estimated cost 99727
Earnest money 2000
Time limit One month

Name of Work: Balance work for the C/O road from link road to Sati Mata Mandir G.P. Hiranagar (SH: C/O C.C. pavement RD 0/256 to 0/278)-under MMSY

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150mm and disposal of scarified material within all lift and lead as per technical specification 301.4 as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	78.00	Per square metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 60mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.94	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (one cement, four sand, eight graded crushed stone aggregate 40mm/forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plan/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard design mix of grade M-25 (M-twenty) cement concrete not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.82	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018.				G.Total	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3)1/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP PWD, Haroli

547

SCHEDULE OF QUANTITY

Estimated cost 99458
Earnest money 2000
Time limit One month

Name of Work: Balance work for C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh tarsem Lal ward No2 GP Beetan (SH: P/L C.C. pavement RD 0/094 to 0/108)- under MMSY						
S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm, forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukhiana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, mukhiana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, mukhiana, toll tax, GST labour cess or other taxes imposed by the Government.	11.86	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)17/20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B)A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3)1/2020-1 dated 7.10.2021					
					G.Total	0


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

34

Schedule of quantity

Name of work:- A/R & M/O on link road from Umralli to Dulehar via Goua km. km. 0/00 to 3/200						Estimated Cost: Rs	One month
(SH: C/O Retaining wall at Rd. 2/800 to 0/829.40 Lhs)						Time:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:-	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.76	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	29.91	Cum.				
	Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. P/W (II) 0 (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.W.D. District, Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work: Restoration work for link road from Main road upto Community Centre ward No 7 G.P. Heeran Thara (SH: P/L paver block at RD 01059 to 01111 & C/O edge wall)

Estimated Cost 99403

Earnest Money 2000/-

Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, soil tax, sale tax, GST, labour cess or other taxes imposed by the Government.	4.32	Per cubic metre			
	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement, three sand six graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/ ground, complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, soil tax, GST, labour cess or other taxes imposed by the Government.	15.12	Per cubic metre			
	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M: twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, soil tax, GST, labour cess or other taxes imposed by the Government.	1.20	Per cubic metre			
1	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, soil tax, sale tax, GST, labour cess or other taxes imposed by the Government	33.60	Per square metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations for all type structure complete of reinforced concrete grade M-20 (M:twenty) nominal mix 1:2:4 (One cement, two sand, four graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, soil tax, GST, labour cess or other taxes imposed by the Government.	1.56	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)6(17)2,0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
					Total:	0

Executive Engineer,
H.P.P.W.D. Division Haroli
Devt. Una (H.P.)

SS6

SCHEDULE OF QUANTITY

Estimated cost 99624
 Earnest money 2000
 Time limit One month

Name of work: A/R & M/O link Road to Village Nagnoli Km 0/0 to 5/560 (SH:- C/o Toe Wall for U-shape drain at RD 0/080 to 0/122 LHS (Balance-work))

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.40	cum			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	30.24	cum			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/Q(17)/2/0212 dated 7.6.2018				Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
 Haroli Division

32

SCHEDULE OF QUANTITY						
	Name of work : Restoration of rain damages on Panjagar Bathri to Lalhi Kungrat Dhillan road km.0/0 to 5/500 (SH: C/O U-shape drain in km. 1/430 to 1/460)				Estimated Cost	99921/-
					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	Figures	RATE IN	AMOUNT
					Words	
				800.00	Rubpees	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.00	Per cubic met			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.30	Per c me			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.70	Per cu metn			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.20	Per Cub metre			
5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	71.75	Per Kilogramme			

6	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes (SI) marked including fixing with approved adhesive etc. complete 200mm(two hundred millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST ,labour cess or other taxes imposed by the Government.	7.50	Per Running metre	
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018			
	2) The rates shall be including of all types of taxes including GST ectra)			
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			


Executive Engineer
Haroli Division
HP.PWD.,Haroli

SCHEDULE OF QUANTITY

Estimated cost 99661

Earnest money 2000

Time limit One month

Name of Work: Balance work for the C/O road from link road to Sati Mata Mandir G.P. Hiran Nagar (SH: C/O C.C. pavement RD 0/278 to 0/300)-under MMSY

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150mm and disposal of scarified material within all lift and lead as per technical specification 301.4 as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	78.00	Per square metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 60mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers, with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malikana, toll tax, GST labour cess or other taxes imposed by the Government.	5.94	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	7.94	Per cubic metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilograms) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malikana, toll tax, GST labour cess or other taxes imposed by the Government.	11.82	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)17/2021 dated 7.8.2018				G.Total	
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)A(3)17/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3)17/2020-1 dated 7.10.2021					

Executive Engineer
Haroli Division
HP PWD, Haroli

Sub

SCHEDULE OF QUANTITY

Name of work: Restoration work for link road from Main road upto Community Centre ward No 7 G.P. Heeran Thara (SH: PIL paver block at RD 0/143 to 0/175)

Estimated Cost 99110
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	102.40	Per square metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal size in or under water and curing sand, four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	3.62	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PRW(B)HQ(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PRW(B)A(3)1/2020 dated 22.07.20					
					Total:	0

Executive Engineer,
H.P.P.W.D. Division Hargaji
Distt. Una (H.P.)

S/S

SCHEDULE OF QUANTITY

Estimated cost 99555

Earnest money 2000

Time limit One month

Name of work: Construction of boundary wall at PM Shri GUSS Kangar Distt Una (C/O boundary wall)- phase-I

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement, four sand eight graded crushed stone aggregate 40mm, forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.40	Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : three coarse sand) six graded crushed stone aggregate 20 mm, twenty millimeter) (twenty millimeter) nominal size) as directed by Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, mukana, toll tax, GST labour cess or other taxes imposed by the Government.	7.02	Per cubic metre			
4	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering and propping etcetera with wooden battens and battens for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plan concrete work in foundation footing and bases of columns etcetera and mass concrete including carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	28.08	Per square metre			
5	Providing and laying damp proof course 38mm (thirty eight millimeter) thick with cement concrete 1:2:4 (One cement two sand four graded crushed stone aggregate 12.5mm (twelve point five millimeter nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
6	Applying a coat of hot bitumen (moughat 80/100 (eighty/hundred) or equivalent, using 1.70 kg (one point seventy kilogramme) per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.51	Per square metre			
7	Block work with common burnt clay F.P.S (Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, mukana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.51	Per cubic metre			

533

S33

8	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arisises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:5 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.57	Per square metre			
9	Providing and laying cement concrete work grade M-20 (M-twenty twenty) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain windows sills, filets, sunken floor etc. upto floor all level and curing curing complete including the cost of centering, shuttering and finishing including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.20	Per cubic metre			
10	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	49.57	Per Square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021			Total		0

Executive Engineer
Haroli Division
HP.PWD.,Haroli

Schedule of quantity

Name of work:- A/R & M/O PWD Non PWD Residential building at Haroli (SH: P/F All in one HP-PC with 15. 12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-B7500D) in Surveyor room at Newly created Khad Sub Division Division Office)					Estimated Cost: Rs	
					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing commercial All in one HP make computer system with inspiron 24" Intel i5 12Th Gen Processor 8 GB Ram & 512TB SSD with Microsoft office & Window 11/12 W, E, & Bluetooth 4.0 M.2/keyboard & optical mouse (3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
2	Providing and fixing Intex UPS 600 VA Gamma including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana, toll tax sale tax, GST labour cess or other taxes imposed by the Government	1.00	Each			
3	Providing and fixing Brother printer DCP-B7620DW with wifi technology including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi royalty malkana toll tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
Total						

Note: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018
2) The rates shall be including of all types of taxes including GST etcetra)

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)