

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2024-25/ 21246-96

Dated/ 19-3-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 26.03.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 25.03.2025 up to 4.00 P.M and the application for issue of tender form shall be received 24.03.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o link road from Yol Dadh Palampur road for Village Ghuggar Sughar road Km 0/00 to 1/500 (SW:- C/o Edge Wall at RD 0/870 to 0/885)	Rs. 72792.00	Rs. 1500.00	Three Months
2	C/o link road from Yol Dadh Palampur road for Village Ghuggar Sughar road Km 0/00 to 1/500 (SW:- P/L Cement Concrete Paver Block at RD 1/200 to 1/250.20)	Rs. 99,605.00	Rs. 2,000.00	Three Months
3	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW :- P/L PVC Pipes 315 MM dia and stone soling, 1:4:8 bed for pipes etc at RD 29/410)	Rs. 51,155.00	Rs. 1,100.00	Three Months
4	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW :- C/o U-Shape drain from RD 29/400 to 29/410 i/c grating over drain)	Rs. 99,846.00	Rs. 2000.00	Three Months
5	A/R & M/O Judge Residence Building (Civil Judge Cum JMFC Residence) at Palampur Distt. Kangra (HP) (SW:- C/o Gate Column, Brick work in Boundary wall, P/F Cupboard in Kitchen & Sanitary work etc, P/F cupboard/ Almirah, Renovation of Toilet and Tile flooring of JMFC and Additional Distt. Session Judge Rooms)	Rs. 92,342.00	Rs. 1,900.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

Name of Work :- C/O link road from Yol dadh Palampur road for village Ghuggar Suggar road Km. 0/000 to 1/500
(S. W. :- C/O Edge wall at RD 0/870 to 0/885)

Schedule of Quantity

Work No. 1
Estimated Cost :- Rs. 98,727/-
Earnest Money :- Rs. 20,000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construct of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	6.90	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	15.60	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	14.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.00	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

ame of Work :- C/O link road from Yol dadh Palampur road for village Ghuggar Suggar road Km. 0/000 to 1/500
(S. W. :- P/L Cement concrete Paver Block at RD 1/200 to 1/250.20

Schedule of Quantity

Work No. 2

Estimated Cost :- Rs. 99,605/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	20.08	Cubic metre		Per Cubic metre	
2	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Km. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the intersices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	8.03	Cubic metres		Per Cubic metre.	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	12.05	Cubic metres		Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

Schedule of Quantity

Name of Work :- Dharamshala Yol Dadh Palampur road Km. 27/000 to 33/000
(S. W. :- P/L PVC Pipes 315 mm dia & stone soling 1:4:8 bed for pipes etc. at RD 29/410

Work No. (3)

Estimated Cost :- Rs. 51,155/-

Earnest Money :- Rs. 1100/-

Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	411.74			Per Kilogram	
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) including carriage of materials with in all leads, lifts and other incidentals.	5.60			Per Cubic metre	
3	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification (finished work including materials and labour) including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	5.60			Per Cubic metre.	
4	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	5.60			Per Cubic metre.	
	Providing and laying PVC pipes 315 mm.(Three hundred fifteen millimetre) dia of superior quality including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	8.50			Per Running metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 4
Name of Work :- Dharamshala Yol Dadh Palampur road Km. 27/000 to 33/000
(S. W. :- C/O U-shape drain from RD 29/400 to 29/410 i/c grating over drain)

Estimated Cost :- Rs. 99,846/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	83.01	Cubic metre		Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	9.21	Cubic metre		Per Cubic metre	
3	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	369.13	Kilogram me		Per Kilogram me	
					Total :-	

Executive Engineer
Palampur Division
H.P. PWD Palampur

Schedule of quantity

Name of Work :- A/R & M/O Judge Residential building (Civil Judge Cum JMFC Residential) at Palampur Dist. Kangra (H.P.)
 Sub Work :- C/O Gate Column, Brick work in Boundary wall, P/F Cupboard in kitchen & Sanitary work etc. Providing and fixing
 Cupboard/Almirah, Renovation of toilet & tile flooring of JMFC & Additional Dist. Session Judge Rooms

Estimate Cost :- Rs. 92,342/-
 Earnest Money :- Rs. 1900/-
 Time Limit :- Three Months

S. No	Description of item	Quantity	in figure	Rate	Unit	Amount
				In Words		Rupees
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads, lifts and other incidental .The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the government.	1.84	Cubic metre		Per Cubic metre	
2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (one cement : one part five coarse sand : three graded stone aggregate twenty millimetres nominal size) as per the entire satisfaction and direction of Engineer-in- Charge.The rate includes octroi,royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	0.75	Cubic metres		Per Cubic metre	
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	75.00	Kilogram me		Per Kilogram me	
4	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	5.94	Square metre		Per Square metre	
5	Steel work welded in built up sections/ framed work/subler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge.The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	135.71	Kilogram me		Per Kilogram me	
6	Providing and fixing cup board shutters with 25 mm thick veneered particle board IS : 3097 marked, exterior grade (Grade I), of approved make, including lind class leak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in-charge with non decorative veneering on both sides including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	8.72	Square metre		Per cubic metre	
7	Providing and fixing 125 mm. (one hundred twenty five millimetre) bright /mat finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.00	Nos.		Each	
8	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. Triple strip vertical type.The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.00	Nos.		Each	

9	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the	1.58	Square metre	Per Square metre	
10	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 ltr/10 sqm complete including cost of Priming coat. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	64.02	Square metre	Per Square metre	
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal outer dia Pipes including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	50.00	Running metre	Running metre	
12	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per direction of Engineer-in-Charge including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	4.50	Square metre	Per Square metre	
13	Providing and fixing C.P. brass bibcock (concealed) of standard design and of approved make conforming to IS:8931. 15 mm nominal bore. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	4.50	Nos.	Each	
14	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	45.40	Sqm.	Per Square metre	
				Total	

Executive Engineer
Palampur Division
H.P. PWD Palampur