

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 20288-337 Dated/10-3-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2024

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

'NOTICE INVITING TENDERS'

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 18.03.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 17.03.2025 up to 4.00 P.M and the application for issue of tender form shall be received 15.03.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o road & Pulli from Main road towards house of Verma & Others (SW:- P/L Hume pipe culvert (900 MM dia) at RD 0/095 and P/L G-I from RD 0/00 to 0/069 (MMGSY)	Rs. 99,491.00	Rs. 2,000.00	Three Months
2	C/o road & Pulli from Main road towards house of Verma & Others (SW:- P/L G-I from RD 0/069 to 0/109 and P/L G-II from RD 0/00 to 0/050) (MMGSY)	Rs. 52,118.00	Rs. 1,100.00	Three Months
3	C/o road from Gugga Marhi to Rensu Basti (SH:- P/L Interlocking Paver Blocks at RD 0/030 to 0/050 (MMGSY)	Rs. 69,700.00	Rs. 1,400.00	Two Months
4	C/o Badminton Court at Bagora (SW:- C/o Badminton Court (MPLAD)	Rs. 99,685.00	Rs. 2000.00	Two Months
5	C/o link road from main road to Industrial Area via Hollymission School (SW:- Balance work of Interlocking Tiles at RD 0/040 to 0/055 (MMGSY)	Rs. 69,885.00	Rs. 1,400.00	Two Months
6	C/o road Darati to Bharthadi Bridge (SW:- Providing and laying CC Pavement at RD 0/155 to 0/190 (MMGSY)	Rs. 99,225.00	Rs. 2,000.00	Two Months
7	Restoration of rain damages on various road under Palampur Sub-division (Section Kandwari) (SH:- Painting and writing on Kilometre stones, Sign boards & Rain Shelter etc)	Rs. 84,750.00	Rs. 1,700.00	Three Months
8	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW:- C/o U-shape drain from RD 31/109 to 31/194)	Rs. 99,146.00	Rs. 2,000.00	Three Months
9	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW:- C/o U-shape drain from RD 31/194 to 31/280)	Rs. 99,043.00	Rs. 2,000.00	Three Months
10	Restoration of rain damages on GPS Ghamrota Rakh Bhont Garh road Km 0/00 to 3/00 (SH:- Balance work of R/Wall at RD 2/110 to 2/114)	Rs. 83,610.00	Rs. 1,700.00	Two Months
11	Restoration of rain damages on various roads under Gopalpur Sub-Division (SH:- Painting KM stones, Concrete wall, Steel board paint along with writing letters)	Rs. 99,683.00	Rs. 2,000.00	Two Months
12	Restoration of rain damages on various roads under Gopalpur Sub-Division (SH:- Painting KM stones, Concrete wall, Steel board paint along with writing letters)	Rs. 99,683.00	Rs. 2,000.00	Two Months
13	C/o Community Hall in Shashi Paul Colony Ward No. 5 Sughar Palampur (HP) (SW:- Providing and laying Vitrified Tiles & painting work etc (Deposit)	Rs. 93,998.00	Rs. 1,900.00	Three Months
14	C/o Community Hall in Shashi Paul Colony Ward No. 5 Sughar Palampur (HP) (SW:- Providing half brick masonry, cement plastering, P/F SS Railing & Steel glazed doors, windows etc (Deposit)	Rs. 93,179.00	Rs. 1,900.00	Three Months
15	OFC Damage on Banuri to Bharmat road Km 0/000 to 2/500 (Sw:- P/L Interlocking Paver Block from RD 1/200 to 1/225)	Rs. 99,624.00	Rs. 2,000.00	Three Months

16	OFC Damage on Banuri to Bharmat road Km 0/000 to 2/500 (SW:- P/L Interlocking Paver Block from RD 1/225 to 1/250)	Rs. 99,860.00	Rs. 2,000.00	Three Months
17	C/o link road to Banuri to Upper Chandpur road Km 0/00 to 1/500 (SW:- P/L Interlocking Concrete Block Pavement from RD 0/300 to 0/325 (OFC Deposit)	Rs. 99,919.00	Rs. 2,000.00	Three Months
18	C/o link road to Angaria Basti Km 0/00 to 0/500 (SW:- C/o U-shape drain, grating work and P/L CC Pavement at RD 0/013 to 0/026)	Rs. 87,024.00	Rs. 1,800.00	Three Months
19	C/o link road from Shitla Mata to Tikka Nihang Km 0/00 to 1/530 (SW:- Cutting in Earth work (MNP)	Rs. 99,475.00	Rs. 2,000.00	Three Months
20	C/o damage on Banuri to Bharmat road Km 0/000 to 2/500 (SW:- P/L Interlocking Paver Blocks from RD 0/575 to 0/600 (Under OFC)	Rs. 99,352.00	Rs. 2,000.00	Three Months
21	C/o damage on Banuri to Bharmat road Km 0/000 to 2/500 (SW:- P/L Interlocking Paver Blocks from RD 0/600 to 0/625 (Under OFC)	Rs. 99,147.00	Rs. 2,000.00	Three Months
22	Restoration of rain damages on Palampur Neugal Park road at RD 0/200 (SH:- Providing and fixing Double Shank Pavement Marker Cat Eyes at Zebra crossing at Various RDs)	Rs. 98,750.00	Rs. 2,000	One Months
23	Restoration of rain damages on Banuri to Saliara road at RD 1/700 (SW:- Providing and fixing Double Shank Pavement Marker Cat Eyes at Zebra crossing at Various RDs)	Rs. 98,750.00	Rs. 2,000	One Months
24	C/o link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800 (SW:- P/L Cement concrete Pavement from RD 2/200 to 2/225)	Rs. 99,051.00	Rs. 2,000.00	Three Months
25	C/o link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800 (SW:- P/L Cement concrete Pavement from RD 2/225 to 2/255)	Rs. 99,284.00	Rs. 2,000.00	Three Months
26	C/o link road to Gujjar Basti Lamlehar (SW:- P/L CC Pavement at RD 0/090 to 0/125 (MMGSY)	Rs. 99,953.00	Rs. 2,000.00	Three Months
27	C/o Jeepable road & RCC Wall from Main road towards Sh. OM Prakash S/o Sh. Suraj Ram, Tilak Raj etc house Ward No. 5 GP Nachhir Bandla (SW:- C/o R/Wall at RD 0/040 to 0/045.10 (MMGSY)	Rs. 99,315.00	Rs. 2,000.00	Three Months
28	C/o Jeepable road & RCC Wall from Main road towards Sh. OM Prakash S/o Sh. Suraj Ram, Tilak Raj etc house Ward No. 5 GP Nachhir Bandla (SW:- C/o R/Wall at RD 0/050.20 to 0/055.30 (MMGSY)	Rs. 98,615.00	Rs. 2,000.00	Three Months
29	C/o Main road Kuthar to Kaloli Mata road (SW:- P/L C.Conc. Pavement at RD 0/300 to 0/356 (MMGSY)	Rs. 96,966.00	Rs. 2,000.00	Three Months
30	C/o Main road Kuthar to Kaloli Mata road (SW:- P/L C.Conc. Pavement at RD 0/356 to 0/411 (MMGSY)	Rs. 98,753.00	Rs. 2,000.00	Three Months
31	C/o Office of the Assistant Director Animal Production Sperm Station Palampur (SW:- C/O Boundary Wall back side of office (Deposit)	Rs. 99,809.00	Rs. 2,000.00	Three Months
32	C/o Office of the Assistant Director Animal Production Sperm Station Palampur (SW:- C/O Boundary Wall back side of Lab (Deposit)	Rs. 99,960.00	Rs. 2,000.00	Three Months
33	A/R & M/O Judge Residential Building Civil Judge Cum JMFC Residence at Palampur Distt. Kangra (HP) (SW:- C/o Boundary Wall & R/R Masonary work)	Rs. 98,582.00	Rs. 2,000.00	Three Months
34	A/R & M/O Judge Residential Building Civil Judge Cum JMFC Residence at Palampur Distt. Kangra (HP) (SW:- P/L Interlocking Concrete Block in Courtyard)	Rs. 98,831.00	Rs. 2,000.00	Three Months
35	C/o Jeepable road & RCC Wall from Main road towards Sh. Om Prakash S/o Sh. Suraj Ram, Tilak Raj etc House Ward NO. 5 GP Nachhir Bandla (SW:- C/o R/Wall at RD 0/040 to 0/045.10 (MMGSY)	Rs. 99,709.00	Rs. 2,000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

name of Work :- C/O road & Pulli from main road towards house of Verma & others
(S. W. :- P/L hume pipe culvert (900 mm dia) at RD 0/095 & P/L G-1 from RD 0/000 to 0/069 (MMGSY)

Work No. 1

Estimated Cost :- Rs. 99,491/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and laying 900 mm.(Nine hundred millimetre) dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	15.00	Running metre			Per Running metre	
2	Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty and other incidentals necessary to complete the work in all respects.	10.08	Cubic metre			Per Cubic metre	
3	Providing, laying, Wearing 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	18.38	Cubic metres			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity
S. W. :- P/L G-I from RD 0/069 to 0/109, P/L G-II from RD 0/000 to 0/050 (MMGSY)

Work No. 2

Estimated Cost :- Rs. 52,118/-
Earnest Money :- Rs.1100/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government.	10.50	Cubic metres			Per Cubic metre	
2	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	13.13	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Road from Gugga Marhi to Rensu Basi. (SH:- Providing and Laying interlocking paver blocks at Rd 0/030 to 0/050), **MMSY**

Sr. No.	Description of Item	Quantity	Estimated cost Rs.	
			Earnest Money Rs.	1400.00
			Time Limits	Two Months
			Rate	
			In Figures	In Word
				Unit
1	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	0.60		Per cubic metre.
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	52.25		Per square metre
	Total			

Executive Engineer,
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Badminton court at Bagora . (SH:-C/o Badminton court). (MPLAD)

Name of work:- C/o Badminton court at Bagora . (SH:- C/o Badminton court). (MPLAD)							ESTIMATED COST		
							Estimated cost Rs.		99685.00
							Earnest Money Rs.		2000.00
							Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORI technical specification clause- 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	16.28			Per cubic metre				
2	Providing and laying Cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plant/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.85			Per cubic metre.				
3	Providing and laying 50 mm thick Cement concrete flooring 1:2:4 (one cement isto two sand isto four graded stone aggregate 20 mm nominal size) laid in one layer finished with a floating coat of neat Cement. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	108.54			Per cubic metre				
4	Providing and fixing pole for Badminton court including carriage of material complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.00			Each				
	Total								

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Main road to Industrial area via Hollymission School. (SH:- Balance work of interlocking Tiles at Rd 0/040 to 0/055). **MMSY**

Name of work:- C/O Link road from Main road to Industrial area via Hollymission School. (SH:- Balance work of interlocking Tiles at Rd 0/040 to 0/055). MMSY							Estimated cost Rs.	69885.00
							Earnest Money Rs.	1400.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.38			Per cubic metre.			
2	Providing and Laying of interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.50			Per square metre			
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.45			Per cubic metre.			
	Total							

Executive Engineer,
Palampur Division
H.P. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o road Daraiti to Bharthadi Bridge. (SH:- Providing and Laying C.C. Pavement at Rd 0/155 to 0/190). **MMSV**

SCHEDULE OF QUANTITY						
Name of work:- C/o road Darait to Bharthadi Bridge. (SH:- Providing and Laying C.C. Pavement at Rd 0/155 to 0/190).			MMMSY		Estimated cost Rs.	99225.00
					Earnest Money Rs.	2000.00
			Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75			Per cubic metre.	
Total						

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- Restoration of Rain Damages on various road under Palampur Sub-Division Section Kandwari
(S. W. :- Pairing & Writing on Kilometre Stones, Sign boards & Rain Shelter etc.

Schedule of Quantity

Work No. 3

Estimated Cost :- Rs. 84,750/-
Earnest Money :- Rs. 1700/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacture. (Make:- Asian Paint). The rate including of octroi, royalty, malkana, toll tax, Sale tax or other taxes imposed by the government.	18.00	Square metre			Per Square metre	
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	48.00	Square metres			Per Square metre	
3	Re-lettering with black Japan paint of approved brand and manufacture. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	42000.00	per letter per cm			per letter per cm	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work :- D/Shala Yol Dadh Palampur road 27/000 to 33/000
S. W. :- C/O U-Shape Drain from RD 31/109 to 31/194

Schedule of Quantity

Estimated Cost :- Rs. 99,146/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

Work No. 8

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructn of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana.Toll tax, GST or any other taxes imposed by the Government.	33.11	Cubic metre		Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	19.61	Cubic metre		Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work No. 9
Schedule of Quantity
Name of Work :- D/Shala Yol Dadh Palampur road 27/000 to 33/000
(S. W. :- C/O U-Shape Drain from RD 31/194 to 31/280)

Estimated Cost :- Rs. 99,043/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	33.07 Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	19.59 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on GPS Ghanrota Rakh Bhot Garh road Km 0/00 to 3/00. (SH:- Balance work of R/wall at Rd 2/110 to 2/114).

Name of work:- Restoration of Rain Damages on GPS Ghanrota Rakh Bhot Garh road Km 0/00 to 3/00. (SH:- Balance work of R/wall at Rd 2/110 to 2/114).									
SCHEDULE OF QUANTITY									
Sr. No.	Description of Item	Quantity	Estimated cost Rs.				Unit	Amount	
			Earnest Money Rs.		Two Months				
			Time Limits						
			In Figures	In Word					
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	18.24				Per cubic metre.			
2	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00				Each			
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	4.32				Per cubic metre			
	Total								

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under Gopalpur Sub Division.(SH:- Painting Km Stone, concrete wall, Steel board paint along with writing letters).

SCHEDULE OF QUANTITY							
Name of work:- Restoration of Rain Damages on various roads under Gopalpur Sub Division.(SH:- Painting Km Stone, concrete wall, Steel board paint along with writing letters).						Estimated cost Rs.	99683.00
						Earnest Money Rs.	2000.00
						Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	29.40			Per square metre		
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	29.40			Per Square metre		
3	Wall painting One or more coats on old work with plastic emulsion paint of approved brand and manufacture to give an even shade. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	29.40			Per Square metre		
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	43.20			Per Square metre		
5	Re-lettering with black Japan paint of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	50081.00			Per letter per cm height		
Total							

Executive Engineer,
Palampur Division
HP, PWD Palampur

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under Gopalpur Sub Division,(SH:- Painting Km Stone, concrete wall, Steel board paint along with writing letters).

Name of work:- Restoration of Rain Damages on various roads under Gopalpur Sub Division.(SH:- Painting Km Stone, concrete wall, Steel board paint along with writing letters).							Estimated cost Rs.		99683.00		
Sr. No.							Earnest Money Rs.		2000.00		
							Time Limits		Two Months		
Description of Item							Quantity	Rate		Unit	Amount
							In Figures	In Word			
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.						29.40			Per square metre	
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.						29.40			Per Square metre	
3	Wall painting One or more coats on old work with plastic emulsion paint of approved brand and manufacture to give an even shade: The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.						29.40			Per Square metre	
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications . Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied (@ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.						43.20			Per Square metre	
5	Re-lettering with black Japan paint of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.						50081.00			Per letter per cm height	
Total											

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity
Name of Work :- C/O Community Hall in Shashi Paul Colony Ward No. 5 Sughar Palampur (H.P.)

Sub Work :- Providing and Laying vitrified tiles & painting work etc. (Deposit)

Estimated Cost : Rupees 93,998/-
Earnest Money : Rupees 8000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	0.94	Cubic metre			Per cubic metre	
2	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	32.94	Square metre			Per Square metre	
3	Providing and laying Vitrified tiles Size of Tile 600x600 mm (thickness to be specified by manufacturer), with water absorption 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	4.00	Square metre			Each	
4	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tolltax, GST or any other taxes imposed by the Government.	208.10	Square metre			Per Square metre	
5	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	208.10	Square metre			Per Square metre	
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary .paint of approved brand and manufacture. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	208.10	Square metre			Per Square metre	
	Total:-						

Executive Engineer
Palampur Division
H.P.PWD Palampur

(13)

Schedule of Quantity
Work :- C/O Community Hall in Shashi Paul Colony Ward No. 5 Sughar Palampur (H.P.)

Sub Work :- Providing Half Brick Masonry, Cement plastering, P/F SS Railing & Steel glazed doors, windows etc. **(Bepesit)**

Estimated Cost : Rupees 93,179/-
 Earnest Money : Rupees 1900/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in Cement mortar 1:4 (one cement :four coarse sand) with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government..	9.40		Rupees Nil		Per Square metre	
2	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D,F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitered and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment). Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size). The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government..	109.116		Rupees Nil		Per Kilogram	
3	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	257.52		Rupees Nil		Per Square metre	
4	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	43.94		Rupees Nil		Per Kilogram	
	Total:-						

Executive Engineer
 Palampur Division
 H.P.PWD Palampur

Schedule of Quantity

Work No. 115

Name of Work :- OFC Damage on Banuri to Bhammat road Km. 0/000 to 2/500
(S. W. :- P/L Interlocking Paver Blocks from RD 1/200 to 1/225)

Estimated Cost :- Rs. 99,624/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.14	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	71.55	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
						Total :-	

~~Executive Engineer~~
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 16
 Estimate of Work :- OFC Damage on Banuri to Bharnat road Km. 0/000 to 2/500
 Earnest Money :- Rs. 2000/-
 (S. W. :- P/L Interlocking Paver Blocks from RD 1/225 to 1/250
 Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.15	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	71.70	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Bid Schedule of Quantity

Work No. **13**

Name of Work :- C/O link road to Banuri to Upper chandpur road Km. 0/000 to 1/500
(S. W. :- P/L Interlocking Concrete Block Pavements from RD 0/300 to 0/325 (OFC Deposit))

Estimated Cost :- Rs. 99,919/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tollax, sale tax or other taxes imposed by the Government.	0.80	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tollax, sale tax or other taxes imposed by the Government.	72.90	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.49	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 18

Name of Work :- C/O link road to Angaria Basti Km. 0/000 to 0/500
(S. W. :- C/O U-shape drain, Grating work ~~at~~ *at R.O. 0/013 to 0/026*)

Estimated Cost :- Rs. 87,024/-
Earnest Money :- Rs. 1800/-
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.13			Per Cubic metre	
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	512.50			Per Kilogram	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802. 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	3.75			Per Cubic metres	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

Schedule of Quantity

Work No. **(19)**
 Estimated Cost : Rs. 99,475/-
 Earnest Money : Rs. 2000/-
 Time limit : Three Months

of Work :- C/O link road from Shilpa Mata Mandir to Tikka Nihang Km. 0/000 to 1/530
 W. :- Cutting in Earth work (MNP)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil soft rock, hard rock chiselling / wedging out of rock (where blasting is prohibited) and their intermediate classification of solid setting out true to the required lines grades with cutting and trimming of side slopes and level and as shown in the drawings and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302.1603 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unusel material for filling in road way, s camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour as required. Recovery of stones to the tune of 10% i.e. 27.63 cubic metre (Twenty seven decimal six three) quantity @ Rs.300/- (Rupees three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per	276.32			Per Cubic metre	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Work No. 20

Name of Work :- DEC Damage on Banuri to Bhammat road Km. 0/000 to 2/500
(S. W. :- P/L Interlocking Paver Blocks from RD 0/575 to 0/600 under of C)

Estimated Cost :- Rs. 99,352/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	0.56	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	74.25	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- OFC Damage on Banuri to Bharmat road Km. 0/000 to 2/500
(S. W. :- P/L Interlocking Paver Blocks from RD 0/600 to 0/625)

Work No. (21)

Estimated Cost :- Rs. 99,147/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	0.56	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, sale tax or other taxes imposed by the Government.	74.09	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
	Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur

Draft Schedule of Quantity

Name of Work :- Restoration of rain damages on Palampur Neugal Park road at RD 0/200
Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra Crossing & various RDs Km.

Estimated Cost : Rs. 98,750/-
Earnest Money : Rs. 2000/-
Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M/Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	250.00 Nos.			Each.	

Executive Engineer
Palampur Division
HP PWD Palampur

Draft Schedule of Quantity

Name of Work :- Restoration of rain damages on Banuri to Saliyana road at RD 1/700
Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra Crossing & various RDS Km.

Estimated Cost : Rs. 98,750/-
Earnest Money : Rs. 2000/-
Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M/Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage.of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in- charge.	250.00 Nos.			Each.	

Executive Engineer
Palampur Division
HP PWD Palampur

Work No. 24
 Schedule of Quantity
 S. W. :- P/L C. Conc. Pavement from RD 2/200 to 2/225

Estimated Cost :- Rs. 99,051/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Providing, laying, Wearing 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government.	7.46	Cubic metres			Per Cubic metre	
2	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer-in-charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	5.59	Cubic metres			Per Cubic metre.	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	11.18	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

of Work :- C/O Link road from Ghar to Upper Dattal & Ghar to Ropa Km. 0/000 to 4/800
(S. W. :- P/L C.Conc. Pavement from RD 2/225 to 2/255

Work No. **95**
Estimated Cost :- Rs. 99,284/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.47			Per Cubic metre	
2	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	5.60			Per Cubic metre.	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	11.21			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- C/O link road to Gullar Basti Lamlehah
(S.W. :- P/L CC Pavement at RD 0/090 to 0/125 (MMGSY)

Schedule of Quantity

Estimated Cost : Rs. 99,953/-
Earnest Money : 2000/-
Time limit : Three Months

Work No. 26

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 6.1 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer-in-charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.72	Cubic metres		Per Cubic metre.	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.72	Cubic metres		Per Cubic metre.	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	10.29	Cubic metre		Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

name of Work :- C/O Jeepable road & RCC wall from Main road towards Sh. Om Parkash S/O Sh. Suraj Ram, Tink Raj etc. house
ward No. 5 GP Nachir Bandla
(S. W. :- C/O R/wall at Rd 0/040 to 0/045.10 (MMGSY)

Schedule of Quantity

Work No. 27

Estimated Cost :- Rs. 99,315/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.09 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.86 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	9.00 Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.65 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- C/O Jeepable road & RCC wall from Main road towards Sh. Om Parkash S/O Sh. Suraj Ram, Tiak Raj etc. house ward No. 5 GP Nachir Bandla

(S. W. :- C/O R/wall at Rd 0/050.20 to 0/055.30 (MMGSY)

Schedule of Quantity

Work No.

Estimated Cost :- Rs. 98,615/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	7.02 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.65 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	10.00 Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.58 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

28

501

Name of Work :- C/O main road Kuthar to Kaloli Mata road
(S. W. :- P/L C.Conc. Pavement at RD 0/300 to 0/356 (MMGSY)

Schedule of Quantity

Work No. 29

Estimated Cost :- Rs. 96,966/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.76	Cubic metres			Per Cubic metre.	
2	Providing Concrete for plain/reinforced concrete: 1:2:4 (one cement: Two sand: four crushed stone aggregate) Nominal mix , P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	15.12	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

name of Work :- C/O main road Kuthar to Kaloi Mata road
(S. W. :- P/L C.Conc. Pavement at RD 0/356 to 0/411 (MMGSY)

Schedule of Quantity

Work No. 30
Estimated Cost :- Rs. 98,753/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.77	Cubic metres			Per Cubic metre.	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C:grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	15.40	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O office of the Assistant Director Animal production, Sperm Station Palampur

Sub Work :- C/O Boundary wall back side of ~~lab~~ *Office* (Deposit)

Estimated Cost : Rupees 99,809/-

Earnest Money : Rupees 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads, lifts and other incidental .The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the government.	13.15	Cubic metre			Per Cubic metre	
	Total:-						

Executive Engineer
Palampur Division
H.P.PWD Palampur

(51)

Schedule of Quantity

Estimated Cost : Rupees 99,960/-

Earnest Money : Rupees 2000/-

Time limit : Three Months.

Name of Work :- C/O office of the Assistant Director Animal production, Sperm Station Palampur
Sub Work :- C/O Boundary wall back side of lab

(Depot)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads, lifts and other incidental . The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	13.17	Cubic metre			Per Cubic metre	
	Total:-						

Executive Engineer
Palampur Division
H.P.PWD Palampur

Name of Work :- A/R & M/O Judge Residential building (Civil Judge Cum JMC Residential) at Palampur Distt. Kangra (H.P.)
Sub Work :- C/O Boundary wall & RR Masonry Work

Schedule of Quantity

Estimated Cost : Rupees 98,582/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ranning of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	4.56 Cubic metre			Per cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	12.04 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	11.00 Nos.			Each	
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads, lifts and other incidental as per the Direction of Engineer-in-Charge.The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the government.	1.35 Cubic metre			Per Cubic metre	
5	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	3.03 Square metre			Per Square metre	
6	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the	2.84 Cubic metre			Per Cubic metre	
	Total:-					

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- A/R & M/O Judge Residential building (Civil Judge Cum JMFC Residential) at Palampur Dist. Kangra (H.P.)
Sub Work :- P/L Interlocking Concrete Block in Courtyard

Estimated Cost : Rupees 98,831/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix, P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the	1.18	Cubic metre			Per Cubic metre	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm. as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in-charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	68.28	Square Metre			Per square metre	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) with in all leads, lifts and other incidental .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	0.53	Cubic metre			Per Cubic metre	
	Total:-						

Executive Engineer
Palampur Division
H.P.PWD Palampur

(34)

Name of Work :- C/O Jeepable road & RCC wall from Main road towards Sh. Om Parkash S/O Sh. Suraj Ram, Tilak Raj etc. house ward No. 5 GP Nachir Bandla

(S. W. :- C/O R/wall at Rd 0/060 to 0/065.15 (MMGSY)

Schedule of Quantity

Work No. 35

Estimated Cost :- Rs. 99,709/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	7.16 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.06 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00 Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.73 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur