

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.SD-III-CB-Tender/2024-25-29450

Dated:- 24/3/25


To

The Executive Engineer (IT Cell),
HP.PWD.,Nigam Vihar,Shimla-2.

Subject:- Tender Notice

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on department website as per notification of Principal Secretary (PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July,2021 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:- as above


Executive Engineer,
Shimla Division No. III,
HP.PWD.Shimla-3.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Sealed percentage rate tenders on form No. 6&8 are hereby invited by the Executive Engineer, Shimla Division No. III, H.P.PWD, Shimla-3 on behalf of the Governor of H.P. for the following works from the eligible Contractors/Firms enlisted in H.P.PWD, so as to reach in his office on or before **04-04-2025** up to **10:30 A.M.** and will be opened on the same day at **11.00 A.M.** in the presence of the intending Contractors/Firms or their authorized representatives. The tender form can be had from his office against cash payment (non-refundable) on any working day up to **04.30 P.M.** on **03-04-2025** and the application for issue of tender form shall be received up to **1.00 P.M.** on **03-04-2025.**

The earnest money in the shape of National saving Certificate/Time deposit account/saving account in any of the post office in HP, duly pledged in favour of Executive Engineer, Shimla Division No-III must accompany with the application form for the tender offer. Conditional tender and the tender received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reason there to. Other conditions are applicable as perform No. 6&8. The offer shall remain open for 30 days.

Sr. No	Name of work	Estimated Cost in Rs.	Earnest Money in Rs.	Time	Form No	Cost of form
1	Repair/ renovation of various residential buildings under Division No-III Shimla. (SH:- Providing of mold steel staging for water tank and providing new tank for Burj Cottage near Chaura maidan Under Peterhoff Section Shimla).	Rs.98671.00	Rs.1973.00	One Month	6&8	350/-
2	A/R & M/O to various residential buildings under division No.III Shimla. (SH:- White washing, repair of cupboard shutters and other miscellaneous repair work in set No.8 type-IV at willy park under Vidhan Sabha Sub-Division).	Rs.99158.00	Rs.1983.00	One Month	6&8	350/-
3	A/R & M/O to various residential buildings under Division NO.III Shimla. (SH:- White washing, repair of chajja front side and repair of cupboard shutters and other miscellaneous repair work in set N. A-6 type-IV at MLA crossing under Vidhan Sabha Sub-division).	Rs.98739.00	Rs.1975.00	One Month	6&8	350/-
4	A/R & M/O to various residential buildings under Division No.III Shimla. (SH:- Distempering work in servant qtrs No. 16,9,3 and various vacation / due sets at Brock-Hurst Shimla).	Rs. 95500.00	Rs.1910.00	One Month	6&8	350/-
5	A/R & M/O to various residential buildings under Division No-III Shimla. (SH:-Repair of cupboards and distempering work in type-III set No.12 at Brock-Hurst Shimla).	Rs.99770.00	Rs.1995.00	One Month	6&8	350/-

1. The contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.
2. The contractor/firm should attach attested copy of registration/renewal.
3. Copy of PAN card be attached with the application form.

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3.

Dated: 24/3/24

NO.SD-III-CB-Tender/2024-25-

29451-65

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla-2.
2. The Chief Engineer (S) HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2.
3. The Superintending Engineers, 4th Circle HPPWD Shimla -3.
4. The Deputy Commissioner, Shimla Distt. Shimla.
5. The Sub-Divisional Magistrate (U) Shimla.
6. All the Assistant Engineers working under this Division.
7. All the heads of the branches in this office.
8. Notice board.

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 98671.00
 Earnest Money Rs. :- 1973.00
 Time:- One Month.

Name of work:- Repair/renovation of various residential buildings under division no III Shimla. (SH:- Providing of mild steel staging for water tank and providing new tank for Burj Cottage near Chaura Maidan Under Peterhoff Section Shimla.)

SR. No.	Items of work	Quantity		Rate		Unit.	Amount.
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.73	Cum	1150.00	Rupees One Per Thousand One Per Hundred Fifty Only	cubic	840.00
2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : 15 mm to 40 mm nominal bore	12.00	Rmt	50.00	Rupees Fifty Only	Per running metre	600.00
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	0.73	Cum	350.00	Rupees Three Hundred Fifty Only	cum	256.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge - All work up to plinth level:- 1:3:6 (1 cement : 3 fine sand : 6 graded stone aggregate 20mm nominal size)	0.73	Cum.	5500.00	Rupees Five Per Thousand Five metre. Hundred Only	cubic	4015.00
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	540.00	kg	115.00	Rupees One Per Hundred Fifteen Only	Per/Kilogramme	62100.00
6	Providing and fixing M.S. welded mesh 25mm X 25mm X 3mm thick as per approved design complete by welding with electrical plant complete including applying priming coat of red lead paint as per HP.PWD. Specification 1990 Volume-I and including carriage of materials upto all leads and lifts by mechanical means and manual labour and as directed by the Engineer in Charge.	15.30	Sqm	650.00	Rupees Six Hundred Fifty Only	Per Square meter	9945.00
7	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials within all leads and lifts.(1000litre capacity)	1.00	No.	8000.00	Rupees Eight Each Thousand Only		8000.00
8	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials within all leads and lifts.(500litre capacity)	1.00	No.	4000.00	Rupees Four Each Thousand Only		4000.00
9	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore (External)	12.00	Rmtr	325.00	Rupees Three Per Hundred metre	running	3900.00
10	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete : 15 mm nominal bore	4.00	No.	150.00	Rupees One Each Hundred Fifty		600.00

11	Providing and fixing ball cock with ball and float valve 20mm dia complete including carriage of materials within all leads and lifts.	No.	550.00	Rupees	Five Each.	3300.00
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10- sqm of approved brand and manufacture	Sqm	65.00	Rupees	Hundred Fifty Sixty Per meter	Square 995.00
13	Providing and fixing ISI marked oxidised M.S. pressed butt hinges with necessary screws etc. complete.	No.	60.00	Rupees	Sixty Each.	120.00
				Only		
					Total	98671.00

Quoted rate in words

Quoted rate in Figure

Conditions:-

Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.

Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

SCHEDULE OF QUANTITY

Estimated Cost Rs. 99158.00
 Earnest Money Rs. 1983.00
 Time - One Month.

Name of work:- A/R and M/O to various residential buildings under division no III Shimla. (SH:- White washing , repair of cupboard shutters and other miscellaneous repair work in Set No 8 Type-IV at willy Park under Vidhan sabha Sub-Division)

SR. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	108.99	Sqm.	10.00	Rupees Ten Per Square meter	1090.00
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	108.99	Sqm.	60.00	Rupees Sixty Per Square meter	6539.90
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade one or more coats on new work complete including carriage of materials within all leads and lifts.	155.70	Sqm.	60.00	Rupees Sixty Per Square meter	9342.00
4	Painting with synthetic enamel paint on previously painted wood work surface of approved brand and manufacture of required colour to give an even shade one or more coats on old work including carriage of materials in all leads and lifts.	173.12	Sqm	60.00	Rupees Sixty Per Meter	10387.00
5	Providing and fixing C-Channel slider with roller necessary screws etc. complete as per direction of engineer in charge.	25.00	Rmtr	150.00	Rupees One Per Hundred Fifty Meter	3750.00
6	Providing and fixing 19mm thick Commercial Board shutters for We fixing with nickel plated piano hinges with screws etc complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	5.86	Sqm	1500.00	Rupees One Per Thousand Five meter Hundred Only	8790.00
7	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards ply wood sheets with approved adhesive and nails etc complete.transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	5.86	Sqm	890.00	Rupees Eight Per Hundred meter Ninety Only	5215.00
8	Providing and fixing square edges cover fillets (beading) 19mmx6mm section i/e mitring at junctions with wood screws and nails complete, 1st class deodar wood. complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	4.84	Rmt	30.00	Rupees Thirty Per Meter	145.00
9	Providing and fixing 35mm thick panelled glazed or panelled and glazed shutters for doors windows and clerestory windows Including black enamelled iron butt hinges with necessary screws etc. complete including carriage of materials within all leads and lifts in 2nd class deodar wood.	8.20	Sqm	4500.00	Rupees Four Per Thousand Five Meter Hundred Only	36900.00

10	Providing and fixing 35mm thick wire gauge shutters using galvanised M.S. wire gauge of I.S. 4.25 gauge designation 85G with wire of dia 0.56mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws complete including carriage of material within all leads and lifts as per direction of Engineer-in-charge in 2nd class deodar wood.	Sqm	4000.00	Rupees Four Per Thousand Only meter	Square 17000.00
					Total 99158.00

Quoted rate in words

Quoted rate in Figure

Conditions:-

Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.

Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

(3)

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 98739.00
 Earnest Money Rs. :- 1975.00
 Time :- One Month.

Name of work :- A/R and M/O to various residential buildings under division no III Shimla. (SH:- White washing, repair of chajja front side and repair of cupboard shutters and other miscellaneous repair work in Set No a-6 Type-IV at MLA crossing under Vidhan sabha Sub-Division)

SR. No.	Items of work	Quantity		Rate		Unit.	Amount.
				In figures	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	157.58	Sqm.	10.00	Rupees Only	Ten Per meter	Square 1576.00
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	157.58	Sqm.	60.00	Rupees Only	Sixty Per meter	Square 9455.00
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade one or more coats on new work complete including carriage of materials within all leads and lifts.	242.43	Sqm	60.00	Rupees Only	Sixty Per meter	Square 14548.00
4	Painting with synthetic enamel paint on previously painted wood work surface of approved brand and manufacture of required colour to give an even shade one or more coats on old work including carriage of materials in all leads and lifts.	207.41	Sqm	60.00	Rupees Only	Sixty Per meter	Square 12445.00
5	Providing and fixing C-Channel slider with roller necessary screws etc. complete as per direction of engineer in charge.	50.00	Rmtr	150.00	Rupees Only	One Per Hundred Fifty Meter	running 7500.00
6	Providing and fixing 19mm thick Commercial Board shutters for We fixing with nickel plated piano hinges with screws etc complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	11.71	Sqm	1500.00	Rupees Only	One Per Thousand Five Hundred	Square 17565.00
7	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards ply wood sheets with approved adhesive and nails etc complete. transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	23.43	Sqm	890.00	Rupees Only	Eight Per Hundred Ninety meter	Square 20863.00
8	Providing and fixing square edges cover fillets (beading) 19mmx6mm section i/e mitring at junctions with wood screws and nails complete, 1st class deodar wood. complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	19.36	Rmt	30.00	Rupees Only	Thirty Per Meter	Running 581.00
9	Steel work in built up tubular (round, square orrectangular hollow tubes etc.) trusses etc. including cutting, hoisting, fixing in position and applying apriming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	37.20	kg	115.00	Rupees Only	One Per/Kilogramme Fifteen	4276.00
10	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than, including carriage of materials within all leads and lifts	2.10	Sqm.	1150.00	Rupees Only	One Per Thousand Hundred Fifty meter	Square 2415.00

- 11 Providing flushing 38cm. overall in plain G.I. sheet fixed with galvanised iron J or L hooks, bolts and nuts, G.I. limpet washer and bitumen washers complete bent to shape and fixed in walls with cement mortar 1:3 (1 cement, 3 sand) 3.50
- 12 Providing and fixing M.S. BP Sheet 2mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) 2.80

Rmtr	750.00	Rupees Seven Per Hundred Fifty metre	Running 2625.00
Sqm	1750.00	Rupees One Per square metre	4900.00
		Thousand Seven Hundred Fifty Only	
		Total	98739.00

Quoted rate in words

Quoted rate in Figure

Conditions:

Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.

Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No. III
HP. PWD. Shimla-3.

4

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 95500.00
 Earnest Money Rs. :- 1910.00
 Time :- One Month

Name of work:-A/R and M/O to various residential buildings under division no III Shimla. (SH:-Distempering workin servant qtrs no 16,9,3 and various vacation /due sets at Brock-Hurst Hurst)

Sl. No.	Items of work	Quantity	Unit	Rate		Amount.
				In figures	In words	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping sand papering and preparing the surface smooth including necessary repairs to scratches etc.	450.00	Sqm	10.00	Rupees Ten Only	4500.00
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts.	450.00	Sqm	60.00	Rupees Sixty Only	27000.00
3	Painting wood work work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work complete including carriage of materials within all leads and lifts.white & other than white	300.00	Sqm	60.00	Rupees Sixty Only	18000.00
4	Painting steel work work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work complete including carriage of materials within all leads and lifts.	100.00	Sqm	55.00	Rupees Fifty Five Only	5500.00
5	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :Old work (one or more coats)	900.00	Sqm	45.00	Rupees Forty Five Only	40500.00
Total						95500.00

Quoted rate in words

Quoted rate in Figure

Conditions:-

Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.

Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer
 Shimla Division No.III
 HP. PWD. Shimla-3.

1092

5

Draft SCHEDULE OF QUANTITY

Estimated Cost Rs. 159275.00
 Earnest Money Rs. 1595.00
 Date Jan Month

Name of work:-A/R and M/O to various residential buildings under division no III Shimla. (SH:-Repair of cupboards and distempering work in Type-III set no-12 at Brock-Hurst Shimla.)

Sl. No.	Items of work	Quantity		Rate	Unit	Amount.
				In figures In words		
1	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink including carriage of materials within all leads, lifts and other incidentals.	40.00	Sqm	40.00 Rupees Forty Only	Per square metre	1600.00
2	Painting wood work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coats on new work complete including carriage of materials within all leads and lifts.	40.00	Sqm	70.00 Rupees Only	Seventy Per square metre	2800.00
3	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete including carriage of materials in all leads and lifts A) 125 mm	15.00	No	70.00 Rupees Only	Seventy Each	1050.00
4	Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete including carriage of materials in all leads and lifts 250x16mm	1.00	No	240.00 Rupees Hundred Forty Only	Two Each	240.00
5	Providing and fixing aluminium tower bolts (berrel type) anodized transparent or dyed to required shade and colour with screws etc. complete including carriage of materials in all leads and lifts A) 200x10mm	10.00	No	75.00 Rupees Five Only	Seventy Each	750.00
6	Providing and fixing bright finished or/and black enamelled iron (Helical door spring 150mm) complete including carriage of materials within all leads and lifts.	2.00	No	105.00 Rupees Hundred Five Only	One Each	210.00
7	Providing and fixing bright finished brass handles with screws etc. complete including carriage of materials within all leads and lifts. i) 125 mm	25.00	No	170.00 Rupees Hundred Only	One Each Seventy	4250.00
8	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete including carriage of materials within all leads and lifts.	12.00	Sqm	1400.00 Rupees Thousand Hundred Only	One Per square Four metre	16800.00
9	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) complete including carriage of materials within all leads and lifts. i) 6mm thick	12.00	Sqm	650.00 Rupees Hundred Fifty Only	Six Per square metre	7800.00
10	Providing and fixing 19mm thick Commercial Board shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete including carriage of materials within all leads and lifts.	16.50	Sqm	1500.00 Rupees Thousand Hundred Only	One Per square Five metre	24750.00
11	Providing and fixing magnetic catcher ISI marked with necessary screws etc. complete including carriage of materials within all leads and lifts.	10.00	No	40.00 Rupees Forty Only	Each	400.00

12 Providing and fixing square edges cover fillets (beading) 19mmx6mm section i/c mitring at junctions with wood screws and nails complete including carriage of materials within all leads and lifts. 1st class deodar wood	20.00	Rmt	30.00 Rupees Thirty Only	Per running metre	600.00
13 Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including carriage of materials within all leads and lifts.	16.20	Sqm	850.00 Rupees Hundred Fifty Only	Eight Per square metre	13770.00
14 Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc.	100.00	Sqm	10.00 Rupees Ten Only	Per square metre	1000.00
15 Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts.	100.00	Sqm	60.00 Rupees Sixty Only	Per square metre	6000.00
16 Painting wood work work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work complete including carriage of materials within all leads and lifts white & other than white.	100.00	Sqm	60.00 Rupees Sixty Only	Per square metre	6000.00
17 Painting steel work work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work complete including carriage of materials within all leads and lifts.	50.00	Sqm	55.00 Rupees Fifty Only	Five Per square metre	2750.00
18 Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade. (Old work (one or more coats)	200.00	Sqm	45.00 Rupees Forty Only	Five Per square metre	9000.00
				Total	99770.00

Quoted rate in words

Quoted rate in Figure

Conditions -

Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.

Sample of all the materials to be used on work shall be got approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No. III
HP, PWD, Shimla-3.