

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO:-PW/TD/CB/TA/NIT /2024- 25-

17245

Dated- 06-03-2025

To

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,


Subject:- Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and sechedule of quantity.


Executive Engineer
Tanda Division
HP PWD Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **13-03.2025** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **12.03.2025** up to **4:00 P.M** and the application for issue of tender form shall be received on **11.03.2025** up to **12:00** noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages on various roads under Baroh Sub- Division HP PWD Baroh in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Baroh Section).	99290.00	2000.00	Two Months
2	Restoration of rain damages on various roads under Nagrota Sub- Division HP PWD Nagrota Bagwan in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Nagrota Bagwan & Dadh Section).	99099.00	2000.00	Two Months
3	Restoration of rain damages on various roads under Baroh Sub- Division HP PWD Baroh in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Kandi Section).	99096.00	2000.00	Two Months
4	Restoration of rain damages on various roads under Nagrota Sub- Division HP PWD Nagrota Bagwan in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Nagrota Bagwan & Massal Section).	99815.00	2000.00	Two Months
5	Restoration of rain damages on various roads under Baroh Sub- Division HP PWD Baroh in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Radh Section).	99096.00	2000.00	Two Months
6	Restoration of rain damages on various roads under Nagrota Sub- Division HP PWD Nagrota Bagwan in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Dadh & Balldhar Section).	99733.00	2000.00	Two Months
7	Restoration of rain damages on various roads under Baroh Sub- Division HP PWD Baroh in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Sunhi Section).	99296.00	2000.00	Two Months
8	Restoration of rain damages on various roads under Tanda Sub- Division, HP PWD Tanda In Distt. Kangra HP (SH: Providing and laying G-III and Removal of Slips etc)	99257.00	2000.00	Two Months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK


Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2024-25- 17225-244 Dated/ **06-03-2025**
Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Director, Information & Publications Department, H.P. Shimla
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-TD-CB-TA 2024-25- 17225-2244 dated 06-03-2023, are of urgent nature.


Executive Engineer
Tanda Division
HP PWD at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST: - ₹ 99290.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : TWO MONTHS

Restoration of rain damages on various roads under Baroh Sub-Division, H.P.P.W.D., Baroh in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Baroh Section).

S. No.	Description of items	Quantity	In fig.	Rate In words	Unit	Amount
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming; stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	Cubic metres			Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	Cubic meters			Per cubic metre	
		240.00				
TOTAL :-						

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 99099.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : TWO MONTHS

Restoration of rain damages on various roads under Nagrota Sub-Division, H.P.P.W.D., Nagrota Division in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Nagrota Bagwan & Dadih Section).

S. No.	Description of items	Quantity	Rate	Unit	Amount
		In fig.	In words		
1	2	3	4	5	6
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, band packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	38.02	Cubic metres	Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	220.00	Cubic meters	Per cubic metre	
TOTAL :-					


 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

ESTIMATED COST:-	₹	99096.00
EARNEST MONEY :-	₹	2000.00
TIME LIMIT :		TWO MONTHS

Providing and laying G-III and Removal of slips etc; (Kandi Section).

NAME OF WORK : -

[illegible]

~~Executive Engineer,
H.F.P.W.D., Division,
Tanda at Nagrota Bagwan.~~

Schedule of Quantity

ESTIMATED COST :- ₹ 99815.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

Restoration of rain damages on various roads under Nagrota Sub-Division, H.P.P.W.D., Nagrota Division in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Nagrota Bagwan & Massal Section).

S. No.	Description of Items	Quantity	In fig.	Rate In words	Unit	Amount
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming; stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	Cubic metres 39.50			Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	Cubic meters 200.00			Per cubic metre	
TOTAL :-						


Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99096.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on various roads under Baroh Sub-Division, H.P.R.W.D., Baroh in Distt. Kangra (H.P.)
SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Radh Section).

S. No.	Description of items	Quantity	In fig.	Rate In words	Unit	Amount
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming. stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	Cubic metres 37.46			Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	Cubic meters 230.00			Per cubic metre	
TOTAL :-						


H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99733.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

Restoration of rain damages on various roads under Nagrota Sub-Division, H.P.P.W.D., Nagrota Division in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Dadh & Balidhar Section).

S. No.	Description of items	Quantity	Rate	Unit	Amount
1	2	3	In fig.	4	5
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.P.W.D technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	Cubic metres	38.90	Per cubic metre	7
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	Cubic meters	210.00	Per cubic metre	
TOTAL :-					

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99296.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT TWO MONTHS

Restoration of rain damages on various roads under Baroh Sub-Division, H.P.P.W.D., Baroh in Distt. Kangra (H.P.)

Providing and laying G-III and Removal of slips etc; (Sunhi Section).

NAME OF WORK :-
SUB HEAD :-

S. No.	Description of Items	Quantity	Rate	Unit	Amount
		In fig.	In words		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	38.12		Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	220.00		Per cubic metre	
TOTAL :-					

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.


Schedule of Quantity

ESTIMATED COST :- ₹ 99257.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on various roads under Tanda Sub-Division, H.P.P.W.D., Tanda in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc;

S. No.	Description of items	Quantity	Rate	Unit	Amount
1	2	3	4	5	6
In fig.	In words	7			
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point two cubic metre) per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	38.10		Per cubic metre	
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	220.00		Per cubic metre	
TOTAL :-					


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.