

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2024-25- 17986

Dated:- 15-03-2025

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _ Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- NIT copy & 9 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **20-03.2025** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **19.03.2025** up to **4:00 P.M.** and the application for issue of tender form shall be received on **19.03.2025** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages on various roads under Nagrota Sub- Division HP PWD Nagrota Bagwan in Distt. Kangra H P (SH: Providing and laying G-III and Removal of slips etc (Nagrota Bagwan Section).	95402.00	1950	Two Months
2	A/R & M/O Kangra Tanda Thanpuri Sadarpur road km 0/00 to 6/00 in distt. Kangra HP (SH: Bush Cutting at various Rds).	97380.00	1950.0	Two Months
3	Annual repair and Maintance of various road under Nagrota Sub- division HP PWD Nagrota Bagwan in distt. Kangra HP (SH: Construction of Unlined drain and filling of berms etc. Nagrota Bagwan Section).	83967.00	1700.00	Two Months
4	Construction of School of Nursing in Dr. RPGMC at Tanda in Distt. Kangra HP Deposit work (SH: Balance work of providing and laying carpet flooring in Additional Alteration (civil work) Critical care Skill Lab / Simulation Lab etc)	86775.00	1750.00	Two Months
5	Construction of link road from Barohbar to manimahesh in Distt. Kangra H P (SH: Construction of vented causeway alongwith wing walls at Rd 0/645 (P-III)	99707.00	2000.00	Two Months
6	Construction of Parking and Shopping complex at Nagrota Bagwan in district Kangra HP (SH: Geo Technical investigation).	97500.00	1950.00	One Months
7	Construction of School of Nursing in Dr. RPGMC at Tanda in Distt. Kangra HP Deposit work (SH: Balance work of providing and laying carpet flooring in Additional Alteration (civil work) Critical care Skill Lab / Simulation Lab etc)	86736.00	1750.00	Two Months
8	Annual repair and Maintance of various road under Nagrota Sub- division HP PWD Nagrota Bagwan in distt. Kangra HP (SH: Construction of Unlined drain and filling of berms etc. Nagrota Bagwan Section).	82600.00	1700.00	Two Months
9	Construction of Parking and Shopping complex at Nagrota Bagwan in district Kangra HP (SH: Geo Technical investigation).	97500.00	1950.00	One Months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2024-25- **17944-64**

Dated/ **15-03-2025**

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Executive Engineer IT Cell Shimla HP PWD Shimla.
3. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. All the S.E.s/E.E.s under North Zone.
6. The Sub-Divisional Officer(C) Nagrota Bagwan.
7. All the Assistant Engineer under this Division.
8. The Drawing /Accounts Branch in this office.
9. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2024-25-1790569 Dated:- 15-03-2025 are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST: - ₹ 95402.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on various roads under Nagrota Sub-Division, H.P.P.W.D., Nagrota Bagwan in Distt. Kangra (H.P.)

SUB HEAD :- Providing and laying G-III and Removal of slips etc; (Nagrota Bagwan Section).

S. No.	Description of items	Quantity	In fig.	Rate In words	Unit	Amount
			4	5		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point Twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	37.26 Cubic metres			Per cubic metre	7
2	Removal of muck, slips and boulder etc; in involving any kind of soil inclusive of all lead and lift upto 200 mtrs (Two hundred metres) complete and as directed by the Engineer-in-charge.	200.00 Cubic meters			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 97380.00
EARNEST MONEY : - Rs. 1950.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- A/R & M/O M/O Kangra Tanda Thanpuri Sadarpur Road Km 0/00 to 6/00 in Distt. Kangra Himachal Pradesh
SUB-HEAD :- Bush cutting at various RDs

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm (Thirty centimetres) measured at a height of 1 metre above ground and removal of rubbish upto any distance of outside the periphery of the area cleared: as directed by the Engineer-in-Charge including entire carriage of materials within all leads, lifts and other incidentals.	13525.00 Square meters			Per square metre	
TOTAL: -						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 83967.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Annual repair and maintenance of various road under Nagrota Sub-Division, H.P.W.D., Nagrota Bagwan in Distt. Kangra (H.P.)
 SUB HEAD :- Construction of Unlined drain and filling of berms etc; (Nagrota Bagwan Section).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site complete, including entire carriage of materials within all leads, lifts and other incidentals..	1000.00 Running meters			Per running metre	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead (Maintenance of Earthen shoulder (filling with fresh selected soil) as per technical specification Clause 1903, as per directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	1728.00 Square meters			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 86775.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of School of Nursing in Dr. R.P.Govt. Medical College at Tanda in Ditt.Kangra, (Himachal Pradesh). **DEPOSIT WORK.**

SUB-HEAD :- Balance work of providing and laying carpet flooring in Additional Alteration (Civil work) Critical Care Skill Lab./Simulation Lab. etc;

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 3.15mm (Three point fifteen millimetre) thick non-woven carpet in flooring with 8mm (Eight millimetre) thick pile height any shade and colour complete as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	44.50 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99707.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road from Barohbar to Manimahesh in Distt. Kangra (H.P.)
 SUB HEAD :- Construction of vented causeway alongwith wing walls at RD 0/645 (P-III)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	15.04 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	2.14 Cubic metres			Per cubic metre	
3	Providing concrete for plain/reinforced concrete in substructure complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 in 1:2.5:5 (One cement : Two and half sand : five graded) broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size PCC grade M-15 (M-Fifteen), as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	5.41 Cubic metres			Per cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	8.45 Cubic metres			Per cubic metre	
5	Providing and laying non-pressure NP2 class R.C.C. hume pipes 900mm (Nine hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	5.00 Running metre			Per running metre	
6	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	2.10 Running metres			Per running metre	
7	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	4.03 Cubic metres			Per cubic metre	

8	Filling available excavated earth (excluding rock) intranches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer -in - charge.as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	7.10 Cubic metres			Per cubic metre
TOTAL :-					


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97500.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Parking and Shopping Complex at Nagrota Bagwan in District Kangra (Himachal Pradesh)
 SUB-HEAD :- Geo-technical Investigation.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig 4	In words 5		
1	Investigation Bearing capacity of soil at Bridge Site at different locations of minimum 15.00 (fifteen) meter depth of each bore and submitted the test result complete in all respect as per H.P.D. technical specifications as directed by the Engineer-Incharge including entire carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3 13.00 Running metres			6 Per running metre	7
TOTAL :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 86736.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of School of Nursing in Dr. R.P.Govt. Medical College at Tanda in Diti.Kangra, (Himachal Pradesh). DEPOSIT WORK.
 SUB-HEAD :- Balance work of providing and laying carpet flooring in Additional Alteration (Civil work) Critical Care Skill Lab./Simulation Lab. etc;

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 3.15mm (Three point fifteen millimetre) thick non-woven carpet in flooring with 8mm (Eight millimetre) thick pile height any shade and colour complete as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax. GST and any other taxes imposed by the Government.	44.48 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 82600.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Annual repair and maintenance of various road under Nagrota Sub-Division, H.P.P.W.D., Nagrota Bagwan in Distt. Kangra (H.P.)
 SUB HEAD :- Construction of Unlined drain and filling of berms etc; (Nagrota Bagwan Section).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site complete, including entire carriage of materials within all leads, lifts and other incidentals..	3 1120.00 Running meters	4	5	6 Per running metre	7
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead (Maintenance of Earthen shoulder (filling with fresh selected soil) as per technical specification Clause 1903, as per directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	1440.00 Square meters			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97500.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Parking and Shopping Complex at Nagrota Bagwan in District Kangra (Himachal Pradesh)
SUB-HEAD :- Geo-technical Investigation.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig 4	In words 5		
1	Investigation Bearing capacity of soil at Bridge Site at different locations of minimum 15.00 (fifteen) meter depth of each bore and submitted the test result complete in all respect as per H.P.P.D. technical specifications as directed by the Engineer-Incharge including entire carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3 13.00 Running metres			6 Per running metre	7
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.