



Office of the
Executive Engineer
Una Division, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No.PWU/CB//TA/Tender/2024-25/- 160/7-22

Dated - 10-03-2025

To

The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.


Subject: - Regarding publication of Tenders Notice.

Sir,

"JAI HIND"


Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.


Executive Engineer,
Una, Division,
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.


Executive Engineer,
Una, Division
HPPWD, Una

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"**

Sealed item rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Una Division HPPWD Una H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office or before **19.03.2025 upto 11.00 A.M.** and will be opened on the same day at **11.30 A.M.** in presence of the intending contractor s or their authorized representatives who may like to be present. If it happened be holiday on the day of opening of tender the same will be opened on next working day at the same time. The application for obtaining the tender forms will be received latest by **17.03.2025 at 10.00 AM upto 11.00 Noon** and the tender form can be had from this office upto **18.03.2025 at 10.00 AM to 3.00 PM** against cash payment (non-refundable).

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Una Division HPPWD Una , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice. The offers of the tender (s) shall be kept open for 75 days from the date of opening the tender(s).

Sr. No.	Name of work	Estimate d cost	Earnest Money	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	Repair of Restoration of Rain damages of internal road at IRB Bangarh km 0/0 to 1/600 (SH:- Retaining wall near Barrack No.2 Mohal (Phase-I)	98832/-	2,000/-	One Month	350/-	Class-C & D
2	Repair of Restoration of Rain damages of internal road at IRB Bangarh km 0/0 to 1/600 (SH:- Retaining wall near Barrack No.2 Mohal (Phase-III)	98832/-	2,000/-	One Month	350/-	Class-C & D
3	C/O GraminSampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop uptoJatinder House ward No.05 at Barsara GP Jankour (under VKVNY) (SH:- P/L 60 mm thick pavers blocks & C/O V-shape drain) (Phase-I) (Deposit work)	98365/-	2000/-	One Month	350/-	Class-C & D
4	C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop uptoJatinder House ward No.05 at Barsara GP Jankour (under VKVNY) (SH:- P/L 60 mm thick pavers blocks & C/O V-shape drain) (Phase-II) (Deposit work)	98529/-	2,000/-	One Month	350/-	Class-C & D
5	Construction of Path & Paver block near the house of Sh. Tara Singh GP JalgranTabba tehsil & Distt. Una under VKVNY scheme (D.W.) (Phase-III)	78809/-	1600/-	One Month	350/-	Class-C & D
6	Repair of Path Ram Asra House to Vidya Sagar House ward No. 5 in Lower Dehlan (GP Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/0 to 0/053) (Deposit work)	99,913/-	2,000/-	One Month	350/-	Class-C & D
7	Repair of Path Main link road to House of Des Raj ward No.7 in Lower Dehlan (G.P. Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/0 to 0/040) (Deposit work)	99,834/-	2,000/-	One Month	350/-	Class-C & D

8	Repair of Path Main link road to House of Des Raj ward No.7 in Lower Dehlan (G.P. Lower Dehlan) (SH:- P/L CC pavement, 150 mm PVC pipe & MS Covers etc. in RD 0/040 to 0/080) (Deposit work)	99,834/-	2,000/-	One Month	350/-	Class-C & D
9	C/O link road to Bana Beli Ram Dera to ward No.06 LalsingiUna km 0/0 to 1/600 (SH:- C/O Brest wall at RD 0/969 to 1/0) Under OTMNP	99,894/-	2,000/-	One Month	350/-	Class-C & D
10	Repair of damages on UnaMalahat road km 0/0 to 2/0 (SH:- Earthen Shoulder at RD 0/0 to 2/0) Under OFC Deposit	96,600/-	2,000/-	One Month	350/-	Class-C & D
11	Construction of path Muhalla Kalia Nichla ward No.3 GP Jakhera (SH:-P/L CC pavement, 150mm PVC pipes & MS covers etc. in RD 0/135 to 0/167) (Deposit work)	99,727/-	2,000/-	One Month	350/-	Class-C & D
12	Construction of Retaining wall and Gramin Samprak near the house of Gurcharan Muhalla Dole ward No.1, GP Rampur Tehsil & Distt. Una (HP0 (SH:- C/O R/wall at RD 0/011 to 0/014) (Scheme ID-VKV 2024/27) (Deposit work)	99,600/-	2,000/-	One Month	350/-	Class-C & D
13	Repair of damages on link road from Dehlan to Basdehra upto Punjab Boundary km 0/0 to 2/400.(SH:- Providing and laying 450mm Dia NP2 pipes in RD 2/231 to 2/288(UNDER MDPE Gas pipe line Deposit	99,750/-	2000/-	One Month	350/-	Class-C & D
14	Repair of damages on link road from Dehlan to Basdehra upto Punjab Boundary km 0/0 to 2/400.(SH:- Providing and laying 450mm Dia NP2 pipes in RD 2/300 to 2/357(UNDER MDPE Gas pipe line Deposit	99,750/-	2000/-	One Month	350/-	Class-C & D
15	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/045 to 0/060 (RHS) (Deposit work)	99,688/-	2,000/-	One Month	350/-	Class-C & D
16	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/135 to 0/150 (RHS) (Deposit work)	97,648/-	2,000/-	One Month	350/-	Class-C & D
17	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/060 to 0/075 (RHS) (Deposit work)	99,348/-	2,000/-	One Month	350/-	Class-C & D
18	Construction of road from Santoshgarh Swan bridge Left Bank to Gowthani Aquachem Private Limited Factory (SH:- C/O R/wall etc. in RD 0/150 to 0/165 (RHS) (Deposit work)	97,308/-	2,000/-	One Month	350/-	Class-C & D
19	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/850) under Black spot	99,899/-	2,000/-	One Month	350/-	Class-C & D
20	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/950) under Black spot	99,503/-	2,000/-	One Month	350/-	Class-C & D
21	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/220 to 1/237) (RHS) under OFC Deposit	97548/-	2,000/-	One Month	350/-	Class-C & D
22	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/271 to 1/288) (RHS) under OFC Deposit	97548/-	2,000/-	One Month	350/-	Class-C & D
23	Repair of damages on Behdala Jankour via Abada Barana road km 0/0 to 4/600 (SH:- C/O U-shape drain both side at RD 1/220 to 1/260) (LHS) under OFC Deposit	98165/-	2,000/-	One Month	350/-	Class-C & D
24	Repair of damage on 120 mtr. span bridge at Rampur on Una Santoshgarh road at RD 1/760 (SH:- P/L bituminous concrete both side ramp) under OFC Deposit	78450/-	1600/-	One Month	350/-	Class-C & D

25	Improvement of Vulnerable spots on the Old Hoshiarpur road km 0/0 to 0/430 (SH:-Providing and erecting crash barrier, Convex mirror at RD 1/900) under Black spot	98,549/-	2,000/-	One Month	350/-	Class-C & D
26	Repair of damages on Behdala Chattara Pirnigah road km 0/0 to 2/0 (SH:- P/L overlay interlocking paver at Rd 0/631 to 0/655.20) Under OFC Deposit)	99,899/-	2,000/-	One Month	350/-	Class-C & D
27	Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760 SH:- Channelization of Khad on upstream side of Rampur bridge 1/760 RHS	98,847/-	2,000/-	One Month	350/-	Class-C & D
28	Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760 SH:- Channelization of Khad on upstream side of Rampur bridge 1/760 along the length of bridge	99,286/-	2,000/-	One Month	350/-	Class-C & D
29	Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760 SH:- Channelization of Khad on upstream side of Rampur bridge 1/760 LHS	99,537/-	2,000/-	One Month	350/-	Class-C & D
30	C/o Gramin Sampark Marg with R/Wall near the H/o Sh. Bodh Raj Raman Kumar Ward No. 9 Sunehra at RD 0/0 to 0/111 (SH:- C/o R/Wall at RD 0/100 to 0/103.45) (Deposit work)	98,005/-	2,000/-	One Month	350/-	Class-C & D
31	C/o Gramin Sampark Marg with R/Wall near the H/o Sh. Bodh Raj Raman Kumar Ward No. 9 Sunehra at RD 0/0 to 0/111 (SH:- C/o R/Wall at RD 0/106.90 to 0/110.35)(Deposit Work)	98,005/-	2,000/-	One Month	350/-	Class-C & D
32	C/o Gramin Sampark marg M/R to H/o Mukesh Kumar Ward no. 3 Jankour Km 0/0 to 0/080 (SH:- P/L interlocking paver blocks at RD 0/0 to 0/026.95) (Deposit Work)	99,961/-	2,000/-	One Month	350/-	Class-C & D
33	C/o Gramin Sampark marg M/R to H/o Mukesh Kumar Ward no. 3 Jankour Km 0/0 to 0/080 (SH:- P/L interlocking paver blocks at RD 0/026.95 to 0/053.91) (Deposit Work)	99,979/-	2,000/-	One Month	350/-	Class-C & D
34	Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km 0/0 to 2/500 Tehsil & Distt. Una (HP) (SH:- C/o R/wall at RD 2/455 to 2/460) (Deposit Work)	99,053/-	2,000/-	One Month	350/-	Class-C & D
35	Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km 0/0 to 2/500 Tehsil & Distt. Una (HP) (SH:- C/o R/wall at RD 2/460 to 2/465) (Deposit work)	99,393/-	2,000/-	One Month	350/-	Class-C & D
36	Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km. . 0/0 to 0/300 (SH:- P/L RCC NP2 pipes in RD. 0/180 to 0/209(LHS) (Deposit work)	99210/-	2000/-	One Month	350/-	Class-C & D
37	Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km. . 0/0 to 0/300 (SH:- P/L RCC NP2 pipes in RD.0/215 to 0/244(LHS) Deposit work	99210/-	2000/-	One Month	350/-	Class-C & D
38	Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km. . 0/0 to 0/300 (SH:- P/L RCC NP2 pipes in RD0/260 to 0/289(LHS) (UNDER MDPE Gas pipe line Deposit)	99210/-	2000/-	One Month	350/-	Class-C & D
39	Construction Harijan basti Fathewal to village Bangarh Km. 0/0 to 2/200(SH:- C/O Embankment km. 1/800 to 1/940(UNDER OTMNP)	92400/-	2000/-	One Month	350/-	Class-C & D
40	Construction Harijan basti Fathewal to village Bangarh Km. 0/0 to 2/200(SH:- C/O Embankment km. 1/940 to 2/0 and C/o edge wall in km. 1/992 to 2/0(Under OTMNP)	94152/-	2000/-	One Month	350/-	Class-C & D

41	C/O Path with R/Wall & Drainage near the house of Sh. Dharampal GP Bharolian kalan (SH:- C/o U-shape drain & R/wall in RD . 0/070 to 0/096) (Deposit work)	77210/-	2000/-	One Month	350/-	Class-C & D
42	C/O Path with R/Wall & Drainage near the house of Sh. Dharampal GP Bharolian kalan (SH:- C/o U-shape drain & R/wall in RD . 0/024 to 0/046) (Deposit work)	94180/-	2000/-	One Month	350/-	Class-C & D
43	C/O Path with R/Wall & Drainage near the house of Sh. Dharampal GP Bharolian kalan (SH:- C/o U-shape drain & R/wall in RD . 0/048 to 0/071) (Deposit work)	94761/-	2000/-	One Month	350/-	Class-C & D
44	C/O Path with R/Wall & Drainage near the house of Sh. Dharampal GP Bharolian kalan (SH:- C/o U-shape drain & R/wall in RD . 0/0 to 0/023) (Deposit work)	94683/-	2000/-	One Month	350/-	Class-C & D
45	C/O Badehar Sasan Udaipur road km. 0/0 to 3/600(SH:- P/L NP2 pipes 300mm dia at RD. 0/135 to 0/160 LHS & CC Shoulder at RD. 0/312 to 0/328(RHS) (Under OTMNP)	99,381/-	2000/-	One Month	350/-	Class-C & D
46	C/O Badehar Sasan Udaipur road km. 0/0 to 3/600(SH:- P/L NP2 pipes 450 mm dia at RD. 0/395 to 0/415 RHS & CC paved Shoulder at RD. 0/358 to 0/380(RHS) (Under OTMNP)	99,958/-	2000/-	One Month	350/-	Class-C & D
47	C/O Badehar Sasan Udaipur road km. 0/0 to 3/600(SH:- P/L NP2 pipes 450 mm dia at RD.0/415 to 0/ 440(RHS) (Under OTMNP)	99,958/-	2000/-	One Month	350/-	Class-C & D
48	C/O Badehar Sasan Udaipur road km. 0/0 to 3/600(SH:- P/L NP2 pipes 450 mm dia at RD.0/380 to 0/495 RHS & CC Paved shoulder at RD .0/328 to 0/358(RHS) (UNDER OTMNP)	99312/-	2000/-	One Month	350/-	Class-C & D
49	Repair of Damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona Km. 0/ to 0/800(SH:- P/L interlocking Cement concrete paver blocks at RD 0/293 to 0/300 & 0/478 to 0/488) (UNDER MDPE Gas pipe line Deposit)	99,528/-	2000/-	One Month	350/-	Class-C & D
50	Repair of Damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona Km. 0/ to 0/800(SH:- P/L interlocking Cement concrete paver blocks at RD 0/303 to 0/310 & 0/491 to 0/510) (UNDER MDPE Gas pipe line Deposit)	99,528/-	2000/-	One Month	350/-	Class-C & D
51	Repair of Damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona Km. 0/ to 0/800(SH:- P/L interlocking Cement concrete paver blocks at RD 0/250 to 0/257 & 0/400 to 0/410) (UNDER MDPE Gas pipe line Deposit)	99,528/-	2000/-	One Month	350/-	Class-C & D
52	Repair of Damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona Km. 0/ to 0/800(SH:- P/L interlocking Cement concrete paver blocks at RD 0/260 to 0/267 & 0/412 to 0/422) (UNDER MDPE Gas pipe line Deposit)	99,528/-	2000/-	One Month	350/-	Class-C & D
53	A/R & M/O Various Non -Residential building at Unadistt. Una(SH:- Providing Services out sources basis of one No. supervisor /work inspector for period for period of five month i.e . Ist April 2025 to 31 August 2025)	82,716/-	2000/-	One Month	350/-	Class-C & D
54	Repair of damages on Bharolian Badehar Charatgarh road km. 0/0 to 4/200(SH:- C/O U-Shape drain with chambers etc in RD. 3/283 to 3/311) (UNDER MDPE Gas pipe line Deposit)	99,593/-	2000/-	One Month	350/-	Class-C & D
55	Repair of damages on Bharolian Badehar Charatgarh road km. 0/0 to 4/200(SH:- C/O U-Shape drain with chambers etc in RD. 3/255 to 3/280) (UNDER MDPE Gas pipe line Deposit)	99,519/-	2000/-	One Month	350/-	Class-C & D

56	Repair of damages on Bharolian Badehar Charatgarh road km. 0/0 to 4/200(SH:- C/O U-Shape drain with chambers etc in RD. 3/314 to 3/342) (UNDER MDPE Gas pipe line Deposit)	99,593/-	2000/-	One Month	350/-	Class-C & D
57	Repair of damages on Bharolian Badehar Charatgarh road km. 0/0 to 4/200(SH:- C/O U-Shape drain with chambers etc in RD. 3/345 to 3/373) (UNDER MDPE Gas pipe line Deposit)	99,593/-	2000/-	One Month	350/-	Class-C & D
58	Repair of damages on Bharolian Badehar Charatgarh road km. 0/0 to 4/200(SH:- C/O U-Shape drain with chambers etc in RD. 3/375 to 3/403) (UNDER MDPE Gas pipe line Deposit)	99,593/-	2000/-	One Month	350/-	Class-C & D
59	Repair of damages link road to village Bass km. 0/0 to 0/750(SH:- Providing and laying 300mm dia RCC pipe NP2 from km.0/730 to 0/750) (UNDER OFC Deposit)	98462/-	2000/-	One Month	350/-	Class-C & D
60	Repair of damages on Dehlan Badehar road km 0/0 to 3/060(SH;-C/O U-Shape drain , P/L NP2 pipe with CC Chambers etc. in RD. 0/895 to 0/917(UNDER MDPE Gas pipe line Deposit	99,922/-	2000/-	One Month	350/-	Class-C & D
61	Repair of damages on Dehlan Badehar road km 0/0 to 3/060(SH;-C/O U-Shape drain in RD . 0/919 to 0/937(UNDER MDPE Gas pipe line Deposit)	97,993/-	2000/-	One Month	350/-	Class-C & D
62	Repair of damages on Dehlan Badehar road km 0/0 to 3/060(SH;-C/O U-Shape drain in RD . 0/940 to 0/960(UNDER MDPE Gas pipe line Deposit)	97,998/-	2000/-	One Month	350/-	Class-C & D
63	Repair of Damages on Dehlan Badehar road km. 0/0 to 3/060 (SH:- C/O U-Shape drain , P/L NP2 pipe with CC Chambers etc . in RD. 0/870 to 0/892(UNDER MDPE Gas pipe line Deposit)	99,657/-	2000/-	One Month	350/-	Class-C & D
64	Restoration of damages Behdala Jakhera road Km. 0/0 to 4/600(SH:- C/O U-Shape drain along road from RD. 2/630 to 2/658.50 UNDER OFC Deposit)	99,052/-	2000/-	One Month	350/-	Class-C & D
65	Repair of damages link road Dehlan Jakhera Morbar Bhatoli Road KM. 0/0 to 3/600(SH:-Repair of U- Shape drain at Rd. 1/300 to 1/321) (UNDER MDPE Gas pipe line Deposit)	99,983/-	2000/-	One Month	350/-	Class-C & D
66	Repair of damages link road Dehlan Jakhera Morbar Bhatoli Road KM. 0/0 to 3/600(SH:-Repair of U- Shape drain at Rd. 1/324 to 1/345) (UNDER MDPE Gas pipe line Deposit)	99,947/-	2000/-	One Month	350/-	Class-C & D
67	Repair of damages link road Dehlan Jakhera Morbar Bhatoli Road KM. 0/0 to 3/600(SH:-Repair of U- Shape drain at Rd. 1/372 to 1/393) (UNDER MDPE Gas pipe line Deposit)	99,952/-	2000/-	One Month	350/-	Class-C & D
68	Repair of damages link road Dehlan Jakhera Morbar Bhatoli Road KM. 0/0 to 3/600(SH:-Repair of U- Shape drain at Rd. 1/348 to 1/369) (UNDER MDPE Gas pipe line Deposit)	99,957/-	2000/-	One Month	350/-	Class-C & D
69	Repair of damages link road Dehlan Jakhera Morbar Bhatoli Road KM. 0/0 to 3/600(SH:-Repair of U- Shape drain at Rd. 1/396 to 1/405) (UNDER MDPE Gas pipe line Deposit)	99,859/-	2000/-	One Month	350/-	Class-C & D

TERM & CONDITIONS:-

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.

[Handwritten signature]

3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board "Men at work / work in progress" shall be placed " by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
10. The tender shall be issued to those contractors/ firms who have not more than two works in hand.
11. Work should be completed by the contractor within stipulated period.


Executive Engineer
Una Division, HP: PWD,
Una.

No. PWU/CB/T-1/2024-25:- 15967-16016

Dated:- 10-03-2025

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur/ The S.E. 15th circle HP PWD Una.
3. All the Assistant Engineers under this Division.
4. The Deputy Commissioner, Una.
5. The Sub Divisional Officer (C), Una.
6. The District Treasury Officer, Una.
7. The Block Development Officer, Una.
8. The Municipality, Una.
11. All the Head of the Branches in this office.
12. The Notice Board.



Executive Engineer
Una Division, HP: PWD,
Una

Certificate

Certified that the tenders called vide this office letter
No.PWU/CB/T-I/2024-25:- 15967-16016 dated-10.03.2025 emergent nature and in
Public interest.


Executive Engineer,
Una Division, ~~HP~~ PWD,
Una

SCHEDULE OF QUANTITY						
					Estimated Cost	99832/-
Name of work :Repair of Restoration of Rain damages of internal road at IRB Bangarh km.0/0 to 1/600 (SH: Retaining wall near Barrack No.2 Mohal.(Phase-I)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.84	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803. 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental.	29.23	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material within all leads and lifts and other incidental.	11.00	Each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					Total:	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						


 Executive Engineer
 Una Divn. HP. PWD.,
 Una

(2)

SCHEDULE OF QUANTITY							Estimated Cost	99832/-
Name of work :Repair of Restoration of Rain damages of internal road at IRB Bangarh km.0/0 to 1/600 (SH: Retaining wall near Barrack No.2 Mohal.(Phase-III)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.84	Per cubic metre					
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification. Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	29.23	Per cubic metre					
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental.	11.00	Each					
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018							Total:	
2) The rates shall be including of all types of taxes including GST ectra)								
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021								


Executive Engineer
Una Divn.HP.PWD.,
Una

196

3

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (Under VKVNY) (SH: P/L 60mm thick pavers blocks & C/O V-shape drain)(Phase-I) (Deposit work)						
					Estimated Cost	98365/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.31	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.88	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level:- as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.15	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 200mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Per running metre			

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark. C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	61.25	Per square metre			
6	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD
 Una

197

4

SCHEDULE OF QUANTITY

Name of work :C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (Under VKVNY) (SH: P/L 60mm thick pavers blocks & C/O V-shape drain)(Phase-II) (Deposit work)

Estimated Cost 98529/-
Earnest Money 2000/-
Time limit one month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.05	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.50	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.05	Per cubic metre			
4	Providing and laying in-position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.58	Per cubic metre			

5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 200mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.00	Per running metre			
6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	61.10	Per square metre			
7	Providing and laying in position specified grade of reinforced cement concrete -1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.14	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer


Una Divn. HP. PW.D.,

Una

148

SCHEDULE OF QUANTITY

					Estimated Cost	78809/-
Name of work :Construction of Path & Paver block near the house of Sh. Tara singh GP Jalgran Tabbha tehsil & Distt.Una under VKVNY scheme.(Deposit work) Phase-III					Earnest Money	1600/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	0.47	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.24	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	54.95	Per square metre			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						


Executive Engineer
Una Divn.HP.PWD.,Una

203

6

SCHEDULE OF QUANTITY							
Name of work : Repair of Path Ram Aasra House to Vidya Sagar House Ward No.5 in Lower Dehlan(G.P.Lower Dehlan) (SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/0 to 0/053) (Deposit work)							
						Estimated Cost	\$9913/-
						Earnest Money	2000/-
						Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.88	Per cubic metre				
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.76	Per cubic metre				
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.18	Per cubic metre				
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	57.50	Per running metre				

5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per direction by the Engineer-in-charge .The rate includes octroi, royalty, malkhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.95	Per cubic metre			
6	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malkhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government. .	37.50	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etc (ra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer

Una Divn.HP.PWD.

Una

183

7

SCHEDULE OF QUANTITY							
Name of work :Repair of Path Main link road to House of Des Raj Ward No.7 in Lower Dehlan(G.P.Lower Dehlan) (SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/0 to 0/040) (Deposit work)							
						Estimated Cost	99834/-
						Earnest Money	2000/-
						Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	3.00	Per cubic metre				
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.01	Per cubic metre				
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.84	Per cubic metre				
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	44.50	Per running metre				

5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.40	Per cubic metre			
6	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	37.50	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Una Divn. HP. PWD.,
Una

184

8


SCHEDULE OF QUANTITY

Name of work : Repair of Path Main link road to House of Des Raj Ward No.7 in Lower Dehlan (G.P. Lower Dehlan)
(SH: P/L CC Pavement, 150mm PVC pipe & MS Covers etc. in RD.0/040 to 0/080) (Deposit work)

Estimated Cost 99834/-
Earnest Money 2000/-
Time limit one month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.01	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.84	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete: 150mm dia of Supreme / Kisan / finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	44.50	Per running metre			
5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge. The rate includes octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.40	Per cubic metre			

6	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	37.50	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

218

9

DRAFT SCHEDULE OF QUANTITY

Estimated cost 99894/-

Earnest money 2000/-

Time limit One month

Name of Work: C/O link road to Baba Beli Ram Dera to ward No.6 Lalsingi Una km.0/0 to 1/600(SH: C/O Breast wall at RD.0/969 to 1/0) Under OTMNP

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.23	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	28.25	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	34.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021					

Executive Engineer,
Una Divn. HP. PWD., Una

222

SCHEDULE OF QUANTITY


SCHEDULE OF QUANTITY						
Name of work :Repair of damages on Una Malahat road km.0/0 to 2/0 (SH: Earthern shoulder at RD.0/0 to 2/0)				Estimated Cost		96600/-
) Under OFC Deposit				Earnest Money		2000/-
				Time limit		One month
Sl No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Maintenance of earthen shoulder (stripping of excess soil) stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specicical clause 1903 including carriage of material within all leads and lifts other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4600.00	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

K. K. K.
Executive Engineer,
Una Division, HPPWD.,
Una

204 (1)

SCHEDULE OF QUANTITY						
Name of work :Construction of Path Muhalla Kalia Nichla ward No.3 GP Jakhera (SH: P/L CC Pavement, 150mm PVC pipes & MS covers etc. in RD.0/135 to 0/167)(Deposit work)						
					Estimated Cost	99724/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	8.37	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.37	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing-out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802:803:1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.37	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc complete 150mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	32.00	Per running metre			

5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.37	Per cubic metre			
6	Steel work work (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	40.50	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer

Una Divn.HP:PW.D.

Una


202

19

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							Estimated Cost	99600/-
Name of work :Construction of Retaining wall and Gramin Samprak near the house of Gurcharan Muhalla Dole ward No.1 , G.P.Rampur Tehsil & Distt.Una (HP)(SH: C/O R/wall at RD. 0/011 to 0/014))(Scheme ID-VKV 2024/27) (Deposit work)							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	9.85	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement:five sand: ten graded stone aggregate 40mm(forty millimetre) nominal size plain/reinforced concrete in open foundations and curing complete including cost of form work on ground or under water including pumping and bailing out water,dewatering, removal of sluch as required at site which may arrise at the time of laying under water complete in all heights/depths in Retaining wall and parapets etc.complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per drawing and HP.PWD., technical specification including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.10	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	26.00	Per cubic metre					

4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each			
5	Back filling with granular material behind abutments, wing wall, return walls and retaining walls complete as per drawings and technical specification MORD technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.25	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PW
 Una

225

13

Schedule of Quantity

Estimated Cost :- Rs. 99750.00

Name of work: Repair of damages on link road from Dehlan to Basdehra upto Punjab boundary Km 0/0 to 2/400.

Earnest Money :- Rs. 2000.00

SH:- Providing and Laying 450mm Dia NP2 pipes in RD 2/231 to 2/288 (Under MDPE Gas pipe line Deposit)

Time limit :-

One Month

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying non-pressure NP2 class (light duty) 450 mm dia. R.C.C. pipe R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete complete including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	57.00	Metre			
	Total					

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018

2) The rates shall be inclusive of all types of taxes including GST etcetera)


Executive Engineer
Una Divn.HP.PWD.,
Una

274

14

Schedule of Quantity

Name of work: Repair of damages on link road from Dehlan to Basdehra upto Punjab boundary Km 0/0 to 2/400.

Estimated Cost :- Rs. 99750.00

Earnest Money :- Rs. 2000.00

SH:- Providing and Laying 450mm Dia NP2 pipes in RD 2/300 to 2/357 (Under MDPE Gas pipe line Deposit)

Time limit :-

One Month

Sr. No.	Item of work	Quantity	Unit	Rate		Amount
				In Figures	In Words	
1	Providing and laying non-pressure NP2 class (light duty) 450 mm dia. R.C.C. pipe R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete complete including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	57.00	Metre			
	Total					

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018

2) The rates shall be inclusive of all types of taxes including GST etcetera)

K. S. Sharma
Executive Engineer
Una Divn.HP.PWD,
Una

222

15

SCHEDULE OF QUANTITY

Name of work : Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/045 to 0/060(RHS) (Deposit work)

Estimated Cost 99688/-
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Unit	RATE In		AMOUNT
			Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	15.90 Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental.	28.05 Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	26.00 Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018			Total:	
	2) The rates shall be including of all types of taxes including GST ectra)				
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(E) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021				

Executive Engineer
Jna Divn. HP. PWA
Una

228

SCHEDULE OF QUANTITY						
Name of work : Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/135 to 0/150(RHS) (Deposit work)				Estimated Cost	97648/-	
				Earnest Money	2000/-	
				Time limit	One month	
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other Incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octrol, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	14.00	Each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					Total:	
2) The rates shall be including of all types of taxes including GST etc(ra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021						


R. K. Singh
Executive Engineer
Una Divn.HP.PWD
Una

229

(17)

SCHEDULE OF QUANTITY

					Estimated Cost	99348/-
	Name of work : Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/060 to 0/075(RHS) (Deposit work)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	15.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	24.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD.
 Una

230

SCHEDULE OF QUANTITY						
			(18)		Estimated Cost	97308/-
	Name of work :Construction of road from Santoshgarh Swan bridge left Bank to Gowthani Aquachem Private Limited Factory (SH: C/O R/wall etc. in RD.0/150 to 0/165(RHS) (Deposit work)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work		Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.90	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.	28.05	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	12.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer
Una Divn.HP.PWD,
Una

222

SCHEDULE OF QUANTITY						(19)				
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, comvex mirror at RD.1/850(Deposit work) <u>under black spot</u> .								Estimated Cost	99899/-	
								Earliest Money	2000/-	
								Time limit	one month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT				
				Figures	Words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre							
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre							
3	Providing and erecting a "W" metal wear crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm. above road/ground level , fixed on ISMC series channel vertical post 150x75x5mm speed 2m centre to centre 1.8m. high 1.1m. below ground/ road level, all steel parts and fitments to be galvansed by hot dip process, all fittings to conform to IS: 1367 and IS: 1364 , metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm , 330mm long complete as per clause 810including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	17.00	Per Running metre							
4	Providing and fixing of road safety convex(size 80 cm) made of polycarbonate and ABS body suitable for indorr/ outdoor with hood complete with mounting hardware including post as per drawing and technical specifications including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.00	each							

5	Providing and fixing of dual-directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side)provided with twp steel zinc plated nails of 12mm and of length 120mm for fixing in road by hammering CAT PART No GPL-07-02 Make GREEN or equivalent as per direction of Engineer in-charge including carriage of material within all loads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.
 Una

228

SCHEDULE OF QUANTITY						
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, convex mirror at RD.1/950(Deposit work) under Black spot					Estimated Cost	99503/-
					Earnest Money	2000/-
					Time limit	one month
Sl No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.91	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.91	Per cubic metre			
3	Providing and fixing a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70mm above road/ground level fixed in ISMC series channel vertical post 150x75x5mm spaced 2m centre to centre 1.8m high 1.1m below ground level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS: 1367 and IS: 1384, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 6 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	18.00	Per Running metre			
4	Providing and fixing of dual-directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side)provided with two steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No.GPL-07-02 Make GREENs or equivalent as per direction of Engineer-in-charge including carriage of material within all leads and lifts	44.00	each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST etcra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

Executive Engineer

Una Divn.HP.PWD,Una

221

SCHEDULE OF QUANTITY				Estimated cost	97548/-
				Earnest money	2000/-
				Time limit	One month

Name of Work: Repair of damages on Behdala Jankour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/220 to 1/237)(RHS) Under O/C Deposit

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.77	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.06	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	18.03	Per cubic metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una

224

22

SCHEDULE OF QUANTITY						Estimated cost	97548/-
						Earnest money	2000/-
						Time limit	One month
Name of Work: Repair of damages on Behdals Jankour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/271 to 1/288)(RHS) Under OFC Deposit							
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in Rs.)	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.77	Per cubic metre				
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/ or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.06	Per cubic metre				
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	18.03	Per cubic metre				

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018.				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una

228

23

	SCHEDULE OF QUANTITY				Estimated cost	98165/-
--	----------------------	--	--	--	----------------	---------

Earnest money 2000/-

Time limit One month

Name of Work: Repair of damages on Belidala Janikour via Abada Barana road km.0/0 to 4/600(SH: C/O U-shape drain both side at RD.1/220 to 1/260)(LHS)
Under OFC Deposit

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	18.80	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.20	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	17.00	Per cubic metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out-water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights	120.40	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)D(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer ,
 Una Division, HPPWD.,
 Una

221

24

SCHEDULE OF QUANTITY						
					Estimated Cost	78450/-
	Name of work : <u>Repair</u> of road damage on 120 mtr. Span bridge at Rampur on Una Santoshgarh road at RD.1/760 (SH: P/L bituminous concrete both side ramp.) <u>Under ofc. Deposit</u>				Earnest Money	2000/- 1600/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.25	Per cubic metre			
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts. and other incidentals. The rate including octroi royalty, malkana toll taxes, GST, labour cess or taxes imposed by the Government	150.00	Per square metre			
3	Providing and applying tack coat with BITUMEN emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero decimal two five to zero decimal three zero kilogram) per square metre on the prepared dry and hungry bitumenious surface cleaned with Hydraulic broom as per specifications clause No. 503 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	150.00	Per Square metre			

4	Providing and laying bituminous concrete 30mm (thirty millimetre) thick with 9.5mm (nine point five millimetre) nominal minimum aggregate size with 100-120 TPH (one hundred to one hundred twenty tonne per Hour) (Hot Mix Plant) producing an average output of 75 (seventy five) tonnes per hour premixed with bituminous binder VG-30 @ 5.5% (five point five per cent) minimum aggregate grading as per table 500.15 and Filler @ 2% (two per cent) of weight of aggregates as per clause No. 509.2.4.2 design mix as per clause 509.4.3.2 transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, camber, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH -2014 specification clause No. 509 complete in all respects The Hot Mix Plant should be situated within the distance of 30Km (thirty kilometre) from work site including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.50	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					


 Executive Engineer
 Una Divn.HP.PWD.
 Una

229

SCHEDULE OF QUANTITY						
Name of work :Improvement of Vulnerable spots on the Old Hoshiarpur road km.0/0 to 0/430(SH: Provoding and erecting crash barrier, comvex mirror at RD.1/900(Deposit work) <i>under black spot.</i>					Estimated Cost	98549/-
					Estmated Money	2000/-
					Time limit	one month
No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty,maikhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,maikhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.70	Per cubic metre			
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam 100mm above road/ground level, fixed on ISMC series end metal vertical post 150x75x5mm spaced 2m centre to centre 1.8m, high 1.1m, below ground/ road level, all steel plates and fittings to be galvanised by hot dip process, all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a space of channel section 120x75x5mm, 330mm long complete as per clause 810including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.00	Per Running metre			
4	Providing and fixing of dual-directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 275x150x32mm having 6 glass large 12mm dia reflective lenses to one side(12 Nos.on both side)provided with twp steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No.GPL-07-02 Make GREENs or equivalent as per direction of Engineer-in-charge including carriage of material within all leads and lifts	51.00	each			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

K. K. K.
Executive Engineer
Una Divn.HP.PWD,Una

26

	SCHEDULE OF QUANTITY				Estimated cost	99899/-
--	----------------------	--	--	--	----------------	---------

Earnest money 2000/-
Time limit One month

Name of Work: Repair of damages on Behdala Chattara Pirnigah road km.0//0 to 2/0 (SH: P/L overlay interlocking paver at RD.0/631 to 0/655.20)(Under OFC Deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.70	Per cubic metre			
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of requiredstrength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extrasand 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	113.74	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Executive Engineer,
Una Divn.HPPWD,Una

237

(27)

Estimated cost:- Rs. :- 98847
 Earnest money:- Rs. :- 2000
 Time limit :- ^{one} ~~two~~ Month

DRAFT SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760

SH :- Channelization of Khad on upstream side of Rampur bridge 1/760 RHS

Sr. No.	Description of Item	Quantity	Unit	Rate	Rate in Words	Amount
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90 cum. Bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tx, sale tax, GST, labour cess or other taxes imposed by the by government.	945.00	Cum			
	Total					

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Chief Secy. To the Govt. of HP. Vide letter No

PBW(B)(17)2/2012 dated 7/8/2018

2) The rates shall be including of all types of taxes including GST etc

3) The bidder are requested to submit their bid as per notification issued by the Principal Sacy.PW to the Govt. of HP Vide Letter No

PBW(B)A(3)1/2020 dated 22/7/2020 & Govt.of HP vide letter No PBW(B)A(3)1/2020-1 dated 7/10/2021


 Executive Engineer
 Una Division
 H.P.P.W.D.Una

225

28

Estimated cost:- Rs. :- 99286
 Earnest money:- Rs. :- 2000
 Time limit :- ^{one}Two Month

DRAFT SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760

SH :- Channelization of Khad on upstream side of Rampur bridge 1/760 along the length of bridge

Sr. No.	Description of Item	Quantity	Unit	Rate	Rate in Words	Amount
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90 cum. Bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tx. sale tax, GST, labour cess or other taxes imposed by the by government.	949.20	Cum			
	Total					

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Chief Secy. To the Govt. of HP. Vide letter No

PBW(B)(17)2/2012 dated 7/8/2018

2) The rates shall be including of all types of taxes including GST etc

3) The bidder are requested to submit their bid as per notification issued by the Principal Sacy.PW to the Govt. of HP Vide Letter No

PBW(B)A(3)1/2020 dated 22/7/2020 & Govt of HP vide letter No PBW(B)A(3)1/2020-1 dated 7/10/2021


 Executive Engineer
 Una Division
 H.P.W.D.Una

286

29

Estimated cost:- Rs. :-

99537

Earnest money:- Rs. :-

2000

Time limit :-

One
Two Month**DRAFT SCHEDULE OF QUANTITY**

Name of work: - Restoration of Rain damage on 120 mtr span bridge at Rampur on Una Santoshgarh road at RD 1/760

SH :- Channelization of Khad on upstream side of Rampur bridge 1/760 LHS

Sr. No.	Description of Item	Quantity	Unit	Rate	Rate in Words	Amount
1	Excavation for roadway in marshy soil with hydraulic excavator 0.90 cum. Bucket capacity including cutting and loading in tippers and disposal within any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the by government.	951.60	Cum			
	Total					

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Chief Secy. To the Govt. of HP. Vide letter No PBW(B)(17)2/2012 dated 7/8/2018

2) The rates shall be including of all types of taxes including GST etc

3) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP Vide letter No

PBW(B)A(3)1/2020 dated 22/7/2020 & Govt. of HP vide letter No PBW(B)A(3)1/2020-1 dated 7/10/2021



Executive Engineer

Una Division

• H.P.P.W.D.Una

199

30

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark marg with R/wall near the h/o Sh. Bodh Raj Raman Kumar ward No.9 Sunehra at RD.0/0 to 0/111 (SH: C/O R/wall at RD.0/100 to 0/103.45)(Deposit work)					Estimated Cost	98005/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.43	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	26.92	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.00	each			

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification MORD 2014 clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.60	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etc(ira)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

201

(31)

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark marg with R/wall near the h/o Sh. Bodh Raj Raman Kumar ward No.9 Sunehra at RD.0/0 to 0/111 (SH: C/O R/wall at RD.0/106.90 to 0/110.35)(Deposit work)				Estimated Cost	98005/-	
				Earnest Money	2000/-	
				Time limit	one month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.43	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.92	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	each			

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification MORD 2014 clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.60	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

Kaushal
Executive Engineer
Una Divn, HP, PW
Una


194

32

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark marg M/R to H/O Mukesh Kumar ward No.3 Jankour km.0/0 to 0/080 (SH: P/L interlocking paver blocks at RD.0/0 to 0/026.95)(Deposit work)				Estimated Cost	99961/-	
				Earnest Money	2000/-	
				Time limit	one month	
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.81	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.70	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	72.77	Per square metre			

4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkarja, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.40	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018 2) The rates shall be including of all types of taxes including GST etcra)				G.Total	
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

195

33

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark marg M/R to H/O Mukesh Kumar ward No.3 Jankour km.0/0 to 0/080 (SH: P/L interlocking paver blocks at RD. 0/026.95 to 0/053.91) (Deposit work)					Estimated Cost	99979/-
					Earnest Money	2000/-
					Time limit	one month
SL. No.	Description of work	Quantity	Unit	RATE in		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.81	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	9.70	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	72.79	Per square metre			

4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.40	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)IC(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD.,
 Una

214

34

SCHEDULE OF QUANTITY					Estimated cost	99053/-
					Earnest money	2000/-
					Time limit	One month
Name of Work: Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km.0/0 to 2/500 Tehsil & Distt.Una (HP) (SH: C/O R/wall at RD.2/455 to 2/460) (Deposit work)						
S. No.	Description of work	Quantity	Unit	Rates (In. Rs.)		Amount (in Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.75	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.75	Per cubic metre			

3	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of same for in-situ reinforced concrete and plain concrete work in vertical surfaces such as walls(any thickness) partitions and the like including attached pilasters buttresses,plinth and string courses and the like including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.00	Per Square metre			
4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una

215 ✓ 35

SCHEDULE OF QUANTITY					Estimated cost	99393/-
					Earnest money	2000/-
					Time limit	One month
Name of Work: Restoration of rain damages Bangarh Nangran road to Ghalore Chowk upto Punjab Boundary km.0/0 to 2/500 Tehsil & Distt.Una (HP) (SH: C/O R/wall at RD.2/460 to 2/465) (Deposit work)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	7.75	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.75	Per cubic metre			
3	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of same for in-situ reinforced concrete and plain concrete work in vertical surfaces such as walls(any thickness) partitions and the like including attached pilasters buttresses,plinth and string courses and the like including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	16.00	Per Square metre			

4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,melkhana ,toll tax,GST,labour cess or other taxes imposed by the Government...	10.00	Each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer,
 Una Division, HPPWD.,
 Una

252

36

DRAFT SCHEDULE OF QUANTITY						
					Estimated Cost	99210/-
Name of work : Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km.0/0 to 0/300(SH: P/L RCC NP2 pipes in RD.0/180 to 0/209(LHS) (Deposit work)					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing brick work manually/ by mechanical means in CC 1:4:8 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.26	Per cubic metre			
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.70	Per cubic metre			
3	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 300mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government..	29.00	Per running metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.74	Per cubic metre			
5	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.23	Per cubic metre			

6	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 150mm (One hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	103.44	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn. HP. PWD.
 Una

253

31

SCHEDULE OF QUANTITY								
							Estimated Cost	99210/-
Name of work : Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km.0/0 to 0/300(SH: P/L RCC NP2 pipes in RD.0/215 to 0/244 (LHS) (Deposit work)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing brick work manually/ by mechanical means in CC 1:4:8 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.25	Per cubic metre					
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.70	Per cubic metre					
3	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 300mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	29.00	Per running metre					
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.74	Per cubic metre					

5	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.23	Per cubic metre			
6	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm(One hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	103.44	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.
 Una

(254)

(38)

SCHEDULE OF QUANTITY							Estimated Cost	99210/-
Name of work : Balance work Repair of damages on L/R to village Lower Dehlan Badehar to Bela Bali Khad to Mohalla Pada Somnath km.0/0 to 0/300(SH: P/L RCC NP2 pipes in RD.0/260 to 0/289 (LHS) (Under MDPE Gas pipe line Deposit)							Earnest Money	2000/-
							Time limit	One month
							S. No.	
					Figures	Words		
1	Demolishing brick work manually/ by mechanical means in CC 1:4:8 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			7.26	Per cubic metre			
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			8.70	Per cubic metre			
3	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 300mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.			29.00	Per running metre			
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			1.74	Per cubic metre			
5	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			9.23	Per cubic metre			

6	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 150mm (One hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	103.44	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B) (17) 2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3) 1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD.
 Una


39

SCHEDULE OF QUANTITY					
				Estimated Cost	92400-
	Name of work : Construction of Harijan basti Fathewal to village Bangarh km.0/0 to 2/200(SH: C/O Embankment km.1/800 to 1/940(Under OTMNP)			Earnest Money	2000/-
				Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT
			Figures	Words	
1	Construction of embankment with approved materials obtained from borrow pit, with any lift transporting to site and compacted with 80-100 KN. static/ vibratory road roller to meet the requirements of table 300.1 and 300.2 specifications to lines, grades, level and cross sections as per drawings or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including handling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respect as per direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals.	369.60	Per cubic metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018			Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)				
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021				

Executive Engineer
Una Divn.HP.PWD.,
Una

40

SCHEDULE OF QUANTITY					
				Estimated Cost	94152/-
Name of work :Construction of Harijan basti Fathewal to village Bangarh km.0/0 to 2/200(SH: C/O Embankment km.1/940 to 2/0 and C/O edge wall in km.1/992 to 2/0(Under OTMNP)				Earnest Money	2000/-
				Time limit	One month
Sl. No.	Description of work	Qty	Unit	RATE In	
				Figures	Words
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental .	9.60	Per cubic metre		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.	14.40	Per cubic metre		
3	Construction of embankment with approved materials obtained from borrow pit,with any lift transporting to site and compacted with 80-100 KN. static/ vibratory road roller to meet the requirements of table 300.1 and 300.2 specifications to lines, grades, level and cross sections as per drawings or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including handling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentials necessary to complete the work in all respect as per direction of the Engineer-in-charge including carriage of material witin all leads and lifts and other incidentials.	180.00	Per cubic metre		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	
2) The rates shall be including of all types of taxes including GST ectra)					
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

(248)

(41)

SCHEDULE OF QUANTITY								
							Estimated Cost	77210/-
	Name of work : C/O Path with R/wall & drainage near the house of Sh. Dharampal GP Bharolian Kalan (SH: C/O U-shape drain & R/wall in RD.0/070 to 0/096)(Depositwork)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually/ by mechanical means in cement concrete 1:3:6 including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST.labour cess or other taxes imposed by the Government..	2.33	Per cubic metre					
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.53	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.84	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.88	Per cubic metre					
5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm(one hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.50	Per Running metre					

6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	39.00	Per square metre			
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.52	Per Cubic metre			
8	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	25.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn. HP. PWD,
 Una

(249)

(42)

SCHEDULE OF QUANTITY						
					Estimated Cost	94180/-
	Name of work : C/O Path with R/wall & drainage near the house of Sh. Dharampal GP Bharolian Kalan (SH: C/O U-shape drain & R/wall in RD.0/024 to 0/046)(Deposit work)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually/ by mechanical means in cement concrete 1:3:6 including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.43	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.71	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	16.82	Per cubic metre			
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	0.20	Per cubic metre			
5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 150mm (one hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.50	Per Running metre			

6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	33.00	Per square metre		
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.44	Per Cubic metre		
8	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	30.21	Per Kilogramme		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018			Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)				
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021				


 Executive Engineer
 Una Divn.HP.PWD
 Una

(250)

(43)

SCHEDULE OF QUANTITY								
							Estimated Cost	94761/-
	Name of work : C/O Path with R/wall & drainage near the house of Sh. Dharampal GP Bharolian Kafan (SH: C/O U-shape drain & R/wall in RD.0/048to 0/07f)(Depositwork)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually/ by mechanical means in cement concrete 1:3:6 including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.13	Per cubic metre					
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.26	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.68	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.27	Per cubic metre					
5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm(one hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.00	Per Running metre					

6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	37.50	Per square metre			
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.50	Per Cubic metre			
8	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	28.16	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD.,
 Una

(251)

(44)

SCHEDULE OF QUANTITY									
								Estimated Cost	94683/-
	Name of work : C/O Path with R/wall & drainage near the house of Sh. Dharampal GP Bharolian Kalan (SH: C/O U-shape drain & R/wall in RD.0/0 to 0/023)(Deposit work)							Earnest Money	2000/-
								Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT			
				Figures	Words				
1	Demolishing cement concrete manually/ by mechanical means in cement concrete 1:3:6 including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.13	Per cubic metre						
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.26	Per cubic metre						
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.68	Per cubic metre						
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.58	Per cubic metre						
5	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 150mm(one hundred fifty millimetre) dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.30	Per Running metre						

6	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	34.50	Per square metre			
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.46	Per Cubic metre			
8	Providing and fixing Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	28.16	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn. HP. PWD.
 Una

228

45

SCHEDULE OF QUANTITY								
							Estimated Cost	99381/-
Name of work : C/O Badehar Sasan Udaipur road km.0/0 to 3/600 (SH: P/L NP2 pipes 300mm dia at RD.0/135 to 0/160 LHS & CC Shoulder at RD.0/312 to 0/328(RHS) (Under OTMNP)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing brick work manually/ by mechanical means in CC 1:3:6 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.25	Per cubic metre					
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.34	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.35	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.84	Per cubic metre					

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	4.69	Per Cubic metre			
6	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 300mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	25.00	Per running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	74.85	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

277

46

SCHEDULE OF QUANTITY								
							Estimated Cost	99958/-
	Name of work : C/O Badehar Sasan Udaipur road km.0/0 to 3/600 (SH: P/L NP2 pipes 450mm dia at RD.0/395 to 0/415 RHS & CC paved Shoulder at RD.0/358 to 0/380(RHS) (Under OTMNP)						Earnest Money	2000/-
								Time limit
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing brick work manually/ by mechanical means in CC 1:3:6 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.10	Per cubic metre					
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.08	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.95	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST labour cess or other taxes imposed by the Government..	1.60	Per cubic metre					

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.93	Per Cubic metre			
6	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	20.00	Per running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	74.85	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

276

47

SCHEDULE OF QUANTITY								
							Estimated Cost	99958/-
	Name of work : C/O Badehar Sasan Udaipur road km.0/0 to 3/600 (SH: P/L NP2 pipes 450mm dia at RD.0/415 to 0/440 (RHS) (Under OTMNP)						Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing brick work manually/ by mechanical means in CC 1:3:6 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.63	Per cubic metre					
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	12.75	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.50	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering – All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.19	Per cubic metre					

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.25	Per Cubic metre			
6	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	25.00	Per running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	124.75	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

279

48

SCHEDULE OF QUANTITY						
				Estimated Cost		99312/-
Name of work : C/O Badehar Sasan Udaipur road km.0/0 to 3/600 (SH: P/L NP2 pipes 450mm dia at RD.0/380 to 0/495 RHS & CC paved Shoulder at RD.0/328 to 0/358(RHS) (Under OTMNP)				Earnest Money		2000/-
				Time limit		One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing brick work manually/ by mechanical means in CC 1:3:6 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.71	Per cubic metre			
2	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.03	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.65	Per cubic metre			
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.32	Per cubic metre			

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.98	Per Cubic metre			
6	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.00	Per running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	74.85	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn,HP.PWD,
 Una

255

49

SCHEDULE OF QUANTITY						
					Estimated Cost	99528/-
	Name of work : Repair of damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona km.0/0 to 0/800(SH: P/L interlocking cement concrete paver blocks at RD.0/293 to 0/300 & 0/478 to 0/488) (Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.48	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.58	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.15	Per cubic metre			
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	68.00	Per square metre			

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.78	Per Cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

256

50

SCHEDULE OF QUANTITY						
					Estimated Cost	99528/-
	Name of work : Repair of damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona km.0/0 to 0/800(SH: P/L interlocking cement concrete paver blocks at RD.0/303 to 0/310 & 0/491 to 0/510) (Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.48	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.58	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.15	Per cubic metre			

4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	68.00	Per square metre			
5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.78	Per Cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

(257)

(51)

SCHEDULE OF QUANTITY								
							Estimated Cost	99528/-
	Name of work : Repair of damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona km.0/0 to 0/800(SH: P/L interlocking cement concrete paver blocks at RD.0/250 to 0/257 & 0/400 to 0/410) (Under MDPE Gas pipe line Deposit)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	11.48	Per cubic metre					
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.58	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	3.15	Per cubic metre					
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/ laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	68.00	Per square metre					

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.78	Per Cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn. HP. PWD.,
 Una

258

52

SCHEDULE OF QUANTITY								
							Estimated Cost	99528/-
	Name of work : Repair of damages due to laying of MDPE Natural Gas Pipeline on link road to village Poona km.0/0 to 0/800(SH: P/L interlocking cement concrete paver blocks at RD.0/260 to 0/267 & 0/412 to 0/422) (Under MDPE Gas pipe line Deposit)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.48	Per cubic metre					
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.58	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.15	Per cubic metre					
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	68.00	Per square metre					

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.78	Per Cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B) (17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD.,
 Una

242

53

	Schedule of Quantity						
						Estimated Cost	82716/-
Name of work: A/R & M/O Various Non-residential building at Una Distt.Una (SH: Providing services out sources basis of One No.Supervisor/work inspector for Period of five month i.e. 1st April 2025 to 31 August 2025)						Earnest Money	2000/-
						Time limit	One month
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing Services on temporary basis of Supervisor /work inspector to assist court cases during working hour 10AM to 5 PM or as when required by the officer-in-charge.	153 days	P/day				
					Total:	•	



 Executive Engineer
 Una Divn.HP.PWD,
 Una

263

54

SCHEDULE OF QUANTITY									
								Estimated Cost	99593/-
	Name of work : Repair of damages on Bharolian Badehar Charatgarh road km.0/0 to 4/200(SH: C/O U-shape drain with chambers etc. in RD.3/283 to 3/311) (Under MDPE Gas pipe line Deposit)							Earnest Money	2000/-
								Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT			
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	36.00	Per cubic metre						
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.35	Per cubic metre						
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.05	Per Cubic metre						
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	94.50	Per Kilogramm e						

5	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	30.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

(262)

(55)

SCHEDULE OF QUANTITY						
					Estimated Cost	99519/-
	Name of work : Repair of damages on Bharolian Badehar Charatgarh road km.0/0 to 4/200(SH: C/O U-shape drain with chambers etc. in RD.3/255 to 3/280)(Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within any leads and lifts.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.13	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	33.30	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	18.15	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.05	Per Cubic metre			
5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	94.50	Per Kilogramm e			

6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	30.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.,
 Una

259

56

SCHEDULE OF QUANTITY						
					Estimated Cost	99593/-
	Name of work : Repair of damages on Bharolian Badehar Charatgarh road km.0/0 to 4/200(SH: C/O U-shape drain with chambers etc. in RD.3/314 to 3/342) (Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	36.00	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.35	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.05	Per Cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	94.50	Per Kilogramme			

5	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toil tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	30.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

260

S7

SCHEDULE OF QUANTITY						
					Estimated Cost	99593/-
	Name of work : Repair of damages on Bharolian Badehar Charatgarh road km.0/0 to 4/200(SH: C/O U-shape drain with chambers etc. in RD.3/345 to 3/373) (Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	36.00	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	19.35	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.05	Per Cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	94.50	Per Kilogramme			

5	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	30.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

(261)

(58)

SCHEDULE OF QUANTITY								
							Estimated Cost	99593/-
	Name of work : Repair of damages on Bharolian Badehar Charatgarh road km.0/0 to 4/200(SH: C/O U-shape drain with chambers etc. in RD.3/375 to 3/403) (Under MDPE Gas pipe line Deposit)						Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	36.00	Per cubic metre					
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.35	Per cubic metre					
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.05	Per Cubic metre					
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	94.50	Per Kilogramm e					

5	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	30.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer
 Una Divn.HP.PWD.,
 Una

247

(59)

SCHEDULE OF QUANTITY					Estimated cost	98462/-
					Earnest money	2000/-
					Time limit	One month
Name of Work: Repair of damages link road to village Bass km.0/0 to 0/750(SH: Providing and laying 300mm dia RCC pipes NP2 from km.0/730 to 0/750) (Under OFC Deposit)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level including disposal of unserviceable material and stacking the serviceable material RB/RCC works within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.00	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.52	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.96	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.90	Per cubic metre			
5	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	Per Running metre			


6	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.80	Per cubic metre			
7	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	32.00	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etcra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.,
 Una

60

SCHEDULE OF QUANTITY								
							Estimated Cost	99922/-
Name of work : Repair of damages on Dehlan Badehar road km.0/0 to 3/060(SH: C/O U-shape drain, P/L NP2 pipes with CC Chambers etc. in RD.0/895 to 0/917(Under MDPE Gas pipe line Deposit)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.60	Per cubic metre					
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.25	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.45	Per cubic metre					
4	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per running metre					


5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.20	Per Cubic metre			
6	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	305.00	Per Kilogramme			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	90.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	•
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn. HP. PWD,
 Una

(61)

SCHEDULE OF QUANTITY								
							Estimated Cost	97993/-
Name of work : Repair of damages on Dehlan Badehar road km.0/0 to 3/060(SH: C/O U-shape drain in RD.0/919 to 0/937(Under MDPE Gas pipe line Deposit)							Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.60	Per cubic metre					
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government .	9.25	Per cubic metre					
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.45	Per cubic metre					
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.20	Per Cubic metre					


5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	330.75	Per Kilogramm e			
6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	90.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etctra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD,
 Una

(62)

SCHEDULE OF QUANTITY						
				Estimated Cost	97998/-	
Name of work : Repair of damages on Dehlan Badehar road km.0/0 to 3/060(SH: C/O U-shape drain in RD.0/940 to 0/960(Under MDPE Gas pipe line Deposit)				Earnest Money	2000/-	
				Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.60	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.25	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.45	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand); 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.20	Per Cubic metre			

5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	330.80	Per Kilogramme			
6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	90.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST etcetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					



 Executive Engineer
 Una Divn.HP.PWD.,
 Una

(63)

SCHEDULE OF QUANTITY								
							Estimated Cost	99657/-
	Name of work : Repair of damages on Dehlan Badehar road km.0/0 to 3/060(SH: C/O U-shape drain, P/L NP2 pipes with CC Chambers etc. in RD.0/870 to 0/892(Under MDPE Gas pipe line Deposit)						Earnest Money	2000/-
							Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Demolishing cement concrete manually/ by mechanical means in CC 1:3:6 including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.70	Per cubic metre					
2	Demolishing RCC work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within leads and lifts. including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.37	Per cubic metre					
3	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.60	Per cubic metre					
4	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	9.25	Per cubic metre					

5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.45	Per cubic metre			
6	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per running metre			
7	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.20	Per Cubic metre			
8	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	265.00	Per Kilogramme			
9	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	90.00	Per Kilogramme			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					Total:	
2) The rates shall be including of all types of taxes including GST ectra)						

	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
--	--	--	--	--	--	--


 Executive Engineer
 Una Divn.HP.PWD
 Una

(264)

(64)

SCHEDULE OF QUANTITY						
					Estimated Cost	99052/-
	Name of work : Restoration of damages Behdala Jakhera road km.0/0 to 4/600(SH: C/O U-shape drain along road from RD.2/630 to 2/658.50)(under OFC Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	13.47	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	21.16	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.86	Per cubic metre			

4	Supplying fitting and placing HYSD bar in reinforcement in substructure complete as per drawing and technical specification clauses—1002,1005,1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	120.96	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Una Divn.HP.PWD.
 Una

269

65

SCHEDULE OF QUANTITY					Estimated cost	99983/-
					Earnest money	2000/-
					Time limit	One month
Name of Work: Repair of damages link road Dehlan Jakhera Morbar Bhatoli road km.0/0 to 3/600 (SH: Repair of U-shape drain at RD.1/300 to 1/321) (Under MDPE Gas pipe line Deposit)						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolition above GL upto floor two level including disposal of unserviceable material and stacking the serviceable material RB/RCC works within any leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.62	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.16	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.41	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.405	Per cubic metre			
5	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	40.50	Per Kilogramm e			

6	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	145.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD,
 Una

270

C6

	SCHEDULE OF QUANTITY				Estimated cost	99947/-
					Earnest money	2000/-
					Time limit	One month

Name of Work: Repair of damages link road Dehlan Jakhera Morbar Bhatoli road km.0/0 to 3/600 (SH: Repair of U-shape drain at RD.1/324 to 1/345)
(Under MDPE Gas pipe line Deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.16	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	17.41	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.405	Per cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	40.50	Per Kilogramme			

5	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	152.90	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD,
 Una

(271)

(67)

	SCHEDULE OF QUANTITY				Estimated cost	99952/-
--	-----------------------------	--	--	--	----------------	---------

Earnest money 2000/-

Time limit One month

Name of Work: Repair of damages link road Dehlan Jakhera Morbar Bhatoli road km.0/0 to 3/600 (SH: Repair of U-shape drain at RD.1/372 to 1/393)
(Under MDPE Gas pipe line Deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.16	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.41	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.405	Per cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	40.50	Per Kilogramme			

5	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Running metre			
6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	152.95	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD.
 Una

272

68

	SCHEDULE OF QUANTITY				Estimated cost	99957/-
					Earnest money	2000/-
					Time limit	One month

Name of Work: Repair of damages link road Dehlan Jakhera Morbar Bhatoli road km.0/0 to 3/600 (SH: Repair of U-shape drain at RD.1/348 to 1/369)
(Under MDPE Gas pipe line Deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.16	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.41	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.405	Per cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	40.50	Per Kilogramm e			

5	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Running metre			
7	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	153.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer ,
 Una Division, HPPWD,
 Una

273

69

	SCHEDULE OF QUANTITY				Estimated cost	99859/-
--	----------------------	--	--	--	----------------	---------

Earnest money 2000/-

Time limit One month

Name of Work: Repair of damages link road Dehlan Jakhera Morbar Bhatoli road km.0/0 to 3/600 (SH: Repair of U-shape drain at RD.1/396 to 1/405)
(Under MDPE Gas pipe line Deposit)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.16	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	17.41	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.405	Per cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	40.50	Per Kilogramme			

5	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Running metre			
6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	152.00	Per Kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


Executive Engineer ,
Una Division, HPPWD.,
Una