

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25- 175-78  
To

DATED: 17/04/25

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar,  
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,  
HPPWD Division,  
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,  
Dehra Division HP.PWD.,  
Dehra.

### H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors ( C&D Class) enlisted in HPPWD.


#### TENDER SCHEDULE:

- |                                                             |                            |
|-------------------------------------------------------------|----------------------------|
| 1. Date and time of receipt of application for tender form: | 25.04.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form:                   | 26.04.2025 upto 5.00 PM    |
| 3. Date and time of receipt of tenders:                     | 28.04.2025 upto 10.30AM    |
| 4. Date and time of opening of tenders:                     | 28.04.2025 at 11.00 AM     |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

| Job No. | Name of work                                                                                                                                                                                                                                                                   | Estimated cost | Earnest money | Time limit | Cost of form |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|---------------|------------|--------------|
| 01      | Preparation of Forest Diversion Case under FRA-2006 for the construction of various Roads under HPPWD Sub Division Haripur (1) L/R from Gharyar to Othra KM 0/0 to 1/612 (2) L/R to Village Gharyar KM 0/0 to 1/174 (SH: Preparation of Forest Diversion Case under FRA-2006). | Rs. 93,930.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 02      | Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road KM 0/0 to 0/500 (SH: Repair to Pot Holes at Various RD's in KM 0/0 to 0/500).                                                                                                                                    | Rs. 99,645.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 03      | Restoration of Rain Damages on Road from Pir Bar Satsang Ghar to Beh Dhounta via Paniali i/c Causeway Khad KM 0/0 to 7/160 (SH: C/o R/Wall at RD 5/530 to 5/535).                                                                                                              | Rs. 98,946.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 04      | Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road KM 0/0 to 0/500 (SH: Repair to Pot Holes at Various RD's in KM 0/0 to 0/500).                                                                                                                                    | Rs. 99,610.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 05      | Restoration of Rain Damages on Road from Pir Bar Satsang Ghar to Beh Dhounta via Paniali i/c Causeway Khad KM 0/0 to 7/160 (SH: C/o R/Wall at RD 5/535 to 5/540).                                                                                                              | Rs. 99,048.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 06      | Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road KM 0/0 to 0/500 (SH: Repair to Pot Holes at Various RD's in KM 0/0 to 0/500).                                                                                                                                    | Rs. 99,663.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 07      | Construction of Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace Road KM 9/00 to 22/200 (SH: C/o U-Shape Drain and C.C. Berms at RD 9/800 to 9/825).                                                                                                            | Rs. 99,710.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 08      | Construction of Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Sansarpur Terrace Road KM 9/00 to 22/200 (SH: C/o U-Shape Drain and C.C. Berms at RD 9/825 to 9/850).                                                                                                            | Rs. 99,859.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 09      | Repair and Maintenance of Type-II Quarter in PWD Colony at Dehra in Distt. Kangra (H.P.) (SH: Providing and fixing Sanitary Fitting etc.) (Part-V).                                                                                                                            | Rs. 99,643.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 10      | Repair and Maintenance of Type-II Quarter in PWD Colony at Dehra in Distt. Kangra (H.P.) (SH: Providing and fixing Curtains etc.) Part-VI).                                                                                                                                    | Rs. 99,838.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 1       | The contractors/firms should possess the following documents (Photocopy to be attached):                                                                                                                                                                                       |                |               |            |              |
| (i)     | Latest renewal of enlistment.                                                                                                                                                                                                                                                  |                |               |            |              |
| (ii)    | PAN (Permanent Account No.)                                                                                                                                                                                                                                                    |                |               |            |              |
| (iii)   | Registration under HP GST/ (TIN No.).                                                                                                                                                                                                                                          |                |               |            |              |
| (iv)    | EPF (Employee Provident Fund Account No.)                                                                                                                                                                                                                                      |                |               |            |              |

|   |                                                                                                                                     |
|---|-------------------------------------------------------------------------------------------------------------------------------------|
| 2 | Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.                 |
| 3 | If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.                |
| 4 | The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).                  |
| 5 | The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand. |
| 6 | The next tender will be issued only after completion of previous works in hand.                                                     |
| 7 | The offer of the tender shall remain valid upto 30 days after the opening.                                                          |

9.   
 Executive Engineer  
 HPPWD Division Dehra  
 Distt Kangra H.P  
 on behalf of Governor of Himachal Pradesh

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs.93930.00

Earnest Money :-Rs.2000.00

Time Limit :- One Month

**Name of work:-** Preparation of forest diversion case under FRA, 2006 for the construction of various roads in Haripur Sub Division 1. Link road from Gharyar to Othara Km 0/00 to 1/612 Km. 2. Link road to Village Gharyar Km 0/00 to 1/174 Km. (SH:- Preparation of Forest Diversion Case under FRA, 2006)

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity        | Rate in  |                            | Unit          | Amount           |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|----------|----------------------------|---------------|------------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                 | Figures  | Words                      |               |                  |
| 1       | Preparation of KML File, Topo Sheet Map, Alternative Map and Geo Referenced Digital map of proposed land. Preparation of 3 number of proposal folders including Reclamation Plan, Cost Benefit Analysis, Muck Management, complete in all respect Assistance to User Agency to attend the queries and clarification sought by Forest Department. The Rates are inclusive of all equipment within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 2.00 Number     | 40000.00 | Rupees Forty Thousand Only | Each          | 80,000.00        |
| 2       | Preparation of revenue paper for land acquire in the project. Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                                                                                                             | 2.786 Kilometre | 5000.00  | Rupees Five Thousand Only  | Per Kilometre | 13 930.00        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                 |          |                            |               | <b>93,930.00</b> |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                 |          |                            |               |                  |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                 |          |                            |               |                  |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                 |          |                            |               |                  |

Executive Engineer,  
Dehra Division,  
HPPWD DEHRA



PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99645.00  
 Earnest Money:- Rs. 2,000.00  
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road in Km. 0/00 to 0500 (SH)-Repair to Pot Holes at various RD's in Km. 0/00 to 0/500)

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity            | Rate in |                                              | Unit             | Amount           |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------|----------------------------------------------|------------------|------------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                     | Figures | Words                                        |                  |                  |
| 1       | Providing laying, spreading by manual/mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheeled vibratory roller 80-100 (Eighty to Hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic meter) per ten square meter of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                   | 1.14 Cubic metre    | 1750.00 | Rupees One Thousand Seven Hundred Fifty Only | Per Cubic metre  | 1,995.00         |
| 2       | Repair to pot holes by removal of loose material, trimming of sides, cleaning of surface, then providing tack coat at the rate of 0.300Kg (Zero point three zero kilogramme) per square meter road surface with bitumen VG-10 followed 20mm (Twenty millimetre) thick compacted pre-mix carpet using 1.46Kg (One point four six kilogramme) of bitumen VG-10 and 0.027 Cum (Zero point zero two seven) cubic meter of crushed stone aggregate of proper grading per square meter of road surface mixed and heated to proper temperature in mix-all 6-10 tonne capacity rolled to desired density with 8-10 tonne weight static road roller followed by seal coat IRC type B using 0.68Kg (Zero point six eight kilogramme) of bitumen VG-10 and 0.006 (Zero point zero zero six) cubic meter sand per square meter of road surface duly mixed and heated in mixall to the required temperature and property rolled after laying with 8-10 tonne weight static road roller to the desired density as per technical specification Clause 1904 2. direction of the Engineer-in-Charge. including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 279.00 Square metre | 350.00  | Rupees Three Hundred Fifty Only              | Per Square metre | 97,650.00        |
|         | <b>TOTAL</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                     |         |                                              |                  | <b>99,645.00</b> |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                     |         |                                              |                  |                  |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                     |         |                                              |                  |                  |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                     |         |                                              |                  |                  |

*Bill of quantity checked and approved  
for Rs. 99,645.00/- only*

*[Signature]*  
 Executive Engineer,  
 Dehra Division,  
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 98946.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Road from Pir Bar Satsang Ghar at Beh Dhounta via Paniali i/c Causeway Khad km 0/00 to 7/160 (SH:- C/o R/wall at RD.5/530 to 5/535)

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity          | Rate in |                                 | Unit            | Amount    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|---------------------------------|-----------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                   | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 15.00 Cubic meter | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic meter | 4,350.00  |
| 2       | Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm ( forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 20.41 Cubic meter | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic meter | 82,661.00 |

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity          | Rate in |                                 | Unit            | Amount    |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|---------------------------------|-----------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                   | Figures | Words                           |                 |           |
| 3       | Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 16.00 Number      | 250.00  | Rupees Two Hundred Fifty Only   | Each            | 4,000.00  |
| 4       | Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                    | 10.58 Cubic meter | 750.00  | Rupees Seven Hundred Fifty Only | Per Cubic meter | 7,935.00  |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                   |         |                                 |                 | 98,946.00 |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                   |         |                                 |                 |           |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |         |                                 |                 |           |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                   |         |                                 |                 |           |

*Bill of quantity checked and approved  
for Rs. 98,946.00/- only*

*[Signature]*  
Executive Engineer,  
Dehra-Division,  
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99610.00  
 Earnest Money:- Rs. 2,000.00  
 Time Limit :- One Month.  
 at various RD's in Km. 0/00 to 0/500)

Name of work:- Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road in Km. 0/00 to 0500 (SH)-Repair to Pot Holes

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity            | Rate in |                                              | Unit             | Amount    |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------|----------------------------------------------|------------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                     | Figures | Words                                        |                  |           |
| 1       | Providing laying, spreading by manual/mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheeled vibratory roller 80-100 (Eighty to Hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic meter) per ten square meter of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                        | 1.12 Cubic metre    | 1750.00 | Rupees One Thousand Seven Hundred Fifty Only | Per Cubic metre  | 1,960.00  |
| 2       | Repair to pot holes by removal of loose material, trimming of sides, cleaning of surface, then providing tack coat at the rate of 0.300Kg (Zero point three zero zero kilogramme) per square meter road surface with bitumen VG-10 followed 20mm (Twenty millimetre) thick compacted pre-mix carpet using 1.46Kg (One point four six kilogramme) of bitumen VG-10 and 0.027 Cum (Zero point zero two seven) cubic meter of crushed stone aggregate of proper grading per square meter of road surface mixed and heated to proper temperature in mix-all 6-10 tonne capacity rolled to desired density with 8-10 tonne weight static road roller followed by seal coat IRC type B using 0.68Kg (Zero point six eight kilogramme) of bitumen VG-10 and 0.006 (Zero point zero zero six) cubic meter sand per square meter of road surface duly mixed and heated in mixall to the required temperature and property rolled after laying with 8-10 tonne weight static road roller to the desired density as per technical specification Clause 1904.2, direction of the Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 279.00 Square metre | 350.00  | Rupees Three Hundred Fifty Only              | Per Square metre | 97,650.00 |
|         | TOTAL                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                     |         |                                              |                  | 99,610.00 |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                     |         |                                              |                  |           |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                     |         |                                              |                  |           |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                     |         |                                              |                  |           |

BRO of quantity checked and approved  
 for Rs. 99,610.00/- only.

Executive Engineer,  
 Dehra Division  
 HPPWD Dehra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs 99048.00  
 Earnest Money :-Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Road from Pir Bar Satsang Ghar at Beh Dhounta via Paniali i/c Causeway Khad km 0/00 to 7/160 (SH:- C/o R/wall at RD.5/535 to 5/540)

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity          | Rate in |                                 | Unit            | Amount    |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|---------------------------------|-----------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                   | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 15.35 Cubic meter | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic meter | 4,452.00  |
| 2       | Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm ( forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 20.41 Cubic meter | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic meter | 82,661.00 |

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity          | Rate in |                                 | Unit            | Amount    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|---------------------------------|-----------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                   | Figures | Words                           |                 |           |
| 3       | Providing and laying 100mm (One Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 16.00 Number      | 250.00  | Rupees Two Hundred Fifty Only   | Each            | 4,000.00  |
| 4       | Back filling behind abutment Retaining wall/breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                     | 10.58 Cubic meter | 750.00  | Rupees Seven Hundred Fifty Only | Per Cubic meter | 7,935.00  |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                   |         |                                 |                 | 99,048.00 |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                   |         |                                 |                 |           |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                   |         |                                 |                 |           |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                   |         |                                 |                 |           |

*Bid of quantity checked and approved for Rs. 9904800/- only*

*S.D*  
Executive Engineer,  
Dehra Division,  
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99663.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Month.  
 Name of work:- Restoration of Rain Damages on Dehipukhar to Mowa Kundli Road in Km. 0/00 to 0500 (SH:-Repair to Pot Holes at various RD's in Km. 0/00 to 0/500)

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity            | Rate in |                                              | Unit             | Amount    |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------|----------------------------------------------|------------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                     | Figures | Words                                        |                  |           |
| 1       | Providing laying, spreading by manual/mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheeled vibratory roller 80-100 (Eighty to Hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (zero point one eight cubic meter) per ten square meter of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                         | 1.15 Cubic metre    | 1750.00 | Rupees One Thousand Seven Hundred Fifty Only | Per Cubic metre  | 2,013.00  |
| 2       | Repair to pot holes by removal of loose material, trimming of sides, cleaning of surface, then providing tack coat at the rate of 0.300Kg (Zero point three zero kilogramme) per square meter road surface with bitumen VG-10 followed 20mm (Twenty millimetre) thick compacted pre-mix carpet using 1.46Kg (One point four six kilogramme) of bitumen VG-10 and 0.027 Cum (Zero point two seven) cubic meter of crushed stone aggregate of proper grading per square meter of road surface mixed and heated to proper temperature in mix-all 6-10 tonne capacity rolled to desired density with 8-10 tonne weight static road roller followed by seal coat IRC type B using 0.68Kg (Zero point six eight kilogramme) of bitumen VG-10 and 0.006 (Zero point zero six) cubic meter sand per square meter of road surface duly mixed and heated in mixall to the required temperature and property rolled after laying with 8-10 tonne weight static road roller to the desired density as per technical specification Clause 1904.2, direction of the Engineer-in-Charge. including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 279.00 Square metre | 350.00  | Rupees Three Hundred Fifty Only              | Per Square metre | 97,650.00 |
|         | <b>TOTAL</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                     |         |                                              |                  | 99,663.00 |
|         | <b>% Above/below</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                     |         |                                              |                  |           |
|         | <b>Quoted Amount in Figures</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                     |         |                                              |                  |           |
|         | <b>Quoted Amount in Words</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                     |         |                                              |                  |           |

13.00 of quantity checked and approved  
 for Rs. 99,663.00/- only

Executive Engineer,  
 Dehra Division  
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.

99,710.00

Earnest Money :- Rs.

2,000.00

Time Limit :- One Month.

Name of work:- C/o Kalaha -Pragpur- NehranPukhar-Dhaliara-Dada Siba-Sansarpur Terrace road km 9/00 to 22/200).(S.H):- C/o U-shape Drain and CC herms at Rd 9/800 to 9/825.

| Sr. No.                  | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity          | Rate in |                                              | Unit            | Amount    |
|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|----------------------------------------------|-----------------|-----------|
|                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   | Figures | Words                                        |                 |           |
| 1                        | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material, complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 12.00 Cubic metre | 2901.00 | Rupees Two Hundred Ninety Only               | Per Cubic metre | 3,481.00  |
| 2                        | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 P C C nominal mix 1:4:8 (40 mm aggregate) complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                              | 6.92 Cubic metre  | 4050.00 | Rupees Four Thousand Fifty Only              | Per Cubic metre | 28,026.00 |
| 3                        | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                                | 7.92 Cubic metre  | 4950.00 | Rupees Four Thousand Nine Hundred Fifty Only | Per Cubic metre | 39,324.00 |
| 4                        | Providing & Laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per IIPPW/D specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                               | 5.00 Cubic metre  | 5800.00 | Rupees Five Thousand Eight Hundred Only      | Per Cubic metre | 29,000.00 |
| <b>Total</b>             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   |         |                                              |                 | 99,710.00 |
| % Above/below            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   |         |                                              |                 |           |
| Quoted Amount in Figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   |         |                                              |                 |           |
| Quoted Amount in Words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   |         |                                              |                 |           |

Engineer  
Dehra Division,  
HPPWD Dehra



PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,859.00  
 Earnest Money :- Rs. 2,000.00

Time Limit :- One Month.  
 Name of work:- C/o Kaloha -Pragpur- Nehrpu-Pukhar-Dhaliara-Dada Sila-Sansarpur Terrace road km 9/00 to 22/200,(S.H):- C/o U-shape Drain and C.C herms at Rd 9/825 to 9/850).

| Sl. No. | Description of Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity          | Rate In |                                              | Unit            | Amount           |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|---------|----------------------------------------------|-----------------|------------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                   | Figures | Words                                        |                 |                  |
| 1       | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 12.00 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only               | Per Cubic metre | 3,480.00         |
| 2       | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clauses 802, 803, 1202 and 1203 P.C.C nominal mix 1:4:8 (40 mm aggregates) complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                           | 6.02 Cubic metre  | 4050.00 | Rupees Four Thousand Fifty Only              | Per Cubic metre | 28,026.00        |
| 3       | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                                                                                                                               | 7.95 Cubic metre  | 4950.00 | Rupees Four Thousand Nine Hundred Fifty Only | Per Cubic metre | 39,353.00        |
| 4       | Providing & laying cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete and as per I.P.P.W.D specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.                                                                                                                                                                                            | 5.00 Cubic metre  | 5800.00 | Rupees Five Thousand Eight Hundred Only      | Per Cubic metre | 29,000.00        |
|         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |         |                                              |                 | <b>99,859.00</b> |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                   |         |                                              |                 |                  |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                   |         |                                              |                 |                  |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                   |         |                                              |                 |                  |

  
 Executive Engineer,  
 Dehra Division,  
 I.P.P.W.D Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,643.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Month.

Name of Work:- Repair and Maintenance of Type-II Quarter in PWD Colony Dehra Tehsil Dehra District Kangra (H.P) (SH:- Providing and fixing Sanitary fitting etc. (Part-V).

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity     | Rate in |                                                                  | Unit | Amount    |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|---------|------------------------------------------------------------------|------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |              | Figures | Words                                                            |      |           |
| 1       | Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40mm, (Forty millimetre) including painting of fittings and brackets, cutting and making good the walls wherever required: 510x1040mm (Five hundred ten into one thousand forty millimetre) bowl depth 250 complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 1.00 Number  | 4608.30 | Rupees Four Thousand Six Hundred Eight And Paise Thirty Only     | Each | 4,608.00  |
| 2       | Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40mm, (Forty millimetre) including painting of fittings and brackets, cutting and making good the walls wherever required: 510x1040mm (Five hundred ten into one thousand forty millimetre) bowl depth 250 complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 1.00 Number  | 2257.60 | Rupees Two Thousand Two Hundred Fifty Seven And Paise Sixty Only | Each | 2,258.00  |
| 3       | Providing and fixing wash basin with C.I. brackets, 15mm (Fifteen millimetre) C.P. brass pillar taps, 32mm (Thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                  | 3.00 Numbers | 4100.00 | Rupees Four Thousand One Hundred Only                            | Each | 12,300.00 |
| 4       | Providing and fixing C.P. Brass Long Nose with capstan head 15mm (Fifteen millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                                                                                                                                                 | 2.00 Numbers | 1340.00 | Rupees One Thousand Three Hundred Forty Only                     | Each | 2,680.00  |

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity      | Rate in |                                                          | Unit | Amount    |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|---------|----------------------------------------------------------|------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                           |               | Figures | Words                                                    |      |           |
| 5       | Providing and fixing C.P. brass angle valve 15mm (Fifteen millimetre) without nuts and pipe complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                            | 2.00 Numbers  | 532.00  | Rupees Five Hundred Thirty Two Only                      | Each | 1,064.00  |
| 6       | Providing and fixing C.P. Angle cocks 15mm (Fifteen millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                    | 12.00 Numbers | 1350.00 | Rupees One Thousand Three Hundred Fifty Only             | Each | 16,200.00 |
| 7       | Providing and fixing C.P. Brass pillar tap with capstan head 15mm (Fifteen millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                             | 2.00 Numbers  | 1750.00 | Rupees One Thousand Seven Hundred Fifty Only             | Each | 3,500.00  |
| 8       | Providing and fixing PVC connection with brass unions 15mm (Fifteen millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                    | 11.00 Numbers | 43.10   | Rupees Forty Three And Paise Ten Only                    | Each | 474.00    |
| 9       | Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etcetera 110mm (One hundred ten millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 8.00 Numbers  | 94.30   | Rupees Ninety Four And Paise Thirty Only                 | Each | 754.00    |
| 10      | Providing and fixing PVC offset 45° ISI marked including fixing with approved adhesive etcetera 110mm (One hundred ten millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 6.00 Numbers  | 111.60  | Rupees One Hundred Eleven And Paise Sixty Only           | Each | 670.00    |
| 11      | Providing and fixing PTMT ball valve of approved quality and colour 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                             | 1.00 Number   | 338.70  | Rupees Three Hundred Thirty Eight And Paise Seventy Only | Each | 339.00    |



| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity            | Rate in |                                                      | Unit              | Amount   |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------|------------------------------------------------------|-------------------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                     | Figures | Words                                                |                   |          |
| 12      | Providing and fixing PVC door bend ISI marked including fixing with approved adhesive etcetera 110mm (One hundred ten millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 6.00 Numbers        | 230.00  | Rupees Two Hundred Thirty Only                       | Each              | 1,380.00 |
| 13      | Providing and fixing G.I. Sockets 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                              | 15.00 Numbers       | 55.00   | Rupees Fifty Five Only                               | Each              | 825.00   |
| 14      | Providing and fixing G.I. Tee equal 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                            | 16.00 Numbers       | 65.00   | Rupees Sixty Five Only                               | Each              | 1,040.00 |
| 15      | Providing and fixing G.I. Elbows 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                               | 12.00 Numbers       | 35.00   | Rupees Thirty Five Only                              | Each              | 420.00   |
| 16      | Providing and fixing G.I. Nipple 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                               | 12.00 Numbers       | 20.00   | Rupees Twenty Only                                   | Each              | 240.00   |
| 17      | Providing and fixing G.I. plug 15mm (Fifteen millimetre) nominal bore complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                 | 13.00 Numbers       | 15.00   | Rupees Fifteen Only                                  | Each              | 195.00   |
| 18      | Providing and fixing PVC Pipes 150mm (One hundred fifty millimetre) dia complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                               | 10.00 Running metre | 165.15  | Rupees One Hundred Sixty Five And Paise Fifteen Only | Per Running metre | 1,652.00 |



| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity     | Rate in |                                                    | Unit | Amount   |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|---------|----------------------------------------------------|------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |              | Figures | Words                                              |      |          |
| 19      | Providing and fixing PVC floor trap 110mmx90mm (One hundred ten millimetre into ninety millimetre) complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                      | 4.00 Numbers | 90.00   | Rupees Ninety Only                                 | Each | 360.00   |
| 20      | Providing and fixing Towel rail brackets fixed to wooden cleats with CP brass screws with con cealed fittings arrangement of approved quality and colour 600mm (Six hundred millimetre) long towel rail complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 2.00 Numbers | 1250.00 | Rupees One Thousand Two Hundred Fifty Only         | Each | 2,500.00 |
| 21      | Providing and fixing Towel ring brackets fixed to wooden cleats with CP brass screws with con cealed fittings arrangement of approved quality and colour 600mm (Six hundred millimetre) long towel rail complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 1.00 Number  | 520.00  | Rupees Five Hundred Twenty Only                    | Each | 520.00   |
| 22      | Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                     | 2.00 Numbers | 750.00  | Rupees Seven Hundred Fifty Only                    | Each | 1,500.00 |
| 23      | Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                    | 5.00 Numbers | 1735.00 | Rupees One Thousand Seven Hundred Thirty Five Only | Each | 8,675.00 |

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity            | Rate in |                                                      | Unit              | Amount   |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------|------------------------------------------------------|-------------------|----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                     | Figures | Words                                                |                   |          |
| 24      | Providing and fixing Shower of standard design and of approved make conforming to IS:8931 complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                                                                        | 2.00 Numbers        | 1490.00 | Rupees One Thousand Four Hundred Ninety Only         | Each              | 2,980.00 |
| 25      | Providing and fixing wall Mixture for water outlet of standard design and of approved make conforming to IS:8931 complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                                                 | 1.00 Number         | 5200.00 | Rupees Five Thousand Two Hundred Only                | Each              | 5,200.00 |
| 26      | Providing and fixing soap Dish Holder having length of 138mm, (One hundred thirty eight millimetre) breadth 102mm (One hundred two millimetre) height of 75mm (Seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms. complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.     | 3.00 Numbers        | 360.00  | Rupees Three Hundred Sixty Only                      | Each              | 1,080.00 |
| 27      | Providing and fixing 600x450mm (Six hundred into four fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6mm (Six hundred millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 3.00 Numbers        | 1400.00 | Rupees One Thousand Four Hundred Only                | Each              | 4,200.00 |
| 28      | Providing and fixing Stainless steel pipe curtain rods with steel plated brackets and screw with finials 20mm (Twenty millimetre) diameter complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                       | 30.00 Running metre | 284.30  | Rupees Two Hundred Eighty Four And Paise Thirty Only | Per Running metre | 8,529.00 |

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity      | Rate in |                          | Unit | Amount    |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|---------|--------------------------|------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                             |               | Figures | Words                    |      |           |
| 29      | Providing and fixing Curtain of high quality cotton fabric having size (7' x 4 feet) complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and <b>entire</b> satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 15.00 Numbers | 900.00  | Rupees Nine Hundred Only | Each | 13,500.00 |
|         | <b>TOTAL</b>                                                                                                                                                                                                                                                                                                                                                                                                                |               |         |                          |      | 99,643.00 |
|         | % Above/below                                                                                                                                                                                                                                                                                                                                                                                                               |               |         |                          |      |           |
|         | Quoted Amount in Figures                                                                                                                                                                                                                                                                                                                                                                                                    |               |         |                          |      |           |
|         | Quoted Amount in Words                                                                                                                                                                                                                                                                                                                                                                                                      |               |         |                          |      |           |

*Bill of quantity checked and approved for Rs. 99,643.00/only.*

Executive Engineer,  
Dehra Division,  
BPPWD Dehra.



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 99,838.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Month.

Name of Work:- Repair and Maintenance of Type-II Quarter in PWD Colony Dehra Tehsil Dehra District Kangra (H.P) (SH:- Providing and Fixing Curtains etc. (Part-VI).

| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity      | Rate in  |                                              | Unit | Amount    |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|----------|----------------------------------------------|------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                      |               | Figures  | Words                                        |      |           |
| 1       | Providing and fixing Curtain of high quality cotton fabric having size (7) x 4 feet) complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 21.00 Numbers | 900.00   | Rupees Nine Hundred Only                     | Each | 18,900.00 |
| 2       | Providing and fixing Curtain of high quality cotton fabric having size (9) x 4 feet) complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 6.00 Numbers  | 975.00   | Rupees Nine Hundred Seventy Five Only        | Each | 5,850.00  |
| 3       | Providing and Fixing wooden Dressing Table Small including polishing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                      | 1.00 Number   | 13000.00 | Rupees Thirteen Thousand Only                | Each | 13,000.00 |
| 4       | Providing & Fixing wooden Dressing Table Big size including polishing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                     | 1.00 Number   | 22000.00 | Rupees Twenty Two Thousand Only              | Each | 22,000.00 |
| 5       | Providing & Fixing wooden side Table Small including polishing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                            | 1.00 Number   | 1300.00  | Rupees One Thousand Three Hundred Only       | Each | 1,300.00  |
| 6       | Providing and fixing C.P. Brass Short Body Bib Tap with capstan head 15mm (Fifteen millimetre) dia as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.                                                                      | 5.00 Numbers  | 1340.00  | Rupees One Thousand Three Hundred Forty Only | Each | 6,700.00  |



| Sr. No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity          | Rate in  |                                              | Unit            | Amount           |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|----------|----------------------------------------------|-----------------|------------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   | Figures  | Words                                        |                 |                  |
| 7       | Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40mm (Forty millimetre) flush bend, 20mm (Twenty millimetre) over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government. | 1.00 Number       | 12000.00 | Rupees Twelve Thousand Only                  | Each            | 12,000.00        |
| 8       | Supplying and filling soil in Kitchen Garden including watering, ramming, consolidating and dressing complete in all respect including entire carriage of materials within all leads lifts and other incidentals, and as per specification and as per directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 14.88 Cubic metre | 1350.00  | Rupees One Thousand Three Hundred Fifty Only | Per Cubic metre | 20,088.00        |
|         | <b>TOTAL</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                   |          |                                              |                 | <b>99,838.00</b> |
|         | <b>% Above/below</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                   |          |                                              |                 |                  |
|         | <b>Quoted Amount in Figures</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                   |          |                                              |                 |                  |
|         | <b>Quoted Amount in Words</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                   |          |                                              |                 |                  |

*Blk of 99838.00 cheques  
8 99838.00 99838.00*


Executive Engineer,  
Dehra Division,  
UPPWD Dehra.

## Exigency Certificate

It is certified that the tenders invited vide this office NIT No.....175-78.....dated.....17/04/25 are of emergent nature of work and in public interest.

Place:

Dated:

  
Executive Engineer,  
PPWD Division,  
Dehra.