



**OFFICE OF
EXECUTIVE ENGINEER (KILLAR DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KILLAR, PANGI-176323
FAX: 01897-242223, email.hp-chm1@nic.in**

No. PW-KD-(Killar)E-Tender/NIT-2024-25/-71-75

Dated: 07/04/2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: Publishing of Tender Notice on the Departmental Website

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting Tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No. PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the tender notice are of urgent nature and in the public interest. Kindly ensure the prompt publication of the same on the website.

Encl.: Notice Inviting Tender
& Schedule of Quantity

Yours faithfully,

Executive Engineer
Killar Division,
HPPWD Killar (Pangi)

Copy for information and necessary action to:

1. The Superintending Engineer, 7th Circle, HPPWD, Dalhousie.
2. All Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer
Killar Division,
HPPWD Killar (Pangi)



OFFICE OF
EXECUTIVE ENGINEER (KILLAR DIVISION)
H.P. PUBLIC WORKS DEPARTMENT, KILLAR, PANGI-176323
FAX: 01897-242223, email.hp-chm1@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED
WIDE THIS OFFICE LETTER NO-PW-KD-CB-GA/TENDER 2024-25 71-75 DATED
07-04-2025 ARE URGENT NATURE AND PUBLIC INTEREST.



Executive Engineer,
Killar Division,
HP.PWD. Killar (Pangi)

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Killar Division H.P.PWD., Killar on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **17.04.2025** up to **10.30 A.M** and will be opened on the same day at **11.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (Non refundable) on **16.04.2025** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **16.04.2025** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Killar must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest moncy as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Job No.	Name of Work	Estimated cost	Earnest Money	Cost of form (Rs.)	Time period for completion	Form No.	Eligibility of contractor's
1	R/o rain and snow damage on Sural Bhatori road Km. 0/0 to 17/300 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
2	R/o rain and snow damage on Sural Bhatori road Km. 0/0 to 17/300 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
3	R/o rain and snow damage on Kutha road Km. 0/0 to 2/500 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
4	R/o rain and snow damage on Chaloli road Km. 0/0 to 2/600 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
5	Restoration of Rain and snow damages on Sach to Twoan Road Km. 0/0 to 24/290 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
6	Restoration of Rain and snow damages on Link Road to Village Udeen Km. 0/0 to 2/800 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
7	Restoration of Rain and snow damages on Saichu to Leo-Shoon road Km. 0/0 to 6/500 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
8	Restoration of Rain and snow damages on Saichu to Leo-Shoon road Km. 0/0 to 6/500 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
9	Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori road Km. 0/0 to 11/280 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD

10	Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori road Km. 0/0 to 11/280 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
11	Restoration of Rain and snow damages on Sach to Twoan road Km. 0/0 to 24/290 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
12	Restoration of Rain and snow damages on Phindroo to Guwari road Km 0/0 to 6/600 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
13	Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori road Km. 0/0 to 11/280 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
14	Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori road Km. 0/0 to 11/280 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
15	Restoration of Rain and snow damages on Purthi to Thandal road Km. 0/0 to 6/500 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
16	R/o rain and snow damage on Killar to Killar to Tattan Mata Mandir Road KM. 0/0 to 7/0 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
17	R/o rain and snow damage on Killar to Tattan Mata Mandir Road KM. 0/0 to 7/0 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
18	R/o rain and snow damage on Killar to Tattan Mata Mandir Road KM. 0/0 to 7/0 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
19	R/o rain and snow damage on Bus Stand to Helipad road Km. 0/0 to 2/500 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
20	R/o rain and snow damage on Bus Stand to Chowki Bazaar road Km. 0/0 to 2/500 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
21	R/o rain and snow damage on Program road Km. 0/0 to 4/0 (Sub Head:- Hiring of JCB for removal of solidified snow, slips and boulders at different Rds.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
22	Restoration of Rain and snow damages on Various road Under Sub Division NO-II Sach (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
23	Restoration of Rain and snow damages on Various road Under Sub Division NO-II Sach (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
24	Restoration of Rain and snow damages on Various road Under Sub Division NO-II Sach (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders at different RD.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD

25	Restoration of Rain and snow damages on Killar to Punto road Km. 0/0 to 5/0 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders are various RDs.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
26	Restoration of Rain and snow damages on Program road Km. 0/0 to 4/0 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders are various RDs.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
27	Restoration of Rain and snow damages on Seri Karyuni road Km. 0/0 to 8/0 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders are various RDs.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
28	Restoration of Rain and snow damages on Seri Karyuni road Km. 0/0 to 8/0 (Sub Head Hiring of JCB for removal of solidified snow, slips, and boulders are various RDs.)	99540.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
29	Restoration of Rain and snow damages on Lujay Valley road Km. 0/0 to 17/00 (Sub Head C/o R/Wall at Rd 5/620 to 5/623.)	99229.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
30	Restoration of Rain and snow damages on Lujay Valley road Km. 0/0 to 17/00 (Sub Head C/o R/Wall at Rd 5/623 to 5/626.)	99229.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
31	A/R & M/O I No Tpye,III quarater (Assistant Engineer Resisdence No-I) (Sub.Head:-Prividng Crona board flooring etc.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
32	A/R & M/O I No Tpye,III quarater (Assistant Engineer Resisdence No-I) (Sub.Head:-Prividng Crona board flooring and tile work etc.)	99857.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
33	A/R & M/O I No Tpye,III quarater (Assistant Engineer Resisdence No-I) (Sub.Head:-Prividng Crona board flooring and teak ply ceiling work etc.)	99983.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
34	A/R & M/O I No Tpye,III quarater (Assistant Engineer Resisdence No-I) (Sub.Head:- Prividng ply wood ceiling, water supply and sanitary fitting etc.)	97972.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
35	Restoration of Rain and snow damages on Lujay Valley road Km 0/0 to 17/300 (Sub-Head:-Removal of slips at various RDs).	99569.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
36	Restoration of Rain and snow damages on Lujay Valley road Km 0/0 to 17/300 (Sub-Head:-Removal of slips at various RDs).	99569.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
37	Repair and Maintenance of Non Residential Building at Killar (Civil Supply). (Sub Head:- Random Ruble Masonry and Cement plastering.)	99997.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
38	Restoration of Rain and snow damages on Gref Junction to Mall road Killar Km. 0/0 to 3/0 (Sub-Head:- C/o R/wall at Rd 0/122.50 to 0/125).	99968.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
39	Restoration of Rain and snow damages on Link road from Thamloo to Ghisal Km. 0/0 to 4/500 (Sub-Head:- C/o R/wall at Rd 1/691.20 to 1/695.40.)	98667.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD

40	Restoration of Rain and snow damages on Link road from Thamloo to Ghisal Km. 0/0 to 4/500 (Sub-Head:- C/o R/wall at Rd 1/695.40 to 1/699.60.)	98667.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
41	R/o rain and snow damage on Killar to Hudan Bhatori road Km. 0/0 to 14/600 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
42	R/o rain and snow damage on Killar to Hudan Bhatori road Km. 0/0 to 14/600 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
43	R/o rain and snow damage on Killar to Hudan Bhatori road Km. 0/0 to 14/600 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
44	R/o rain and snow damage on Killar to Hudan Bhatori road Km. 0/0 to 14/600 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
45	R/o rain and snow damage on Killar to Karyas upto Tattan Mata Mandir road Km. 0/0 to 7/0 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
46	R/o rain and snow damage on Killar to Karyas upto Tattan Mata Mandir road Km. 0/0 to 7/0 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
47	R/o rain and snow damage on Dharwas to Sural Bhatori road Km. 0/0 to 17/300 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
48	R/o rain and snow damage on Dharwas to Sural Bhatori road Km. 0/0 to 17/300 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
49	R/o rain and snow damage on Dharwas to Sural Bhatori road Km. 0/0 to 17/300 (Sub-Head:- Removal of slips at various RDs.)	99978.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
50	Restoration of Rain and snow damages on various road under Store Sub Division Trella at Killar (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	98000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
51	Restoration of Rain and snow damages on various road under Store Sub Division Trella at Killar (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	98000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
52	Restoration of Rain and snow damages on various road under Store Sub Division Trella at Killar (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	98000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
53	Restoration of Rain and snow damages on various road under Store Sub Division Trella at Killar (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	98000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
54	Restoration of Rain and snow damages on Alwas Killar Road KM. 0/0 to 27/500 (SH:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	99000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD

55	Restoration of Rain and snow damages on Alwas Killar Road KM. 0/0 to 27/500 (SH:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	99000.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
56	Restoration of Rain and snow damages on Alwas Killar Road KM. 0/0 to 27/500 (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	99855.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD
57	Restoration of Rain and snow damages on Alwas Killar Road KM. 0/0 to 27/500 (Sub-Head:- Hiring of Balero camper /Jeep for shifting of labour and material from PWD store to site of work.)	99855.00	2000	350	One Months	6&8	Class "D" enlisted in HPPWD

TERMS & CONDITION:-

- 1 The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. I sales Tax clearance certificate from the Excise and Taxation Department.
- 2 The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will **not** be entertained.
- 3 In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time an
- 4 Only two tenders form will be issued to the contractor/firm which may be noted.
- 5 Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- 6 The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- 7 All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- 8 The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved permit



Executive Engineer,
Killar Division HP,PWD,
Killar (Pangi)

For and on behalf of the governor of HP.

No. PW- KD- CB-GA-Tender/2024-25/-76-85

DATED: - 07-04-2025

Copy forwarded for information and necessary action to:-

- 1 The Engineer-in-Chief, HPPWD, Shimla.
- 2 The Chief Engineer (KZ) HPPWD Dharmshala.
- 3 The Resident Commissioner Pangi at Killar.
- 4 All the Superintending Engineer's/Executive Engineers in HPPWD.
- 5 The Tehsildar, Pangi at Killar.
- 6 The Block Development Officer, Pangi at Killar.
- 7 All the Assistant Engineer's working under this Division.
- 8 All the Head of Branches of this office.
- 9 All the contractors.
- 10 Notice Board.



Executive Engineer,
Killar Division HP,PWD,
Killar (Pangi)

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Surat Bhatori road km 0/0 to 17/300 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).


Sr. No.	Description of Items	No. or Qty	Unit	Estimated Rate (in Rs.)	Time	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
					One Month		
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B. /Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5:00 PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period execution shall be the absolute responsibility of the J.C.B. /Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and Spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00		99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
	Quoted Rate in Figures		Select			99540.00	
	Quoted Rate in Words						

Quoted Rate in Figure (+/-) (.....%/-)
Quoted Rate in Words (+/-) (.....-----.....%/-)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Sural Bhatori road km 0/0 to 17/300 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
						One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc, happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures

Quoted Rate in Words

Select

99540.00

Quoted Rate in Figures (+/-) (.....,.....,.....%)
Quoted Rate in Words (+/-) (.....,.....,.....%)

Condition :-

Rate should be quoted for all heights including all loads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
HPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain and snow damages on Kutha road km 0/0 to 2/500 (Sub Head:-Hiring of JCB for removal of solidified snow slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Time	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the Public/ private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	99540.00 Rupees Ninety Nine Thousand Five Hundred & Forty Only	

Quoted Rate in Figures
Quoted Rate in Words

Quoted Rate in Figures (+/-) {% }
Quoted Rate in Words (+/-) {% }

99540.00
Select

Conditions :-

Rate should be quoted for all heights including all leads and l.s.s.

The contractor shall procure all the materials confirming to the specifications of M.R.T at his own risk and cost.



Executive Engineer
Killer Division
HPPWD Killer

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Chaloli road km 0/0 to 2/600 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including treanning and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1,583.00	99,540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures

Quoted Rate in Words


Quoted Rate in Figure(+/-) { ,..... ,..... }

Quoted Rate in Words (+/-) { ,..... ,..... }

Condition :-

Rate should be quoted for all heights including all leads and off.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Sach to Swoan road km 0/0 to 24/290 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RDs).

PERCENTAGE SCHEDULE OF QUANTITY					
Name of Work:-Restoration of Rain and snow damages on Sach to Twoan road km 0/0 to 24/290 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD's)			Estimated Cost		
Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Earnest Money
1	Hiring of J.C.B. Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including reaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 30 PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	158.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
					Select
					99540.00
					Quoted Rate in Figures
					Quoted Rate in Words

Quoted Rate in Figure (+/-) (.....%
Quoted Rate in Words (+/-) (.....%)

Conditions

Conclusion :- Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTI at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain and snow damages on Link road to Village Udeen km 0/0 to 2/800 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00 Rupees Ninety Nine Thousand Five Hundred & Fourty Only
			Select		99540.00

Quoted Rate in Figures
Quoted Rate in Words

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORT/H at his own risk and cost.



Executive Engineer
Kittar Division
IIPWD Killar

Percentage Bill of Quantity

Name of Work: Restoration of Rain and snow damages on Saiehu to Leo-Shoon Road Km 0.0 to 6/500 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
				Time	One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including removing and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loulder should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
Total:				99540.00	
Quoted Rate in Figures		Select			
Quoted Rate in Words					

Quoted Rate in Figure (+/-) (.....,.....,.....%)

Quoted Rate in Words (+/-) (.....,.....,.....%)


Sr. No 844 for the year 2024-25

DNT/Bill of Quantity approved for Rs. 99540.00 Only

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTI at his own risk and cost.



Executive Engineer
Killar Division
of KMP Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Saichu to Leo-Shoon Road Km 0/0 to 6/500 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and kind including treasuring and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
	Quated Rate in Figures					99540.00
	Quoted Rate in Words					Select

Quoted Rate in Figure (+) (.....%)

Condition 1

Role should be adopted for all helobs including all leads and lift

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Kilar Division
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatorji Road Km 0/0 to 11/280 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
					Time	
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9:00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Fourty Only

Quoted Rate in Figures

Quoted Rate in Words

Quoted Rate in Figure (+/-) (.....,.....,%)
 Quoted Rate in Words (+/-) (.....,.....,%)

Select

99540.00

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
HPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work-Restoration of Rain and snow damages on Sachremoval of solidified snow, slips, and boulders at different RD.

PERCENTAGE SCHEDULE OF QUANTITY					
Sr. No.	Description of Items	No. of Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loulder should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The file and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
					99540.00

Quoted Rate in Figure(f+g) (.....,.....,
Quoted Rate in Weiszfeld (.....,
Quoted Rate in Weiszfeld (.....,

Condition

CATHARINE H. BROWN

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.


Executive Engineer
Kiflar Division
PPAW/D. Killor

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Sach to Twoan road km 0/0 to 24/290 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Time	One Month
				Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Rs.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate In Figures

Quoted Rate In Words

Quoted Rate in Figure(+/-) (.....,.....%)

Quoted Rate in Words (+/-) (.....,.....%)

99540.00

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

SOL NO. 12

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Phindroo to Guwari road km 0/0 to 6/600 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Time	One Month	
						Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfaction's of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1581.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures

Quoted Rate in Figure(+/-) (.....,.....,.....%)
 Quoted Rate in Words (+/-) (.....,.....,.....%)

Quoted Rate in Words

99540.00

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
IPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Scope of Work: Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori Road Km 0/0 to 11/280 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

99540.00
2000.00

Earnest Money

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Time	One Month
					Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9:00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupes Ninety Nine Thousand Five Hundred & Fourt Only

Quoted Rate in Figures

Quoted Rate in Words

Quoted Rate in Figure(+/-) (.....%)
Quoted Rate in Words (+/-) (.....-%)

Condition :-
Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Sach to Kumar Parmar Bhatori Road Km 0/0 to 11/280 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
						Time
						One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Fourty Only
	Quoted Rate in Figures			Select		99540.00
	Quoted Rate in Words					

Quoted Rate in Figure(+/-) (.....,.....,.....%)
 Quoted Rate in Words (+/-) (-----,-----,-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilar Div. Sen
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

No. of Work: Restoration of Rain and snow damages on Purthi to Thandal road km 0/0 to 6/500 (Sub Head:-Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Estimated Cost	9954.00
						Time	One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, Watch and ward of Excavator also be borne by the contractor/gamer. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Total Amount with all taxes Including GST in Rs.	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures

Quoted Rate in Figure (+/-) (.....,.....,.....%)

Quoted Rate in Words

Quoted Rate in Words (+/-) (.....,.....,.....%)

Select

99540.00

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Kilar, Divisional
Head PWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Estimated Cost Earnest Money	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 39 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The file and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	2000.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
		Select				
	Quoted Rate in Figures			99540.00		
	Quoted Rate in Words					

Quoted Rate in Figure (+/-) (.....,....., %)

Quoted Rate in Words (+/-) (-----,-----,--%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain and snow damages on Killar to Tattan Mata Mandir Road Km 0/0 to 7/0 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Rupees Ninety Nine Thousand Five Hundred & Forty Only
				Time	One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and load including framing and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfaction of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 Hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spares, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures

Quoted Rate in Words

Quoted Rate in Figure(+/-) (.....,.....,.....%)

Quoted Rate in Words (+/-) (.....,.....,.....-%)

99540.00

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTI at his own risk and cost.

Executive Engineer
Killar Division
HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Killar to Tattan Mata Mandir Road Km 0/0 to 7/0 (Hiring of jCB for removal of solidified snow, slips, and boulders at different RD).

PERCENTAGE SCHEDULE OF QUANTITY					
Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfaction of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and Spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00 Rupees Ninety Nine Thousand Five Hundred & Forty Only
					99540.00
					Select

卷之二

Dotted Rate in Figure (+) (.....%)
Dashed Rate in Words (+/-) (-----%)

卷之三

388 *Malay J. Hist.* [Vol. 36, No. 2, 2004]

The contractor shall procure all the materials confirming to the specifications
Rate should be quoted for all heights including all leads and lift.

Executive Engineer
Kellar Division
HPPWD Kellar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Bus Stand to Helpad road km 0/0 to 2/500 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and lead including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Forty Only
	Quoted Rate in Figures		Select		99540.00	
	Quoted Rate in Words					

Quoted Rate in Figure (+/-) { , % }
 Quoted Rate in Words (+/-) (..... , %)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



S. A. Engineer
Killar Division
WPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Bus Stand to Chawki Bazaar road km 0/0 to 2/500 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qn.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Time	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debries clear from road surface upto any height, depth and load including breaking and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator can Loader should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	6.3.00	Per cubic metre	1580.00	99540.00	One Month	Rupees Ninety Nine Thousand Five Hundred & Forty Only

Quoted Rate in Figures**Quoted Rate in Words**

Quoted Rate in Figure (+/-) (.....,.....,%)
Quoted Rate in Words (+/-) (.....,.....,%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killer Division
IPPWD Killer

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Program Road Km 0/0 to 4/0 (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Time	
					One Month	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	99540.00 Rupees Ninety Nine Thousand Five Hundred & Fourty Only	

Quoted Rate in Figures

Quoted Rate in Words


Quoted Rate in Figure(+/-) (.....,...%)
Quoted Rate in Words (+/-) (-----,...%)

99540.00

Condition:-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killer Division
HPWD Killer

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain and snow damages on Various road under Sub-Division No-II Sach (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sl. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Estimated Cost	
				Time	Total Amount with all taxes Including GST in Words.
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and load including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum Junta per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be borne by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580.00	99540.00	Rupees Ninety Nine Thousand Five Hundred & Fourty Only
	Quoted Rate in Figures		Select		99540.00
	Quoted Rate in Words				

Quoted Rate in Figure (+/-) (.....,.....,.....,.....%)
Quoted Rate in Words (+/-) (.....,.....,.....,.....,.....%)

Condition :-

Rate should be quoted for all heights including all leads and lifts.
The contractor shall procure all the materials confirming to the specifications
of M.O.R.T at his own risk and cost.



Executive Engineer
Kellar Division
H.P.W.D. Kellar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain and snow damages on Various road under Sub-Division No-II Sach (Hiring of JCB for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in	Estimated Cost
						Earnest Money
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and load including teaming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfaction of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5.00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00	Per cubic metre	1580.00	99540.00	Rupes Ninety Nine Thousand Five Hundred & Four Only

Quoted Rate in Figures	Quoted Rate in Words
	Select

Quoted Rate in Figure(/-) (.....,.....,.....,.....,.....)
Quoted Rate in Words (+/-) (.....,.....,.....,.....,.....)

Condition :-

Rate should be quoted for all heights including all loads and lift.
The contractor shall procure all the materials confirming to the specifications
of MORTH at his own risk and cost.



Executive Engineer
Kilar Division
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain and snow damages on Various road under Sub-Division No-II Sach (Hiring of JC B for removal of solidified snow, slips, and boulders at different RD).

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Estimated Cost	99540.00
				Time	One Month
1	Hiring of J.C.B./Excavator for removal of slips, boulders and debris clear from road surface upto any height, depth and lead including trimming and cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer-in-Charge. The J.C.B./Excavator cum Loader should work minimum 8.00 hours from 9.00 AM to 5:00PM daily and excavate at least 30 cum quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	63.00 Per cubic metre	1580/-	99540.00	Rupees Ninety Nine Thousand Five Hundred & Fourty Only

Quoted Rate in Figures

Quoted Rate in Words

Quoted Rate in Figures (+/-) {% }
 Quoted Rate in Words (+/-) {% }

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTI at his own risk and cost.

Executive Engineer
Killar Division
MPPWD Killar

Scheduled Bill of Quantity						
Sl. No.	Description of work	Qty	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs.	Time Limit
1	Hiring of JC/ Excavator cum loader for removal of solidified snow, slips, boulders and debries clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcera happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/ Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary hutmentage etcera shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including of GST, toll tax, sale tax or other taxes imposed by the government.	63.00	per Hour	1580	99540	One month
	Quoted Rate in Figure				99540	
	Quoted Rate in Words					

Quoted Rate in Figure (+/-).....%)

Quoted Rate in Words(+/-).....%)

Condition:-

Rate should be quoted for all height including all leads and lif
 The contractor shall procure all the materials confirming to the specifications,
 Of MORTH at his own risk and cost.



Executive Engineer
 Kullar Division IIP PWD
 Kullar (Pangi)

Scheduled Bill of Quantity						
Sr. No.	Description of work	Qty	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs.	ESTIMATED COST
1	Hiring of JCB Excavator cum loader for removal of solidified snow, slips, boulders and debris clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcetera happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/ Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary humentage etcetera shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be verified duly	63.00	per Hour	1580	99540	99540.00 Earliest Minusy 20000.00
	Quoted Rate in Figure (+/-).....%{}					
	Quoted Rate in Words(+/-).....%{}					
	Quoted Rate in Words(+/-).....%{}					

Quoted Rate in Figure (+/-).....%{}

Quoted Rate in Words(+/-).....%{}

Condition:-

Rate should be quoted for all height including all leads and Iff
 The contractor shall procure all the materials confirming to the specifications.
 Of MORTH at his own risk and cost.



Contractor's Signature
 Kular Division HP PWD
 Kilar (Pangi)

Scheduled Bill of Quantity					
Sr. No.	Description of work	Qty	Unit	ESTIMATED COST	99540.00
				Total amount with all taxes including GST in Rs.	
1	Hiring of JCB Excavator cum loader for removal of solidified snow, slips, boulders and debries clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of E.Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcera happened during the course of hiring period execution shall be the absolute responsibility of the JCB. Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary hutmentage etcera shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be duly verified	63.00	per Hour	1580	99540
	Quoted Rate in Figure				99540
	Quoted Rate in Words				

Quoted Rate in Figure { +/-% }

Quoted Rate in Words { +/-% }

Condition:-

Rate should be quoted for all height including all leads and if
The contractor shall procure all the materials confirming to the specifications.
OR MORTH at his own risk and cost.



Executive Engineer
Kajal Division (IP PMV)
Kallar (Panj)


Scheduled Bill of Quantity						
Sr. No.	Description of work	Qty	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs.	Time Limit
1	Hiring of JC/ Excavator cum loader for removal of solidified snow, slips, boulders and debries clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcera happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/ Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary hutmentage etcera shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be duly verified	61.00	per Hour	1580	99540	One month
	Quoted Rate in Figure				99540	
	Quoted Rate in Words					

Quoted Rate in Figure (+/-).....%)

Quoted Rate in Words(+/-).....%)

Condition:-

Rate should be quoted for all height including all leads and lif
 The contractor shall procure all the materials confirming to the specifications
 Of MORTH at his own risk and cost.



Executive Engineer
 Kilbar Division (P.P.W.)
 Kilbar (Pung)

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-R/o of rain and snow damages on Lujay Valley road km 0/0 to 17/300 (Sub Head:-C/o Rwall at Rd 5/620 to 5/623)

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.) with all taxes Including GST in D.	Total Amount with all taxes Including GST in Words.	Estimated Cost		
					Earnest Money	Time	One Month
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary Rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawing and M O R D technical specifications Clause 305 and 1603.4 as per direction of the Engineer -in - charge including setting out, shoring and bracing, removal of stumps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer - in Charge . Including carriage of materials within all leads and lifts and other incidental . The rate including of GST or other taxes imposed by the government	8.34	Per cubic Metre	539.90	4503.00	Rupes Five Hundred & Thirty Nine - Paise Ninety Only	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:6 1:2. one cement is to six sand (is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days - in open foundations for all type of structures as in Retaining walls, Breast walls, Abutments, toe walls and the like in foundation of Rwalls, B/walls etcetera including pumping or hauling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M O R D technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer -in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.47	Per Cubic Metre	6871.89	10102.00	Rupes Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only	
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:4.81 one cement is to four sand (is to eight graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days - in open foundations for all type of structures as in Retaining walls, Breast walls, Abutments, toe walls and the like in foundation of Rwalls, B/walls etcetera including pumping or hauling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M O R D technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.60	Per Cubic Metre	7345.40	4407.00	Rupes Seven Thousand Three Hundred & Forty Five - Paise Fourty Only	
4	Random rubble masonry uncoursed/brought to courses with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, abutments and similar works etcetera, in all heights/depths in or under water including pumping or hauling out water (surface and sub soil water) / dewatering, removal of slushes, which may arisens at the time of masonry work under water including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and to the entire satisfaction/direction of Engineer -in-Charge including hauling /carriage of materials to various locations through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	7.17	Per Cubic Metre	5338.80	38279.00	Rupes Five Thousand Three Hundred & Thirty Eight - Paise Eighty Only	

5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etc in all heights/depths as per MORD technical specification clause 702,704,706.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respects. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.91 Per Cubic Metre	4037.80	35977.00 Rupees Four Thousand & Thirty Seven - Paisa Eighty Only
6	Back filling with granular material behind abutment wing wall and return wall and retaining/ breast walls, complete as per drawing and M.O.R.D technical specifications clause 1604.7 and section 3(i), as per direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	4.40 Per Cubic Metre	1354.70	5961.00 Rupees One Thousand Three Hundred & Fifty Four - Paisa Seventy Only
		Select		99229.00


Executive Engineer
Malkana Division
M.P.W.D. Kilar

Quoted Rate in Figures
Quoted Rate in Words

Quoted Rate in Figure(+)/- (..... %) %)
Quoted Rate in Words (+/-) (..... %) %)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work: R/o of rain and snow damages on Lujay Valley road km 0/0 to 17.300 (Sub Head-C/o R/wall at Rd 5/623 to 5/626)

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Time	Estimated Cost	
							Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Words.
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary Rock, Hard rock, chiseling/digging out of rock (where blasting is prohibited) as per drawing and M O R D technical specifications Clause 305 and 1003.4 as per direction of the Engineer -in-charge including setting out, shoring and bracing, removal of stumps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer - in Charge . Including carriage of materials within all leads and lifts and other incidental . The rate including of GST or other taxes imposed by the government.	834	Per cubic Metre	539.90	4503.00	Rupees Five Hundred & Thirty Nine - Paise Ninety Only	Rupees Five Hundred & Thirty Nine - Paise Ninety Only	Rupees Five Hundred & Thirty Nine - Paise Ninety Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1.6 12/ (one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter & Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days - in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments, toe walls and the like in foundation of R/walls. B/walls etcetera - including pumping or hauling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M O R D technical specification Clauses 80/2,80/3,120/2 and 120/3 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	147	Per Cubic Metre	6871.89	10102.00	Rupees Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only	Rupees Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only	Rupees Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1.4-8/ (one cement is to four sand is to eight graded crushed stone aggregate 20millimeter & Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days - in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments, toe walls and the like in foundation of R/walls. B/walls etcetera - including pumping or hauling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M O R D technical specification Clauses 80/2,80/3,120/2 and 120/3 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.60	Per Cubic Metre	7345.40	4407.00	Rupees Seven Thousand Three Hundred & Forty Five - Paise Forty Only	Rupees Seven Thousand Three Hundred & Forty Five - Paise Forty Only	Rupees Seven Thousand Three Hundred & Forty Five - Paise Forty Only
4	Random rubble masonry -as coursed/brought to splices with hard stones of approved quality in sub structure in cement mortar 1.6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, abutments and similar works existing in all heights/depths in or under water including pumping or hauling out water (surface and sub soil water) / dewatering, removal of slushes, which may arissen at the time of masonry work under water including curing complete as per drawing and technical specification clause 70/2, 70/4,120/2 and 120/4 and to the entire satisfaction/direction of Engineer - in- Charge including hauling /carriage of materials to various locations through all modes of transportation all leads, lifts and other incidental complete in all respect . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	717	Per Cubic Metre	5338.80	38279.00	Rupees Five Thousand Three Hundred & Thirty Eight - Paise Eighty Only	Rupees Five Thousand Three Hundred & Thirty Eight - Paise Eighty Only	Rupees Five Thousand Three Hundred & Thirty Eight - Paise Eighty Only

5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etc in all heights/depths as per MORD technical specification clause 702,704,706,5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Makana, tolltax. Sale Tax or other taxes imposed by the government.	8.9 Per Cubic Metre	4037.80	35977.00	Rupees Four Thousand & Thirty Seven - Paise Eighty Only
6	Back filling with granular material behind abutment wing wall and return wall and retaining breast walls, complete as per drawing and M.R.D. technical specification's clause 1604.7 and section 300, as per direction of Engineer in Charge including carriage of materials with in all heads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	4.40 Per Cubic Metre	1354.70	5961.00	Rupees One Thousand Three Hundred & Fifty Four - Paise Seventy Only
Quoted Rate in Figures		Select		99229.00	
Quoted Rate in Words					

Quoted Rate in Figures (+/-) (.....
.....%)
Quoted Rate in Words (+/-) (.....,.....,.....%)

Condition :-

Rate should be quoted for all flights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications.

Executive Engineer
Katal Division
HPPWD Kollar

PERCENTAGE SCHEDEULE OF QUANTITY

Name of Work:-A/R & M/O I No Type III Quarter (Assistant Engineer Residence No-I) at Killar Pangi (Sub Head:- Providing crona board flooring etc.)		Estimated Cost	Estimated Cost
		Earnest Money	99978.00
Sr. No.	Description of Items	No. or Qty.	Estimated Rate (in Rs.)
1	Providing and fixing High density fire proof arm stong 8.30mm thick flooring complete and 4mm thick density crona board (Corana /ARM Stong or Equivalent Board) as per the direction of Engineer-in-Charge, as per specification, approved drawing, design, to the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	35.08 Per Square Metre	2850.00
	Quoted Rate in Figures		99978.00
	Quoted Rate in Words	Select	99978.00

Quoted Rate in Figures(+/-) {% }

Quoted Rate in Words (+/-) {-% }

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications
of MORTH at his own risk and cost.


 Executive Engineer
 Killar Division
 RPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Works, A/R & M/O 1 No Type III Quarter (Assistant Engineer Residence No-1) at Killar Pangi (Sub Head:- Providing crona board flooring and tile work etc.)				Estimated Cost	Estimated Cost
				Earnest Money	20000.00
Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount including GST with all taxes
1	Providing and fixing High density fire proof arm strong 8.30mm thick flooring complete and 4mm thick density crona board (Corona /ARM Strong or Equivalent Board) as per the direction of Engineer-in-Charge, as per specification, approved drawing, design, to the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	4.20	Per Square Metre	2850.00	11970.00 Rupees Two Thousand Eight Hundred & Fifty Only
2	Providing and laying vitrified tiles of Kajaria/Orient or equivalent of Nitco tiles 600x600mm (six hundred into six hundred) millimetre Anti skid in flooring (readies of steps laid on a bed of 12mm (twelve millimetre) thick cement mortar 1:3 (one cement two sand) finished with flush pointing in white cement with pigment if required to match shade complete as per HPPWD specifications, as per the entire satisfaction and direction of Engineer in charge including hauling carriage of materials to various location through all modes of transportation within all leads, lifts and other incidental complete in all respect. The rate inclusive of GST,octroi,royalty,malkhana and all type of taxes imposed by the Govt.	28.18	Per Sqm.	2150.00	60587.00 Rupees Two Thousand One Hundred & Fifty Only
3	Providing wood work in frames of false ceiling, partition etc of soft wood in position first class Kail wood complete, as per HPPWD specifications, approved Drawings/design, as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi,royalty,malkhana and all type of taxes imposed by the Govt..	0.26	Per Cubic Metre	105000.00	27300.00 Rupees One Lakh Five Thousand Only
	Quoted Rate in Figures		Select		99857.00
	Quoted Rate in Words				

Quoted Rate in Figure(+/-) (.....,.....,.....%)

Quoted Rate in Words (+/-) (.....,.....,.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.


 Executive Engineer
 Killar Division
 HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Works-A/R & M/O 1 No Type III Quarter (Assistant Engineer Residence No-I) at Killar Pangj (Sub Head:- Providing crona board flooring and teak ply ceiling work etc.)

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
					Time
1	Providing wood work in frames of false ceiling, partition etc/ra of soft wood in position first class Kail wood complete, as per HPPWD specifications, approved Drawings/design, as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi,royalty,malkam and all type of taxes imposed by the Govt..	0.09 Per Cubic Metre	10500.00	9450.00	Rupees One Lakh Five Thousand Only
2	Providing and fixing High density fire proof' arm strong 8.30mm thick flooring complete and 4mm thick density crona board (Coriana /ARM Storing or Equivalent Board) as per the direction of Engineer-in-Charge, as per specification, approved drawing, design, to the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	1.40 Per Square Metre	285.00	3990.00	Rupees Two Thousand Eight Hundred & Fifty Only
3	Providing and fixing decorated teak ply 4mm thick in ceiling, moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/nails on the edges of the Pre-laminated particle board including all leads and lifts as per direction of the Engineer-in-Charge	46.78 Per square metre	185.00	86543.00	Rupees One Thousand Eight Hundred & Fifty Only
	Quoted Rate in Figures		Select		99983.00
	Quoted Rate in Words				

Quoted Rate in Figure(+) (.....%)
Quoted Rate in Words (+-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTI at his own risk and cost.


 Executive Engineer
 Killar Division
 HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST	Time	Total Amount with all taxes including GST in Words.
					Including GST in		
1	Providing and fixing 6mm (Six millimetre) thick commercial ply wood ceiling of approved quality and with butt jointing and nails complete (Frame work and cover fittings to be measured and paid for separately) as per HPPWD specifications, approved Drawings,design, as per the entire satisfaction and direction of Engineer in charge including hauling carriage of materials to various location through all modes of transportation within all leads, lifts and other incidental complete in all respect. The rate inclusive of GST,octroi,royalty,malkana and all type of taxes imposed by the Govt.	46.78	Per square metre	1350.00	63153.00 Rupees One Thousand Three Hundred & Fifty Only	One Month	
2	Providing plinth protection 50mm(fifty millimetre) thick in cement concrete 1:3:6 (one cement : 5three sand six graded stone aggregate 20mm(twenty millimetre) nominal size as per HPPWD specifications,approved Drawing,design as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals. The rate includes, royalty charges, octroi, sale tax, GST, malkana and any other taxes imposed by the Government.	26.04	Per Square Metre	780.00	20311.00 Rupees Seven Hundred & Eighty Only		
3	Providing and fixing 610x310mm (Six hundred ten into five hundred ten millimetre) with bowl depth 200mm (Two hundred millimetre) stainless steel kitchen sink of approved standard ISI make with drain board and CP waste with CI or MS brackets painted white including cutting holes and making good the same but excluding fittings tap Jaquar,Jai or ESS make complete as per HPPWD specifications, to the entire satisfaction and direction of Engineer in charge including hauling carriage of materials to various location through all modes of transportation within all leads, lifts and other incidental complete in all respect. The rate inclusive of GST,octroi,royalty,malkana and all type of taxes imposed by the Govt.	1.00	Each.	4500.00	4500.00 Rupees Four Thousand Five Hundred Only		
4	Providing and fixing 15mm dia (Fifteen millimetre) diametres C.P. (Chromium Plated) Brass Bib tap No.12, with capstan head of Continental series of Jaquar/Classic series of Hindware/ Floral series of Cera, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, well tax, sale tax, GST or any other taxes imposed by the Government.	3.00	Each	980.00	2940.00 Rupees Nine Hundred & Eighty Only		
5	Providing and fixing 75 mm (seventy five) dia nominal size PVC high pressure spigot and socket soil, waste and ventilating pipes ISI marked to be fixing with approved adhesive complete, as per HPPWD specifications,approved Drawing,design as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi,royalty,malkana and all type of taxes imposed by the Govt.	14.00	Per Running Metre	16.00	2268.00 Rupees One Hundred & Sixty Two Only		

6	Providing and fixing vitruous china wash basin 630x450 mm flat back I.S. marked no.-1025(chair) C.I. or M.S. brackets painted white including cutting holes and making good the same with pedestal bat excluding fittings within all leads, lifts of materials and other incidentals.	1.00 Each	4800.00	4800.00	Rupees Four Thousand Eight Hundred Only
	Quoted Rate in Figures				
	Quoted Rate in Words		Select		9792.00

Quoted Rate in Figure (+/-) (.....,.....%)
 Quoted Rate in Words (+/-) (-----,-----%)

Condition :

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications
 of MORTHL at his own risk and cost.



Executive Engineer
 Killar Division
 HPPWD Killar

Percentage Schedule of Quantity						
			Estimated Cost		Earnest Money	
Sr. No.	Description of Items	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	634.20	Per cubic metre	157.00	99569.00	Rupees Ninety Nine Thousand Five Hundred & Sixty Nine Only
Total:-						
	Quoted Rate in Figures					
	Quoted Rate in Words			Select		

Quoted Rate in Figure(+/-) (.....,...,%)

Quoted Rate in Words (+/-) (-----,-%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar


Percentage Schedule of Quantity					
Name of Work:-R/o Rain and Snow damages on Lujay Valley road km 0/0 to 17/300 (SH:-Removal of Slips at Various Rds)				Estimated Cost Earnest Money	
Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	634.20	Per cubic metre	157.00	Rupees Ninety Nine Thousand Five Hundred & Sixty Nine Only
Total:-					99569.00
Quated Rate in Figures					
Quoted Rate in Words			Select		

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Name of Work:-Repair and Maintenance of Non Residential Building at Killar (Civil Supply).
 (Sub-Head: - Random Rubble Masonry and Cement plastering)

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Estimated Cost	99510.00
				Earnest Money	2000.00
				Time	One Month
				Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etcera in all type of classification of soil comprising of ordinary soil ordinary Rock Hard rock, chiseling wedging out of rock (where blasting is prohibited) as per drawing and M.O.R.D. technical specifications Clause 305 and 1603.4 as per direction of the Engineer -in - charge including setting out, shoring and bracing, removal of stumps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) completed thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer - in Charge - including carriage of materials within all leads and lifts and other incidental . The rate including of GST, or other taxes imposed by the government.	8.10 Per cubic Metre	539.90	4373.00 Rupees Four Thousand Three Hundred & Seventy Three Only	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:4:8C one cement is to four sand is to eight graded crushed stone aggregate 20mm(Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls, Abutments,toe walls and the like in foundation of R/walls, D/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.75 Per Cubic Metre	7345.50	5509.00 Rupees Five Thousand Five Hundred & Nine Only	
3	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcera in all heights/depths as per MORD technical specification clause 702,704,1606.5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	14.90 Per Cubic Metre	5338.80	79548.00 Rupees Seventy Nine Thousand Five Hundred & Forty Eight Only	

4	15 mm (Fifteen millimetre) cement plaster in single coat on rough side of brick/ concrete/stone masonry for interior plastering @/- per floor all levels including arched, internal rounded angle, chamber and or rounded angle not exceeding 80mm (eighty millimetres) in girth and finished even and smooth in cement mortar 1:6 (one cement six sand) as per directions of Engineer-in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Makana, tolltax, Safe Tax or other taxes imposed by the government.	36.00 Per Square Metre	280.00	10080.00 Rupees Ten Thousand & Eighty Only
Total:			99510.00	
		Select		

Quoted Rate in Figures
Quoted Rate in Words (+/-) (.....,.....,.....%)
Quoted Rate in Words (+/-) (.....,.....,.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Executive Engineer
Kijlar Division
MPPWD Kilar

Percentage Schedule of Quantity

Name of Work:-R/o of rain and snow damages on Gref Junction to Mall road Killar km 0/0 to 3/0 (Sub Head:-C/o R/wall at Rd 0/122.50 to 0/125)

Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Estimated Cost	99968.00
				Time	One Month	Earnest Money	2000.00
1	Earth work in excavation for all types of road structures such as retaining wall,breast wall, culverts, drains and parapets etc in all type of classification of soil comprising of ordinary soil, ordinary Rock,Hard rock, chiseling/weeding out of rock (where blasting is prohibited) as per drawing and M.O.R.D technical specifications Clause 305 and 1603.4 as per direction of the Engineer-in-charge including setting out, shoring and bracing, removal of stumps and other deleterious material and disposal of material upto any leads and upto any lots, including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer -in Charge Including carriage of materials within all leads and lots and other incidental. The rate including of GST, or other taxes imposed by the government.	9.05	Per cubic Metre	5339.90	4886.00	Rupees Four Thousand Eight Hundred & Eighty Six Only	Rupees Four Thousand Eight Hundred & Eighty Six Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1.6 12 (one cement is to six sand is to twelve graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D technical specification Clauses 802.803.1202 and 1203, and as per directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.22	Per Cubic Metre	6871.89	8384.00	Rupees Eight Thousand Three Hundred & Eighty Four Only	Rupees Eight Thousand & Eighty Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1.4-84 one cement is to four sand is to eight graded crushed stone aggregate 25millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments,toe walls and the like in foundation of R/walls, B/walls etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D technical specification Clauses 802.803.1202 and 1203, and as per directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.10	Per Cubic Metre	7345.40	8080.00	Rupees Eight Thousand & Eighty Only	Rupees Eight Thousand & Eighty Only
4	Random rubble masonry uncoursed/brought to courses with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutments and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) / dewatering, removal of slushes, which may arise at the time of masonry work under water including curing complete as per drawing and technical specification clause 702, 704.1202 and 1204 and to the entire satisfaction/direction of Engineer -in- Charge including hauling carriage of materials to various locations through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	6.80	Per Cubic Metre	5338.80	36304.00	Rupees Thirty Six Thousand Three Hundred & Four Only	Rupees Thirty Six Thousand Three Hundred & Four Only

5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etc in all heights depths as per MORD technical specification clause 702.704.1606.5 and as per directions of Engineer - in- Charge including handling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of petroli, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	9.02 Per Cubic Metre	4037.80	36421.00 Rupees Thirty Six Thousand Four Hundred & Twenty One Only
6	Back filling with granular material behind abutment wing wall and return wall and retaining breast walls, complete as per drawing and M.R.D technical specifications clause 1604.7 and section 300, as per direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	4.35 Per Cubic Metre	1354.70	5893.00 Rupees Five Thousand Eight Hundred & Ninety Three Only
	Total:-			99968.00
	Quoted Rate in Figures			
	Quoted Rate in Words			
		Select		

Quoted Rate in Figures (----) (-----) a_0

Quoted Rate in Words (+/-) (-----) a_0

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of M.R.D at his own risk and cost.



Executive Engineer
Kilar Division
HPPWD Kilar

PERCENTAGE SCHEDULE OF QUANTITY

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Time		Total Amount with all taxes Including GST in Words.
				Total Amount with all taxes Including GST in Rs.	One Month	
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etcetera in all types of classification of soil comprising of ordinary soil, ordinary Rock, Hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawing and M.O.R.D. technical specifications Clause 305 and 1603.4 as per direction of the Engineer -in - charge including setting out, shoring and bracing, removal of stamps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer - in Charge . Including carriage of materials within all leads and lifts and other incidental . The rate including of GST, or other taxes imposed by the government.	8.57 Per cubic Metre	539.90 P-	4627.00	Rupees Five Hundred & Thirty Nine - Paise Ninety Only	
2	Providing and laying cement concrete 1:6:12 (One cement: Six sand: Twelve graded stone aggregate 40mm (forty millimetres) nominal size) and curing complete including cost of form work in foundation and plinth, and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of GST, or other taxes imposed by the government.	1.81 Per Cubic Metre	6871.89	12438.00	Rupees Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only	
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8, one cement is to four sand is to eight graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls, Abutments,toe walls and the like in foundation of Rovails, Bawalis etcetera (including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Makana, tolltax, Sale Tax or other taxes imposed by the government.	0.76 Per Cubic Metre	7345.40	5583.00	Rupees Seven Thousand Three Hundred & Fourty Five - Paise Forty Only	

		Quoted Rate in Figures	Quoted Rate in Words		
4	Random rubble masonry uncoursed/brought to courses with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutments and similar works etcetera, in all heights/depths in or under water including pumping or bailing out water (surface and sub soil water) /dewatering, Removal of slushes, which may arise at the time of masonry work under water including curing complete as per drawing and technical specification clause 702, 704,1202 and 1204 and to the entire satisfaction/direction of Engineer -in- Charge including hauling /carriage of materials to various locations through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	6.68 Per Cubic Metre	5338.80	35663.00	Rupees Five Thousand Three Hundred & Thirty Eight - Paisa Eighty Only
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetera in all heights/depths as per MORD technical specification clause 702,704,1606,5 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.49 Per Cubic Metre	4037.80	34781.00	Rupees Four Thousand & Thirty Seven - Paisa Eighty Only
6	Back filling with granular material behind abutment wing wall and return wall and retaining/ breast walls, complete as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300, as per direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	3.11 Per Cubic Metre	1345.70	4185.00	Rupees One Thousand Three Hundred & Forty Five - Paisa Seventy Only
7	Providing and laying P.C.C. M-20 coping on the top of the wing wall,return wall & Breast wall etc.complete as per drawing and technical specification clause 612.710.1204.3.1(1-2,4)and as per directions of Engineer -in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of GST, or other taxes imposed by the government.	4.20 Per Running Metre	450.00	1890.00	Rupees Four Hundred & Fifty Only
		Select		98667.00	

Quoted Rate in Figure(+/-) (.....%) (.....%)
 Quoted Rate in Words (+/-) (.....%) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications



Executive Engineer
 Killar Division
 HPPWD Killar

PERCENTAGE SCHEDULE OF QUANTITY

Sr. No.	Description of Items	No. or Unit Qty.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.	Total Amount with all taxes Including GST in Words.
					Time One Month
1	Earth work in excavation for all types of road structures such as retaining wall, breast wall, culverts, drains and parapets etc in all type of classification of soil comprising of ordinary soil, ordinary Rock, Hard rock, chiselling/wedging out of rock (where blasting is prohibited) as per drawing and M.O.R.D. technical specifications Clause 305 and 103.4 as per direction of the Engineer -in - charge including setting out, shoring and bracing, removal of stamps and other deleterious material and disposal of material upto any leads and upto any lifts , including dressing of sides and bottom and buckfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and pumping and hauling out water (surface and sub soil water) upon any depth and any quantum of water including cleaning of slush which may arise out during desilting as per the direction of the Engineer - in Charge . Including carriage of materials within all leads and lifts and other incidental . The rate including of GST, or other taxes imposed by the government.	8.57 Per cubic Metre	539.90	4627.00	Rupes Five Hundred & Thirty Nine - Paise Ninety Only
2	Providing and laying cement concrete 1:6: 12 (One cement: Six sand: Twelve graded stone aggregate 40mm (forty millimetres) nominal size) and curing complete including cost of form work in foundation and plinth, and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of GST, or other taxes imposed by the government.	1.81 Per Cubic Metre	6871.89	12438.00	Rupes Six Thousand Eight Hundred & Seventy One - Paise Eighty Nine Only
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concretenominal mix 1:4:8(one cement is to four sand is to eight graded crushed stone aggregate 20millimeter (Twenty millimeter) nominal size in or under water and curing complete for 14(fourteen) days , in open foundations for all type of structures as in Retaining walls, Breast walls,Abutments, toe walls and the like in foundation of R.walls, Br.walls etcetera including pumping or hauling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights ' depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Makana, tolltax, Sale tax or other taxes imposed by the government.	0.76 Per Cubic Metre	7345.40	5583.00	Rupes Seven Thousand Three Hundred & Fourty Five - Paise Fourty Only

Name of Work: R/o rain and snow damages on Link road from Thamloo to Ghisal km 0/0 to 4/500 (Sub Head:-C/I o R/wall at Rd 1/695.40 to 1/699.60)

		Quoted Rate in Figures	Quoted Rate in Words
4	Random rubble masonry uncoursed/brought to courses with hard stones of approved quality in sub structure in cement mortar 1:6 (one cement is to six sand) for structure like retaining walls, breast walls, wing walls, toe walls, abutments and similar works etcetera, in all heights/depths in or under water including pumping or bailing on water (surface and sub soil water) / dewatering, removal of slushes, which may arisens at the time of masonry work under water including curing complete as per drawing and technical specification clause 702, 704, J202 and J204 and to the entire satisfaction/direction of Engineer - in Charge including hauling /carriage of materials to various locations through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	6.68 Per Cubic Metre	5338.80
5	Random course rubble dry stone masonry with hard stone of approved quality in sub structure for structure like retaining walls, breast walls etcetera in all heights/depths as per MORD technical specification clause 702, 704, J206.5 and JS per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	8.49 Per Cubic Metre	4057.80
6	Back filling with granular material behind abutment wing wall and return wall and retaining/ breast walls, complete as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300, as per direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of GST, or other taxes imposed by the government.	3.11 Per Cubic Metre	1345.70
7	Providing and laying P.C.C. M-20 coping on the top of the wing wall,return wall & Breast wall etc complete as per drawing and technical specification clause 612.7.10.1204.3.1(1:2:4) and as per directions of Engineer - in Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate including of GST, or other taxes imposed by the government.	4.20 Per Running Metre	450.00
		Select	9866.00

Quoted Rate in Figures (+/-) (-----,-----,-----%)
 Quoted Rate in Words (+/-) (-----,-----,-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications



Executive Engineer
Kilbar Division
HPPWD Kilbar

Percentage Schedule of Quantity					
Name of Work:- Restoration of Rain and snow damages on Killar to Hudan Bhatori road km 0/0 to 14/600 (Sub Head:- Removal of Slips on Various Rds)			Estimated Cost 99978.00		
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.) with all taxes Including GST in Word	Total Amount with all taxes Including GST in Word
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	636.80	Per cubic metre	157.00 Rupees One Hundred & Fifty Seven Only	99978.00
	Total:-				99978.00
	Quoted Rate in Figures				
	Quoted Rate in Words		Select		

Quoted Rate in Figures (+/-)%
 Quoted Rate in Words (+/-)%
Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

Percentage Schedule of Quantity				Estimated Cost	99978.00
Name of Work:- Restoration of Rain and snow damages on Killar to Hudan Bhatori road km 0/0 to 14/600 (Sub Head:- Removal of Slips on Various Rds)				Earnest Money	2000.00
Sr. No	Description of work	Quantity	Unit	Estimated Rate (in Rs.) Including GST in Word	Time
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	636.80	Per cubic metre	157.00 Rupees One Hundred & Fifty Seven Only	One Month
	Total:				99978.00
	Quoted Rate in Figures			Select	
	Quoted Rate in Words				

Quoted Rate in Figure (+/-) (.....
.....%)
Quoted Rate in Words (+/-) (.....
.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MOR I H at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

Percentage Schedule of Quantity					
Name of Work:- Restoration of Rain and snow damages on Killar to Hudan Bhatori road km 0/0 to 14/600 (Sub Head:- Removal of Slips on Various Rds)			Estimated Cost 99978.00		
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.) with all taxes Including GST	Earnest Money 2000.00
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	636.80	Per cubic metre	157.00 Rupees One Hundred & Fifty Seven Only	99978.00
	Total-				99978.00
	Quoted Rate in Figures				
	Quoted Rate in Words		Select		

Quoted Rate in Figure (+/-)
 Quoted Rate in Words (+/-)
 Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications
 of MORTH at his own risk and cost.



Executive Engineer
 Killar Division
 HPPWD Killar

Job No. 44

Percentage Schedule of Quantity					Estimated Cost	99978.00
					Earnest Money	2000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Word	Time
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	636.80	Per cubic metre	157.00	Rupees One Hundred & Fifty Seven Only	99978.00
	Total:-					99978.00
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figured (+/-) (.....)
Quoted Rate in Words (+/-) (-----)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

Percentage Schedule of Quantity
Name of Work:- Restoration of Rain and snow damages on Killar to Karyas upto Tattan Mata Mandir road km 0/0
(Sub Head:- Removal of Slips on Various Rds)

Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount Including GST in Rs.)	Estimated Cost	Earnest Money
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	636.80	Per cubic metre	157.00	Rupees One Hundred & Fifty Seven Only	99978.00	2000.00
	Total:-					99978.00	
	Quoted Rate in Figures			Select			
	Quoted Rate in Words						

Quoted Rate in Figure(+/-)%
 Quoted Rate in Words (+/-) (.....-----.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MOR III at his own risk and cost.



Executive Engineer
Kilar Division
HPPWD Kilar

Percentage Schedule of Quantity					
Name of Work:- Restoration of Rain and snow damages on Killar to Karyas upto Tatian Mata Mandir road km 0/0 to 7/0 (Sub Head:- Removal of Slips on Various Rds)				Estimated Cost	99978.00
Sc. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Earnest Money
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	636.80	Per cubic metre	157.00	Rupees One Hundred & Fifty Seven Only
	Total:-				99978.00
	Quoted Rate in Figures				
	Quoted Rate in Words		Select		

Quoted Rate in Figures (+/-)%
 Quoted Rate in Words (+/-)%

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
HPPWD Killar

Percentage Schedule of Quantity					Estimated Cost	99978.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Ernest Money	2000.00
					Time	One Month
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	636.80	Per cubic metre	157.00	Rupees One Hundred & Fifty Seven Only	99978.00
	Total:-					99978.00
	Quoted Rate in Figures					
	Quoted Rate in Words		Select			

Quoted Rate in Figure (+/-) (.....) %
 Quoted Rate in Words (+/-) (.....) %

Condition :-

Rate should be quoted for all heights including all leads and lifts.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilaru Division
HPPWD Kilaru

Percentage Schedule of Quantity
Name of Work:- Restoration of Rain and snow damages on Dharwas to Sural Bhatori road km 0/0 to 17/300 (Sub Head:- Removal of Slips on Various Rds)

Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount Including GST in Word	Estimated Cost	99978.00
				Time	One Month	Earnest Money	2000.00
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and other incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	636.80	Per cubic metre	157.00	Ruppes One Hundred & Fifty Seven Only		99978.00
				Total:-			99978.00
	Quoted Rate in Figures						
	Quoted Rate in Words			Select			

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Kilbar Division
HPWD Kilbar

Percentatge Schedule of Quantity				Estimated Cost	99978.00
				Earnest Money	2000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.) with all taxes Including GST in Word	Total Amount with all taxes Including GST in Word
1	Removal of slips in all kinds of soil hilly area in all type of saturated soil in ordinary rock not requiring blasting by mechanical means including cutting and trimming of side slopes bed including disposal of cut un serviceable material within all leads and lifts and dother incidentals as directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases .	636.80	Per cubic metre	157.00 Rupees One Hundred & Fifty Seven Only	99978.00
	Total:-				99978.00
	Quoted Rate in Figures		Select		
	Quoted Rate in Words				

Quoted Rate in Figure(+/-) (.....
.....%
Quoted Rate in Words (+/-) (-----
-----%
Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTII at his own risk and cost.



Executive Engineer
Kollar Division
HPPWD Kollar

Percentage Schedule of Quantity

Name of Work:- Restoration of Rain and snow damages on Various road under Store Sub-Division Trella at Killar(Hiring of Bulero camper/jeep for shifting of labour and material from PWD store to site of work)				Estimated Cost	98000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Time
1	Hiring of Bulero camper/jeep for carriage of material from PWD store to site of work and shifting of labour ar different RDs as per direction and entire satisfactions of Engineer-in-Charge. The Bulero camper/jeep should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily (approximately 70 kms) Hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the bulero camper/jeep owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of roller also be born by the contractor/owner. Thecarriage vehical/ machine will not be hired which life is not more then 5 (Five) year vide which the registration copy of machine/carriage vehical be pludged with the tender form duly signed by the compitent authority the daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The Rate inclusive of all Octroi,Royality,malkana,toolTax ,Sale Tax,GST or other tax as imposed by the state Govt.time to time.	28.00	Per Day	3500.00	98000.00
	Total:-				98000.00
	Quated Rate in Figures			Select	
	Quoted Rate in Words				

Quoted Rate in Figure(+/-) (.....%/-)

Quoted Rate in Words (+/-) (.....%/-)

Condition :-

Rate should be quoted for all heights including all leads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
Killar Division
IPPWD Killar

Percentage Schedule of Quantity					Estimated Cost	98000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Earnest Money	2000.00
					Time	Three Month
1	Hiring of Bulero camper/jeep for carriage of material from PWD store to site of work and shifting of labour ar different RD's as per per direction and entire satisfactions of Engineer-in-Charge. The Bulero camper/jeep should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily (approximately 70 kms) Hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the bulero camper/jeep owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of roller also be born by the contractor/owner. Thecarriage vehical/machine will not be hired which life is not more then 5 (Five) year vide which the registration copy of machine/carriage vehical be pludged with the tender form duly signed by the compaint authority the daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The Rate inclusive of all Octroi,Royality,malkana,toolTax ,Sale Tax,GST or other tax as imposed by the state Govt.time to time.	28.00	Per Day	3500.00	98000.00	Rupees Ninety Eight Thousand Only
	Total:-				98000.00	
	Quoted Rate in Figures			Select		
	Quoted Rate in Words					

Quoted Rate in Figure(+/-) (.....%) Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all loads and lift.

The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.



Executive Engineer
HPPWD Killar

Percentage Schedule of Quantity					Estimated Cost	98000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Earnest Money	2000.00
1	Hiring of Bulero camper/jeep for carriage of material from PWD store to site of work and shifting of labour ar different RD's as per per direction and entire satisfactions of Engineer-in-Charge. The Bulero camper/jeep should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily (approximately 70 kms) Hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the bulero camper/jeep owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of roller also be born by the contractor/owner. Thecarriage vehical/ machine will not be hired which life is not more then 5 (Five) year vide which the registration copy of machine/carriage vehical be pludged with the tender form dully signed by the competent authority the daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The Rate inclusive of all Octroi,Royality,malkana,too Tax ,Sale Tax,GST or other tax as imposed by the state Govt.time to time.	28.00	Per Day	3500.00	Time	Three Month
	Total:-					98000.00
	Quoted Rate in Figures					-
	Quoted Rate in Words			Select		

Quoted Rate in Figure(+/-) (.....%)
 Quoted Rate in Words (+/-) (-----%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.


 Executive Engineer
 Killar Division
 HPPWD Killar

Percentage Schedule of Quantity				Estimated Cost	98000.00
Sr. NO	Description of work	Quantity	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST in Rs.
1	Hiring of Bulero camper/jeep for carriage of material from PWD store to site of work and shifting of labour ar different RD's as per per direction and entire satisfactions of Engineer-in-Charge. The Bulero camper/jeep should work minimum 8.00 hours from 9.00 AM to 5: 00PM daily (approximately 70 kms) Hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the bulero camper/jeep owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of roller also be born by the contractor/owner. Thecarriage vehical/machine will not be hired which life is not more then 5 (Five) year vide which the registration copy of machine/carriage vehical be pludged with the tender form duly signed by the competent authority the daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The Rate inclusive of all Octroi,Royality,malkana,toolTax ,Sale Tax,GST or other tax as imposed by the state Govt.time to time.	28.00	Per Day	3500.00	98000.00
	Total:-				98000.00
	Quoted Rate in Figures			Select	
	Quoted Rate in Words				

Quoted Rate in Figure(+/-) {% }
 Quoted Rate in Words (+/-) (.....%)

Condition :-

Rate should be quoted for all heights including all leads and lift.
 The contractor shall procure all the materials confirming to the specifications of MOR RH at his own risk and cost.



Executive Engineer
Kilbar Division
HPPWD Kilbar

Schedule of Quantity					
Sr. No.	Description of work	Qty	Unit	ESTIMATED RATE (in Rs.)	ESTIMATED COST
				Total amount with all taxes including GST in Rs.	Earliest Money
1	Hiring of Bolero camper Jeep for shifting of Labour all kind of construction material from quarry stone to site of work as per direction and entire satisfaction of Engineer in Charge. The Bolero camper should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and cart out least private property. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of bolero camper also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including of GST, toll tax, sale tax or other taxes imposed by the government.	30.00	Day	3300	99000,
					99000

Quoted Rate in Figure (+/-).....%.....

Quoted Rate in Words(+/-).....%.....

Condition:-

Rate should be quoted for all height including all leads and lifit
The contractor shall procure all the materials confirming to the specifications.
Of MORTH at his own risk and cost.


Executive Engineer
KJ Bar Division HP PWD
Killar (Panig)

Schedule of Quantity					
Sr. No.	Description of work	Qty	+Unit	Estimated Rate (in Rs.)	ESTIMATED COST Earnest Money
1	Hiring of Bolero camper Jeep for shifting of Labour all kind of construction material from quarry stone to site of work as per direction and entire satisfaction of Engineer in Charge. The Bolero camper should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and cart out least private property. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of bolero camper also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including of GST, toll tax, sale tax or other taxes imposed by the government.	30.00	Day	3300	99000
	Quoted Rate in Figure				99000
	Quoted Rate in Words				

Quoted Rate in Figure (+/-).....%)

Quoted Rate in Words(+/-).....%)

Condition:-

Rate should be quoted for all height including all leads and Ifs
 The contractor shall procure all the materials confirming to the specifications.
 Of MORTH at his own risk and cost.



Executive Engineer
 Kilnar Division HP PWD
 Kilnar (Pangi)

Schedule of Quantity				ESTIMATED COST	99855.00
				Earnest Money	2600.00
Sr. No.	Description of work	Qty	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs.
1	Hiring of JCB/ Excavator cum loader for removal of solidified snow, slips, boulders and debries clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcetra happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/ Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary humentage etcetra shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including of GST, toll tax, sale tax or other taxes imposed by the government.	63.00	per Hour	1585	99855 Rupees Ninety Nine Thousand Eight Hundred & Fifty Five Only
	Quoted Rate in Figure				99855
	Quoted Rate in Words				

Quoted Rate in Figure (/-)%)

Quoted Rate in Words(/-)%)

Condition:-

Rate should be quoted for all height including all leads and lif
 The contractor shall procure all the materials confirming to the specifications.
 Of MORTH at his own risk and cost.



Executive Engineer
 Kallar Division HP PWD
 Kallar (Panj) [Signature]

Schedule of Quantity					
				ESTIMATED COST Earnest Money	99855.00 2000.00
Time Limit	One month				
Sl. No.	Description of work	Qty	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs.
1	Hiring of JCB/ Excavator cum loader for removal of solidified snow, slips, boulders and debries clear form road surface upto any height, depth and lead including clearing the road surface to the required line, grade and width as per direction and entire satisfactions of Engineer-in-Charge. The physical output of work done at site shall be ensured and measured/be recorded in measurement book. Any loss to the public/private property or any accident etcetra happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/ Excavator cum loader owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The crawling and temporary hutmentage etcetra shall also be born by the contractor and nothing shall be charged extra. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including of GST, toll tax, sale tax or other taxes imposed by the government.	63.00	per hour	1585	99855 Ninety Nine Thousand Eight Hundred & Fifty Five Only
	Quoted Rate in Figure				99855
	Quoted Rate in Words				

Quoted Rate in Figure (/-).....%)

Quoted Rate in Words(/-),.....%)

Condition:-

Rate should be quoted for all height including all leads and lift
 The contractor shall procure all the materials confirming to the specifications.
 Of MORTH at his own risk and cost.



Executive Engineer
 Kharar Division H.P PWD
 Kharar (Pangri)