OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA

PW-BGN-CB/T-1/2025-26-1207-176 No:-To

Dated:- 2008

The Executive Engineer (IT Cell), Nigam Vihar, HP Shimla-2. cc-pwd-hp@nic.in.

Subject:-

Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender.As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity And "A" Certificate.

Copy forwarded with its enclosures for information to:-

- 1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
- 2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
- 3. The Superintending Engineer, 15th Circle, HPPWD, Una.
- 4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
- 5. Drawing Branch in this office.
- 6. Accounts Branch in this office.
- 7. Supdt of C Branch in this office.
- 8. Notice Board.

Executive Engineer Bangana Division HPPWD Bangaria

Executive Engineer Bangana Division HPPWD Bangana.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

CERITIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26-

1207-1216 dated 2005.

Executive Engineer Bangana Division HPPWD Bangana.

OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on 27-05-2025 up to 10.30 A.M and same will be opened on the same day at 11.00 AM in presence of the interested contractors or their authorized representative. The application will be received in this office on at 26.05.2025 upto 11.30 PM. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on 26-05-2025 during office Hours 2.00 PM to 4.30 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of
	A/R & M/O Chalola Nangal Salangri Sanjhot road (SH:-Maintenance of berms & drain in km. 0/000 to 4/000)	99916.00	2000.00	Two Month	D
2	A/R & M/O Dhamandri Ambehra Road (SH:-SH:-Maintenance of berms & drain in km. 0/000 to 3/000)	99990.00	2000.00	Two	D
3	C/O Link road Una Barera Road to Surjehra Khuhi to Shiv Mandir and Satsang Ghar km. 0/000 to 0/800(SH:- C/O Embankment for both side of 6.00 meter Span)	99774.00	2000.00	Month Two Month	D
4	C/O Link road Una Barera Road to Surjehra Khuhi to Shiv Mandir and Satsang Ghar km. 0/000 to 0/800(SH:- C/O Edge wall in km. 0/070 to 0/097) R.H.S.	99731.00	2000.00	Two Month	D
5	H.P.(SH:- Providing and Fixing Network video recorded L.E.D. Samsung 43")	99238.00	2000.00	Two Month	D
6	A/R & M/O Assistant Engineer office at Dera Baba Rudru Sub Division (SH:- Preparation of Working Estimates)	99800.00	2000.00	Two Month	D
7	C/O Combined office building at Bangana Distt. Una H.P.(SH: Fixing and installation of RJ 45 Connector 32 Nos. Cabling box)	949 90.00	2000.00	Two Month	D
8	C/O Combined office building at Bangana Distt. Una H.P.(SH: Providing and Fixing 16.00 Nos. Cameras.)	98530.00	2000.00	Two	D
9	A/R & M/O UAM Road km. 19/000 to 39/70(SH:- Patch work in km. 13/000 to 14/000)	99677.00	2000.00	Month Two Month	D

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer Bangana Division HPPWD Bangana

On behalf of Governor of Him thal Pradesh.



Name of work:- A/R & M/O Chalola Nanal Salangri Sanjhot road km. 0/000 to 4/000(SH:- Maintenance of Berms & Drain in km. 0/000 to 4/000)

1	7		
0		5	
7	7	5	
1		1	
A A J	1		
0	-	2	
	-	1	

			ω			No. 9	G.
		Outed Rate in Figures	Construction of unlined surface drain in all kinds and classification of soil average cross sectional area 0.40 (Zero point forty) square metre in soil to specified lines, grades, levels and dimension. Excavated materials to be used in embankment with any lift and lead as per M.O.R.D. technical specification Clause 307 including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	Making in Top of material in the Scription of Work	Estimated Cost 99916.00
Less(-)	Excess(+)		204.00	1404.00	1414.00	Quantity	99916.00
			Per Running metre	Per Square meter	Per Square meter	Unit	Earnest Money
			59.00	17.00	45.27	Estimated Rate in Words	2000.00
		99916.00	12036.00	23868.00	64012.00	Total amount without Taxes	Time Limit
			Rupees Fifty Nine Only	Rupees Seventeen Only	Rupees Fourty Five - Paise Twenty Seven Only	AMOUNT Rs. P	Two Month





Name of work:- A/R & M/O Dhamandri Ambehra road km. 0/000 to 3/000(Sh:- Maintenance of Berms and Drain in km. 0/000 to 3/000)

PRICE SCHEDULE

			cu cu	2		Zv	
	Quoted Rate in Figures	Total in Figures	3 Construction of unlined surface drain in all kinds and classification of soil average cross sectional area 0.40 (Zero point forty) square metre in soil to specified lines, grades, levels and dimension. Excavated materials to be used in embankment with any lift and lead as per M.O.R.D. technical specification Clause 307 including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1 Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	Sr. Description of work	
			inds and classification of soil average cross tre in soil to specified lines, grades, levels and embankment with any lift and lead as per uding carriage of material within all leads and of octroi, royality, Malkana, toll tax, sale tax	to achieve the approved level and compacting ngs and technical specification Clause 1903 and lifts and other incidental. The rates are x, sale tax or other taxes imposed by the	shoulders to the design level by adding fresh oppropriate equipment at OMC upto any lead as carriage of material within all leads and lifts octroi, royality, Malkana, toll tax, sale tax or	n of work	Estimated Cost
Less(-)	Excess(+)		217.16	1400.00	1400.00	Quantity	99990.00
			Per Kunning metre	Per Square meter	Per Square meter	Unit	Earnest Money
			59.00	17.00	45.27	Estimated Rate in Words	2000.00
		99990.00	12812.00	23800.00	63378.00	Total amount without Taxes	Time Limit
			Rupees Fifty Nine Only	Rupees Seventeen Only	Rupees Fourty Five - Paise Twenty Seven Only	AMOUNT Rs. P	Two Month





Embankment for both side of 6.00 meter Span) Name of work:- C/O Link road Una Barera Road to Surjehra Khuhi to Shiv Mandir and Satsang Ghar km. 0/000 to 0/800(SH:- C/O

PRICE SCHEDULE

			-	No.	Ç.
	Quoted Nate III rigures	Total in Figures	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 303 upto any lead as per MORD 2014 Technical Specification Clause 303 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	Description of work	Estimated Cost
Less(-)	Excess(+)		332.58	Quantity	99774.00
			Per Cubic metre.	Unit	Earnest Money
			300.00	Estimated Rate in Words	2000.00
		99774.00	99774.00	Estimated Rate Total amount in Words without Taxes	Time Limit Two Month
			Rupees Three Hundred Only	AMOUNT Rs. P	Two Month





Name of work:- C/O Link road Una Barera Road to Surjehra Khuhi to Shiv Mandir and Satsang Ghar km. 0/000 to 0/800(SH:- C/O Edge wall in km. 0/070 to 0/097)R.H.S.

PRICE SCHEDULE

2	4 2.55	No.	2
Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty milimetre) nominal size)mechaniclly mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-incharge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and subsoil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	Description of work	Estimated Cost
21.87	10.94	Quantity	99731.00
Per Cubic metre.	Per Cubic metre.	Unit	Earnest Money
3985.00	350.00	Estimated Rate in Words	2000.00
87152.00	3829.00	Total amount without Taxes	Time Limit
Rupees Three Thousand Nine Hundred &	Rupees Three Hundred & Fifty Only	AMOUNT Rs. P	Two Month

	T			4
	0	Quoted Rate in Figures	Total in Figures	wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe of make D-PLAST/POLY.having working pressure of 4.0 kg (four kilogramme) per square centimeter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per drawing and MORD 2014 technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge including carriage of materials with in all leads and lifts including other incidentals. The rate including octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.
Less(-)	Excess(+)			nt, 25.00 D- ter 1 : 1 : 1 : 1 : 1 : 1 : 1 : 1 : 1 : 1 :
				Each
				350.00
		99731.00		8750.00
				Rupees Three Hundred & Fifty Only

Executive Engineer
Bangana Division
H.P.P.W.D.Bangana



recorder L.E.D. 43") Name of work:- C/O Combined office building at Bangana Tehsil Bangana Distt. Una (H.P.)(SH:- Providing and fixing Network video

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the rellevant columns, else the bidder is liabe to be rejacted for this tender. Bidders are allowed to enter Bidder name and values only

			-	No.	C
L	Quoted Kate in Figures	Total in Figures	NVE(Network Video recorder) 265 HD memory storage 107 b H.D.D. with power supply unit L.E.D. Samsung 43" as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	Description of work	Estimated Cost 99238.00
Less(-)	Excess(+)		1.00	Quantity	99238.00
			Job	Unit	Earnest Money
			99238.00	Estimated Rate in Words	2000.00
		99238.00	99238.00	in Words Without Taxes	Time Limit
				AMOUNT Rs. P	Time Limit Two Month

Executive Engineer Bangana Division H.P.P.W.D.Bangana



Name of work:- A/R & M/O Assistant Engineer office at Dera Baba Rudru Sub Division (SH:- Preparation of working estimates)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the rellevant columns, else the bidder is liabe to be rejacted for this tender. Bidders are allowed to enter Bidder name and values only

									-	-	Zo.	Sr		
		res	Total in Figures		The solution of the solution o	or other taxes imposed by the Covernment	incidentals. The rate includes certain results. Mellions tell the rate includes certain results. Mellions tell the rate includes certain results.	Engineer-in-charge including carriage of motorial within all leads of the	for labour material and carriage etc. Complete in all respect to the state of the s	Dranging of working to the state of the stat	Description of work	December of the latest of the	Estimated Cost	
Less(-)	Excess(+)								2.00		Quantity		99800.00	
									Job		Unit	Money	Earnest	,
									49900.00	m words	Estimated Rate		2000.00	
		99800.00							99800.00	without Taxes	Total amount		Time Limit	
				Only	Hundred	Nine	Thousand	Fourty Nine	Rupees	Rs. P	AMOUNT		Time Limit Two Month	

Executive Engineer Bangana Division H.P.P.W.D.Bangana

Connector, 32 nos. Cabling box) Name of work:- C/O Combined office building at Bangana Tehsil Bangana Distt. Una (H.P.)(SH:- Fixing and installation of RJ. 45

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the rellevant columns, else the bidder is liabe to be rejacted for this tender. Bidders are allowed to enter Bidder name and values only

			-	Sr.		
	Quoted Rate in Figures	Total in Figures	Wire CAT6 D-LINK 68mm SWG UTP 23 AWG bord width UPTO 250 mhz, PVC. PIPE 3/4" make poly plast NVR. Rack D-LINK. 4U, Wall mount 16 ch, Giga Port. P.O.E Switch 4 TB H.D.D RJ. 45 connector 32 nos, Camera Boxes - 32 nos, cabling fixing instalation as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	Description of work	Estimated Cost	critical bidders are allowed to enter bidder name and values only
Less(-)	Excess(+)		1.00	Quantity	94990.00	e and values or
			Job	Unit	Earnest Money	шу
			94990.00	Estimated Rate in Words	2000.00	
		94990.00	94990.00	Total amount AMOUNT without Taxes Rs. P	Time Limit Two Month	
			Rupees Ninety Four Thousand Nine Hundred & Ninety Only	AMOUNT Rs. P	Two Month	

Executive Engineer Bangana Division H.P.P.W.D.Bangar



Name of work:- C/O Combined office building at Bangana Tehsil Bangana Distt. Una (H.P.)(SH:- Providing and Fixing 16.00 Nos. Cameras)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the rellevant columns, else the bidder is liabe to be rejacted for this tender. Bidders are allowed to enter Bidder name and values only

										I	No.	Sr.			
	Quoted Rate in Figures	Total in Figures				cess or other taxes imposed by the Government.	other incidentals. The rate includes octror, royality, Malkana, toll tax, goods service tax, labour	direction of the Engineer-in-charge including carriage of material within all leads and lifts and	Ethernet connectivity protocol 30 tbs H-265+/264, 3D DNR Cmos, photo senser, as per the	16 Chanels I.P. Cameras 4MP with day night colour, audio two way .1080 P full H.D.		Description of work		Estimated Cost	tilly ally falles of the market are allowed to either blinder light early solling
Less(-)	Excess(+)				11					16.00		Quantity		98530.00	ic and values of
										Nos.		Unit	Money	Earnest	ПУ
	4									6158.13	ın Words	Estimated Rate		2000.00	
		98530.00								98530.00	without Taxes	Estimated Rate Total amount AMOUNT		Time Limit	
			Only	Thirteen	Paise	Fifty Eight -	Hundred &	One	Thousand	Rupees Six	Rs. P	AMOUNT		Time Limit Two Month	

Executive Engineer
Bangana Division
H.P.P.W.D.S...



Name of work:- A/R & M/O UAM Road km. 0/000 to 19/000(SH:- Patch work in km. 13/000 to 14/000)

PRICE SCHEDULE

tax, s	specii Mill), cours weigh divers carria	Sr. No.	
The state of the s	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government	Description of work	Estimated Cost
98.56	7.39	Quantity	99677.00
Per Square metre	Per Cubic metre.	Unit	Earnest Money
54.70	1866.00	Estimated Rate in Words	2000.00
5391.00	13790.00	Estimated Rate Total amount in Words without Taxes	Time Limit Two Month
Rupees Fifty Four - Paise Seventy Only	Rupees One Thousand Eight Hundred & Sixty Six Only	AMOUNT Rs. P	Two Month



	Ouoted Rate in Figures	track coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimetre) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two cubic metres), mixed with Bitumen VG-30 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/Forty) Tonne per hour capcity, transporting mixed material with tipper and laying mannually to the required grade and camber and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and other incidental. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.
Excess(+) Less(-)		234.00
		Per Square metre
		344.00
	99677.00	80496.00

Executive Engineer
Bangana Division
H DBW.D