

OFFICE OF

EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA  
HIMACHAL PRADESH, PUBLIC WORK DEPARTMENT CHAMBA  
Phone No, 01899-222229 Email ee-cha-hp @nic.in

NOTING INVITING TENDER

Sealed item rate tender on form 688 are hereby invited by the undersigned on behalf of the Governor of Himachal Pradesh from the approved and eligible contractors enlisted in HPPWD So as to reach in his office on or before 07/05/2025 to 11:00 AM and will be opened on the same day at 11:30 AM, in the presence of the intending Contractor or their authorized representatives if any. The tender application will be received in this office on 05/05/2025 upto 10.00 AM to 12.30 PM and tender form can be had from this office on 06-05-2025 from 3.00 PM to 5.00 PM. The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Chamba Division HPPWD Chamba must be accompanied with each tender The tender form will be issued to contractor who giving proof of enlistment, GST Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tenders without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class.
1.	2.	3.	4.	5	6	7.
1	Rest of rain damages on Sahapur Sihunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH:- Hiring of Tipper for disposal of muck of slip)	99540/-	2000/-	350 /-	One Month	D & C
2	Rest of rain damages on Sahapur Sihunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH:- Hiring of Tipper for disposal of muck of slip)	99540/-	2000/-	350 /-	One Month	D & C
3	Rest of rain damages on Various road under Jhumar section HPPWD Chamba (SH:- Hiring of Excavator cum loader for removal of slips at various Rd,s)	99000/-	2000/-	350 /-	One Month	D & C

4	Rest of rain damages on Various road under Jhumar section HPPWD Chamba (SH:- Hiring of Excavator cum loder for removal of slips at various Rd,s)	99000/-	2000/-	350 /-	One Month	D & C
5	A/R & M/O Various road Chamba Division HPPWD Chamba (SH:- Supply/ stacking of machine made bricks)	97500/-	2000/-	350 /-	One Month	D & C
6	A/R & M/O Various road Chamba Division HPPWD Chamba (SH:- Supply/ stacking of machine made bricks)	97500/-	2000/-	350 /-	One Month	D & C
7	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- Formation cutting at Rd.0/827 to 0/839)	82565/-	1700/-	350 /-	One Month	D & C
8	Rest of rain damages on Sahapur Sihunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH:- Hiring of Excavator cum loder for removal of slips at various Rd,s)	99000/-	2000/-	350 /-	One Month	D & C
9	Rest of rain damages on Sahapur Sihunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH:- Hiring of Excavator cum loder for removal of slips at various Rd,s)	99000/-	2000/-	350 /-	One Month	D & C
10	Rest of rain damages on Sahapur Sihunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH:- Hiring of Excavator cum loder for removal of slips at various Rd,s)	99000/-	2000/-	350 /-	One Month	D & C
11	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- C/o crate work for dumping site at Rd. 0/275.50 to 0/281)	98656/-	1773/-	350 /-	One Month	D & C
12	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- C/o crate work for dumping site at Rd. 0/281 to 0/286.50)	98656/-	1773/-	350 /-	One Month	D & C
13	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- C/o crate work for dumping site at Rd. 0/286.50 to 0/292)	98656/-	1773/-	350 /-	One Month	D & C
14	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- C/o crate work for dumping site at Rd. 0/270 to 0/275.50)	98656/-	1773/-	350 /-	One Month	D & C
15	Const of link road from Sarahan to Chubara Dadar road Km. 0/0 to 1/750 (SH:- C/o crate work for dumping site at Rd. 0/292 to 0/297.50)	98656/-	1773/-	350 /-	One Month	D & C
16	Const of link road from Satlei to Chubara Dadar road at Km. 0/0 to 1/500 (SH:- Formation Cutting at Rd. 0/028 to 0/055)	99325/-	2000/-	350 /-	One Month	D & C
17	Const of link road from Satlei to Chubara Dadar road at Km. 0/0 to 1/500 (SH:- Formation Cutting at Rd. 0/055 to 0/085)	98361/-	1970/-	350 /-	One Month	D & C

18	Const of link road from Sattlei to Chubara Dadar road at Km. 0/0 to 1/500 (SH:- Formation Cutting at Rd. 0/270 to 0/299)	96303/-	1926/-	350 /-	One Month	D & C
19	Rest of rain damages on Parotha Kurena road Km. 0/0 to 7/00 (SH:- C/o P.C.C R/wall at Rd. 0/030 to 0/033)	95012/-	1900/-	350 /-	One Month	D & C
20	Rest of rain damages on Parotha Kurena road Km. 0/0 to 7/00 (SH:- C/o P.C.C R/wall at Rd. 0/033 to 0/036)	95012/-	1900/-	350 /-	One Month	D & C
21	Rest of rain damages on Parotha Kurena road Km. 0/0 to 7/00 (SH:- C/o P.C.C R/wall at Rd. 0/036 to 0/039)	95012/-	1900/-	350 /-	One Month	D & C
22	Rest of rain damages on Parotha Kurena road Km. 0/0 to 7/00 (SH:- C/o P.C.C R/wall at Rd. 0/039 to 0/042)	95012/-	1900/-	350 /-	One Month	D & C
23	Rest of rain damages on Parotha Kurena road Km. 0/0 to 7/00 (SH:- C/o P.C.C R/wall at Rd. 0/042 to 0/045)	95012/-	1900/-	350 /-	One Month	D & C

Certificated that tender of above works are being called of emergent nature in exigency of Public interest

#### TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have this registration and GST No. the copy of same be attached with the application
4. The earnest Money shall be deposited duly pledged in favour of executive Engineer. Chamba Division HPPWD Chamba and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.

Executive Engineer,  
Chamba Division  
HPPWD Chamba


No.PWC-WA-II/Contract/2024-25

1529-49

Dated: 30.04.2025

Copy forwarded to:-

1. Copy of The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD., Shimla
3. The Chief Engineer (KZ) HPPWD Dharamshala
- 4 The Superintending Engineer, 7th Circle HPPWD Dalhousie.
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Department website.
- 6 All the Assistant Engineers under Chamba Division
7. All the A Contractor working under this division
- 8 H.D.M./Supdt./Acctt. of this office.
9. Notice Board.

  
Executive Engineer,  
Chamba Division  
HPPWD.Chamba

OFFICE OF


EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA

HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA

Phone No. 01899-222229 Email [ee-cha-hp@nic.in](mailto:ee-cha-hp@nic.in)

CERTIFICATE

Certified that tender of works, as called vide this office letter No.  
PWC-WA-II/Contract/2024-25 1529.49 Dated: 20.04.2025 are emergent nature in  
exigency of public interest

  
Executive Engineer,  
Chamba Division  
HPPWD.Chamba

Name of work :- Restoration of road damages on Shahpur Sihinuta Chowari Chamba lot road Km. 76/0 to 87/0  
(SH : Hiring of Tipper for disposal of muck of slip).

Draft schedule of quantity

Estimated cost : Rs. 99540/-

Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	126.00	790.00	Rupess seven hundred ninety and paise zero only	Per hour	99540.00
Total						99540.00

Assistant Engineer  
Chamba Sub Division (H.P.)  
H.P.W.D. Chamba (H.P.)  
Executive Engineer  
Chamba Division  
H.P.W.D., Chamba

*04117 abhijit has 11544-*



Draft schedule of quantity

Name of work : - Restoration of road damages on Shalpur Siluina Chowari Chamba for road Km. 76/0 to 87/0  
(Sl: Hiring of Tipper for disposal of muck of slip).

Estimated cost : Rs. 99540/-  
Earnest money : Rs. 2000/-  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig -	In words		
1	Hiring of Tipper 10cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge.	126.00	790.00	Rupees seven hundred ninety and paise zero only	Per hour	99540.00
Total						99540.00

Assistant Engineer  
Chamba Division  
H.P.P.W.D. Chamba

*DHIT approved R-RS 99540/-*

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

# DNIT

me of work :- Restoration of rain damages on various road under Jhumar Section HPPWD Chamba (SH :  
 of Excavator cum Loader for removal of slips).

Estimated cost : Rs. 99,000/-  
 Earnest money : Rs. 2,000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana & its tax, sale tax, GST or other taxes imposed by the Government	90.00 Hour	1100.00	Rupees one thousand one hundred only.	Per hour.	99000.00
					Total	99000.00

DNIT approved for Rs 99,000/- only

Assistant Engineer,  
 Chamba Sub Division No-1  
 H.P.W.D. Chamba

Executive Engineer,  
 Chamba Division  
 H.P.W.D. CHAMBA

5

DNIT

1. Name of work :- Restoration of rain damages on various road under Jhumar Section H.P.P.W.D. Chamba (SH :  
2. Hiring of Excavator cum Loader for removal of slips).

Estimated cost : Rs. 99,000/-  
Earnest money : Rs. 2,000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, with sale tax, GST or other taxes imposed by the Government.	90.00 Hour	1100.00	Rupees one thousand one hundred only.	Per hour.	99000.00
Total						99000.00

Assistant Engineer  
Chamba Division No-1  
Chamba

Executive Engineer  
Chamba Division  
H.P.P.W.D. CHAMBA

DNIT approved for Rs. 99000/- only



## DNIT

Name of work : A/R & M/O various roads under Chamba Division HPPWD Chamba  
(SH:- Supply/stacking of Machine made bricks)

Estimated cost : Rs. 97500/-

Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount	
			In fig	In words			
1	Supply and stacking of machine made bricks of size 23x 11x7.00 cm ( twenty three into eleven into seven centimetrs) well finished of all side free from organic materials, less water absorbent, free from cavity & other injurious materials involving all taxes, octroi etc complete. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	3000.00	No.	32.50	Rupees thirty two decimal five zero only	Each	97500.00
Total						97500.00	

Assistant Engineer  
Chamba Sub Division No.-1  
H.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.W.D. CHAMBA

DNIT approved for Rs 97500/mth

DNIT

Name of work : A/R & M/O various roads under Chamba Division HPPWD Chamba  
(Sh. - Supply/stacking of Machine made bricks)

Estimated cost : Rs. 97500/-

Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	No.	Rate		Unit	Amount
				In fig	In words		
1	Supply and stacking of machine made bricks of size 23x 11x7.00 cm ( twenty three into eleven into seven centimeters) well finished of all side free from organic materials, less water absorbent, free from cavity & other injurious materials involving all taxes, octroi etc complete. The rate is including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government	3000.00		32.50	Rupees thirty two decimal five zero only	Each	97500.00
Total							97500.00

DNIT approved

for Rs 97500/- only

Assistant Engineer  
Chamba Sub Division No-1  
H.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.W.D CHAMBA

Draft Schedule of quantity

Estimated Cost Rs. 82565/-  
 Earnest Money :- Rs. 1700/-  
 Time Limit :- one month

Name of work :- C/O LMS ROAD FROM SARAYAN, CHURRA DOKAR ROAD, CHHATTISGARH AT RD 0/82780/839.

S.No.	Item	Qty.	Unit	Rate		Amount
				In fig.	In words.	
01	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the M.C.D. technical specification, section 300 & 1600 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machines, materials, tools, equipments and safety measures and other incidental expenses; to complete the work by mechanical means/ labour if required. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Mahana, toll tax, GST or any other taxes imposed by the Government.	445.68	Per Cubic Metre	187.50		83575/-
Total						83575/-

Assistant Engineer  
 Sub. Division No.1  
 H.P. P.W.D. Chamba (H.P.)

Executive Engineer  
 Chamba Division  
 H.P.P.W.D. Chamba

*DHIT approval Rs 83575/- only*

# DNIT

Name of work :- Restoration of road damages on Shalpur Silimta Chowari Chamba Jor road Km. 76/0 to 87/0 (SH :  
Hiring of Excavator cum Loader for removal of slips at various RDs).

Estimated cost : Rs. 99000/-  
Earnest money : Rs 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for cutting/ widening of road and removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana toll tax, GST, or any other taxes imposed by the Government.	90-40	1100.00	Rupees one thousand one hundred fifty & paise zero only	Per hour	99000.00
Total :						99000.00

*0417 Chamba Rs 99000/-*

Executive Engineer  
Chamba Division  
Assistant Engineer  
Chamba Sub Division No. 11  
H.P.W.D., Chamba  
H.P.W.D. Chamba (H.P.)

# DNIT

Name of work :- Restoration of road damages on Shalpur Situmia Chowari Chamba Jot road Km. 76.0 to 87.0 (SH).  
Hiring of Excavator cum Loader for removal of slips at various RDs).

Estimated cost : Rs. 99000/-  
Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for cutting/ widening of road and removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, GST, or any other taxes imposed by the Government.	90.00	~1100.00	Rupees one thousand one hundred fifty & paise zero only	Per hour	99000.00
Total :						99000.00

Assistant Engineer  
Chamba Sub-Division No-II  
H.P.P.W.D. Chamba (H.P.)

Executive Engineer  
Chamba Division  
H.P.P.W.D., Chamba

*DNIT approved Rs 99000/-*



10

DNIT

Name of work :- Restoration of road damages on Shahpur Simunta Chowari Chamba Jot road Km. 76/0 to 87/0 (SH :  
Hiring of Excavator cum Loader for removal of slips at various RDs).

Estimated cost : Rs. 99000/-  
Earnest money : Rs. 2000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader for cutting/ widening of road and removal of slips in all kinds of soil and disposing of all excavated earth and un-serviceable material from the road surface upto all leads and lifts and upto all heights and depths as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spair , watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by The Engineer-in-Charge. The rate is including the Octroi, royalty, Malkana, toll tax, GST, or any other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand one hundred fifty & paise zero only	Per hour	99000.00
Total :						99000.00

Assistant Engineer  
Chamba Sub-Division No. 11  
H.P.W.D. Chamba (H.P.)

DNIT approved for Rs 99000/-

Executive Engineer  
Chamba Division  
H.P.W.D. Chamba

D.N.I.T

Estimated cost:- 98656/-  
FARMEST MONTH:- 1773.0  
T.M.E. 10/11/17

Work:- c/o Link road - Saradan Chubra Dada road km 0 to 1750  
(S.H. - c/o State work for Dumping site at R.D 0/275.50 to 281)

Sr. No.	Description of Work / Item (s)	Qty.	Rate	Unit	Amount
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre). Compacted thickness including showing and setting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octro, royalty, Malkana toll, tax, sale tax or other taxes imposed by the Government.	4.95	350.00	Per Cubic Metre	1733.0
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS: two hundred eighty) and IS: 4835 (IS: four thousand eight hundred thirty five) in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (two x 2 diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40kg (forty kilogram) each as per drawing and MORD technical specification clause 1301 and as per directions of Engineer-in-Charge including the carriage of material within all leads, lifts and other incidental. The rate including octro, royalty, Malkana toll, tax, sale tax or any other taxes imposed by the Government.	34.37	2820.00	Per Cubic Metre	96923.0
Total					98656.00

Sub Division No. 1  
H.P.W.D. Chamba

Executive Engineer  
Chamba Division  
H.P.W.D. Chamba

DAIT approved Rs 98656/- only

D.N.I.T

Estimated cost:- 98656/-  
 Earned money:- 1973/-  
 Time limit:- one month

mead work:- C/O Link road- Saraban chubba Dadar road km 0.5 to 1.750  
 B.H. - C/O create work for Dumping site at R.D 0/281 to 286.50

Sl. No.	Description of Work / Item (s)	Qty.	Rate	Unit	Amount
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	4.95	350.00	Per Cubic Metre	1733.0
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS: two hundred eighty) and IS: 4936 (IS: four thousand eight hundred thirty six) in 100mmx100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40kg (forty kilogram) each as per drawing and MORD technical specification clause 1301 and as per directions of Engineer-in-charge including the carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	34.37	2820.00	Per Cubic Metre	96923.0
Total					98656.00

Assistant Engineer  
 Sub Division No.-1  
 P.P.W.D. Chamba

Executive Engineer  
 Chamba Division  
 P.P.W.D. Chamba

D.N.I.T approved for Rs 98656/-



Estimated cost :- 98656/-  
 Earnest money :- 1973/-  
 Time Limit :- one month

C/O Link road - Sabarwal chubra Dahan road 1 km d/o to 1750  
 B.H. - C/O create work for Dumping site at R.D 0/286.50 to 2922

Sr. No.	Description of work / Item (S)	Qty.	Rate	Unit	Amount
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etc. etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is provided) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and up to any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantity, of water including clearing of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including over, royalty, Malakal, toll tax or other taxes imposed by the Government.	4.95	350.00	Per Cubic Metre	1733.0
2	Providing and laying of boulder apron laid in wire crates with four millimetre dia G.I. wire (Galvanized iron wire) conforming to IS 280 (15 two hundred eighty) and IS 4836 (15 four thousand eight hundred thirty six) in 100mm (one hundred millimetre) into one hundred millimetre mesh (woven diagonally) including 10% (ten percent) extra for laps and joints and with stone boulders weighing not less than 40kg (forty kilogram) each as per drawing and MORD technical specification clause 1301 and as per directions of Engineer-in-Charge including the carriage of material within all leads, lifts and other incidental. The rate including over, royalty, Malakal, toll tax or any other taxes imposed by the Government.	34.37	2820.00	Per Cubic Metre	96923.0
Total					98656.0

Approved  
 Sub Division No. 1  
 H.P.W.D. Chamba

Approved  
 Executive Engineer  
 Chamba Division  
 H.P.W.D. Chamba

8

11

D.N.I.T

98656/-  
1973/-  
T.M.B. B.M.T. C.A. B.M.T.

Sl. No. Description of Work / Item (S)  
C/O L.M.K. Road Saraban Chubra Dadar Road km d/o to 11750  
B.H. - C/O Gate work for Dumping site at R.D. 0/270 to 275.50)

Sl. No.	Description of Work / Item (S)	Qty.	Rate	Unit	Amount
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.95	350.00	Per Cubic Metre	1733.0
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS: two hundred eighty) and IS: 4836 (IS: four thousand eight hundred thirty six) in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40kg (forty kilogram) each as per drawing and MORD technical specification clause 130.1 and as per directions of Engineer-in-Charge including the carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or any other taxes imposed by the Government.	34.37	2820.00	Per Cubic Metre	96923.0
Total					98656.00

Approved by  
D.N.I.T  
98656/-  
1973/-  
T.M.B. B.M.T. C.A. B.M.T.

Sub Division No. -  
HPWPD Chamba

Executive Engineer  
Chamba Division  
H.P.W.D. Chamba



15

Name of work: C/O Link Road Santhan Chubba Dada, road km 0/0 to 1/750  
 S.H. C/O Gate work for Dumping Site at R.D 0/292 to 297.50

Estimated cost - 98656/-  
 Estimated money - 1973/-  
 Time Limit - one month

Sr. No.	Description of Work / Item (S)	Qty.	Rate	Unit	Amount
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of silt which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malikana, toll tax sale tax or other taxes imposed by the Government.	4.95	350.00	Per Cubic Metre	1733.0
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS: two hundred eighty) and IS: 4836 (IS: four thousand eight hundred thirty six) in 100mm x 100mm (one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40kg (forty kilogram) each as per drawing and MORD technical specification clause 130.1 and as per directions of Engineer-in-Charge including the carriage of material within all leads, lifts and other incidental. The rate including octroi, royalty, Malikana, toll tax sale tax or any other taxes imposed by the Government.	34.37	2820.00	Per Cubic Metre	96923.0
Total					98656.0

Assistant Engineer  
 Sub Division No.-5  
 HPWPD Chamba

Executive Engineer  
 Chamba Division  
 HPWPD Chamba

2

DHIT approved for Rs 98656/- only

Estimated Cost: Rs.  
Earnest Money: Rs.  
Time Limit:

Home of work: Ch Link road from Saffet to Chubana Dindar road of km 4/0 to 1/500

C. Formation cutting at RD 1/028 to 1/035

S.No.	Item	Qty.	Unit	Rate	Amount
			In fig.	In words.	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil consisting of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes to level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load and animal transport and mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on his account. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The removal of slips during the construction period shall be responsibility of the contractor. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	426.93	Per cubic metre	232.65	99,325.00
		Total			99,325.00

DNTI Approved for D. 99325/-

Executive Engineer  
Chamba Division  
HPPWD CHAMBA

10/2

Estimated Cost: Rs.  
Earnest Money: Rs.

Time Limit: -

Name of work/Link Road from Deller to Chibbar Deller road at km of 1/500

GR: Formation cutting at RD 1/55 To 1/585

S.No.	Item	Qty.	Unit	Rate		Amount
				In Rs.	In words.	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes to level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1500 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load and animal transport and mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on his account. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The removal of slips during the construction period shall be responsibility of the contractor. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	422.80	Per Cubic Metre	232.64		98,361.00
Total						98,361.00

DNIT approved pro. 98361/-

✓

ADP

Executive Engineer  
Charing Division  
CHANDIGARH



DNIT

Estimated Cost: Rs.  
Earnest Money: Rs.  
Time Limit:

Name of work - Link Road From Sattai to Chubara Dadar Road Km 0/6 to 1/500

Estimated quantity at 05/12/70 to 1/2/99

S.No.	Item	QTY.	Unit	Rate		Amount
				In fig.	In words.	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes to level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 3600 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, canber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load and animal transport and mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on his account. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The removal of slips during the construction period shall be responsibility of the contractor. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	413.96	per Cubic Meter	232.64		96,303.00
Total		96,303.00				

DNIT Approved for v. 96303/-

Executive Engineer  
Chamba Division  
HPPWD CHAMBA

ADP/12

STATE OF WORK - *Rate of R/Manings on Retha Kurena Road KPI 0/0.740*  
 (SH Construction of PCC & Wall at RD 0/030.00 To 0/033.00)

*ABSTRACT OF COST*

Sr. No.	Description of items	Quantity	In fig.	Rate		Unit	Estimated cost:-	
				In words			Earnest money:-	Tune Limit:- One Month
1	Earth work in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals.	7.06	350.00	Three Hundred & Fifty Only		Per cum	2471.00	
2	Providing and laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and H.P.W.D. technical specifications clause 802, 803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	17.73	4900.00	Forty Nine Thousand Only		Per cum	8,877.00	
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	4.41	556.00	Nine Hundred Fifty Only		Per cum	4,189.00	
4	Providing weaboies in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and H.P.W.D. technical specifications clauses 614, 709, 1204.3.7	5	295.00	Two Hundred Ninety Five Only		Each	1475.00	
	TOTAL						95,012.00	

*Estimate technically Smeetha Ar 25 95012/m14*

*Shgk*

Executive Engineer  
 Charba Division  
 H.P.W.D., Chamba



STATE OF WORK - *Resto. of Runways on North Kumbha Road KM 0/0 to 7/00*  
 (8). Construction of R.C. Runway at RD 0/033.00 to 0/038.00

**ABSTRACT OF COST**

Sr No.	Description of items	Quantity	In fig.	Rate		Estimated cost :-	
				In words	Per cum	Earned money - Tune Limit - One Month	Amount
1	Earthwork excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all beds including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all beds and lifts as per the direction of the Engineer in charge and other incidental.	7.76 cu	350.00	Three Hundred & Fifty Only	Per cum	2471.00	
2	Providing and laying plain cement concrete 1:5:10 (one cement into five sand into ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and H.P.W.D technical specifications clause 802.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all beds and lifts and other incidental.	17.73 cu	4900.00	Forty Nine Thousand Only	Per cum	8,677.00	
3	Backfilling with granular material behind abutment wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.5	4.41 cu	950.00	Nine Hundred Fifty Only	Per cum	4,189.00	
4	Providing wallholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with slope of 1(V):2(H) wards drawing face complete as per drawing and H.P.W.D technical specifications clauses 614, 709, 1204.3.7	5	235.00	Two Hundred Thirty Five Only	Each	1475.00	
	<b>TOTAL</b>						<b>95,012.00</b>

*Estimate Fee being 1% amount to Rs 9520/-*

*24*

**Executive Engineer**  
 Chamba Division  
 H.P.W.D., Chamba

(21)

ABSTRACT OF COST  
 NAME OF WORK - Repair of Damages on Ruzha Kurena Road KM 0/0 to 7/00  
 (SH. Construction of PCC Road at RD 0/036.00 to 0/039.00)

Sr No.	Description of items	Quantity	In fig.	Rate		Unit	Estimated cost:-	
				In words			Earnest money:-	Time Limit - One Month
1	Earthwork in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of shumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals..	7.06 cu	350.00	Three Hundred & Fifty Only	Per cum		2471.00	
2	Providing and laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and HPPWD technical specifications clause 802, 803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	17.73 cu	4900.00	Forty Nine Thousand Only	Per cum		86,877.00	
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	4.41 cu	950.00	Nine Hundred Fifty Only	Per cum		4189.00	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and IT. PWD technical specifications clauses 614, 709, 1204, 3.7	5	295.00	Two Hundred Ninty Five Only	Each		1475.00	
	TOTAL						95,012.00	

Estimate technically Smeetha A.R.S 95012 only

Executive Engineer  
 Chambe Division  
 H.P.P.W.D., Chambe



ABSTRACT OF COST  
 NAME OF WORK - Repair of P/Manholes on Kuzhitha Kuzhena Road W/M of P. No. 7700  
 (SH: Construction of PCC R/W all at RD 0/033.00 to 0/042.00)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In Rs.	In words		
1	Earth work in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals.	7.76 cu	350.00	Three Hundred & Fifty Only	Per cum	2471.00
2	Providing and laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and HPPWD technical specifications clause 862.803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	17.73 cu	4900.00	Forty Nine Thousand Only	Per cum	86,877.00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	4.41 cu	950.00	Nine Hundred Fifty Only	Per cum	4189.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and HPPWD technical specifications clauses 614.709, 1204.3.7	5	295.00	Two Hundred Ninety Five Only	Each	1475.00
TOTAL						95,012.00

Estimate technically Satisfactory No. 95012/m/s

Executive Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

# ABSTRACT OF COST

NAME OF WORK: Retention of R Damages on Paschim Kuzena Road KM 0/0 to 7/00  
(SH: Construction of PCC Road at RD) 0/042.00 to 0/045.00

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Earthwork in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals.	7.06 cu	350.00	Three Hundred & Fifty Only	Per cum	2471.00
2	Providing and laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and HPPWD technical specifications clause 802, 803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	17.73 cu	4900.00	Forty Nine Thousand Only	Per cum	86,877.00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	4.41 cu	950.00	Nine Hundred Fifty Only	Per cum	4189.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and HPPWD technical specifications clauses 614, 709, 1204, 3.7	5	295.00	Two Hundred Ninty Five Only	Each	1475.00
	TOTAL					95012.00

Estimate Technically Sanction No. 95042/199

Executive Engineer  
Chamba Division,  
H.P.P.W.D., Chamba