

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-  
To

1041-45

DATED:

22/5/25

The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar,  
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,  
HPPWD Division,  
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,  
Dehra Division HP.PWD.,  
Dehra.




## Exigency Certificate

It is certified that the tenders invited vide this office NIT  
No.....1041-45.....dated..22/05/25.. are of emergent nature of work and in  
public interest.

Place:

Dated:

  
Executive Engineer,  
HPPWD Division,  
Dehra.



### H. P. P.W.D. TENDER

Sealed item rate tenders on the form G&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors ( C&D Class) enlisted in HPPWD.

#### TENDER SCHEDULE:

- |   |                            |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 31.05.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form:                   | 02.06.2025 upto 5.00 PM    |
| 3. Date and time of receipt of tenders:                     | 03.06.2025 upto 10.30AM    |
| 4. Date and time of opening of tenders:                     | 03.06.2025 at 11.00 AM     |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

| Job No. | Name of work  | Estimated cost | Earnest money | Time limit | Cost of form |
|---------|---|----------------|---------------|------------|--------------|
| 01      | Construction of Ambulance Road to the house of Sh. Mohinder Singh to Barwara Ward No. 01 (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/022.40) VKV/2023/1304.   | Rs. 96,267.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 02      | Construction of Ambulance Road to the house of Sh. Sant Ram (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/022.40) VKV/2023/127.   | Rs. 96,267.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 03      | Construction of Culvert near the House of Bir Singh, Kultar, Kirpal etc. in Village Churan (SH: C/o Hume Pipe Culvert along with Toe Wall) SDP/2023/752   | Rs. 74,650.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 04      | Construction of Jeepable road from link road to the house of Surinder, Sujan Singh etc. in KM 0/0 to 0/072 (SH: C/o CCP at RD 0/0 to 0/036) VKV/2023/1321   | Rs. 73,125.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 05      | Construction of Jeepable road from link road to the house of Surinder, Sujan Singh etc. in KM 0/0 to 0/072 (SH: C/o CCP at RD 0/036 to 0/072) VKV/2023/1321   | Rs. 73,125.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 06      | Construction of Jeepable road from Ashok Kumar House to Lekh Raj Land in Village Jakundi Ward No. 3 G.P. Paisa (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/025) VKV/2023/1314                           | Rs. 95,142.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 07      | Construction of Jeepable road from Ashok Kumar House Near Atta Chaki in Ward No. 2 G.P. Paisa (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/022.40) VKV/2023/1306   | Rs. 96,267.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 08      | Construction of Jeepable road link road to Jagdish Chand in Ward No. 5 Jakhundi Mohal (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/025) VKV/2023/1311  | Rs. 95,142.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 09      | Construction of Jeepable road from link road Gatal to the house of Sh. Milap Chand, Rakesh Chand Harizan Basti Village Jakhundi Mohal (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/022.40) VKV/2023/1307 | Rs. 96,267.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 10      | Construction of Jeepable road from Jakundi to the house of Kashmir Singh, Ramesh Chand etc. in Village Jakundi G.P. Paisa (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/022.40) VKV/2023/1310             | Rs. 96,267.00  | Rs.2,000/-    | One Month  | Rs.350/-     |
| 11      | Construction of Jeepable road from Nagwal Lahar Ward No. 3 Village Nagwal Lahar (SH: P/L Interlocking Paver Block 60mm at RD 0/0 to 0/017.40) VKV/2023/1303   | Rs. 74,739.00  | Rs.1,500/-    | One Month  | Rs.350/-     |



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 96,267.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

12  
 Dohra  
 40

Name of work:- C/o Ambulance road from to the house of Sh. Mohinder Singh to Barwara ward No.1 (Sh:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/022.40). C V K V / 2023 / 1364

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 6.72 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,949.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.  | 6.72 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 27,216.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount    |
|---|--------------------|---------|---|------------------|-----------|
|   |                    | Figures | Words                                   |                  |           |
| 3 Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 2.03 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 11,774.00 |
| 4 Providing and laying ISI marked factory made chanfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 58.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 55,328.00 |
| TOTAL   |                    |         |   |                  | 96,267.00 |
| % Above/below   |                    |         |   |                  |           |
| Quoted Amount in Figures  |                    |         |   |                  |           |
| Quoted Amount in Words  |                    |         |   |                  |           |

*Bid of quantity checked and approved for Rs. 96,267.00/only.*

Executive Engineer,  
Dehra Division,  
HPPWD Dehra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 96,267.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- C/o Ambulance road from to the house of Sant Ram (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/022.40).

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 6.72 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,949.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.   | 6.72 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 27,216.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount           |
|---|--------------------|---------|---|------------------|------------------|
|   |                    | Figures | Words                                   |                  |                  |
| 3 Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 2.03 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 11,774.00        |
| 4 Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 58.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 55,328.00        |
| <b>TOTAL</b>  |                    |         |   |                  | <b>96,267.00</b> |
| % Above/below   |                    |         |   |                  |                  |
| Quoted Amount in Figures  |                    |         |   |                  |                  |
| Quoted Amount in Words  |                    |         |   |                  |                  |

*Bid of quantity checked and approved for Rs 96,267.00/- only*

Executive Engineer,  
Dehra Division,  
HPPWD Dehra



(31)

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 74,650.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Months.

Name of Work :- Construction of Culvert near the House of Bir Singh, Kulltar, Kripal etc. village Churan, (S.H.-:- Construction of Hume pipe culvert along with toe walls), SDP/2023/752

| Sr.No.                   | Description of Item   | Qty.  | Unit | Rate in |  | Amount    |
|--------------------------|---|-------|------|---------|--|-----------|
|                          |   |       |      | figure  | words  |           |
| 1                        | Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material, complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government. | 11.12 | Cum  | 290.00  | Rupees Two Hundred Ninety Only               | 3225.00   |
| 2                        | Providing and Laying 1:4:8 concrete for plain/reinforced concrete in open foundations/ Breast wall/Retaining wall etc complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.  | 1.25  | Cum  | 4050.00 | Rupees Four Thousand Fifty Only              | 5063.00   |
| 3                        | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) (40mm) size/complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.  | 9.77  | Cum  | 4950.00 | Rupees Four Thousand Nine Hundred Fifty Only | 48362.00  |
| 4                        | Providing and laying 900 mm dia Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.     | 5.00  | Rmt  | 3600.00 | Rupees Three Thousand Six Hundred Only       | 18000.00  |
| Total Amount             |   |       |      |         |  | 74,650.00 |
| % Above/below            |   |       |      |         |  |           |
| Quoted Amount in Figures |   |       |      |         |  |           |
| Quoted Amount in Words   |   |       |      |         |  |           |

*Bill of quantity checked and approved for Rs. 74,650.00 only*

Executive Engineer,  
 Debra Division,  
 HPPWD Dehra



32

# PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 73,125.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Months.

Name of Work :- Construction of Jeepable road from link road to the House of Surinder, Sujan Singh etc. km 0/000 to 0/072.(S.H.:- Construction of Cement concrete Pavement from RD 0/00 TO 0/036).VKV/2023/1321

| Sr.No.                   | Description of Item   | Qty.  | Unit | Rate in |  | Unit             | Amount    |
|--------------------------|---|-------|------|---------|--|------------------|-----------|
|                          |   |       |      | figure  | words                                  |                  |           |
| 1                        | Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                   | 90.00 | Sqm  | 2.50    | Rupees Two And Paise Fifty Only        | Per Square Meter | 225.00    |
| 2                        | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C M 20 nominal mix 1:2:4 as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 13.50 | Cum  | 5400.00 | Rupees Five Thousand Four Hundred Only | Per Cubic Meter  | 72900.00  |
| Total Amount             |   |       |      |         |  |                  | 73,125.00 |
| % Above/below            |   |       |      |         |  |                  |           |
| Quoted Amount in Figures |   |       |      |         |  |                  |           |
| Quoted Amount in Words   |   |       |      |         |  |                  |           |

*Bill of quantity checked and approved  
 for Rs. 73,125.00/- only.*

Executive Engineer,  
 Dehra Division,  
 HPPWD Dehra



33

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 73,125.00  
Earnest Money :- Rs. 2,000.00  
Time Limit :- One Months.

Name of Work :- Construction of Jeppable road from link road to the House of Surinder, Sujana Singh etc. km 0/000 to 0/072.(S.H):- Construction of Cement concrete Pavement from RD 0/036 TO 0/072).VKV/2023/1321

| Sr.No.                   | Description of Item   | Qty.  | Unit | Rate in |  | Unit             | Amount    |
|--------------------------|---|-------|------|---------|--|------------------|-----------|
|                          |   |       |      | figure  | words                                  |                  |           |
| 1                        | Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.                   | 90.00 | Sqm  | 2.50    | Rupees Two And Paise Fifty Only        | Per Square Meter | 225.00    |
| 2                        | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C M 20 nominal mix 1:2:4 as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 13.50 | Cum  | 5400.00 | Rupees Five Thousand Four Hundred Only | Per Cubic Meter  | 72900.00  |
| Total Amount             |   |       |      |         |  |                  | 73,125.00 |
| % Above/below            |   |       |      |         |  |                  |           |
| Quoted Amount in Figures |   |       |      |         |  |                  |           |
| Quoted Amount in Words   |   |       |      |         |  |                  |           |

*Bill of quantity checked and approved for Rs. 73,125.00 only*

Executive Engineer,  
Dehra Division,  
HPPWD Dehra



(34)

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 95,142.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- C/o Jeepable road from Ashok Kumar House to Lekh Raj Land village Jakundi Ward No.3 GP Paissa (SH:- Providing and laying Interlocking

Paver Block 60mm at RD 0/0 to 0/025). SDRF *WKV/2023/1314*

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 7.50 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 2,175.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.   | 4.50 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 18,225.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount    |
|---|--------------------|---------|---|------------------|-----------|
|   |                    | Figures | Words                                   |                  |           |
| Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 2.24 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 12,992.00 |
| Providing and laying ISI marked factory made chantered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 65.00 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 61,750.00 |
| TOTAL   |                    |         |   |                  | 95,142.00 |
| % Above/below   |                    |         |   |                  |           |
| Quoted Amount in Figures  |                    |         |   |                  |           |
| Quoted Amount in Words  |                    |         |   |                  |           |

*Bid of quantity checked and approved  
for Rs. 95,142.00/- only*

*CVS*  
Executive Engineer,  
Dehra Division,  
HPPWD Dehra



(42)

**PERCENTAGE BILL OF QUANTITY**

JOB NO.

Page 1

Estimate Cost :- Rs.

96,267.00

Earnest Money :- Rs.

2000.00

Time Limit :-

One Month.

Name of work:-

C/o Jeepable road from link road to the house of Sh. Ashok Kumar near Atta Chaki ward No.2 (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/022.40). VKV/2023/1306

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 6.72 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,949.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>In Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.  | 6.72 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 27,216.00 |



## Description of Item

JOB NO.

Page 2

| Description of Item   | Quantity           | Rate in |   | Unit             | Amount    |
|---|--------------------|---------|---|------------------|-----------|
|   |                    | Figures | Words                                   |                  |           |
| providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 0mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORC technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering surface and sub-soil water) and removal of the slush which may arise at the time of laying under water or all heights/depths and any quantum of water complete including carriage of materials up to all roads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.               | 2.03 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 11,774.00 |
| providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by the vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 58.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 55,328.00 |
| TOTAL   |                    |         |   |                  | 96,267.00 |
| % Above/below   |                    |         |   |                  |           |
| Quoted Amount in Figures  |                    |         |   |                  |           |
| Quoted Amount in Words  |                    |         |   |                  |           |

Bill of quantity checked and approved  
for Rs. 96,267.00 only.

Executive Engineer,  
Dehra Division,  
HPPWD Dehra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 95,142.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- C/o Jeepable road from link road to Jagdish Chand House to Ward No.5 Jakundi Mohal (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/025). VKV/2023/1311.

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 7.50 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 2,175.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.   | 4.50 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 18,225.00 |



| Description of Item   | Quantity           | Rate in                  |   | Unit             | Amount           |
|---|--------------------|--------------------------|---|------------------|------------------|
|   |                    | Figures                  | Words                                   |                  |                  |
| Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 2.24 Cubic metre   | 5800.00                  | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 12,992.00        |
| Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 65.00 Square metre | 950.00                   | Rupees Nine Hundred Fifty Only          | Per Square metre | 61,750.00        |
| <b>TOTAL</b>  |                    |                          |   |                  | <b>95,142.00</b> |
|   |                    | % Above/below            |   |                  |                  |
|   |                    | Quoted Amount in Figures |   |                  |                  |
|   |                    | Quoted Amount in Words   |   |                  |                  |

*Bill of quantity checked and approved  
for Rs. 95,142.00 only.*

*Executive Engineer,*  
Dehra Division,  
HPPWD Dehra



37

**PERCENTAGE BILL OF QUANTITY**

JOB NO.

Page 1

Name of work:- C/o Jeepable road from link road Gatal to the House of Milap Chand, Rakesh Chand Harizan Basti village Jakundi Mohal (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/22.40). VKV/2023/1307.

Estimate Cost :- Rs. 96,267.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 6.72 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,949.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.  | 6.72 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 27,216.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount    |
|---|--------------------|---------|---|------------------|-----------|
|   |                    | Figures | Words                                   |                  |           |
| 3 Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 2.03 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 11,774.00 |
| 4 Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 58.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 55,328.00 |
| TOTAL   |                    |         |   |                  | 96,267.00 |
| % Above/below   |                    |         |   |                  |           |
| Quoted Amount in Figures  |                    |         |   |                  |           |
| Quoted Amount in Words  |                    |         |   |                  |           |

*Bill of quantity checked and approved for Rs. 96,267.00/- only.*

*Executive Engineer,*  
Bendra Division,  
HPPWD Dabra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 96,267.00  
 Earnest Money :- Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- C/o Jeepable road from link road Jakundi to the House of Kashmir Singh Ramesh Chand etc village Jakundi GP Paisea (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/0 to 0/22.40), SDRF *VK/1/2023/1310*

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 6.72 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,949.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.   | 6.72 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 27,216.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount           |
|---|--------------------|---------|---|------------------|------------------|
|   |                    | Figures | Words                                   |                  |                  |
| Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all loads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.               | 2.03 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 11,774.00        |
| Providing and laying ISI marked factory made charfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all loads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 58.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 55,328.00        |
| <b>TOTAL</b>  |                    |         |   |                  | <b>96,267.00</b> |
| <b>% Above/below</b>  |                    |         |   |                  |                  |
| <b>Quoted Amount in Figures</b>   |                    |         |   |                  |                  |
| <b>Quoted Amount in Words</b>   |                    |         |   |                  |                  |

*Bid of quantity checked and approved for Rs. 96,267.00/- only.*

*MS*  
Executive Engineer,  
Dehra Division,  
HPPWD Dehra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 74,739.00  
 Earnest Money :- Rs. 1500.00  
 Time Limit :- One Month.

Name of work:- C/o Jeepable road from Nagwal Lahar Ward No.3 village Nagwal Lahar (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/000 to 0/017.40). VKV/2023/1303.

| Sr. No. | Description of Item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 5.22 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,514.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.  | 5.22 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 21,141.00 |



| Description of Item   | Quantity           | Rate in |   | Unit             | Amount    |
|---|--------------------|---------|---|------------------|-----------|
|   |                    | Figures | Words                                   |                  |           |
| 3 Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.              | 1.57 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 9,106.00  |
| 4 Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 45.24 Square metre | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 42,978.00 |
| TOTAL   |                    |         |   |                  | 74,739.00 |
| % Above/below   |                    |         |   |                  |           |
| Quoted Amount in Figures  |                    |         |   |                  |           |
| Quoted Amount in Words  |                    |         |   |                  |           |

*Bill of quantity checked and approved  
for Rs. 74,739.00/- only*

Executive Engineer,  
Dehra Division,  
HPPWD Dehra



**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 74,739.00  
 Earnest Money :- Rs. 1500.00  
 Time Limit :- One Month.

Name of work:- C/o Jeepable road from Nagwal Lahar Ward No.3 village Nagwal Lahar (SH:- Providing and laying Interlocking Paver Block 60mm at RD 0/017.40 to 0/034.80). VKV/2023/1303.

| Sr. No. | Description of item  | Quantity         | Rate in |                                 | Unit            | Amount    |
|---------|--|------------------|---------|---------------------------------|-----------------|-----------|
|         |  |                  | Figures | Words                           |                 |           |
| 1       | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government. | 5.22 Cubic metre | 290.00  | Rupees Two Hundred Ninety Only  | Per Cubic metre | 1,514.00  |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water <i>in Retaining wall/breast wall and the like etcetera</i> complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.  | 5.22 Cubic metre | 4050.00 | Rupees Four Thousand Fifty Only | Per Cubic metre | 21,141.00 |



## Description of Item

JOB NO.

Page 2

| Quantity   | Rate in |   | Unit             | Amount    |
|--|---------|---|------------------|-----------|
|  | Figures | Words                                   |                  |           |
| 1.57 Cubic metre   | 5800.00 | Rupees Five Thousand Eight Hundred Only | Per Cubic metre  | 9,106.00  |
| 45.24 Square metre   | 950.00  | Rupees Nine Hundred Fifty Only          | Per Square metre | 42,978.00 |
| TOTAL  |         |   |                  | 74,739.00 |
| % Above/below  |         |   |                  |           |
| Quoted Amount in Figures   |         |   |                  |           |
| Quoted Amount in Words   |         |   |                  |           |
| <p>3 Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water in open foundation for all types of structure and the like in solid causeway etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 &amp; 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.</p> <p>4 Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness &amp; size/ shape, made by table vibratory method using PU mould, laid in required colour &amp; pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.</p> |         |   |                  |           |

*Bill of quantity checked and approved for Rs. 74,739.00 only.*

*Executive Engineer,*  
Dehra Division,  
HPPWD Dehra



PERCENTAGE BILL OF QUANTITY

Name of Work:- Restoration of Rain damages on various road under HPPWD Sub Division Dehra (SH:- Removal of slips on various RD's).

Estimate Cost :- Rs. 99,090.00  
 Earnest Money :- Rs. 2,000.00  
 Time Limit :- One Month.

| Sr. No. | Description of Item   | Quantity           | Rate in |                                     | Unit            | Amount    |
|---------|---|--------------------|---------|-------------------------------------|-----------------|-----------|
|         |   |                    | Figures | Words                               |                 |           |
| 1       | Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government | 734.00 Cubic metre | 135.00  | Rupees One Hundred Thirty Five Only | Per Cubic metre | 99,090.00 |
|         | Total   |                    |         |                                     |                 | 99,090.00 |
|         | % Above/below   |                    |         |                                     |                 |           |
|         | Quoted Amount in Figures  |                    |         |                                     |                 |           |
|         | Quoted Amount in Words  |                    |         |                                     |                 |           |

*Bill of quantity checked & approved*  
*Rs. 99,090/-*  
 Executive Engineer,  
 Dehra Division,  
 HPPWD Dehra.