

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-
To,

340-48

Dated:- 8/05/2025


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 19.05.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 20.05.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 21.05.2025 upto 11.00AM |
| 4. Date and time of opening of tenders: | 21.05.2025 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	A/R & M/O on Tatwali Aghar road Under MMSRRY 2025-26 (SH: Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 72470/-	Rs. 1500/-	One month	350/-	Class D&C
2	A/R & M/O on Sathana to Shah Nehar Barriage AI-I road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 0/910.)	Rs. 72534/-	Rs. 1500/-	One month	350/-	Class D&C
3	A/R & M/O on Chandbeh Diana Bhulana Mandhlahi Diyal road under MMSRRY 2025-26 (Repair of Pot Holes in between km 2/0 to 3/0.)	Rs. 72244/-	Rs. 1500/-	One month	350/-	Class D&C
4	A/R & M/O on Shaheed Ashok Kumar link road to village Lohara under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 0/930.)	Rs. 71542/-	Rs. 1500/-	One month	350/-	Class D&C
5	A/R & M/O on Chandbeh Diana Bhulana Mandhlahi Diyal road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 72154/-	Rs. 1500/-	One month	350/-	Class D&C
6	A/R & M/O on Lohara to Gholi km 0/0 to 0/870 and Hara to Pardah road km 4/0 to 4/410 (Hara Mandhot road) under MMSRRY 2025-26 (Repair of Pot Holes)	Rs. 99994/-	Rs. 2000/-	One month	350/-	Class D&C
7	A/R & M/O on Bhatoli Aghar Rey road to Jakhbar via Kasial road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
8	A/R & M/O on Raja Ka Talab Bari Batrahan Golwan Chattar Lohali to Connection Rehan Samlet road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
9	A/R & M/O on Bhatoli Aghar Rey road to Jakhbar via Kasial road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
10	A/R & M/O on Maira Palli Fatehpur road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
11	A/R & M/O on Raja Ka Talab Bari Batrahan Golwan Chattar Lohali to Connection Rehan Samlet road under MMSRRY 2025-26 (Repair of Pot Holes in between km 4/0 to 5/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
12	A/R & M/O on Jawalamukhi Dehra Jawali Raja Ka Talab road (Portion 79/0 to 80/600) road under MMSRRY 2025-26 (Repair of Pot Holes in between km 79/0 to 80/0.)	Rs. 99415/-	Rs. 2000/-	One month	350/-	Class D&C
13	A/R & M/O on Gholi Bridge MTN to Paplah Khas under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 99724/-	Rs. 2000/-	One month	350/-	Class D&C

14	A/R & M/O on Fatehpur Deothi road under MMSRRY 2025-26 (Repair of Pot Holes in between km 4/0 to 5/0.)	Rs. 70777/-	Rs. 2000/-	One month	350/-	Class D&C
15	A/R & M/O on Gholi Bridge MTN to Paplah Khas under MMSRRY 2025-26 (Repair of Pot Holes in between km 3/0 to 4/0.)	Rs. 99406/-	Rs. 2000/-	One month	350/-	Class D&C
16	A/R & M/O on Raja Ka Talab to Gurial road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 70856/-	Rs. 2000/-	One month	350/-	Class D&C
17	A/R & M/O on Fatehpur Deothi road under MMSRRY 2025-26 (Repair of Pot Holes in between km 6/0 to 7/0.)	Rs. 71015/-	Rs. 2000/-	One month	350/-	Class D&C
18	A/R & M/O on Raja Ka Talab to Gurial road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 71174/-	Rs. 2000/-	One month	350/-	Class D&C
19	A/R & M/O on Rehan to Dadwala via old Bus Adda to Sakri road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 71594/-	Rs. 2000/-	One month	350/-	Class D&C
20	A/R & M/O on Mangarh Baliara road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 71071/-	Rs. 1500/-	One month	350/-	Class D&C
21	A/R & M/O on MTN road to Sohar road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 71162/-	Rs. 1500/-	One month	350/-	Class D&C
22	A/R & M/O on Sunhara to Takwal road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 71204/-	Rs. 1500/-	One month	350/-	Class D&C
23	A/R & M/O on Hatli Khadoun Kuthar road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 71204/-	Rs. 1500/-	One month	350/-	Class D&C
24	A/R & M/O on Patti Jattian to Khukhnara road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
25	A/R & M/O on Hatli Khadoun Kuthar road under MMSRRY 2025-26 (Repair of Pot Holes in between km 2/0 to 3/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
26	A/R & M/O on Hara Pardah road under MMSRRY 2025-26 (Repair of Pot Holes in between km 0/0 to 1/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
27	A/R & M/O on Hatli Khadoun Kuthar road under MMSRRY 2025-26 (Repair of Pot Holes in between km 5/0 to 6/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C
28	A/R & M/O on Patti Jattian to Khukhnara road under MMSRRY 2025-26 (Repair of Pot Holes in between km 1/0 to 2/0.)	Rs. 70777/-	Rs. 1500/-	One month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. **Undertaking that to complete the work with in stipulated period if fail work will be rescinded and E/money will be forfeited without any notice**
4. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
5. The intending contractors are requested to see the site of the work before submitting the tender.
6. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
7. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Tatwali Agliar road Under MMSRRY 2023-26
(5th- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.72470/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. NO	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.95 cubic meter	1750.90	Rupees One Thousand Seven Hundred Fifty And Paise Ninety Only	Per cubic meter	5165.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	67305.00
					Total:-	72470.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehgarh Division HPPWD
Fatehgarh Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Sathana to Shah Nehar Barriage A-I Road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 0/910).

Estimated cost:- Rs.72534/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.75 cubic meter	1775.60	Rupees One Thousand Seven Hundred Seventy Five And Paise Sixty Only	Per cubic meter	8434.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	200.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	64100.00
					Total:-	72534.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Chandbeh Diana Bhulana Mandhlahi Diyal road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 2/0 to 3/0).

Estimated cost:- Rs.72244/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.75 cubic meter	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	4939.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	67305.00
					Total:-	72244.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Shaheed Ashok Kumar link road to village Lohara Under MMSRRY 2025-26 (SH:- Repair of Pot Holes in between Km. 0/0 to 0/930).

Estimated cost:- Rs.71542/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.60 cubic meter	1796.60	Rupees One Thousand Seven Hundred Ninety Six And Paise Sixty Only	Per cubic meter	8264.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	195.00 Square meter	324.50	Rupees Three Hundred Twenty Four And Paise Fifty Only	Per square meter	63278.00
					Total:-	71542.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Chandbeh Diana Bhulana Mandhila Diyal road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.72154/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.70 cubic meter	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	4849.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	67305.00
					Total:-	72154.00

Draft Schedule of Quantity checked
and approved for Rs. 72154/- only by
Seventy Two Thousand One Hundred and
Fifty Four only.

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Link road Lohara to Gholi km. 0/0 to 0/870 and Hara to Pardah road Km. 4/0 to 4/410 (Hara Mandiot Road) Under MMSRRY 2025-26 (SH:- Repair of Pot Holes)

Estimated cost:- Rs.99994/- only
Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10 cubic meter	1575.60	Rupees One Thousand Five Hundred Seventy Five And Paise Sixty Only	Per cubic meter	3309.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	305.00 Square meter	317.00	Rupees Three Hundred Seventeen Only	Per square meter	96685.00
					Total:-	99994.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Pardahpur Division HPPWD
Fatehgarh Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Bhatoli Aghar Rey road to Jakhar via Kasial road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00
	Amount quoted by the contractor in % Above/Below					

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)



SCHEDULE OF QUANTITY

Name of work:- A R&M/O on Raja Ka Talab Bari Batrahan Golwan Chhattar Lohali to connection Rehan Sanict road Under MMSRRY 2025-26 (SH):- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade-ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

9

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Bhatoli Aghar Rey road to Jakhbar via Kasial road Under MMSRRY 2025-26
(S/H:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Mairia Palli Fatehpur road Under MMSRRY 2025-26.
(SH)- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)



SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Raja Ka Talab Bari Batrahan Golwan Chattar Lohali to connection Rehan Samlet road Under MMSRRY 2025-26 (SH)- Repair of Pot Holes in between Km. 4/0 to 5/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Jawalamukhi Dehra Jawali Raja-ka-Talab road (Portion 79/0 to 80/600) Under MMSRRY 2025-26 Estimated cost:- Rs.99415/- only
(SH:- Repair of Pot Holes in between Km. 79/0 to 80/00). Earnest Money : Rs.2000/- only

Time limit:- One month

Sr No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.400 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3817.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	301.00 Square meter	317.60	Rupees Three Hundred Seventeen And Paise Sixty Only	Per square meter	95598.00
					Total:-	99415.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

(B)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Gholi bridge MTN road to Paplah Khas Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.99724/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters. to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	301.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	95748.00
					Total:-	99724.00

Amount quoted by the contractor in % Above/Below

Engineer
Public Works Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Name of work:- A/R&M/O on Fatehpur Deothi road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 4/0 to 5/0).

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters. to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Fatehpur Deothi road Under MMSRRY 2025-26

(SH:- Repair of Pot Holes in between Km. 4/0 to 5/0).

Estimated cost:- Rs.7077/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sl. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

75

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Gholi bridge MTN road to Paplah Khas Under MMSRRY 2025-26
(SH):- Repair of Pot Holes in between Km. 3/0 to 4/0).

Estimated cost:- Rs.99406/- only
Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading - III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade-ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	300.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	95430.00
					Total:-	99406.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Raja Ka Talab to Gurial road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.70856/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.55 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	4055.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70856.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Fatehpur Deothi road Under MMSRRY 2025-26
(SH- Repair of Pot Holes in between Km. 6/0 to 7/0).

Estimated cost:- Rs.71015/- only
Earnest Money : Rs.2000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.65 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	4214.00
2	Repair to pot holes and removal of loose materials, trining of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	71015.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

18

SCHEDULE OF QUANTITY

Estimated cost:- Rs.71174/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Name of work:- A/R&M/O on Raja Ka Talab to Gurial road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km.1/0 to 2/0).

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading - III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.75 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	4373.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	71174.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Rehan to Dadwala via Old Bus Adda to Sakri road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km.0/0 to 1/0).

Estimated cost:- Rs.71594/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.75 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	4373.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.10	Rupees Three Hundred Twenty And Paise Ten Only	Per square meter	67221.00
					Total:-	71594.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

Name of work:- A/R&M/O on Mangarh Baliara road Under MMSRRY 2025-26
(SI:- Repair of Pot Holes in between Km.0/0 to 1/0).

SCHEDULE OF QUANTITY

Estimated cost:- Rs.71071/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.50	Rupees Three Hundred Nineteen And Paise Fifty Only	Per square meter	67095.00
					Total:-	71071.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehgarh Division HPPWD
Fatehgarh Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on MTN road to Solhar road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.71162/- only
Earnest Money : Rs.1500/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.65 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	4214.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.80	Rupees Three Hundred Eighteen And Paise Eighty Only	Per square meter	66948.00
					Total:-	71162.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Sunhara to Takwal road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.71204/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.60 cubic meter	1596.60	Rupees One Thousand Five Hundred Ninety Six And Paise Sixty Only	Per cubic meter	4151.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.30	Rupees Three Hundred Nineteen And Paise Thirty Only	Per square meter	67053.00
					Total:-	71204.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

23

SCHEDULE OF QUANTITY

Estimated cost:- Rs.71204/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Name of work:- A/R&M/O on Hatli Khadom Kuthar road Under MMSRRY 2025-26
(SH):- Repair of Pot Holes in between Km. 0/0 to 1/0).

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.60 cubic meter	1596.60	Rupees One Thousand Five Hundred Ninety Six And Paise Sixty Only	Per cubic meter	4151.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:75 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.30	Rupees Three Hundred Nineteen And paise Thirty Only	Per square meter	67053.00
					Total:-	71204.00

Amount quoted by the contractor in % Above/Below

[Signature]
Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Patta Jattian to Khukhnara road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
Amount quoted by the contractor in % Above/Below						Total:- 70777.00


Executive Engineer
Fatehpur Division HP&WD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Hatli Khadoun Kuthar road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 2/0 to 3/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Hara to Pardah road (Hara Mandhot Road) Under MMSRRY 2025-26
(S.I.E:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter: premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehgarh Division HPPWD
Fatehgarh Distt. Kangra (H.P.)



SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Hatli Khadoun Kuthar road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 5/0 to 6/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Patta Jatian to Khukhnara road Under MMSRRY 2025-26
(SIH:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.70777/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters. to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.50 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	3976.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	318.10	Rupees Three Hundred Eighteen And Paise Ten Only	Per square meter	66801.00
					Total:-	70777.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)