

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-

S/10-60

Dated:- 8/5/2025

To,


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July,2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 22.05.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 23.05.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 24.05.2025 upto 11.00AM |
| 4. Date and time of opening of tenders: | 24.05.2025 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	A/R & M/O on Kodu Bela to Ludhiarchan That Haler road Under MMSSRY 2025-26 (SH: Repair of Pot Holes in between KM 1/0 to 2/0.)	Rs. 73782/-	Rs. 1500/-	One month	350/-	Class D&C
2	A/R & M/O on Jeepable road from Siholi to Marour to Village Lalwana road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/300 to 1/0.)	Rs. 64214/-	Rs. 1300/-	One month	350/-	Class D&C
3	A/R & M/O on Jagnoli Bhatta Baruna Bhawara Hadwal road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 2/0 to 3/0.)	Rs. 73782/-	Rs. 1500/-	One month	350/-	Class D&C
4	A/R & M/O on Jeepable road from Siholi to Marour to Village Lalwana road under MMSSRY 2025-26 km 1/0 to 1/500 and Siholi to Palli road KM 0/0 to 0/600(Repair of Pot Holes)	Rs. 97819/-	Rs. 2000/-	One month	350/-	Class D&C
5	A/R & M/O on Kodu Bela to Ludhiarchan That Haler road Under MMSSRY 2025-26 (SH: Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 73782/-	Rs. 1500/-	One month	350/-	Class D&C
6	A/R & M/O on Rehan Khas to Bhatoli under MMSSRY 2025-26 (SH: Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 73745/-	Rs. 1500/-	One month	350/-	Class D&C
7	A/R & M/O on Golwan Khas to Blahar Chownk road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 1/0 & 3/0 to 3/380)	Rs. 99808/-	Rs. 2000/-	One month	350/-	Class D&C
8	A/R & M/O on Rehan Khas to Bhatoli road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 2/0 to 3/0.)	Rs. 73745/-	Rs. 1500/-	One month	350/-	Class D&C
9	A/R & M/O on Narnhun to Bankroli road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 72256/-	Rs. 1500/-	One month	350/-	Class D&C
10	A/R & M/O on Kehar Kuthandal Kutkana road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 3/0 to 3/780.)	Rs. 71967/-	Rs. 1500/-	One month	350/-	Class D&C
11	A/R & M/O on Raja Ka Talab via Dhaman road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 1/0 to 2/0.)	Rs. 72256/-	Rs. 1500/-	One month	350/-	Class D&C
12	A/R & M/O on Narnhun to Bankroli road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 1/0 to 2/0.)	Rs. 72256/-	Rs. 1500/-	One month	350/-	Class D&C
13	A/R & M/O on Raja Ka Talab to Kher via Dhaman under MMSSRY 2025-26 (Repair of Pot Holes in between KM 2/0 to 2/500.)	Rs. 49701/-	Rs. 1000/-	One month	350/-	Class D&C
14	A/R & M/O on Malhari Kothi road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 72411/-	Rs. 1500/-	One	350/-	Class

15	A/R & M/O on Sohar to Gurial road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 72411/-	Rs. 1500/-	One month	350/-	Class D&C
16	A/R & M/O on Dak to Gurial Khas road under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 1/0.)	Rs. 86834/-	Rs. 1800/-	One month	350/-	Class D&C
17	A/R & M/O on Link road to MTN road to Devi Mandir to Behgurhan under MMSSRY 2025-26 (Repair of Pot Holes in between KM 0/0 to 0/300.)	Rs. 49140/-	Rs. 1000/-	One month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. **Undertaking that to complete the work with in stipulated period if fail work will be rescinded and E/money will be forfeited without any notice**
4. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
5. The intending contractors are requested to see the site of the work before submitting the tender.
6. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
7. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Kodu Bela to Ludhiarchan That Haler road Under MMSRRY 2025-26
(Sh:- Repair of Pot Holes in between Km.1/0 to 2/0).

Estimated cost:- Rs.73782/- only
Earnest Money : Rs.1500/- only

Time limit:- One month

Sl. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III. 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 cubic meter	1760.85	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Five Only	Per cubic meter	6603.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	73782.00

Amount quoted by the contractor in % Above/Below

 Executive Engineer
Fatehpur Division HPPWD
Fatehpur Dist. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Jeepable road from Siholi to Marour to village Lalwana road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km.0/300 to 1/000)

Estimated cost:- Rs.64214/- only
Earnest Money : Rs.1300/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1696.90	Rupees One Thousand Six Hundred Ninety Six And Paise Ninety Only	Per cubic meter	4921.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	185.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	59293.00
					Total:-	64214.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPW
Fatehpur Distt. Kangra (N.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Jagnoli Bhatta Barua Bhawara Hadwal road Under MMSRKY 2025-26
(SH)- Repair of Pot Holes in between Km.2/0 to 3/0).

Estimated cost:- Rs.73782/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 cubic meter	1760.85	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Five Only	Per cubic meter	6603.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	73782.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P.F.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Jeepable road from Siholi to Marour to village Lalwana road Under MMSRRY 2025-26 Km.1/0 to Estimated cost:- Rs.97819/- only
 1/500 and Siholi to Palli road km.Km.0/0 to 0/600 (SH:- Repair of Pot Holes)
 Earnest Money : Rs.2000/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.95 cubic meter	1750.60	Rupees One Thousand Seven Hundred Fifty And Paise Sixty Only	Per cubic meter	5164.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	290.00 Square meter	319.50	Rupees Three Hundred Nineteen And Paise Fifty Only	Per square meter	92655.00
					Total:-	97819.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatenpura Division HPPW
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Kodu Bela to Ludhiarchan That Haler road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km.0/0 to 1/0).

Estimated cost:- Rs.73782/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 cubic meter	1760.85	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Five Only	Per cubic meter	6603.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of line aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	73782.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work: A/R&M/O on Relim khas to Bhatoli Under MMSRRY 2025-26
(SHE- Repair of Pot Holes in between Km.1/0 to 2/0).

Estimated cost:- Rs.73745/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 cubic meter	1750.80	Rupees One Thousand Seven Hundred Fifty And Paise Eighty Only	Per cubic meter	6566.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	73745.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Golwan khas to Blahar Chownk road Under MMSRRY 2025-26
(SH)- Repair of Pot Holes in between Km.0/0 to 1/0 and 3/0 to 3/380).

Estimated cost:- Rs.99808/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and bronning, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters; to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.40 cubic meter	1590.30	Rupees One Thousand Five Hundred Ninety And Paise Thirty Only	Per cubic meter	2226.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	309.00 Square meter	315.80	Rupees Three Hundred Fifteen And Paise Eighty Only	Per square meter	97582.00
					Total:-	99808.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt (Kangra H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Rehan khas to Bhatoli Under MMSRRY 2025-26
(S/L:- Repair of Pot Holes in between Km. 2/0 to 3/0).

Estimated cost:- Rs.73745/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75 cubic meter	1750.80	Rupees One Thousand Seven Hundred Fifty And Paise Eighty Only	Per cubic meter	6566.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	73745.00

Amount quoted by Contractor (+) (-) above/below

Executive Engineer
Farahpur Division HPPWD
Farahpur District, Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Namhun to Bankroli road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.72256/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III. 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1750.80	Rupees One Thousand Seven Hundred Fifty And Paise Eighty Only	Per cubic meter	5077.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	72256.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Kekar Kuthandal Kutkana road Under MMSRRY 2025-26
(SIL- Repair of Pot Holes in between Km. 3/000 to 3/780).

Estimated cost:- Rs.71967/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1650.90	Rupees One Thousand Six Hundred Fifty And Paise Ninety Only	Per cubic meter	4788.60
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	71967.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Raja ka Talab to Kher via Dhaman Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.72256/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III. 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - In- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1750.80	Rupees One Thousand Seven Hundred Fifty And Paise Eighty Only	Per cubic meter	5077.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	72256.00

Amount quoted by the contractor in % Above/Below


 Engineer
 Fatehpur Division HPPWD
 Fatehpur (U.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Narnhun to Bankroli road Under MMSRRY 2025-26
(SH)- Repair of Pot Holes in between Km. 1/0 to 2/0).

Estimated cost:- Rs.72256/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the intersices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1750.80	Rupees One Thousand Seven Hundred Fifty And Paise Eighty Only	Per cubic meter	5077.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	319.90	Rupees Three Hundred Nineteen And Paise Ninety Only	Per square meter	67179.00
					Total:-	72256.00

/ Ref. quoted by Contractor (-) (+) above / below


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Raja ka Talab to Kher via Dhaman Under MMSRRY 2025-26
(SIH- Repair of Pot Holes in between Km. 2/000 to 2/500).

Estimated cost:- Rs.49701/- only
Earnest Money : Rs.1000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.50 cubic meter	1760.80	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Only	Per cubic meter	6163.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	135.00 Square meter	322.50	Rupees Three Hundred Twenty Two And Paise Fifty Only	Per square meter	43538.00
					Total:-	49701.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Dist. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Malhari Kothi road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.72411/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1760.80	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Only	Per cubic meter	5106.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	67305.00
					Total:-	72411.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Dist. Kangra (P)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Sohlar to Gurial road Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.72411/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1760.80	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Only	Per cubic meter	5106.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	67305.00
					Total:-	72411.00

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Fatenpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Dak to Gurial Khas road Under MMSRRY 2025-26
(SH)- Repair of Pot Holes in between Km. 0/0 to 1/0).

Estimated cost:- Rs.86834/- only
Earnest Money : Rs.1800/- only
Time limit:- One month

Sr No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III. 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.90 cubic meter	1760.80	Rupees One Thousand Seven Hundred Sixty And Paise Eighty Only	Per cubic meter	5106.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS-73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	255.00 Square meter	320.50	Rupees Three Hundred Twenty And Paise Fifty Only	Per square meter	81728.00
					Total:-	86834.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (R.P.)

SCHEDULE OF QUANTITY

Name of work:- A/R&M/O on Link road to MTN road to Devi Mandir to Behgurihan Under MMSRRY 2025-26
(SH:- Repair of Pot Holes in between Km.0/0 to 0/300)

Estimated cost:- Rs.49140/- only

Earnest Money : Rs.1000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.20 cubic meter	1750.60	Rupees One Thousand Seven Hundred Fifty And Paise Sixty Only	Per cubic meter	5602.00
2	Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	135.00 Square meter	322.50	Rupees Three Hundred Twenty Two And Paise Fifty Only	Per square meter	43538.00
					Total:-	49140.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur (Distt. Kangra)