

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 792-831

Dated/ 2-5-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP.PWD., (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act 1968 so as to reach in his office on or before 15.05.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 14.05.2025 up to 4.00 P.M. and the application for issue of tender form shall be received 13.05.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P. duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Retaining wall alongwith Path from Sh. Partap Chand house towards Gian Chand House & others Ward No 1 in GP Nachhir (SW:- C/o R/Wall from RD 0/040 to 0/048.45 (Deposit)	Rs. 73,283.00	Rs. 1,500.00	Three Months
2	C/o Retaining wall alongwith Path from Sh. Partap Chand house towards Gian Chand House & others Ward No 1 in GP Nachhir (SW:- P/L C.Conc. for Pucca Path from RD 0/000 to 0/060 (Deposit)	Rs. 75,375.00	Rs. 1,600.00	Three Months
3	Additional to Anganwari Surad Ward No. 7 in GP Nachir (SW:- Providing plastering work, Masonary work, RCC Work in Kitchen & Tile work in Kitchen and bathrooms (Deposti)	Rs. 99,752.00	Rs. 2000.00	Three Months
4	Additional to Anganwari Surad Ward No. 7 in GP Nachir (SW:- Providing fixing shutters for doors, windows, P/L Tile work in flooring at Hall and sanitary work in bathroom & Toilet etc (Deposti)	Rs. 96,768.00	Rs. 2,000.00	Three Months
5	OFC Damages, on D/Sala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- 1.00 mtrs. Span culvert at RD 37/610)	Rs. 99,124.00	Rs. 2,000.00	Three Months
6	OFC Damages on D/Sala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- 1.00 mtrs. Span culvert at RD 37/610)	Rs. 98,307.00	Rs. 2,000.00	Three Months
7	R/D link road from Dharaman Kandwari Speru road Km 0/000 to 5/000 (SW:- C/o 1.00 mtrs Span culvert at RD 3/850)	Rs. 98,891.00	Rs. 2,000.00	Three Months
8	Repair of Dharamshala Yol Dadh Palampur road Km 15/00 to 27/00 (SW:- Repair of RCC Slab Culvert with apoxy grouting at RD 19/400 (D,C Deposit)	Rs. 99,462.00	Rs. 2,000.00	Two Months
9	Repair of Dharamshala Yol Dadh Palampur road Km 15/00 to 27/00 (SH:- C/o unlined drain at various Rd,s between Km 15/00 to 20/500) (DC Deposit)	Rs. 94,860.00	Rs. 1,900.00	Two Months
10	Repair of Rakh Bhont road Km 0/00 to 3/00 (SW:- Balance work of Crate wall at RD 1/240 to 1/252.50 (DC Deposit)	Rs. 81,200.00	Rs. 1,700.00	Two Months
11	Repair of approach road HSC Gwaltikkar Km 0/06 to 0/080 in GP Kand (SW:- C/o R/Wall (Deposit)	Rs. 49,016.00	Rs. 1,000.00	Three Months
12	Repair of approach road HSC Gwaltikkar Km 0/06 to 0/080 in GP Kand (SW:- C/o R/Wall (Deposit)	Rs. 99,965.00	Rs. 2,000.00	Three Months
13	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW:- Painting on Neugal Khad Bridge (120.00 mtrs Span) at RD 27/000 to 27/120 (OFC Deposit)	Rs. 98,376.00	Rs. 2,000.00	Three Months
14	R/M of CHC at Gopalpur (SH:- Shifting of water Tanks) (Deposit)	Rs. 98,637.00	Rs. 2,000.00	Two Months
15	C/o Kuhl alongwith Retaining wall near Sh. Navratn Ram Land Ward No. 2 G.P Darati (Deposit 0.75 lacs)	Rs. 74,073.00	Rs. 1,500.00	Two Months
16	C/o road alongwith interlocking tiles from Industry Area to Rana Basti Ward No. 2 (SDP) (SW:- P/L Interlocking Tiles (SDP Deposit 1.00 lacs)	Rs. 98,974.00	Rs. 2,000.00	Two Months

17	S/R of Nagri to Manimahesh via Bhasmehar Rakh Society road (SW:- P/L Interlocking Tiles at RD 3/675 to 3/697 (Deposit SDRF)	Rs. 99,902.00	Rs. 2,000.00	Two Months
18	C/o First Floor of Dhouladhar Mahila Mandal Ward No. 1 Sukeri GP Drognu (SW:- C/o Hall at 1 st Floor) (VKVNY)	Rs. 98,270.00	Rs. 2,000.00	Two Months
19	C/o Pulli on Kuhal near Mool Raj Dhiman House Ward No. 7 (SH:- C/o Edge wall along with slab (Deposit)	Rs. 73,260.00	Rs. 1,500.00	Two Months
20	C/o R/Wall to protect the land of Sh. Krishan & Mohinder Ward No. 5 (Deposit VKVNY)	Rs. 98,346.00	Rs. 1,500.00	Two Months
21	C/o Pucca Path from Padra Chowk towards Harizan Basti Ward No. 5 (SH:- P/L Interlocking Paver Blocks at RD 0/00 to 0/085 (Deposit VKVNY)	Rs. 99,025.00	Rs. 2,000.00	Two Months
22	C/o Jeepable road alongwith Interlocking Tiles from Onkar Chand House to Sh. Boni Kumar house (Deposit)	Rs. 99,244.00	Rs. 2,000.00	Two Months
23	Completion of Pucca Path from Latwala main road towards Smt. Indu Bala House (Deposit)	Rs. 67,014.00	Rs. 1,400.00	Two Months
24	C/o Pucca Path from Jhulla Pul towards house of Sh. Amar Singh and others Ward No. 4 Village Jugehar (SW:- P/L CC Pavement at RD 0/00 to 0/097 (Deposit VKVNY)	Rs. 99,289.00	Rs. 2,000.00	Two Months
25	S/R of Nagri to Manimahesh via Bhasmehar Rakh Society road (SW:- P/L Interlocking Tiles at RD 3/700 to 3/722 (Deposit SDRF)	Rs. 99,902.00	Rs. 2,000.00	Two Months
26	C/o Retaining Wall and drain on main road near the land of Ravi Kumar Parour Lahla road (Deposit VKVNY)	Rs. 98,605.00	Rs. 2,000.00	Two Months
27	C/o Pucca Path form Naag Marhi towards the house of Sh. Partap Chand S/o Sh. Dharam Chand (SW:- P/L CC Pavement and edge wall (VKVNY)	Rs. 99,471.00	Rs. 2,000.00	Two Months
28	Restoration of rain Rain damages on Dharaman Kandwari Speru road extension road side Km 0/00 to 0/073) (SW:- Hiring of JCB for removal of slip)	Rs. 98,900.00	Rs. 2,000.00	Three Months
29	C/o link road from Rampur Rajehar Sarsawa via Kapen Neelkanth Bhadraina NH road (SW:- Providing and laying Interlocking Concrete Block Pavement at RD 0/150 to 0/174 (NABARD)	Rs. 98,964.00	Rs. 2,000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
UPWD/Palampur

Schedule of Quantity

Work No. ①

Name of Work :- C/O Retaining wall alongwith Path from Sh. Partap Chand house towards Gian Chand house & Others W. No. 1 in G.P. Nachhir
(S. W. :- C/O R/wall from RD 0/040 to 0/048.45 (Deposit))

Estimated Cost :- Rs. 73,283/-
Earnest Money :- rs. 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	6.59	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	15.72	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	2.87	Cubic metre			Per Cubic metre.	
	Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 75,375/-

Earnest Money :- Rs. 1600/-

Time limit : Three Months.

Name of Work :- C/O Retaining wall alongwith Path from Sh. Partap Chand house towards Gian Chand house & Others W. No. 1 in
G.P. Nachhir
(S. W. :- P/L C.Conc. for Pucca path from RD 0/000 to 0/060 (Deposit))

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	2.00	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	11.25	Cubic metre			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Additional to Anganwari Surd W. No. 7 in G.P. Nachbir
Sub Work :- Providing plastering work, masonry work, RCC work in kitchen & tile work in kitchen and bathroom (De Post)

Estimated Cost : Rupees 99,752/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	316.37			Per Square metre	
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in Cement mortar 1:4 (one cement :four coarse sand) with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	6.51			Per Square metre	
3	Reinforced cement concrete work in beams, suspended m/floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) with in all leads, lifts and other incidental . The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	0.22			Per Cubic metre	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level in Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental . The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	29.70			Per Kilogram mes	
5	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the	9.85			Per Square metre	
6	Providing and laying Vitrified tiles Size of Tile 600x600 mm (thickness to be specified by manufacturer), with water absorption 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	14.24			Each	
	Total:-					

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of quantity

Name of Work :- Additional to Anganwari Surd W. No. 7 in G.P. Nachhri
Sub Work :- P/F shutters for doors/windows, P/L tile work in flooring at hall & Sanitary work in bathroom & toilet etc. (Deposit)

Estimate Cost :- Rs. 96,768/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

(4)

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Ruppes
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).in Sal Wood with in all leads, lifts and other incidental .The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the government.	0.21	Cubic metre			Per Cubic metre	
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately, all complete as per direction of Engineer-in-charge.Kiln seasoned selected planks of sheesham wood of 35 mm thick shutters with in all leads, lifts and other incidental .The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the government. Note:- Butt hinges and necessary screws shall be paid separately)	5.83	Square metre			Per Square metre	
3	Providing and fixing aluminium sliding door bolts of size 300x16 mm (Three hundred into sixteen millimetre), ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete . The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the Government.	2.00	Nos.			Each	
4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.						
(a)	Size 300x10 mm . (Three hundred in to ten millimetre)	6.00	Nos.			Each	
(b)	Size 200x10 mm (Two hundred in to ten millimetre)	16.00	Nos.			Each	
5	Providing and fixing aluminium handles 125 mm (One hundred twenty five millimetre), ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	10.00	Nos.			Each	
6	Providing and fixing White Vitreous China pedestal type water closet (European Type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved Municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid including carriage of materials all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	1.00	Nos.			Each	

7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal outer dia Pipes including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	15.00	Running metre				Running metre	
8	Making connection of G.I. distribution branch 25 to 40 mm nominal bore with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	Nos.				Per Square metre	
9	Providing and fixing C.P. brass bib cock 15 mm (fifteen Millimetres) nominal bore of approved quality conforming to IS:8931 as per the entire satisfaction and direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	2.00	Nos.				Each	
10	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety grammes) 15 mm (fifteen Millimetres) nominal bore. as per the entire satisfaction and direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3.00	Nos.				Each	
11	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	4.00	Nos.				Each	
12	Providing and fixing 15 mm (Fifteen millimetre) nominal bore with 30cm length unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	2.00	Nos.				Each	
13	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	29.34	Square metre				Per Square metre	
14	Providing and laying Vitrified tiles Size of Tile 600x600 mm (thickness to be specified by manufacturer), with water absorption 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	2.13	Square metre				Each	
							Total	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 99,124/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Name of Work :- OFC damages on D/Shala Yol Dadh Holta Chadhiyar Sandhole road 33/000 to 40/500
(S. W. :- 1.00 mtr. Span culvert at RD 37/610)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	12.30			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	9.82			Per Cubic metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.40			Per Cubic metre	
4	Providing concrete for plain/reinforced concrete in open foundations 1:1.5:3 (1 cement:1.5 :3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	171.02			Per Kilogram me	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.				Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : -OFC damages on D/Shala Yol Dadh Holtia Chadhiyar Sandhole road 33/000 to 40/500
(S. W. :- 1.00 mtr. Span culvert at RD 37/650)

Estimated Cost :- Rs. 98,307/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

Work No. (6)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	1.78	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	9.75	Cubic metre			Per Cubic metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.39	Cubic metres			Per Cubic metre	
4	Providing concrete for plain/reinforced concrete in open foundations 1:1.5:3 (1cement:1.5 :3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	168.97	Kilogram me			Per Kilogram me	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : R/D Link road from Dharman kandwari Speedu road Km. 0/000 to 5/000
(S. W. :- C/O 1.00 mtr. Span culvert at RD 3/850 ~~(MHP)~~)

Estimated Cost :- Rs. 98,891/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

Work No. (7)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.36 Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	0.84 Cubic metre			Per Cubic metre	
3	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	11.34 Cubic metre			Per cubic metre	
4	Providing and laying Reinforced cement concrete in 1:1.5:3 (one cement : one point five coarse sand : three graded crushed stone aggregate) 20 mm nominal size so as to obtain minimum crushing strength of R.C.C. grade M-25 (M-Twenty Five) and curing complete excluding cost of reinforcement for reinforced concrete work in foundations and plinth as per drawings and technical specifications Clauses 802,803,1202 and 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1.15 Cubic metres			Per Cubic metre	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.71 Cubic metres			Per Cubic metre.	
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	136.00 Kilogram me			Per Kilogram me	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampyy

20

SCHEDULE OF QUANTITY

Name of work:- Repair of Dhamamshala Yol Dadh Palampur road Km 15/00 to 27/00. (SH:- Repair of RCC Slab Culvert with apoxy grouting at Rd 19/400). D.C. Deposit

Name of Work:- Repair of Dharamshala Yol Dadh Palampur road Km 15/00 to 27/00. (SH:- Repair of RCC Slab Culvert with epoxy grouting at Rd 19/400). D.C. Deposit						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.			
			Time Limits			
			In Figures	In Word		Two Months
1	Providing and inserting nipples with approved fixing compound after drilling holes for grouting as per Technical specifications including subsequent cutting/removal and sealing of the hole as necessary of nipples after completion of grouting with Cement/Epoxy. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	100.00			Each	
2	Sealing of crack / porous concrete with Epoxy Grout by injection through nipples complete as per clause 2803.1. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	120.00			Per Kilogram	
3	Applying epoxy mortar over leached, honey combed and spalled concrete surface and exposed steel reinforcement complete as per Technical specification . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.54			Per square metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Repair of Dharamshala Vol Dadh Palampur road Km 15/00 to 27/00. (SH:- C/o unlined drain at various Rd's between Km 15/00 to 20/500). **D.C. Deposit**

Name of work:- Repair of Dhamshala Yo! Dadh Palampur road Km 15/00 to 27/00. (SH:- C/o unlined drain at various Rd's between Km 15/00 to 20/500). D.C. Deposit							Estimated cost Rs.	94860.00
							Earnest Money/ Rs.	1900.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1530.00			Per Running metre			
	Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur

DRAFT SCHEDULE OF QUANTITY

Name of work:- Repair of Rakh Bhont road Km 0/00 to 3/00. (SH:- Balance work of crate/ wall at Rd 1/240 to 1/252.50). D.C.
Deposit

DRAFT SCHEDULE OF QUANTITY						
Name of work:- Repair of Rakh Bhort road Km 0/00 to 3/00. (SH:- Balance work of crate/ wall at Rd 1/240 to 1/252.50). D.C. Deposit			Estimated cost Rs.		81200.00	
			Earnest Money Rs.		1700.00	
			Time Limits		Two Months	
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogram) each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In -Charge including carriage of materials within all leads and lifts and other incidental. The rate includes octroi, royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	27.34			Per cubic metre	

Executive Engineer,
Palampur Division
HP, PWD Palampur

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	4.99 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	10.29 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	5.00 Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.12 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deteterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.80 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete. Including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.95 Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (V) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00 Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	2.83 Cubic metre			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

name of Work :- Dharamshala Yol Dadh Palampur road 27/000 to 33/000
(S. W. :- Painting on Neugal Khad bridge (120.00 mtr. Span) at Rd 27/000 to 27/120 (OFC Deposit)

Estimated Cost :- Rs. 98,376-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Removing dry oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	34.00	Square metres			Per Square metre	
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	850.12	Square metres			Per Square metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/M of CHC at Gopalpur. (SH:- Shifting of water Tanks). Deposit

Sr. No.		Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
				Earnest Money Rs.			
				Time Limits			
				In Figures	In Word		Two Months
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	785.00			Per Kilogram		
2	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, 500 ltr capacity IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	2000.00			Per litre		
3	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS 15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m spacing Internal Exposed on walls PN 16 Pipe, 25mm OD (SDR-7.4). This includes testing of joints complete as per direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	20.00			Per Running metre		
Total							

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Kuthal alongwith Retaining wall near Sh. Navratru Ram Land Ward No.2 G.P. Darati. (Deposit 0.75 Lacs)

SCHEDULE OF QUANTITIES						
Name of work:- C/O Kuthal alongwith Retaining wall near Sh. Navratru Ram Land Ward No.2 G.P. Darati. (Deposit 0.75 Laos)				Estimated cost Rs.		74073.00
				Earnest Money Rs.		1500.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.76			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	16.20			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o road alongwith interlocking tiles from Industry area to Rana Basti ward No. 2 (SDP),(SH:- P/L interlocking tiles). **SDP Deposit 1.00 Lacs**

SCHEDULE OF QUANTITY							98974.00
Name of work:- C/o road alongwith interlocking tiles from Industry area to Rana Basi ward No. 2 (SDP),(SH :- P/L interlocking tiles). SDP Deposit 1.00 Lacs						Estimated cost Rs.	
						Earnest Money Rs.	2000.00
						Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	72.50			Per square metre		
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.98			Per cubic metre.		

Executive Engineer
 Palampur Division
 H.P. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- S/R of Nagri to Minimahesh via Bhasmehar Rakh Society road. (SH:- P/L interlocking tiles at Rd 3/675 to 3/697).
Deposit SDRF

Estimated cost Rs. 99902.00
 Earnest Money Rs. 2000.00

Sr. No.	Description of Item	Quantity	Time Limits		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.80			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.66			Per cubic metre.	
Total						

Executive Engineer,
 Palampur Division
 HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o First floor of Dhauladhar Mahila Mandal ward No. 1, Sukeri G.P. Drogna. (SH:- C/o Hall at 1st Floor).
VK/VNY 1.00 Lacs

Name of work:- C/o First floor of Dhanaudhar Mahila Mandal ward No. 1, Sukeri G.P. Drogna. (SH:- C/o Hall at 1st Floor).						
VK/VNY 1.00 Lacs						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.			
			Time Limits			
			In Figures	In Word		Two Months
1	Brick work with common burnt clay machine moulded perforated bricks With F.P.S.(non modular) bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.62			Per cubic metre	
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.19			Per cubic metre	
Total						

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pulli on Kuhl near Mool Raj Dhiman House ward No. 7. (SH:- C/o edge wall along with slab). **Deposit Rs. 75000/- only**

Name of work:- C/o Pullu on Kuthal near Mooi Raj Dhiman House ward No. 7, (SH:-C/o edge wall along with slab). Deposit Rs. 75000/- only							Estimated cost Rs.	73260.00
							Earnest Money Rs.	1500.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.92			Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depts including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	10.56			Per cubic metre.			
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.50			Per cubic metre.			
4	Supplying fitting and placing HYSD bar reinforcement in super structures in slab complete as per drawings and MORTH technical specifications clause 1600 and 2300, including cutting bending, binding and placing in position complete in all respect including the cost of binding wire upto all heights / depths or as per the direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.13			Per Metric Tonne			
Total								

Executive Engineer,
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/O R/wall to Protect the land of Sh. Krishan & Mohinder Ward No. 5. (Deposit VKVNY 1.00 Lacs)

Sr. No.						Estimated cost Rs.			Earnest Money Rs.			Two Months		
Description of item						Quantity	Rate		Unit	Amount	Time Limits		Amount	
							In Figures	In Word						
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.					11.52			Per cubic metre					
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement, five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.					21.60			Per cubic metre.					
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.					8.00			Each					
Total														


 Executive Engineer,
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path from Padra Chowk towards Harizan Basti ward No. 5. (SH:- P/L interlocking paver Blocks at Rd 0/00 to 0/085). **(Deposit VKVNY 1.00 Lacs)**

0/00 to 0/085). (Deposit VKVNY 1.00 Laes)						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.			
			Time Limits			
			In Figures	In Word		Two Months
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.00			Per square metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed/broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	2.55			Per cubic metre.	
Total						


 Executive Engineer
 Palampur Division
 H.P. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeppable road alongwith interlocking tiles from onkar chand house to Sh. Boni kumar house. (Deposit 1.00 Lacs)

Estimated cost Rs. 99244.00
 Earnest Money Rs. 2000.00
 Time Limits Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.45			Per square metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	0.84			Per cubic metre.	
	Total					

Executive Engineer,
 Palampur Division
 HP. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Completion Of Pucca Path from Latwala main road towards Smt. Indu Bala House. (Deposit 0.70 Lacs)

Estimated cost Rs.	67014.00
Earnest Money Rs.	1400.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling/ wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	12.77			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	6.36			Per cubic metre	
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	3.87			Per cubic metre	
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.58			Per square metre	
	Total					

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path from Jhulla Pul towards house of Sh. Amar Singh and others ward No. 4 village Jugehar. (SH:- P/L C.C. Pavement at Rd 0/00 to 0/097). (Deposit VKVNY 1.00 Laes)

Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	11.64			Per cubic metre	
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading, watering and rolling of binding materials moonum or earth etc. complete as per HP, PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	11.64			Per cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depts including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	17.46			Per cubic metre	
Total						

Executive Engineer,
 Palampur Division
 HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- S/R of Nagri to Manimahesh via Bhasmechar Rakh Society road. (SH:- P/L interlocking tiles at Rd 3/700 to 3/722).
Deposit SDRF

Name of work:- S/R of Nagri to Manimahesh via Bhasmechar Rakh Society road. (SH:- P/L interlocking tiles at Rd 3/700 to 3/722).						
Deposit SDRF			Estimated cost Rs.		99902.00	
			Earnest Money Rs.		2000.00	
Sr. No	Description of Item	Quantity	Rate		Time Limits	Two Months
			In Figures	In Word		Amount
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including cartage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.80			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including cartage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.66			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- C/o Retaining wall and drain on main road near the land of Ravi Kumar Parour Lahla Road. (Deposit VKV/NY 1.00 Lacs)

Estimated cost Rs.	98605.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.80			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	7.53			Per cubic metre.	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidentals complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	13.50			Per cubic metre.	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P V C, pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	5.00			Each	
	Total					

Executive Engineer
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path from Naag Marhi towards the house of Sh. Pratap Chand S/o Sh. Dharan Chand. (SH:- P/L C.C. Pavement and edge wall). **VKVNY Deposit 1.20 Lacs**

Estimated cost Rs.	99471.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.84			Per cubic metre	
2	Stone soling properly hand-packed filling intersices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	6.84			Per cubic metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.26			Per cubic metre.	
4	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	5.25			Per cubic metre.	
	Total					


 Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dharaman Kandwani Speru road extension road side Km. 0/00 to 0/073
(S. W. :- Hiring of JCB for removal of slip)

Estimated Cost :- Rs. 98,900/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of work for removal of slips.The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in -Charge including all leads and lifts.	86.00	Hours				
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Drafts Schedule of Quantity

Name of Work :- C/O link road from Rampur Rajehar Sarsawa via Kapen Neelkanth Bhadraina N.H. road
(S. W. :- P/L Interlocking Concrete block Pavement at RD 0/150 to 0/174 (NABARD))

Work No.

Estimated Cost :- Rs. 98,964/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

(29)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing Concrete for plain/reinforced concrete 1:2:4 (one cement: two sand: four crushed stone aggregate) Nominal mix, P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.08			Per Cubic metre	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	72.00			Per square metre	
					Total :-	

Executive Engineer
Palampur Division
H.P.W.D Palampur