

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"SHORT TERM NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **28-05-2025** up to 11:00 AM, and the same shall be opened on the same day at 11:30 AM, in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **27-05-2025** up to 4:00 P.M and the application for issue of tender form shall be received on **26-05-2025** up to 12:00 Noon.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	C/o Pucca Path alongwith interlocking Tiles from Mango tree to Late Sh. Bhuri Singh freedom fighter House. Under head (vkv/2024/958 (Deposit work). (S.H Providing and laying Interlocking Paver block tiles at Rd 0/165 to 0/191)	88863.00	1800.00	Two Months	350/-
2	Construction of link road from Manai Bharooplalhar road to Chaudhary Basti Jol upto Ramesh Chand House. (Deposit Work).(S.H:-Providing and laying Cement Concrete Pavement between km 0/076 to 0/110).	99916.00	2000.00	Two Months	350/-
3	Repair of workshop in Govt ITI Shahpur Distt Kangra (H.P.) (Deposit work). (S.H:- Providing and Laying water proofing treatment in workshop).	99781.00	2000.00	Two Months	350/-
4	C/o Pucca Path alongwith interlocking Tiles from Mango tree to Late Sh. Bhuri Singh freedom fighter House. Under head (vkv/2024/958 (Deposit work).(S.H: Providing and laying Interlocking Paver block tiles at Rd 0/195 to 0/213)	59930.00	1200.00	Two Months	350/-
5	Repair of workshop in Govt ITI Shahpur Distt Kangra (H.P.) (Deposit work). (S.H:- Fixing of RCC beam in workshop. P/F preprinted sheet and P/L water proofing treatment in workshop.)	99672.00	2000.00	Two Months	350/-
6	R.D Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)(S.H:-Restoration of broken berm and edges at Rd. 0/081 to 0/120 .	91237.00	1850.00	Two Months	350/-
7	C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work). (S.H:-Providing and Laying flooring work and Sanitary Installation etc.)	78940.00	1600.00	Two Months	350/-
8	Preparation of Detailed estimate for Building Estimate of Govt. Degree college at at Rirkmaar in tehsil darini.(S.H:-Preparation of detailed building estimate (Part-I)	99000.00	2000.00	One Months	350/-
9	C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work). (S.H:-Providing and Laying Tile work in flooring .	99683.00	2000.00	Two Months	350/-
10	Hydraulic data of 35mtrs span bridge over Banoi Khad at RD 0/300 on link road to Ruhru km 0/00 to 1/500 under NABARD. (S.H:- Prepartion of Hydraulic data).	58000.00	1200.00	One Months	350/-
11	R.D Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)(S.H:-Extension of berm and edges at Rd. 0/00 to 0/040 (LHS and RHS) & passing place of various Rd	88165.00	1800.00	Two Months	350/-
12	C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work). (SH:-Providing and fixing Aluminium Doors and window including glazing and P/L plaster work.	99919.00	2000.00	Two Months	350/-
13	C/o Pulli Near Joginder Singh House S/o Sh. Dharam Singh House (VKV/2022/2288. (Deposit Work).(S.H:-C/o 2 rows of HP Culvert at Rd 0/020 and both side Wing walls. (Part-I)	94220.00	1900.00	Two Months	350/-
14	C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work). SH:- Providing and fixing Aluminium Doors and window.	98874.00	2000.00	Two Months	350/-
15	C/o link Road Lowr Pandhu to upper Pandhu k 0/000 to 2/760 (S.H:- Preparation of Detailed Project Report)	74520.00	1500.00	Two Months	350/-
16	Hydraulic data of 40 mtrs span bridge over Gaj Khad at RD 0/300 on Balladi Mod to Balah km 0/00 to 1/500 under NABARD. (S.H:- Prepartion of Hydraulic data).	58000.00	1200.00	One Month	350/-
17	Hydraulic data of 50mtrs span bridge over Gaj Khad at RD 0/900 on link road to Balreh. (S.H:- Prepartion of Hydraulic data).	58000.00	1200.00	Two Months	350/-
18	Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work). (S.H:-Construction of Pushta for R/wall from RD 0/410 to 0/414.	99395.00	2000.00	Two Months	350/-

19	Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work). (S.H:-Construction of Pushta for R/wall from RD 0/415 to 0/418.	99231.00	2000.00	Two Months	350/-
20	C/o Pulli Near Joginder Singh House S/o Sh. Dharam Singh House (VKV/2022/2288. (Deposit Work).(S.H:-C/o 2 rows of HP Culvert at Rd 0/020 and both side Wing walls. (Part-II)	96367.00	1950.00	Two Months	350/-
21	Construction of Pucca path from Karam chand house to Suman House Shahpur (SDP/2022/154) (Deposit work).(S.H:-Construction of Drain Cover on the existing drain from RD 0/005 to 0/012.30 (Part-I)	99923.00	2000.00	Two Months	350/-
22	Maintance of Link road Shahpur Kiari Chatrer Road Km 0/00 to 8/955 in Tehsil Shahpur, Distt. Kangra (HP) .(Under S.C.D.P).(S.H:-C/o Approaches for extension of HP culvert at RD 7/319.50 to 7/328.50.).	97635.00	2000.00	Two Months	350/-
23	Construction of Pucca path from Karam chand house to Suman House Shahpur (SDP/2022/154) (Deposit work).(S.H:-Construction of Drain Cover on the existing drain from RD 0/015 to 0/022.35 (Part-II)	99737.00	2000.00	Two Months	350/-
24	C/o Additional fund to stage Chinj Mela Ground Dramman (Deposit Work).(S.H:-Providing and Fixing Prepainted sheet for roofing and PCC 1:2:4).	98433.00	2000.00	Two Months	350/-
25	R.D Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur. Distt. Kangra (HP) Under S.C.S.P.(S.H:-Restoration of broken berm and edges at Rd. 0/041 to 0/080 .	90490.00	1800.00	Two Months	350/-
26	Construction of link road from Manai Bharooplaha road to Chaudhary Basti Jol upto Ramesh Chand House. (Deposit Work).(S.H:-Providing and laying Cement Concrete Pavement between km 0/043 to 0/076).	99238.00	2000.00	Two Months	350/-
27	C/o Additional fund to stage Chinj Mela Ground Dramman (Deposit Work).(S.H:-Providing and Fixing Truss for roofing and Prepainted sheet.)	99619.00	2000.00	Two Months	350/-
28	Maintenance of link road Palwala to Lajot km 0/00 to 0/900 (S.C.D.P) (SH:- C/o U-Shap drain at RD 0/431 to 0/454)	89786.00	1800.00	Two Months	350/-
29	C/o Harnera Mohad Chattari road km 0/00 to 9/100 (SH:- C/o of Retaining wall km 3/884 to 3/893.30)	97791.00	2000.00	Two Months	350/-
30	Maintenance of link road Palwala to Lajot km 0/00 to 0/900 (S.C.D.P) (SH:- C/o U-Shap drain at RD 0/400 to 0/430)	85233.00	1800.00	Two Months	350/-
31	Maintenance of link road Palwala to Lajot km 0/00 to 0/900 (S.C.D.P) (SH:- C/o U-Shap drain at RD 0/375 to 0/399)	90238.00	1800.00	Two Months	350/-
32	Annual repair and maintenance of various roads under HPPWD sub division Gaggal (SH:- Painting and writing lettering, figures and kilometer stone ect.)	99201.00	2000.00	Two Months	350/-
33	Annual repair and maintenance of various roads under HPPWD sub division Shahpur (SH:- Painting and writing lettering, figures and kilometer stone ect.)	99201.00	2000.00	Two Months	350/-


Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

No.PWD/SD/Tender/NIT/2025-26/-
Copy to following for information and necessary action:-

1. The Superintending Engineer, 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board


 Executive Engineer,
 Shahpur Division,
 HP.PWD Shahpur.
 (on behalf of Governor of Himachal Pradesh)
 Dated: 20/05/25

Executive Engineer,
 Shahpur Division,
 HP.PWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 88863.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Pucca Path alongwith interlocking Tiles from Mango tree to Late Sh. Bhuri Singh freedom fighter House. Under head (vkv/2024/958 (Deposit work)).

SUB-HEAD :- Providing and laying Interlocking Paver block tiles at Rd 0/165 to 0/191.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.36 Cubic metres	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	1710.00
2	Providing and laying 60 mm (Sixty millimetre) thick Interlocking M-50 (M-Fifty) grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	72.80 Squire metres	1100.00	Rupees One Thousand One Hundred Only	Per squire metre	80080.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in sub structure grade M-20 (M-Twenty) design mix with cement contents not less than 330 kg (Three hundred thirty killogram) per cubic metre with 40mm (Forty millimetres) nominal size graded crushed stone aggretgate in abutments etcetra as per drawings and MORD technical specifications section 800, 900 and 1200 including the cost of form work and curing complete including carriage of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-In-Charge. The rate is including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	1.15 Cubic metres	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	7073.00
TOTAL :-						88863.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 99916.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of link road from Manai Bharooplahar road to Chaudhary Basti Jol upto Ramesh Chand House. (Deposit Work).

SUB-HEAD :- Providing and laying Cement Concrete Pavement between km 0/076 to 0/110).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.35 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2223.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	8.44 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	7174.00

2	<p>Supply and laying of plain concrete pavement, thickness as per design, over a prepared sub base, with 43 mm coarse sand and gravel, 150mm (1) and per figure 1501 using 125 (Grade), (design mix) concrete, laying and fixing of fine aggregate conforming to IS 2083, maximum size of coarse aggregate not exceeding 25 mm (one and five millimetres), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.</p>	12.66 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	90519.00
TOTAL :-						99916.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur



SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99781.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Repair of workshop in Govt ITI Shahpur Distt Kangra (H.P.) (Deposit work).

SUB-HEAD :- Providing and Laying water proofing treatment in workshop.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing water proofing treatment shall be done in two coats apply First coat of Dr. Fixit Torch SHIELD (P - 3160- 3mm) to the clean and saturated surface maintaining a coverage 0.60 sqm (Zero point six zero square meter) per kilogram to achieve 1mm (one millimeter) thickness this coating shall also be executed up to 300mm vertically. The 2nd coat shall be applied in opposite direction after 4 to 6 (Four to six) hours of application of 1st coat then sprinkle sand on top surface of applied Dr. Fixit Fast flex white still tacky and the second coat. Then apply cement mortar 1:4 (one cement ist four sand) and mixed with Pidiproof LW at the rate 200ml (two hundred millimetre) per 50 (Fifty kilogram) of cement over the floor with suitable gradient towards drain water pipe while the second coat of Dr. Fixit is still tacky.complete as per approved drawing, design including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	212.30 Squire metre	470.00	Rupees Four Hundred Seventy Only	Per squire metre	99781.00
TOTAL :-						99781.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

4

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 59930.00
 EARNEST MONEY:- ₹ 1200.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Pucca Path alongwith interlocking Tiles from Mango tree to Late Sh. Bhuri Singh freedom fighter House. Under head (vkv/2024/958 (Deposit work)).

SUB-HEAD :- Providing and laying Interlocking Paver block tiles at Rd 0/195 to 0/213.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 60 mm (Sixty millimetre) thick Interlocking M-50 (M-Fifty) grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	50.40 Squire metres	1100.00	Rupees One Thousand One Hundred Only	Per squire metre	55440.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in sub structure grade M-20 (M-Twenty) design mix with cement contents not less than 330 kg (Three hundred thirty killogram) per cubic metre with 40mm (Forty millimetres) nominal size graded crushed stone aggregate in abutments etcetra as per drawings and MORD technical specifications section 800, 900 and 1200 including the cost of form work and curing complete including carriage of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-In-Charge. The rate is including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	0.73 Cubic metres	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	4490.00
TOTAL :-						59930.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

5

SCHEDULE OF QUANTITY


ESTIMATED COST:- ₹ 99672.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Repair of workshop in Govt ITI Shahpur Distt Kangra (H.P.) (Deposit work).

SUB-HEAD :- Fixing of RCC beam in workshop, P/F prepainted sheet and P/L water proofing treatment in workshop.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Fixing in position of RCC beam mechanical/ Manual means, upto any height i/c including carriage of matereials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.(Lump Sump Rate)	1 Number	16500.00	Rupees Sixteen Thousand Five Hundred Only	Each	16500.00
2	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and; placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	33.00 Kilogram	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per killograme	3546.00
3	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	35.00 Squire metre	1450.50	Rupees One Thousand Four Hundred Fifty And Paise Fifty Only	Per squire metre	50768.00

4	Providing water proofing treatment shall be done in two coats apply First coat of Dr. Fixit Torch SHIELD (P - 3160- 3mm) to the clean and saturated surface maintaining a coverage 0.60 sqm (Zero point six zero square meter) per kilogram to achieve 1mm (one millimeter) thickness this coating shall also be executed up to 300mm vertically. The 2nd coat shall be applied in opposite direction after 4 to 6 (Four to six) hours of application of 1st coat then sprinkle sand on top surface of applied Dr. Fixit Fast flex white still tacky and the second coat. Then apply cement mortar 1:4 (one cement ist four sand) and mixed with Pidiproof LW at the rate 200ml (two hundred millimetre) per 50 (Fifty kilogram) of cement over the floor with suitable gradient towards drain water pipe while the second coat of Dr. Fixit is still tacky.complete as per approved drawing, design including carriage of materials within all leads, lifts and other incidental, and as per directions of	61.40 Squire metre	470.00	Rupees Four Hundred Seventy Only	Per squire metre	28858.00
TOTAL :-						99672.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(6)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹

91237.00

EARNEST MONEY: - ₹

1850.00


TIME LIMIT :

Two Months

NAME OF WORK :- R.D Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)SUB-HEAD :- Restoration of broken berm and edges at. 0/081 to 0/120

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.67 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3758.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.35 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	16080.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	5.33 Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	33313.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ecttera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.95 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	38086.00
TOTAL :-						91237.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD, Shahpur

67

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 78940.00
EARNEST MONEY: - ₹ 1600.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work).


SUB-HEAD :- Providing and Laying flooring work and Sanitary Installation etc.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing hand rail of 50 mm dia SST stainless steel pipe handrail fixed with 35 mm dia sst pipe as per detail in combination of 35 mm dia and 15 /20 mm sst baluster complete in all respect by welding etc. to steel ladder railing, balcony railing, staircase railing as per specification, drawing, design and direction by the Engineer in charge. as per approved drawing, design including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	40.88	525.00	Rupees Five Hundred Twenty Five Only	Per Killogram	21462.00
2	Providing and fixing polythelene aluminum polythelene (PE- AL-PE) composite pressure pipe U.V. stabilized with carbon block confirming to I.S. 15450-2004 of Kitec for water supply including clamps at appropriate spacing, cutting fixing and making good the walls etcetera; but excluding the cost of fittings (Internal work), including filling the joints with approved adhesive complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 1620 (20mm) twenty millimeter diameter pipe O.D. pipe	40.00	360.00	Rupees Three Hundred Sixty Only	Per Running metre	14400.00
3	Providing and fixing on wall face 150mm (One hundred fifty milimetres) diametres P.V.C. rain water pipes of working pressure 4.6kg (four / six kilogramme) per square centimetre of finolex / Relience / vectus/ prince pipe for rain water pipe fixed with approved adhesive including filling the joints complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	20.00	235.60	Rupees Two Hundred Thirty Five And Paise Sixty Only	Per Running metre	4712.00

4	Providing and fixing 110 x 75mm (One hundred ten into Ninety milimetres) P.V.C. I.S.I. marked floor trap of Finolex / Supreme / Prince ISI marked (confirming to BIS-14735-99) of self cleaning design including with approved adhesive cost of cutting and making good walls and floors complete, within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	550.00	Rupees Five Hundred Fifty Only	Each	550.00
5	Providing and fixing white vitreous china pedestal type water closet (European type) No 20087 (S - 10) Size 57 X 35 X 39 cm (fifty seven into thirty five into thirty nine centimetres) with seat and lid, 10 (ten) litre low level white vitreous china flushing cistern (sleek Plus) Hindware , Cera ,Jaquar of star white / Snow white shade and as shown in the drawing / as per details & C.P. flush bend with fittings & C.I. brackets, 40 mm (forty milimetres) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and	1.00	7210.00	Rupees Seven Thousand Two Hundred Ten Only	Each	7210.00
6	Providing and fixing wash basin White Vitreous China Flat back wash basin Garnet no 10010 size 550x 400 mm (five hundred fifty into four hundred) (Under counter Basin) Hindware , Cera ,Jaquar of star white / Snow white shade and as shown in the drawing / as per details with single 15 mm (Fifteen milimetres) C.P. brass pillar tap with C.I. brackets, 15 mm (fifteen milimetres) C.P. brass pillar taps, 32 mm (Thrity two milimetres) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Each	5450.00
7	Providing and fixing 32mm dia (Thirty two milimetres) diametres M.I. union for wash basin or sink complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	180.00	Rupees One Hundred Eighty Only	Each	180.00
8	Providing and fixing stainless steel kitchen sink size 510 x1040 mm (Five hundred ten into One Thousand forty millimetre) with bowl depth 250 mm (two hundred fifty millimetre) of AMC unik / diamond approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted including cutting holes and making good the same but excluding fitting within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	3606.40	Rupees Three Thousand Six Hundred Six And Paise Forty Only	Each	3606.00
9	Providing and fixing 100mm (One hundred milimetres) diametres C.P. (Chromium plated) Grating ISI Marked IS No. 8934 (Eight thousand nine hundred thirty four) of Continental series of Jaquar / Classik series of Hindware/ Floral series of Cera & Hindon series of Jal for gully floor or Nahni trap as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	120.00	Rupees One Hundred Twenty Only	Each	120.00

10	Providing and fixing flat back 600x450mm (Six hundred into Four hundred fifty millimetres) beveled edge mirror of Continental series of Jaquar / Classik series of Hindware/ Floral series of Cera & Hindon series of Jal of superior glass of approved quality complete with mounted on 6mm (Six millimetres) thick A.C. asbestos cement sheet or ply wood sheet and fixed to wooden plugs with C.P. (Chromium plated) brass screws and washers complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	950.00	Rupees Nine Hundred Fifty Only	Each	950.00
11	Providing and fixing 600mmx20mm (Six hundred millimetre into Twenty millimetres) C.P. (Chromium plated) ISI Marked IS No. 8934 (Eight thousand nine hundred thirty four) of Continental series of Jaquar / Classik series of Hindware/ Floral series of Cera & Hindon series of Jal brass Towel rail with C.P. (Chromium plated) brass brackets fixed to wooden plugs with C.P. (Chromium plated) brass screws complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	390.50	Rupees Three Hundred Ninety And Paise Fifty Only	Each	391.00
12	Providing and fixing 600mmx120mmx5mm (Six hundred millimetres into One hundred twenty into five millimetres) glass shelf of ISI No. 8934 (Eight thousand nine hundred thirty four) of Continental series of Jaquar / Classik series of Hindware/ Floral series of Cera & Hindon series of Jal make brackets and guard rail fixed to wooden plugs with C.P. (Chromium plated) brass screws complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	786.70	Rupees Seven Hundred Eighty Six And Paise Seventy Only	Each	787.00
13	Providing and fixing 8mm dia C.P. jet spray of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal of approved quality and colour with one metre tube within all leads, lifts of materials and other incidentals and as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	490.00	Rupees Four Hundred Ninety Only	Each	490.00
14	Providing and fixing 15mm dia (Fifteen millimetres) diametres nominal bore chromium plated brass (ISI marked No. 8934) (Eight thousand nine hundred thirty four) bib tap (superior or heavy type) of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00	1100.00	Rupees One Thousand One Hundred Only	Each	3300.00
15	Providing and fixing 15mm dia (Fifteen millimetres) diametres C.P. (chromium plated) brass stop cock Conforming ISI Marked IS No. 8934 (Eight thousand nine hundred thirty four) of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	950.00	Rupees Nine Hundred Fifty Only	Each	1900.00

16	Providing and fixing 15mm (Fifteen millimetres) diametres C.P.brass angle valve without nuts of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal as per approved drawing and design directed by the Engineer-in-Charge within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	921.00	Rupees Nine Hundred Twenty One Only	Each	1842.00
17	Providing and fixing 15mm (Fifteen millimetres) nominal bore C.P. brass full valve of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal within all leads, lifts of materials and other incidentals and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
18	Providing and fixing 15mm (Fifteen millimetres) nominal bore PVC (polyvinyl chloride) connection pipe with brass union 30/ 45cm (Thirty or Forty five Centimetres) length, of Finolex, Reliance, Vectus complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	120.00	Rupees One Hundred Twenty Only	Each	240.00
19	Providing and placing water tank make P.V.C. SINTEX three layer having capacity of 1000 (One thousand) liters each, tank with necessary fittings including over flow pipe, scour pipe etcetera and pads required for in let and out let ball valve with cover and locking arrangements complete in all respect within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	10500.00	Rupees Ten Thousand Five Hundred Only	Each	10500.00
TOTAL :-						78940.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HRPWD Shahpur

Schedule of quantity

Name of work :- Preparation of Detailed estimate for Building Estimate of govt Degree college At Rirkmar in Thehsil Darini.	Estimated cost	99000.00
	Earnest money	2000.00
	Time limit	One Month

SUB-HEAD:-Preparation of detailed building estimate .(Part-I)

Sr. No.	Description of Items	Quantity	Rates		UNIT	Amount
			In figure	In words		
1	2	3	4		5	6
	Preparation of detailed estimate to be fair out after approval from the circle office, chief office preparation of approved copies of detailed estimate along with relevent working drawings (Two sets of estimate complete) and soft copies in the form of pan drive . If any correction / amendment is desired by the Head office the same may be corrected as per direction of Engineer-in-charge including carraige of materials of materials within all leads , lifts and other incidental.The rate is inculding octroi ,royalty,Malkana ,toll tax,sale tax or any type of taxes imposed by the Government.	1.00	99,000.00	Rupees one Ninety Nine thousand only	Per job	99,000.00
GRAND TOTAL						99,000.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

137
EXECUTIVE ENGINEER
DIVISION SHAHPUR
HPPWD SHAHPUR

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99683.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work).

SUB-HEAD :- Providing and Laying Tile work in flooring .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simpolo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	47.86	1425.00	Rupees One Thousand Four Hundred Twenty Five Only	Per Squire Metre	68201.00
2	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simpolo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 12 mm (twevle millimetres) thick cement mortar 1:3 (one cement isto three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.66	1430.00	Rupees One Thousand Four Hundred Thirty Only	Per Squire Metre	6664.00
3	Providing and fixing 25mm (twenty fivemillimeters) thick Kota stone of 55X55cm size of rough side same flooring of approved shade as per detail slab in flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	13.67	1450.10	Rupees One Thousand Four Hundred Fifty And Paise Ten Only	Per Squire Metre	19823.00

4	Providing and fixing 25mm (twenty fivemillimeters) thick Kota stone of 55X55cm size of rough side same flooring of approved shade as per detail slab in skirting over 12 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 3 (1 cement : 3 coarse sand) complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	2.70	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Per Squire Metre	4995.00
TOTAL :-						99683.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

(10)

SCHEDULE OF QUANTITY

NAME OF WORK :-HYDRAULIC DATA OF 35 MTR SPAN BRIDGE OVER BANOI KHAD AT RD 0/300 ON LINK ROAD RUHRU TO NARGHOTA KM 0/00 TO 1/500.UNDER NABARD

ESTIMATED COST:-

58,000.00

EARNEST MONEY:-


1,200.00

TIME LIMIT :-

ONE MONTH

SUB HEAD:- PREPARATION OF HYDRAULIC DATA

Sr. No.	Description of Items	NO./QTY./JOB	Unit	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES
1	2	3	4	5	6	7
1	Preparation of hydraulic data complete in all respect in manuscript form and submission of the same in higher office for approval. if any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer-in-charge and higher office complete in all respect, after approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies and payment shall be made after the approval of the same by the higher office. the rate shall be inclusive of all taxes imposed by the government.	1.000	PER JOB	58,000.00	RUPEES FIFTY EIGHT THOUSAND ONLY	58,000.00
				TOTAL		58,000.00
	QUOTED RATE IN FIGURE (%)	AMOUNT TO BE QUOTED BY THE CONT. IN FIGURES				
	QUOTED RATE IN WORDS (%)	AMOUNT TO BE QUOTED BY THE CONT. IN WORDS				


EXECUTIVE ENGINEER
DIVISION SHAHPUR
HPPWD SHAHPUR

SCHEDULE OF QUANTITY

NAME OF WORK :- C/o Link road to village Runehar khad (Nared) KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)
SUB-HEAD :- Extension of Berm at Rd. 0/00 to 0/040 (LHS and RHS) & passing place of various Rds.

ESTIMATED COST:- ₹ 88165.00
EARNEST MONEY:- ₹ 1800.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.69 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3803.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.36 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	16128.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	4.92 Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	30750.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.93 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	37976.00
TOTAL :-						88166.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

73-7
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 99919.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work).

SUB-HEAD :- Providing and fixing Aluminium Doors and window including glazing and P/L plaster work.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing coloured aluminium shutter work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government. ge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government	141.82	510.10	Rupees Five Hundred Ten And Paise Ten Only	Per Killograme	72342.00
2	Second class half brick work using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:4 (one cement :four sand) within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.19	850.00	Rupees Eight Hundred Fifty Only	Per Squire Metre	5262.00
3	15mm (Fifteen milimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty milimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.19	254.80	Rupees Two Hundred Fifty Four And Paise Eighty Only	Per Squire Metre	1577.00

4	15mm (Fifteen millimetres) thick cement plaster in single coat on fair side of brick/concrete/ stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.10	240.00	Rupees Two Hundred Forty Only	Per Squire Metre	744.00
5	Providing and fixing 35mm (Thirty five millimetres) thick factory made flush door shutters both side commercial i.e non-decorative (Phenol bonded termite resistant and boiling water proof, core of black-board construction with frame of first class hard wood and well matched commercial three ply veneer with vertical grains of cross bands and face veneer on both faces of flush shutter ISI marked IS No-2202 of Century ply Board/Kit ply, Green ply and finished with 3mm th. plastic sheet from inside, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.00	3250.50	Rupees Three Thousand Two Hundred Fifty And Paise Fifty Only	Per Squire Metre	6501.00
6	Providing and fixing Fly proof shutters for doors, windows and clerestory windows stainless steel grade 304 with M.S. flat 15X3mm (fifteen into three millimetre) wire gauge with 0.5 mm dia (zero decimal five millimetre) diametre wire and 1.4mm (one decimal four millimetre) wide aperture on both sides complete including carriage of material within all leads, lifts of materials and other incidentals. as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	7.41	750.00	Rupees Seven Hundred Fifty Only	Per Squire Metre	5558.00
7	Providing and fixing glazing glass panes of 5 mm (Five millimetres) thickness (weight not less than 12.50kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gastet etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.90	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Squire Metre	7935.00
TOTAL :-						99919.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HRPWD Shahpur



13

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 94220.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Pulli Near Joginder Singh House S/o Sh. Dharam Singh House (VKV/2022/2288. (Deposit Work).

SUB-HEAD :- C/o 2 rows of HP Culvert at Rd 0/020 and both side Wing walls. (Part-I)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.12 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	11592.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.19 Cubic metres	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	10403.00

3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	13.50	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	72225.00
TOTAL :-						94220.00
(Amount to be quoted by the contractor in Figure)						
Quated Rate in Figure (%)						
(Amount to be quoted by the contractor in words)						
Quated Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98874.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months


NAME OF WORK :- C/o of Balance work OF Community Bhawan Baag in G.P Sehwan Shahpur Distt Kangra (H.P). (Deposit work).


SUB-HEAD :- Providing and fixing Aluminium Doors and window.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing coloured aluminium shutter work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government. ge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government	150.40	508.30	Rupees Five Hundred Eight And Paise Thirty Only	Per Killograme	76448.00
2	Providing and fixing 12 mm (twelve millimetre) thick phenol bonded (both Side) prelaminated BWP Grade particle board in matt finish flat pressed three layer or graded wood particle board conforming to IS: 12823 of Action Tesa / Greenlam / Merinolam / Kitlam / Vista approved shade Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetra complete as per architectural drawings and directions of Engineer- in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side including carriage og material within all leads, lifts and other incidentals, as per approved drawing, design, specifications, specification and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.00	1050.00	Rupees One Thousand Fifty Only	Per Squire Metre	5250.00
3	Providing and fixing aluminium sliding door bolts , (300 x 16 mm) ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00


4	Providing and fixing aluminium tower bolts, (200 x 10 mm) ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.00	92.50	Rupees Ninety Two And Paise Fifty Only	Each	555.00
5	Providing and fixing aluminium tower bolts, (150 x 10 mm) ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	28.00	78.10	Rupees Seventy Eight And Paise Ten Only	Each	2187.00
6	Providing and fixing aluminium handle 125 mm (One hundred twenty five millimetre) ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	12.00	73.10	Rupees Seventy Three And Paise Ten Only	Each	877.00
7	Providing and fixing aluminium handle 100 mm (One hundred millimetre) ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	30.00	66.00	Rupees Sixty Six Only	Each	1980.00
8	Providing and fixing 250 mm (Two hundred fifty millimetre) size aluminium hooks and eyes complete in all respect , within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	28.00	55.00	Rupees Fifty Five Only	Each	1540.00
9	Providing and fixing hydraulic door closer tubular type aliminium section body transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.00	1050.00	Rupees One Thousand Fifty Only	Each	3150.00
10	Providing and fixing aluminium hanging floor door stopper, Twin rubber stopper ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.00	65.40	Rupees Sixty Five And Paise Forty Only	Each	589.00

11	Providing and fixing Glazing with frosted glass panes 4mm (Four milimetre) thickness glass panes (weight not less than 10.00kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gastet etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.14	1310.50	Rupees One Thousand Three Hundred Ten And Paise Fifty Only	Per Squire Metre	183.00
12	Providing and fixing glazing glass panes of 5 mm (Five milimetres) thickness (weight not less than 12.50kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gastet etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.10	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Squire Metre	4715.00
TOTAL :-						98874.00
		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Figure (%)						
		(Amount to be quoted by the contractor in words)				
Quoted Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


15

DNIT						
NAME OF WORK:-C/O LINK ROAD LOWER PADHU TO UPPER PANDHU 0/00TO 2/760.					ESTIMATED COST:-	74,520.00
					EARNEST MONEY:-	1,500.00
					TIME LIMIT :-	ONE MONTHS
SUB HEAD : PREPARATION OF DETAILED PROJECT REPORT						
SR. NO.	DESCRIPTION OF ITEMS	NO./ QTY./ JOB	UNIT	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES IN RS.
1	2	3	4	5	6	7
1	PREPARATION OF DETAILED PROJECT REPORT AND DRAWING COMPLETE IN ALL RESPECT IN MANUSCRIPT FROM AND SUBMISSION OF THE SAME TO HIGHER OFFICE FOR APPROVAL. IF ANY CORRECTION / AMENDMENT HAS DESIRED BY THE HEAD OFFICE. THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY THE ENGINEER - IN - CHARGE COMPLETE IN ALL RESPECT. AFTER APPROVAL, THE SAME SHOULD BE SUBMITTED IN FIVE NOS. SET OF FAIR COPY ALONGWITH 03 SET OF DRAWINGS (MANUSCRIPT INCLUDED). THE PAYMENT EXCLUDES ANY KIND OF SOIL INVESTIGATIONS AND SHALL BE MADE AS PER ACTUAL LENGTH OF ROAD.	2.760	Kms	27,000	TWENTY SEVEN THOUSDAND ONLY	74,520.00
a	TOPOGRAPHY SURVEY BY DIGITAL TOTAL STATION / DUAL FREQUENCY DGPS WITH TWO SECOND ACCURACY, SHOWING ALL OFFSETS SUCH AS TREES, CULVERTS, BRIDGE, ELECTRIC POLES, HAND PUMP SCHOOLS, HABITANTS VILLAGES ETC.					
b	DRAW CROSS SECTION AT 15 M (FIFTEEN METER) INTERVALS, L- SECTION & CALCULATE THE QUANTITY OF EARTH WORK IN STANDARD FORMAT OF AUTO CAD SHOWING ALL LAYERS OF PAVEMENT COMPONENTS.					
c	PREPARATION OF SURVEY PLAN SHOWING ALL PROVISION AS PER HPPWD SPECIFICATION.					
d	PREPARATION OF SURVEY PLAN SHOWING ALL EXISTING PROVISIONS AND PREPARATION OF DETAILED PROJECT REPORT AS PER HPPWD SPECIFICATION.					
					TOTAL	74,520.00
Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)		
Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)		


 EXECUTIVE ENGINEER
 SHAHPUR DIVISION
 HPPWD SHAHPUR


SCHEDULE OF QUANTITY

NAME OF WORK :-HYDRAULIC DATA OF 40 MTR SPAN BRIDGE OVER GAJ KHAD AT RD 0/300 ON BALLADI MOD TO BALAH KM 0/00 TO 1/500.UNDER NABARD

ESTIMATED COST:-	58,000.00
EARNEST MONEY:-	1,200.00
TIME LIMIT :-	ONE MONTHS

SUB HEAD:- PREPARATION OF HYDRAULIC DATA

Sr. No.	Description of Items	NO./QTY./JOB	Unit	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES
1	2	3	4	5	6	7
1	Preparation of hydraulic data complete in all respect in manuscript form and submission of the same in higher office for approval. if any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer-in-charge and higher office complete in all respect, after approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies and payment shall be made after the approval of the same by the higher office. the rate shall be inclusive of all taxes imposed by the government.	1.000	PER JOB	58,000.00	RUPEES FIFTY EIGHT THOUSAND ONLY	58,000.00
				TOTAL		58,000.00
	QUOTED RATE IN FIGURE (%)	AMOUNT TO BE QUOTED BY THE CONT. IN FIGURES				
	QUOTED RATE IN WORDS (%)	AMOUNT TO BE QUOTED BY THE CONT. IN WORDS				


EXECUTIVE ENGINEER
DIVISION SHAHPUR
HPPWD SHAHPUR

SCHEDULE OF QUANTITY

NAME OF WORK :-HYDRAULIC DATA OF 50 MTR SPAN BRIDGE OVER GAJ KHAD AT RD 0/900 ON
LINK ROAD VILLAGE BALREH.

ESTIMATED COST:-

58,000.00

EARNEST MONEY:-

1,200.00

TIME LIMIT :-

ONE MONTHS

SUB HEAD:- PREPARATION OF HYDRAULIC DATA

Sr. No.	Description of Items	NO./QTY./J OB	Unit	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES
1	2	3	4	5	6	7
1	Preparation of hydraulic data complete in all respect in manuscript form and submission of the same in higher office for approval. if any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer-in-charge and higher office complete in all respect, after approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies and payment shall be made after the approval of the same by the higher office. the rate shall be inclusive of all taxes imposed by the government.	1.000	PER JOB	58,000.00	RUPEES FIFTY EIGHT THOUSAND ONLY	58,000.00
				TOTAL		58,000.00
	QUOTED RATE IN FIGURE (%)	AMOUNT TO BE QUOTED BY THE CONT. IN FIGURES				
	QUOTED RATE IN WORDS (%)	AMOUNT TO BE QUOTED BY THE CONT. IN WORDS				


EXECUTIVE ENGINEER
DIVISION SHAHPUR
HPPWD SHAHPUR

SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 99395.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work)
SUB-HEAD :- Construction of Pushta for R/wall from RD 0/410 to 0/414.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.09 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2132.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.18 Cubic metre	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	97263.00
TOTAL :-						99395.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 99231.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work)

SUB-HEAD :- Construction of Pushta for R/wall from RD 0/418 to 0/418.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.08 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2128.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.15 Cubic metre	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	97103.00
TOTAL :-						99231.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

43-1
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 96367.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Pulli Near Joginder Singh House S/o Sh. Dharam Singh House (VKV/2022/2288. (Deposit Work).

SUB-HEAD :- C/o 2 rows of HP Culvert at Rd 0/020 and both side Wing walls. (Part-II)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.87 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5555.00
2	Providing and laying (to level or slope) 900mm dia (nine hundred fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102 and as per direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.00 Running metre	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per running metre	36500.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.65 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6503.00

4	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall,/ Breast wall etcetra including cost of form work and curing,complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.63 Cubic metres	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	45709.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						96367.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST:- ₹ 99923.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Pucca path from Karam chand house to Suman House Shahpur (SDP/2022/154) (Deposit work).

SUB-HEAD :- Construction of Drain Cover on the existing drain from RD 0/005 to 0/012.30 (Part-1)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.84 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2044.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.01 Cubic metre	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	37714.00
3	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings as per Architectural drawing and the like within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.98 Square metres	242.50	Rupees Two Hundred Forty Two And Paise Fifty Only	Per Square metres	4603.00

4	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.80 Cubic metre	6750.00	Rupees Six Thousand Seven Hundred Fifty Only	Per cubic metre	25650.00
5	Providing Tor steel reinforcement of Sail / Tisco /Tata for reinforced cement concrete work including bending, binding, straighting, cutting and placing in position complete including cost of binding wires complete for all floors within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	303.68 Kilo gram	98.50	Rupees Ninety Eight And Paise Fifty Only	Per kilogramme	29912.00
TOTAL :-						99923.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(22) (23.1)

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 97635.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Maintance of Link road Shahpur Kiari Chatrer Road Km 0/00 to 8/955 in Tehsil Shahpur, Distt. Kangra (HP) . (Under S.C.D.P).

SUB-HEAD :- C/o Approaches for extension of HP culvert at RD 7/319.50 to 7/328.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.22 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4627.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	21.06 Cubic metres	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	90558.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2450.00
TOTAL :-						97635.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99737.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Pucca path from Karam chand house to Suman House Shahpur (SDP/2022/154) (Deposit work).

SUB-HEAD :- Construction of Drain Cover on the existing drain from RD 0/015 to 0/022.35 (Part-II)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.88 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2058.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.90 Cubic metre	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	37122.00
3	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings as per Architectural drawing and the like within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.11 Square metres	242.50	Rupees Two Hundred Forty Two And Paise Fifty Only	Per Square metres	4634.00

4	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.75 Cubic metre	6750.00	Rupees Six Thousand Seven Hundred Fifty Only	Per cubic metre	25313.00
5	Providing Tor steel reinforcement of Sail / Tisco /Tata for reinforced cement concrete work including bending, binding, straighting, cutting and placing in position complete including cost of binding wires complete for all floors within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	310.76 Kilo gram	98.50	Rupees Ninety Eight And Paise Fifty Only	Per kilogram	30610.00
TOTAL :-						99737.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

134
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98433.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Additional fund to stage Chinj Mela Ground Dramman (Deposit Work).

SUB-HEAD :- Providing and Fixing Prepainted sheet for roofing and PCC 1:2:4).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.22 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per Cubic metres	427.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square milimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.12 Cubic metres	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metres	7672.00

3	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted insulated steel sheet sand - wich puf roofing , of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	7688 Square metres	1175.00	Rupees One Thousand One Hundred Seventy Five Only	Per square metre	90334.00
TOTAL :-						98433.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

134
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST:- ₹ 90490.00
 EARNEST MONEY:- ₹ 1800.00
 TIME LIMIT : Two Months

NAME OF WORK :- R.D Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)

SUB-HEAD :- Restoration of broken berm and edges at Rd. 0/041 to 0/080 .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.65 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3713.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.30 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	15840.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	5.30 Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	33125.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.90 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	37812.00
TOTAL :-						90490.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD, Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 99238.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of link road from Manai Bharooplaha road to Chaudhary Basti Jol upto Ramesh Chand House. (Deposit Work).

SUB-HEAD :- Providing and laying Cement Concrete Pavement between km 0/043 to 0/076).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.10 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2135.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	8.25 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	7013.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade), (design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.60 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	90090.00
TOTAL :-						99238.00
			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in words)			
Quoted Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

(29)


ESTIMATED COST: - ₹ 99619.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Additional fund to stage Chinj Mela Ground Dramman (Deposit Work).

SUB-HEAD :- Providing and Fixing Truss for roofing and Prepainted sheet.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.20 Running metres	790.00	Rupees Seven Hundred Ninety Only	Per running metre	4898.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.62 Square metres	1450.50	Rupees One Thousand Four Hundred Fifty And Paise Fifty Only	Per square metre	9602.00

3	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and; placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	810.66 Kilogram e	105.00	Rupees One Hundred Five Only	Per Kilogram	85119.00
TOTAL :-						99619.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

28

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 89786.00
EARNEST MONEY :- ₹ 1800.00
TIME LIMIT : Two Months

NAME OF WORK :- Maintenance of link road Palwala to Lajot KM 0/00 TO 0/900. (S.C.D.P).

SUB-HEAD :- Construction of U-Shape drain at Rd 0/431 to 0/454.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.80 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2380.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.95 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	87406.00
TOTAL :-						89786.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97791.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Harnera Mohad Chattari road Km 0/00 to 9/100.

SUB-HEAD :- Construction of Retaining wall Km 3/884 to 3/893.30.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.16 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3556.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	21.10 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	91785.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	7.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2450.00
TOTAL :-						97791.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 85233.00
EARNEST MONEY:- ₹ 1750.00
TIME LIMIT : Two Months

NAME OF WORK :- Maintenance of link road Pakwala to Lajot KM 0/00 TO 0/900. (S.C.D.P).

SUB-HEAD :- Construction of U-Shape drain at Rd 0/400 to 0/430.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseeling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause. 205.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.10 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2485.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900. & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.10 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	82748.00
TOTAL :-						85233.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 90238.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT :: Two Months

NAME OF WORK :- Maintenance of link road Palwala to Lajot KM 0/00 TO 0/900. (S.C.D.P).

SUB-HEAD :- Construction of U-Shape drain at Rd 0/375 to 0/399.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.15 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2503.00
2	providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.01 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	87735.00
TOTAL :-						90238.00
	Quoted Rate in Figure (%)	in	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	in	(Amount to be quoted by the contractor in words)			

137
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99273.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual repair and maintenance of various roads under Under HP.PWD. Sub Division gaggal

SUB-HEAD :- Painting and writing lettering, figures and kilometre stone etcetra.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foregin matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	44.00 Squire metre	36.10	Rupees thirty six and paise ten only	Per square metre	1588.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squire metre	86.10	Rupees Eighty six and paise ten only	Per square metre	3875.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35400.00 Per letter per centimetre hight	2.65	rupees Two and sixty paise only	Per letter per centimetre hight	93810.00
TOTAL :-						99273.00
	Quoted rate in Figure (%)		Amount to be quoted by the contractor in figure			
	Quoted rate in Figure (%)		Amount to be quoted by the contractor in figure			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99201.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual repair and maintenance of various roads under Under HP.PWD. Sub Division Shahpur

SUB-HEAD :- Painting and writing lettering, figures and kilometre stone etcetra.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foregin matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	42.00 Squire metre	36.10	Rupees thirty six and paise ten only	Per square metre	1516.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squire metre	86.10	Rupees Eighty six and paise ten only	Per square metre	3875.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35400.00 Per letter per centimetre hight	2.65	rupees Two and sixty paise only	Per letter per centimetre hight	93810.00
TOTAL :-						99201.00
Quoted rate in Figure (%)		Amount to be quoted by the contractor in figure				
Quoted rate in Figure (%)		Amount to be quoted by the contractor in figure				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur