

Himachal Pradesh
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2024-2025- 2110-11

Dated:-

19-5-2025

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 28-05-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 28-05-2025 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 30-05-2025 .up to 10:30 AM |
| 4. Date of opening of tender:- | 30-05-2025 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O Elysium Devidhar road (SH:- Providing and Fixing railing and Grating in various Rd).	99707/-	2000/-	350/-	30 days	Class-D
2	A/R & M/O various Type-III and Type-IV Qtrs of Gad at kasumpti Shimla-9 (SH:- Providing and Fixing Checkerred tiles in lawn area of Type-III H Block and providing and fixing PVC in Type-III 43 Under Parimahahal section).	98715/-	2000/-	350/-	30 days	Class-D
3	A/R & M/O various type-III and Type-IV Qtrs of GAD at kasumpti Shimla-9 (SH:- Providing and Fixing Checkerrede tiles in lawn area of Type-III H Block and approach stairs under Parimahahal section).	99335/-	2000/-	350/-	30 Days	Class-D
4	A/R & M/O to Elysium Devidahr road (SH;- Providing and fixing railing and Grating in various RDs)	92733/-	1900/-	350/-	30 Days	Class-D
5	A/R & M/O various Type-III and Type-IV Qtrs of GAD at kasumpti Shimla-9 (SH;- Repair of staircase rialing, providing and fixing nosing in lawn of Type-III H Block under Parimahahal section).	99609/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O various roads under Shimla sub Division No.1 (Bharari Section)(SH:- Maintenance of Drain Culvert and shoulders).	96946/-	1900/-	350/-	30 days	30 Days
7	A/R & M/O various roads under Shimla Sub Division No.1 (Lakkar Bazar Section)(SH;- Maintenance of Drain, Culvert and Shoulders).	95915/-	1900/-	350/-	30 days	30 Days
8	A/R & M/O to Bhatta Kuffer to AIMSS (IGMC Phase-II) in km. 0/00 to 2/400 (SH:- Providing and Fixing of road Studs (Hill side) at Rd. 0/350 to 0/525).	97800/-	2000/-	350/-	30 Days	Class-D
9	Additional Alteration to Atal institute of Medical Super Specialties Shimla-6 at Chamyana (SH:- Providing and Fixing Aluminium doors at top 8 th floor R.O unit area and for safety of electrical cables at AIMSS Shimla-6).	38717/-	800/-	350/-	30 Days	Class-D
10	A/R & M/O various Residential qtrs Type-I to Type-VI qtr of GAD at kasumpti Shimla (SH:- Providing and fixing cupboard in type-IV set No.19 under kasumpti Section).	97927/-	2000/-	350/-	30 Days	Class-D
11	A/R & M/O various Residential qtrs Type-I to Type-VI of GAD at kasumpti Shimla (SH:- providing and fixing Type-IV set nO.45 under kasumpti Section).	98241/-	2000/-	350/-	30 Days	Class-D
12	A/R & M/O to Windsor Cottage (PWD Pool) kasumpti Shimla (SH:- Providing Steel pedestal for water tank above Set no.5 and Painting/Distemping etc).	99639/-	2000/-	350/-	30 Days	Class-D
13	A/R & M/O Director of Health Services SDA Complex kasumpti Shimla-9 (SH:- Providing and fixing wallpaper, seat and repair of roof in admin block of Directorate of Health Services ,SDA complex under Parimahahal section).	97916/-	2000/-	350/-	30 Days	Class-D
14	A/R & M/O Director of Health Services, SDA Complex kasumpti Shimla-9 (SH:- Repair of CGIK including carriage of materials in DHS admin block SDA Complex under Parimahahal section).	95484/-	2000/-	350/-	30 Days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

- The valid enlistment/Registration of contractor in Appropriate Class.
- Permanent account No. (PAN NO).
- G.S.T No.
- Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
- The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form . The application received without earnest money & cost of tender form shall summarily be rejected.
- The officer of the tender shall remain valid up to 75 days after the opening of tender.
- Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
- Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
- If the date given above happens to be holiday the same shall be processed on next working day.

10. The Contractor/firms must quote their rates in words as well as in figures failing which CAN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

No.PW-SD-I/CB-Tender/2025-2026-
Copy forwarded to :-

2112-26

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.


Dated :- 19-5-2025

Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 99,70,700	
Name of Work :- A/R & M/O Elysium Devidhar road . (SH:Providing and Fixing railing and Grating in various Rd.).						Earnest Money :- 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	920.75	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	96679.00
2	Painting Steel work with Deluxe MultiSurface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	32.74	sqm	65.00	Rupees Sixty Five Only	Per Square Meter	2128.00
3	Providing and fixing 100*6mm heavy Hinges welding for grating complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	15.00	No	60.00	Rupees Sixty Only	Each	900.00
						Total	99707.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 98,715.00		
Name of Work :- A/R & M/O various Type-III and Type-IV Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Providing and Fixing Checkerred tiles in lawn area of Type-III H Block and Providing and Fixing PVC in Type-III 43 Under Parimahahal Section).					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc complete, on 20 mm thick bed of cement mortar 1:4 (One cement: Four coarse sand)including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)Medium shade pigment using 50% white cement 50% Grey cement.	32.59	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per Square Metre	45626.00
2	Providing and fixing M.S. Hinges complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	20.00	Nos	95.00	Rupees Ninety Five Only	Each	1900.00
3	Providing and Fixing Cemocrete cover for man hole including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 600mm dia.	2.00	Nos	2300.00	Rupees Two Thousand Three Hundred Only	Each	4600.00
4	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	44.37	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square Metre	46589.00
						Total	98715.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,335.00	
Name of Work :- A/R & M/O various Type-III and Type-IV Qtrs. Of GAD at Kasumpti Shimla-9. (SH:-						Earnest Money :- 2,000.00	
Providing and Fixing Checkerred tiles in lawn area of Type-III H Block and approach stairs Under Parimahahal Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	3.06	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	17136.00
2	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc complete, on 20 mm thick bed of cement mortar 1:4 (One cement: Four coarse sand)including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i)Medium shade pigment using 50% white cement 50% Grey cement.	56.59	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per Square Metre	79226.00
3	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)Cement Mortar 1:6 (one Cement: six Sand).	9.91	Sqm	300.00	Rupees Three Hundred Only	Per Square Metre	2973.00
						Total	99335.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 92,733.00		
Name of Work :- A/R & M/O to Elysium Devidhar road. (SH:- Providing and fixing railing and Grating in various RDs).					Earnest Money :- 1,900.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:3:6 or leaner mix (i/e equivalent design mix)	2.93	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	3370.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand); four graded stone aggregate 20mm (Twenty millimeter) nominal size).	2.93	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	18752.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	655.20	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	68796.00
4	Painting steel work with Deluxe Multi surface paint to give an even shade @ 0.90 ltr 10.sqm (zero point ninety litre and ten square metre) over an under coat of primer applied @ 0.80 ltr /10 sqm (zero point eighty and ten square metre) of approved painting Steel work with Deluxe Multi Surface Paint to give an even shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Two or more coat applied)	27.93	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	1815.00
						Total	92733.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,609.00	
Name of Work :- A/R & M/O various Type-III and Type-IV Qtrs. Of GAD at Kasumpti Shimla-9. (SH:-						Earnest Money :- 2,000.00	
Repair of staircase railing, Providing and Fixing nosing in lawn of Type-III H Block Under Parimahal Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In stringers, treads, landings etc of stair cases including use of chequered plate wherever required	834.75	Kgs.	110.00	Rupees One Hundred Ten Only	Per Kilogram	91823.00
1.1	(ii) In stringers, treads, landings etc of stair cases including use of chequered plate wherever required. (Labour Rate)	121.20	Kgs.	55.00	Rupees Fifty Five Only	Per Kilogram	6666.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	0.20	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	1120.00
						Total	99609.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Shimla Division No.I,
 HP PWD Shimla-3

SCHEDULE OF QUANTITY								
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 96,946.00		
Name of Work :- A/R & M/O various roads under Shimla Sub Division No. I. (Bharari Section).(SH:-						Earnest Money :- 1,900.00		
Maintenance of Drain, Culvert and Shoulders).						Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Mainteance of drain including erosion, reoair, cleaning, reshaping, regarding , deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	2000.00	Rmt	5.00	Rupees Five Only	Per Running Meter	10000.00	
2	Mainteance of Hume pipe culvert by way of cleaning, Erosion repair to cracks parapets wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	8.00	Nos	2278.78	Rupees Two Thousand Two Hundred Seventy Eight and Paise	Each	18230.00	
3	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/berms and disposing of the same to suitable locations as per technical specifications Clause 1914 complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge.	7250.00	Sqm.	3.50	Rupees Three and Paise Fifty Only	Per Square Metre	25375.00	
4	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1238.30	Sqm	35.00	Rupees Thirty Five Only	Per Square Meter	43341.00	
						Total	96946.00	
	Quated rates Percentage in figures							
	Quoted rates Percentage in words							
						G.Total		

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY								
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							Estimated Cost:- 95,915.00	
Name of Work :- A/R & M/O various roads under Shimla Sub Division No. I. (Lakkar Bazar Section). (SH:-							Earnest Money :- 1,900.00	
Maintenance of Drain, Culvert and Shoulders).							Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Mainteance of drain including erosion, reoair, cleaning, reshaping, regarding , deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	2000.00	Rmt	5.00	Rupees Five Only	Per Running Meter	10000.00	
2	Maintenance of Hume pipe culvert by way of cleaning, Erosion repair to cracks parapets wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	3.00	Nos	2278.78	Rupees Two Thousand Two Hundred Seventy Eight and Paise	Each	6836.00	
3	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/berms and disposing of the same to suitable locations as per technical specifications Clause 1914 complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge.	9250.00	Sqm.	3.50	Rupees Three and Paise Fifty Only	Per Square Metre	32375.00	
4	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1334.40	Sqm	35.00	Rupees Thirty Five Only	Per Square Meter	46704.00	
	Quated rates Percentage in figures					Total	95915.00	
	Quoted rates Percentage in words							
						G.Total		

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							Estimated Cost:- 97,890.00	
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							Earnest Money :- 2,000.00	
Name of Work:- A/R & M/O to Bhatta Kuffer to AIMSS (IGMC Phase-II) in Km 0/000 to 2/400. (SH:-							Time:- One Month.	
Providing and Fixing of Road Studs (Hill side) at RD 0/350 to 0/525).								
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Providing and Fixing cat eye make (3m) of size 100x20mm made of heavy duty body shall be molded dual ASA/Acyclic Styrene Acrylonitrile or HP/High impact polystyreaon on ABS having electronically welded micro prisnatics lens with abrasion resistant coating as approved by Engineer-in-Charge. The road stud shall support a load of 13635 bt tesdted in accordance with ASTM D4280. The slope of retro reflective surface shall be 35+/-5degree to hences. The reflective panel on both side with at least 12cm of each area side. Te luminance intesity should be as pae the specification ASTM as recommended in BS-S873 part 41973 as per approved sample and manufacture by the Engineer-in-Charge including carriage of material within all leads and lifts the rate are inclusive of octroi, rayality, malkana GST, toll tax, sale tax or other taxes imposed by the Government.	251.00	Nos	390.00	Rupees Three Hundred Ninety Only	Each	97890.00	
						Total	97890.00	
	Quoted rates Percentage in figures							
	Quoted rates Percentage in words							
						G.Total		

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 38,717.00	
Name of Work :- Addition Alteration to Atal institute of Medical Super Specialties Shimla-6 at Chamyana. (SH:- Providing and Fixing Aluminium doors at top 8th floor R.O unit area and for safety of electrical cables at AIMSS Shimla-6).						Earnest Money :- 800.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) (i) For fixed portion (a) Powder coated aluminium (minimum thickness of powder coating 50 micron)	10.31	Kgs.	590.00	Rupees Five Hundred Ninety Only	Per Kilogram	6083.00
1.1	(b) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/neoprene gasket required (Fitting shall be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	34.48	Kgs.	580.00	Rupees Five Hundred Eighty Only	Per Kilo-gram	19998.00
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc complete as per architectural drawings and directions of Engineer- in-Charge Prelaminated particle board with decorative lamination on both sides doors.	4.80	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Squire Metre	6480.00
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neoprene gasket etc. (Cost of aluminium snap beading shall be paid in basic item) including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) With float glass panes of 4.0 mm (Four milimetre) thickness	4.00	Sqm	900.00	Rupees Nine Hundred Only	Per Square Metre	3600.00

4	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Nos	398.95	Rupees Three Hundred Ninety Eight and Paise Ninety Five Only	Each	1596.00
5	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc complete as per direction of Engineer-in- charge Powder coated minimum thickness 50 micron aluminium.	8.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	960.00
						Total	38717.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-97927=00	
Name of Work :- A/R & M/O various Residential qtrs Type -I to type - VI qtr of GAD at Kasumpti Shimla (SH:- Providing and fixing cupboard in Type - IV set no .19 under Kasumpti section)						Earnest Money :-2000=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing HDMR Board including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 19mm thick.	35.19	Sqm	2300.00	Rupees Two Thousand Three Hundred Only	Per Square meter	80937.00
2	Providing and fixing 0.80 mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	12.96	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	11016.00
3	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	48.60	Rmt	90.00	Rupees Ninety Only	Per Running Meter	4374.00
4	Providing and fixing bright finished brass ball catcher 10 num dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	32.00	Nos	50.00	Rupees Fifty Only	Each	1600.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
K						G.Total	97927.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-98241=00	
Name of Work :- A/R & M/O various Residential qtrs Type -1 to type - VI qtr of GAD at Kasumpti Shimla (SH:- Providing and fixing Type - IV Set No .45 under Kasumpti section)						Earnest Money :-2000=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing HDMR Board including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 19mm thick.	35.37	Sqm	2300.00	Rupees Two Thousand Three Hundred Only	Per Square meter	81351.00
2	Providing and fixing 0.80 mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	12.96	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	11016.00
3	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	48.60	Rmt	90.00	Rupees Ninety Only	Per Running Meter	4374.00
4	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	30.00	Nos	50.00	Rupees Fifty Only	Each	1500.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	98241.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 99,639.00

NAME OF WORK:- A/R & M/O to Windsor Cottage (PWD Pool) Kasumpti Shimla. (SH:- Providing Steel Pedestal for water tank above Set No. 5 and Painting/Distemping etc).

Earnest Money :- 2,000.00


Time:- One Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	684.09	Kgs	100.00	Rupees One Hundred Only	Per Kilogram Metre	68409.00
2	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (G.S Sheet).	24.705	Sqm	150.00	Rupees One Hundred Fifty Only	Per Square Metre	3706.00
3	Providing and fixing 0.63mm(zero point sixty three milimetre) thick prepainted C.G.I steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 8mm dia metre with prepainted limpet and bitumen washers complete with all accesoriees as required as per the direction of Engineer-in-charge.	10.20	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square Metre	12750.00
4	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i) 2nd class Rai wood	0.195	Cum	64500.00	Rupees Sixty Four Thousand Five Hundred Only	Per Cubic Metre	12578.00

5	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign matters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With enamel paint other than white.	33.79	Sqm.	65.00	Rupees Sixty Five Only	Per Square Metre	2196.00
						Total	99639.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.



 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-97,916=00		
Name of Work :- A/R & M/O Director of Health Services , SDA Complex Kasumpti Shimla - 9					Earnest Money :-2,000=00		
(SH:- Providing and fixing wallpaper , seat and repair in roof in admin block of Directorate of Health services , SDA complex under Parimahal section)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 0.60mm(zero point six zero milimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and bitumen washers complete with all accesories as required as per the direction of Engineer-in-charge.make Tata , dueroshine or Equivalent make .	16.80	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square Metre	21000.00
	labour Rate	17.50	Sqm	550.00	Rupees Five Hundred Fifty Only	Per Square Metre	9625.00
2	Providing valleys of 90cm wide over all in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1.60mm thick with zinc coating not less than 350gm/m.	7.00	Rmt	850.00	Rupees Eight Hundred Fifty Only	Per Running Metre	5950.00
3	Providing and fixing of 40cm wide over all width plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete, bent to shape and fixed in wall with cement mortar 1:3 (One cement: Three coarse sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1.00mm thick with zinc coating not less than 275gm/m.	7.00	Rmt	750.00	Rupees Seven Hundred Fifty Only	Per Running Metre	5250.00
4	Providing and fixing 15cm wide,45cm overall semi circular plain G.S. sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers etc including making necessary connections with rain water pipes complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 0.63mm (Zero point sixty three milimeter) thick.	3.95	Rmt	850.00	Rupees Eight Hundred Fifty Only	Per Running Metre	3358.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	62.64	Sqm	70.00	Rupees Seventy Only	Per Square Meter	4385.00
6	Providing and fixing copper osidised fittings (iron) butts hinges 75x47x1.70 mm	1.00	Nos	90.00	Rupees Ninety Only	Each	90.00
7	Providing and fixing oxidised M.S. sliding door bolts with bolts and nuts screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 250x16mm (two hundred fifty into sixteen milimetre)	2.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	300.00

8	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a)15mm dia nominal bore	5.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	1750.00
9	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm (Fifteen milimeter) dia bore.	1.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	450.00
10	Providing and fixing brass ball valve in water connection and storage including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore.	2.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
11	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws etc (new work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 15mm dia nominal bore.	1.00	Nos.	170.00	Rupees One Hundred Seventy Only	Each	170.00
12	Providing and fixing Wallpaper as approved by including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	28.55	Sqm	750.00	Rupees Seven Hundred Fifty Only	Per Square Meter	21413.00
13	Providing and fixing seat for setty including carriage of materials in all leads and lifts as per directions (I) 75 mm thick	4.86	No	3000.00	Rupees Three Thousand Only	Each	14580.00
14	Providing and fixing cloth for seat cover including complete stitching including carriage of materials in all leads and lifts as per directions of Engineer - in - charge.	9.45	Sqm	700.00	Rupees Seven Hundred Only	Per Square Meter	6615.00
15	Supplying and fixing welding mesh to wood or steel members in partitions etc. Weight exceeding 3 kg. and not exceeding 5 kgs. per sqm including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Size 25x25x2mm)	2.10	Sqm	800.00	Rupees Eight Hundred Only	Per Square Metre	1680.00
	Quoted rates Percentage in figures					Total	97916.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-95,484=00	
Name of Work :- A/R & M/O Director of Health Services ,SDA Complex Kasumpti Shimla - 9 (SH:- repair of CGI including carriage of materials in DHS admin block SDA complex under parimahal section)						Earnest Money :-2000=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	795.18	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram Metre	83494.00
2	Dismantling roofing including ridges hips valleys and gutters etc and staking the materials with in 50 meters lead of G.S sheet	49.20	Sqm	75.00	Rupees Seventy Five Only	Per square metre	3690.00
3	Providing ridges or hips of width 60 cm(sixty centimetre)overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm(eight millimetre) dia G.I. limpet and bitumen washers complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.50	Rmt	700.00	Rupees Seven Hundred Only	Per Running Meter	4550.00
4	Providing and fixing 0.60mm(zero point six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-in-charge.make Tata, dueroshine or Equivalent make .	3.00	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square Metre	3750.00
	Quoted rates Percentage in figures					Total	95484.00
	Quoted rates Percentage in words						
b						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.