

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 07-07-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 07-07-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 09-07-2025 at 10.30 AM.
4. Date of opening of Tender:- 09-07-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money.	Time	Cost of Tender Form	Eligible class of Contractor
1	Repair & maintenance on Dungi Dho road Km 0/00 to 5/050 (SH:- C/O 300 mm dia RCC Hume pipe culvert at RD 3/838 to 3/883)	97848/-	2000/-	Two Months	Rs. 350/-	Class-D
2	Repair and maintenance on Tikker Khatrian to Kulhera road Km 0/00 to 2/500 (SH:- C/O R/wall at RD 2/105 to 2/109)	99701/-	2000/-	Two Months	Rs. 350/-	Class-D
3	R/M on Panjot to Dharyara via Dart Km 0/00 to 3/500 (SH:- C/O V-shape drain at RD 2/250 to 2/450)	91755/-	2000/-	Two Months	Rs. 350/-	Class-D
4	R/R damages on Awahdevi Bagwara Gharan Dera Parol road Km 0/00 to 9/750 (SH:- C/O R/wall at RD 0/402 to 0/406)	99824/-	2000/-	Two Months	Rs. 350/-	Class-D
5	R/M of Chamboh Dadu road Km 0/00 to 3/500 (SH:- P/L interlocking paverblock pavement at RD 0/951.80 to 0/960)	88723/-	2000/-	Two Months	Rs. 350/-	Class-D
6	A/R & M/O Una Aghar Mandi road Km 0/00 to 79/00 to 91/00 (SH:- C/O B/wall at RD 86/766.50 to 86/773)	96734/-	2000/-	Two Months	Rs. 350/-	Class-D
7	A/R & M/O Una Aghar Mandi road Km 0/00 to 79/00 to 91/00 (SH:- C/O B/wall at RD 86/760 to 86/766.50)	96734/-	2000/-	Two Months	Rs. 350/-	Class-D
8	R/R damages on (i) Dadu Chamboh road Km 0/00 to 3/500 (ii) Bassi Badhani Chamboh road Km 0/00 to 9/225 under HPPWD Sub Division Samirpur HPPWD Samirpur (SH:- Providing & manufacturing sign Board)	98000/-	2000/-	Three Months	Rs. 350/-	Class-D
9	R/R damages on (i) Panjot Dhariyara via Dart road Km 0/00 to 4/00 (ii) Dungi Dho Kanjian road Km 0/00 to 4/00 under HPPWD Sub Division Samirpur HPPWD Samirpur (SH:- Providing & manufacturing sign Board)	98000/-	2000/-	Three Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:-

No.-PW/BHD/TA/NIT/2024-

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

NAMF

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance on Dungi Dho Road km. 0/00 to 5/050
S.H :- C/O 300 mm dia RCC Hume pipe culvert at RD 3/838 to 3/883.

Estimated Cost
Earnest Money
Time

Rs 97848/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.40	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M- ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Per cubic meter			
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 300mm (three hundred millimeters) dia. as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00	Per Running meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME / WORK:- Repair and Maintenance on Tikker Khatrian to kulhera Road km. 0/00 to 2/500 . (SH:- C/O R/Wall at RD 2/105 to 2/109.)

Estimated Cost
Earnest Money
Time

Rs 99701/-
Rs. 2000/-
2 month

Sr	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.32	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.04	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.40	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HQ PWD Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- R/R Damages on Panjot to Dharyara via Dart km. 0/00 to 3/500.(SH:-C/O V-shape drain at RD 2/250 to 2/450.)

Estimated Cost
Earnest Money
Time

Rs 91755/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.50	Per cubic meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

AE OF WORK:- R/R Damages on Awahdevi Bagwara Gharan Dera Parol Road km. 0/00 to 9/750 . (SH:- C/O R/Wall at RD 0/402 to 0/406.)

Estimated Cost
Earnest Money
Time

Rs 99824/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.32	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe. De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.40	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR,PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Chambodh Dadu road km . 0/0 to 3/500.(SH:- P/L Interlocking paverblock pavement at RD 0/951.80 to 0/960).

Estimated Cost
Earnest Money
Time

Rs 88,723/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates In Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.56	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size including shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.87	Per cubic metre			
3	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (n.t.c), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	38.70	Per square meter			
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.23	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.R.PWD Bhoranj

SCHEDULE OF QUANTITY

E OF WORK:- A/R & M/O Una-Aghar-Mandi Road km. 79/00 to 91/00 . (SH:- C/O B/Wall at RD 86/766.50 to 86/773 .)

Estimated Cost
Earnest Money
Time

Rs 96734/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.89	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.29	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg. per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
Total						
Terms and Condition:-						

1 Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
Rd PWD Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- A/R & M/O Una-Aghar-Mandi Road km. 79/00 to 91/00 . (SH:- C/O B/Wall at RD 86/760 to 86/766.50.)

Estimated Cost
Earnest Money
Time

Rs 96734/-
Rs. 2000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.89	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.29	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	Each			
	Total					
	Terms and Condition:-					

1 Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
A/R PWD Bhoranj

Schedule of Quantity

Estimated Cost :- 98000.00

Earnest Money:- 2000.00

Time: - 3 months

Name of Work:- R/R Damages on (i) Dadu chamboh road Km.0/0 to 3/500. (ii) Bassi Badhani Chamboh road Km 0/0 to 9/225 under HPPWD Sub- Division Samirpur HPPWD Samirpur .
(SH:-Providing & manufacturing sign Borad)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

Executive Engineer
HPPWD Division,
Bhoranj.

Schedule of Quantity

Estimated Cost :- 98000.00

Earnest Money:- 2000.00

Time: - 3 months

**Name of Work:- R/R Damages on (i) Panjot Dhariyara via Dart road Km.0/0 to 4/00. (ii) Dungi Dho Kanjian road Km 0/0 to 4/00 under HPPWD Sub- Division Samirpur HPPWD Samirpur .
(SH:-Providing & manufacturing sign Borad)**

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

Executive Engineer
HPPWD Division
Bhoranj.