

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Scaled item rate / percentage rate tender are hereby invited on Form No. 6 & 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 19-06-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 19-06-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 20-06-2025 at 10.30 AM.
4. Date of opening of Tender:- 20-06-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damages on Awahdevi Bamnoh road Km. 0/00 to 1/800 (SH:- C/O R/wall at RD 0/142 to 0/147)	99664/-	2000/-	Two Months	Rs. 350/-	Class-D
2	A/R & M/O various roads under Samirpur Sub Division (SH:- Supply & stacking of 50mm to 25mm G-III)	99968/-	2000/-	Two Months	Rs. 350/-	Class-D
3	R/R damages on Awahdevi Bamoh road km 0/00 to 1/800 (SH:- C/O R/wall at RD 0/135 to 0/140)	99664/-	2000/-	Two Months	Rs. 350/-	Class-D
4	A/R & M/O various roads under Samirpur Sub Division (SH:- Supply & stacking of 50mm to 25mm G-III)	99880/-	2000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:- 13/06/2025

No:-PW/BHD/TA/NIT/2024- 2068-97

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

OF WORK:- R/R Damages on Awahdevi Bannoh Road km. 0/00 to 1/800. (SH:- C/O RMWall at RD 0/142 to 0/147.)

Estimated Cost
Earnest Money
Rs 99664/-
Rs. 2000/-
2 month

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structling and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.80	Per Cubic Meter			
Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.81	Per Cubic Meter			
Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plastiflolex/ vecdus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V); 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.70	Per Cubic Meter			
Total					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
HIP, PWD Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O various roads under Samirpur Sub Division (SH:- Supply & Stacking of 50mm to 25mm G-III)

Estimated Cost
Earnest Money
Time

Rs 99,968/-
2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Supply and stacking at site of work broken/crushed stone aggregate of approved quality 50mm to 25mm nominal size including carriage of material in all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	56.80	Per cubic meter			
Total						
Terms and Condition:-						
1.Work shall be executed as per PWD specification.						

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

WORK: R/R Damages on Awahdevi Bamnoh Road km. 0/00 to 1/800. (SH:- C/O R/Wall at RD 0/135 to 0/140.)

Description of Items	Quantity	Unit	Rate	Estimated Cost	R ₃ 99664/-
				Earnest Money Time Rates in Words	R ₃ 2000/- 2 month Amount
Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.80	Per Cubic Meter			
Providing and laying mechanically mixed cement concrete 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.81	Per Cubic Meter			
Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe De-plast/moexy vedus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.70	Per Cubic Meter			
Total					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-AIR & M/O various roads under Samirpur Sub Division (SH:- Supply & Stacking of 50mm to 25mm G-III)

Supply and stacking of items

Supply and stacking at site of work broken/crushed stone aggregate of approved quality 50mm to 25mm nominal size including carriage of material in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkans, toll and sales tax or other taxes imposed by the Government

Total

Terms and Condition:-

Work shall be executed as per PWD specification.

Quantity	Unit	Rate	Estimated Cost Earnest Money Time Rates in Words	Rs 99,880/- 2000/- 2Months Amount
56.75	Per cubic meter			

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj