

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 06-06-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 06-05-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 09-06-2025 at 10.30 AM.
4. Date of opening of Tender:- 09-06-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O Link road Jahu to Hour via High School Jahu km 0/00 to 1/200 (SH:- P/L Cement Concrete Pavement in Km. 1/044 to 1/072) SCDP	96479.00	2000/-	Two Months	Rs. 350/-	Class-D
2	C/O Link road Jahu to Hour via High School Jahu km 0/00 to 1/200 (SH:- P/L Cement Concrete Pavement in Km. 1/072 to 1/100)SCDP	96479.00	2000/-	Two Months	Rs. 350/-	Class-D
3	Restoration of Rain damages on various road under HPPWD Bhoranj Sub Division (SH:- Dressing and cutting , filling road side Berms/ shoulders & unlined drain) (Bhoranj Section)	99122.00	2000/-	Two Months	Rs. 350/-	Class-D
4	C/O link road Dho to Doh road km 0/00 to 2/00 (II) C/O Patta Awah Devi road km 10/00 to 17/500 under HPPWD Sub Division Samirpur HPPWD Samirpur (SH:- Providing & manufacturing Sign Board) (Dho Section)	98000.00	2000/-	Two Months	Rs. 350/-	Class-D
5	C/O Panjot Dhairyara road Km 0/00 to 4/500 (II) C/O link road Dharoun to Dharoun to Dhariyara Km. 0/00 to 0/900 under HPPWD Sub Division Samirpur HPPWD Samirpur (SH:- Providing & manufacturing sign Board) Dho Section)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
6	C/O Executive Engineer Office Building (PWD) Bhoranj (SH:-P/L interlocking paverblock and C/O E/wall at RD 0/043 to 0/051.60) (Deposit work)	94022/-	2000/-	Two Months	Rs. 350/-	Class-D
7	Repair & maintenance on Chambah Dadu road km 0/00 to 3/500/ (SH:- P/L interlocking paver block at RD 0/939.80 to 0/951.80)	99985/-	2000/-	Two Months	Rs. 350/-	Class-D

8	A/R & M/O HPPWD Rest House at Town Bharari Distt Hamirpur (SH:- Providing and fixing of decorative etc)	99972/-	2000/-	Two Months	Rs. 350/-	Class-
9	Repair & maintenance on Chamboh Dadu road km 0/00 to 3/500) (SH:- P/L interlocking paverblock at RD 0/927.80 to 0/939.80)	99985/-	2000/-	Two Months	Rs. 350/-	Class-

The earnest money in the shape of National Saving Certificate/ Time Deposit/ s account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned mu accompanied with each tender. The Conditional tender and tender not accompanying the earnest money proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the which any be attached with their applications (The proof of ownership of machinery/ legal t arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The ea money for the above work should be submitted with the application for the purchase of the tender forms application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pande Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:- 30-08-2025

No:-PW/BHD/TA/NT/2024-

1438-78

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road Jahu to Hour via High School Jahu km. 0/00 to 1/200.(SH:- P/L Cement Concrete Pavement in km. 1/044 to 1/072.)(SCDP)

Estimated Cost
Earnest Money
Time

Rs 96479/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	P/L of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.54	Per Cubic Meter			
2	Providing and laying cement concrete 1:4:8 (1 cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.40	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.54	Per Cubic Meter			
Total						

Terms and Condition:-

- 1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

OF WORK:- C/O link road Jahu to Hour via High School Jahu km. 0/00 to 1/200,(SH:- P/L Cement Concrete Pavement in km. 1/072 to 1/200)

Estimated Cost
Earnest Money

Rs 96479/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Plt. of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR value 30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.54	Per Cubic Meter			
2	Providing and laying cement concrete 1:4:8 (1cement :4 sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.40	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate(20mm)(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work, steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.54	Per Cubic Meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on various road under HPPWD Bhoranj sub-division.
Item:- Dressing and Cutting , filling road side Berms/shoulders & unlined drain) (Bhoranj Section)

Estimated Cost
 Earnest Money
 Time

Rs 99122/-
 Rs. 2000/-
 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including carriage of material within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	977.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including carriage of material within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	600.00	Per Running Mtr.			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj

Draft Schedule of Quantity

Estimated Cost :- 98000.00

Earnest Money:- 2000.00

Time: - 3 months

Name of Work:- C/O link road Dho to Doh road. Km. 0/00 to 2/00 (ii) C/O Patta Awah Devi road Km 10/0 to 17/500 under HPPWD Sub- Division Samirpur HPPWD Samirpur.
(SH:-Providing & manufacturing sign Borad) *Dtho Section*

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

[Signature]
Executive Engineer
HPPWD Division
Bhoranj.

Draft Schedule of Quantity

Estimated Cost :- 98000.00
Earnest Money:- 2000.00
Time: - 3 months

Name of Work:- C/O Panjot Dhariyara road Km.0/0 to 4/500. (ii) C/O link road Dharoun to Dhariyara Km 0/0 to 0/900 under HPPWD Sub- Division Samirpur HPPWD Samirpur.
(SH:-Providing & manufacturing sign Borad) (Dho Section)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

Executive Engineer
HPPWD Division,
Bhoranj.

SCHEDULE OF QUANTITY

WORK:- Repair & Maintenance on Chambhod Road km. 0/00 to 3/500.
Interlocking paverblock at RD 0/939.80 to 0/951.80).

Estimated Cost
 Earnest Money
 Time

Rs 99985/-
 Rs. 2000/-
 2 Months

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
2 Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.20	Per cubic metre			
3 Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade including border or curb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm (eighty millimeters) thick inter locking blocks (NTC Tile), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	42.00	Per square meter			
4 Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.80	Per Cubic Meter			
Total					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 MP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance on Chambod Dadu road km. 0/00 to 3/500.
 H:- P/L interlocking paverblock at RD 0/927.80 to 0/939.80.

Estimated Cost
 Earnest Money
 Time

Rs 99985/-
 Rs. 2000/-
 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.20	Per cubic metre			
3	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm (eighty millimeters) thick inter locking blocks (NTC Tile), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	42.00	Per square meter			
4	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.80	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 IN PWD OF ...