

Offline

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PWD-Dal/TA/Tender /2025-26 1258-60
To

Dated: - 10-06-2025


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 1258-60 dated. 10-06-25 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 1258-60 dated. 10-06-25 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Offline

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- 20.06.2025 onward (between 2:00 p.m.to 4:30.p.m.)


2. Date of issue/sale of tender form against Cash payment (non refundable). 20.06.2025.

The tender shall be received up to 3:00 PM on 21.06.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on 20.06.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	A/R & M/O Jandrihat to Pukhri road Km. 0/0 to 2/100 (SH:-Construction of Breast wall at RD.0/860 to 0/863.70.)	96760.00	2000.00	350.00	Two Months	D & C
2.	Construction of link road village China Km. 0/0 to 0/750 (SH:- Formation Cutting between Km. 0/520 to 0/615.)	91410.00	2000.00	350.00	Two Months	D & C
3	A/R & M/O HP:PWD Circuit House at Dalhousie (SH:- Dismantling, Plastering, tile work and Sanitary work in Bathroom at Circuit House Dalhousie.)	62248.00	1300.00	350.00	One Months	D & C
4	A/R & M/O to DSP Office Cum Residence at Dalhousie (SH:- Dismantling work, Brick work, Plastering & Painting etc.)	98089.00	2000.00	350.00	Two Months	D & C
5	Restoration of rain Damage on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Construction of PCC Retaining wall at RD 10/201.70 to 10/203.40.)	95700.00	2000.00	350.00	Two Months	D & C
6	A/R & M/O Jandrihat to Pukhri road Km. 0/0 to 2/100 (SH:- Construction of Breast wall at RD 0/867.40 to 0/871.10.)	96749.00	2000.00	350.00	Two Months	D & C
7	Restoration of Rain Damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH:- Removal of Slips at RD 1/350 to 1/360.)	98124.00	2000.00	350.00	One Month	D & C
8	Restoration of Rain Damage on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Removal of Slips at various RD's.)	99512.00	2000.00	350.00	One Month	D & C
9	Restoration of Rain Damage on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Construction of PCC Retaining wall at RD. 10/208.50 to 10/210.20.)	95005.0	2000.00	350.00	Two Months	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.



Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 1261-1311

Dated:- 10-06-25

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.



Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Quantity.

Estimated Cost :- Rs.	96760.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Name of work: -A/R & M/O Jandrigat to Pukhri road Km. 0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/860 to 0/863.70).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus mud generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	14.15			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer in-charge. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and as per direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
	Total:-					


 Executive Engineer
 Dalhousie Division,
 HPWD, Dalhousie


Schedule of Quantity.

Estimated Cost - Rs.	91410.00
Earnest Money :- Rs.	2000.00

Time Limit :- Two Months

Name of work: - Construction of Link road to village China Km. 0/0 to 0/750 (SH: - Formation Cutting between Km. 0/520 to 0/615).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rates is inclusive of the octroi, royalty, Malkana, Toll tax, sale tax, GST or other taxes imposed by the Government.	378.98			Per Cubic Metre	
					Total: -	


 Executive Engineer
 Dalhousie Division,
 HPWD, Dalhousie

Schedule of Quantity.


Job No. 03 TS 08

Name of work: - A/R & M/O HP PWD Circuit House at Dathousie (SH: - Dismantling, Plastering, tile work and Sanitary work in Bathroom at Circuit House Dathousie).

Estimated Cost: - Rs. 62248.00
Earnest Money :- Rs. 1300.00
Time Limit :- Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Dismantling tile work in floors and roofs. Jam in cement mortar manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 (fifty) meter lead as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	19.20			Per Square Metre	
2	Providing and fixing 15mm (fifteen millimeter) nominal bore Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	42.00			Per Running Metre	
3	15mm cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chatters and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand), within all leads and lift and as per the directions of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	12.48			Per Square Metre	
4	Providing and laying mechanically mixed plain cement concrete nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20 mm (Twenty millimeter) nominal size) and curing complete work in foundation, footing bases and the alike and mass concrete as required at site including the cost of form work as per drawing and MORD technical specification sections 802,803,1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	0.67			Per Cubic Metre	
5	Providing and laying 12 mm (twelve millimeter) thick 300x300 mm (Three hundred is to three hundred Millimeter) anti skid ceramic wall tiles of Reslite/Nico/ Rak/Kajaria/Orient& Bell/Simpolo/Johnson/AGL/Somay laid on 20mm (Twenty millimeter) thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per Square meter) including grouting the joints with white cement and matching pigments etc., complete including grouting of joints (Payment for grouting of joints to be made separately), as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	12.48			Per Square Metre	
6	Providing and laying 12 mm (twelve millimeter) thick 300x300 mm (Three hundred is to three hundred Millimeter) anti skid ceramic floor tiles of Reslite/Nico/ Rak/Kajaria/Orient& Bell/Simpolo/Johnson/AGL/Somay laid on 20mm (Twenty millimeter) thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per Square meter) including grouting the joints with white cement and matching pigments etc., complete including grouting of joints (Payment for grouting of joints to be made separately), as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	6.72			Per Square Metre	

	Providing and fixing white vitreous China Pedestal type water closet (European type W.C. Pan) (of approved brand like Hindware, cera, jagaur etc.) with seat and lid, 10 litre (ten liter) low level white P.V.C. flushing cistern, including flushh pipe, with manually controlled device (Handle Lever), conforming to IS: 7231, with all fittings and fixture complete, including cutting and making good the walls and floors wherever required as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	1.00				Each	
8	Providing and fixing White Vitreous China size 630X450 mm (six hundred thirty into four hundred fifty millimeter) with Cast Iron brackets, 15mm (fifteen millimeter) chrome-plated brass pillar type, 32mm (thirty two millimeter) C.P Brass waste of standard pattern, Including painting of fittings and brackets, cutting and making good the walls wherever requires as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	1.00				Each	
9	Providing and fixing C.P. Brass shower rose with 15 mm (fifteen millimeter) or 20 mm (twenty millimeter) inlet 150 mm (one hundred fifty millimeter) dia and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	1.00				Each	
						Total: -	


 Executive Engineer
 Dathousie Division,
 HP PWD, Dathousie

Schedule of Quantity.

Job No. 09 TS 112

Estimated Cost :- Rs.	95005.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Name of work: - Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/208.50 to 10/210.20).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	5.34			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	17.92			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.45			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	6.00			Each	
	Total: -					


Executive Engineer
Dalhousie Division,
HPWD, Dalhousie

Schedule of Quantity.

Name of work: -Restoration of rain damage on Dathousie Jandgrighat Chamba via Kohlari road Km. 0/0 to 11/0-40 (SH: - Removal of Slips at various RD's.).

Estimated Cost :- Rs.	99512.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	796.73			Per Cubic Metre	
					Total:-	



 Executive Engineer
 Dathousie Division,
 HPWD, Dathousie

Schedule of Quantity.

Name of work: - Restoration of rain damage on Ournour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD 1/350 to 1/360).

Estimated Cost :- Rs.	98124.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611, or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	785.75			Per Cubic Metre	
					Total:-	


 Executive Engineer
 Dalhousie Division,
 HPPMD, Dalhousie

Schedule of Quantity.

Job No. 06 TS 106

Name of work: -A/R & M/O Jandrighat to Pukhri road Km. 0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/867.40 to 0/871.10).

Estimated Cost: - Rs.	96749.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	14.13			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure. Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
	Total: -					

Executive Engineer
Dathousie Division,
M.P.M.D. Dathousie

Schedule of Quantity.

Name of work: -Restoration of Rain damage on Dalhousie Jandripath Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/201.70 to 10/203.40).

Job No. 05 TS 110
Estimated Cost: - Rs. 95700.00
Earnest Money :- Rs. 2000.00
Time Limit :- Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	6.22			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkhana, Toll tax, sales tax, GST or any other taxes imposed by the Government.	17.92			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORO technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkhana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.72			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkhana, Toll tax, sale tax GST or other taxes imposed by the Government.	6.00			Each	
Total: -						

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie


Schedule of Quantity.

Name of work: - A/R & M/O to DSP Office Cum Residence at Dailhousie (SH: - Dismantling work, Brick work, Plastering & Painting etc.).

Job No. 04 TS 14
Estimated Cost - Rs. 98089.00
Earnest Money :- Rs. 2000.00
Time Limit :- Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Demoishing brick work manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within all leads and lift and as directed by Engineer-in-Charge with in all leads and lifts, disposed earth to be levelled and neatly dressed including carriage of materials within all leads and lifts. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government	1.60			Per Cubic Meter	
2	Brick work using common burnt clay building bricks in foundation and plinth in Cement Mortar 1:6 (one Cement isto six Sand) Second Class Bricks and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	0.25			Per Cubic Meter	
3	Providing and fixing second class deodar wood work in frame of doors, windows, clerestory windows and other frames wrought framed and fixed in position complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	0.35885			Per Cubic Meter	
4	Providing and fixing 35mm (thirty five millimeter) thick shutter Second class devdar wood panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per the directions of the Engineer-in-charge (Note: - But hinges and necessary screws shall be paid separately) including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	5.55			Per Square Meter	
5	Providing and fixing 200x10mm (two hundred into ten millimeters) aluminum anodized tower bolts (Barrel type) make of pilot/sheet or equivalent anodized transparent or dyed to required colour and shade with screws etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, toll tax, GST or any taxes imposed by the Government.	4.00			Each	
6	Providing and fixing matt finished aluminium handles anodized transparent or dyed to required shade and colour with screws etcetra complete 125 mm (one hundred twenty five millimetre) as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	4.00			Each	
7	15mm cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand), within all leads and lifts and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.44			Per Square Metre	

	applying birla white/J.K white two or more coats wall care putty over plaster surface after thoroughly brushing the surface free from mortar droppes, dust loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete upto all floor level as per PWD specification and directed by the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.44				Per Square Metre	
9	Wall painting with two coat Acrylic emulsion of Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on undecorated wall having interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams / litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	10.44				Per Square Metre	
10	Painting one coat (excluding priming coat) Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on newly painted wood or wood based surface with enamel paint to given and even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	11.10				Per Square Metre	
						Total: -	


 Executive Engineer
 Dalhousie Division,
 HPPMD, Dalhousie