Himachal Pradesh Public Works Department

No PW/DD/CB/Tender/2025-26:-

1910

Dated: 25. 6. 2025

To

The Executive Engineer (I T Cell) O/o the Engineer-In- Chief Nigam Vihar HPPWD Shimla-2

Subject:-

Publication of Tender Notice.

Dear Sir,

Enclosed please fined herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sect.(PW) to the Govt. of Himachal Prsdesh letter No PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Intviting Tender.

Executive Engineer, Dharamshay Division HPPWD Dharamshay

Copy forwarded for information to:-

- The Superintending Engineer 5th Circle HPPWD Palampur.
- 2. All the Assistant Engineer working under this Division.
- 3. Copy to Ab/ DB of this Division.
- 4. Notice Board.



Office of Executive Engineer Dharamshala Division HPPWD Dharamshala Himachal Pradesh Public Works Department Dharamshala -176215 Phone No.01892-224946 Fax 222065 E-mail ee-dha-hp@nic.in

#### "NOTICE INVITING TENDERS"

Sealed percentage rate tenders on forms 6 & 8 are hereby invited by the Executive Enginee Dharamshala Division, HPPWD Dharamshala on emergent basis for the below mentioned works from the approved and eligible contractors enlisted in HPPWD so as to reach in his office on or before 01.07,2025 upto 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the tender opening committee and intending contractors/firms or their authorize representatives. The tender documents can be had from this office against cash payment/Non refundable) on 30.06.2025 betwee 2:00 PM to 5:00 PM and the applications for issue of tender forms shall be received upto 12:30 PM on 30.06.2025.

The Earnest Money in the shape of NSC's / FDR's Deposit/Bank Guarantee at Call of any of the Po office/Bank duly pledged in favour of XEN HPPWD. Dharamshala must be accompanied with the tender documents. Please note that n exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentione above will summarily be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserves the right to reject an tender or all tenders without assigning any reasons. The contractors should be registered as a dealer GST Tax Act 2018 and also produce the clearance certificate from the Excise and Taxation department and the contractor will also have to attach the labouar employer licence from the labour office with the application. The tender documents shall only be issued to those contractors/firms who will produce the photo copy of the enlistment/renewal, if happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue:-

Sr. No.	Name of Work	Estimated cost in Rs.	EMD	Time limit	Cost of Tender form
L	Repair of lonk road Dal Satobari Barnet road km 0/00 to 5/030 in Tehsil Dharamshala Distt, Kangra HP Deposit work (SH:- Construction of U-Shape Drain at RD 2/250 to 2/270)	99344/-	2000/-	Two Month	350/-
2.	Annual repair & Maintenance of Non- residential building at Dharamshala Distt. Kangra HP (SH:- providing Skilled worker for Minister block of circuit House Dharamshala.	977367-	2000/-	20 days	350/-
3.	Restoration of rain damage on various road under Mecleoganj Section in Sub Division I HPPWD Dharamshala Dist. Kangra HP (SH:- Removal of Slips at Various RDs	98640/-	2000/-	One Month	350/-
4.	Construction of Jogiwara road from Kotwali Bazar lower Dharamshala Distt. Kangra HP (Deposit work) (SH:- Providing and laying Cement Concrete Pavement at RD 2/350 to 2/360, 2/400 to 2/408, 2/600 to 2/610 and 2/620 to 2/628)	97133/-	1950/-	Two Month	350/-
5.	Repair of link road Dharamshala upto Delak Hospital km 0/000 to 2/600 Dharamshala Distr. Kangra HP (Deposit Work) (SH:-Construction of unlined surface drain, cutting of bushes & surface dressing etc. at various RDs)	98910/-	2000/-	One Month	350/-
6.	Repair of restoration of min damage on Dharamshala to Khaniyara road Rd 0/000 to 8/000 in Tehsil Dharamshala Distt. Kangra HP(SH:- Construction of V-Shape drain at RD 0/350 to 0/390	94215/-	1990/-	Two Month	350/-
7.	Construction of Additional Room and Toilet for Mahila Mandal Bhawan Shiva inward No 8 in Tehsil Dharamshala Distt. Kangra HP (Deposit work) (SH:- Providing and laying reinforced cement concrete and plastering work etc.(Balance Work)	99956/-	2000/-	Two Month	350/
8.	Constrution of Totlet Block for boys (near B.C.A & Biotechnology Block) in Govt. College at Dharamshala Distt. Kangra Hp (Deposit work) (SH:- Providing and laying fixing M.S Steel work etc)	86940/-	1800/-	One Month	350/
9.	Restoration of rain Damage on Various road under Chamunda & Sidhabari Section in Sub Division No II HPPWD Dharamshala Distt, Kangra HP (Sh:- Removal of Slip at Various)	98400/-	2000/-	One Month	350/
0.	Repair' Improvement of Black Spot near Kali Matta Mandir Kotwali Bazar on Gaggal Chetru Dharamshala Mecleoganj road (Portion Gandhi Purk to Kala pul.) In Tehsil Dharamshala Distt. Kangra HP (Deposit Work)(Sh.: Providing and laying Grading –III and Back filling between km 1/000 to 1/017)	99090/-	2000/-	Two Month	350/
1.	Construction of link road from 2nd Battalian (IRBN) Sakoh to Chetru via Banwala km 0/00 to 1/550 in Tehsil Dharamshala Distt, Kangra HP (Sh:- Construction of P.C.C Retaining wall including unlined surface drain at RD 1/320 to 1/325)	99027/-	2000/-	Two	350/
2.	Restoration of rain damage on Sidhpur to Khaniyara road via Mouli road in km 0/000 to 4/000 in Tehsil Dharamshala Distt, Kangra HP (Sh;- Construction of Culvert Including M.S grating at RD 1/970)	99060/-	2000/-	Two Month	350/
13.	Construction of Ambulance road from Naddi near sunset Point to Dhiyal ward No 3 upto wood Whistlers School km 0/00 to 0/810 in Tehsil Dharamshala Disti. Kangra HP (SH:- Providing and laying Granular filling between km 0/582 to 0/592	91875/-	1900/-	Two Months	350/

14.	Special repair to residence of Executive Engineer (PWD) at Chilgari Dharamshala Distt, Kangra HP (SH:- Providing and fixing venyl flooring and other minor repair work etc.)	99196/-	2000/-	Two Months	350/
15.	Special repair of Health Sub Centr Building at Sidhbari in Tehsil Dharamshala Distt, Kangra HP( Deposit work) (SH:-Cleaning of Chamber)	32500/-	700/-	One Month	350/
16.	Constrution of Toilet Block for boys (near B.C.A & Biotechnology Block) in Govt. College at Dharamshala Distt. Kangra Hp (Deposit work) (SH:- Providing and fixing aluminiuam work, distempering and painting work etc.)	96637/-	2000/-	Two	350/-
17.	Repair of Path from Link road to Ashok Kumar house Ward No 3 G.P Rakkar in Tehsil Dharamshala Distt. Kangra HP)(Deposit Work) (SH:- Providing and laying Interlocking paver Block)	98493/-	2000/-	Two Month	350/

Certified that above work for Sr. No 1 to 17 are urgent nature and require immediate execution.

Executive try beer, Dharamshad Division, HPPWD Dharamshala

On behalf of Governor of Himachal Pradesh.

Dated 25.06.2025

No. PWD-DD/CB/M-34/-2025-26- 1878 - 1909 Copy to the following for information and necessary action:

- The Chief Engineer (KZ) HP.PWD Dharamshala.
- The Superintending Engineer, 5th Circle HP.PWD, Palampur.
- The Deputy Commissioner Kangra at Dharamshala.
- The Commissioner Dharamshala Municipal Corporation.
- All the Executive Engineer, working under Kangra Zone.
- The SDM & Tehsildar Dharamshala.
- 7. The BDO Dharamshala /Rait.
- All the Assistant Engineers working under this Division.
- All the Head of the Branches in this office.
- 10. All the Contractors working under this Division.
- Notice Board.

Name (SH:-	(SH:- Construction of U-Shape drain at RD 2/250 to 2/270)  S.  No.  Description of Remarks and Secretaries such as retaining walk beauty and the secretaries walk beauty and the secretaries walk beauty and the secretaries walk beauty.		LP) Deposi	LP) Deposit work  Quantity In Figures	LP) Deposit work  Estimated cost Rs.  Earnest Money Rs.  Time Limits  Quantity In Figures In Word  Estimated cost Rs.  Earnest Money Rs.  Time Limits
E S	in for all type of road structure such as retaining stall, because it.		Quantity	Quantity	Quantity R
	classification of soil, comprising of ordinary soil, ordinary rock, hard rock chisching / wedging out rocks (where blassing is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other defections materials and disposal of materials upon any lead and put any lift including diressing of sides and bottom and back filling in trenches with excavated solitable / approved materials to the original surface in layers not (surface and soil water) upto any depth and any quantum of water including shoring and strutting and pumping and balling out water (surface and sats soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octror, royality, Malkama, toll tax. GST or other taxes imposed by the Government.	ra in all type of ulibited) as per vet, construction by lift including the in layers not alling out water watering as per octror, royality,	6.20	6.20	6.20 360.00
	2 Providing and laying mechanically mixed and vibrated plain coment concrete in open foundation for all type of structure complete using plain terment concrete grade M-10 (M-ten) nominal mix 1.3.6 (one coment isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights depths including the cost of form work in toe wall entern as per drawings and MORD, technical specification section/ clause 800,900 & 1200 and as per the direction and entere satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octrol, toll tax, GST or any other taxes imposed by the Coveriment.	te 40 mm (forty te 40 mm (forty ter, dewatering ding the cost of and as per the ther incidentals	plete using 4.90 mm (forty lewatering the cost of as per the acidentals		4.90
	steel primer using structural steel etc. as required in gratings, frames, guard bur, ladder, railings, brackets, gates and similar works as per direction of Engineer-in-charge in cement mortar as per direction of Engineer-in-charge in cement mortar as per direction of Engineer-in-charge in cement mortar within all leads and lifts and other incidental. The rate is including actroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	approved as per is and	approved 550.30 as per is and	4.90	550,30
4	4 Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD teclusical specifications section 800, 900, 1200 and 1600 nominal mix 1.4.8 (One general isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall electra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	ations section 40mm (Forty ring complete scientals. The	nts section 2.50 num (Forty geomplete ntals, The		2.50
	Omotor Pared In Co.	Total	Total	Total	Total
	Supergraves of the Control of the Co	-18	Excess (+)	Excess (+)	
_	G.Total in Figures	_	_	_	_
-	G. Total in Words	ds	rds	rds	ds
	The second secon	100000000000000000000000000000000000000	To the same of the		



83

#### SCHEDULE OF QUANTITY

ESTIMATED COST: -

TIME UMIT EARNEST MONEY: -

Twenty days

97736.00

NAME OF WORK :-Annual Repair & Maintenance of Non-Residential buildings at Dharamshala in Distt. Kangra Himachal Pradesh

		(Amount to be quoted by the contractor in Words)	noted by	Amount to be q	Quated Rate in Words (%)	
		(Amount to be quoted by the contractor in Figure )	uoted by	Amount to be q	Quated Rate in Figure (%)	
97736.00	Total:-					
48868.00	Per Day	610.85 Rupees six hundred ten and paise eighty five only	610.8	80.00 Days	5). Helper/ Attendent (4 Nos x20 = 80)	
12217.00	Per Day	610.85 Rupees six hundred ten and palse eighty five only	610.8	20.00 Days	4). Mali	
12217.00	Per Day	610.85 Rupees six hundred ten and paise eighty five only	610.83	20.00 Days	3). Sweeper	
12217.00	PerDay	610.85 Rupees six hundred ten and paise eighty five only	610.88	20.00 Days	2). Cook Helper	
12217.00	Per Day	610.85 Rupees six hundred ten and paise eighty five only	610,85	20.00 Days	1), Cook	
					Providing skilled worker for operation of newly constructed minister block in the complex of Circuit house Oharamshala for the Period of 1.07.2025 to 20.07.2025	H
7	6	5	44	3	2	1
		in words	In fig			No.
Amount	Unit	RATES		Quantity	Description of items	S

89

## Schedule of Quantity

ESTIMATED COST: -

98640.00

EARNEST MONEY : -One month 2000.00

TIME LIMIT

Restoration of rain damages on various road under Mcleodganj Section in Sub Division No. 1, HPPWD Dharamshala in Distt. Kangra

Removal of slips at various R.D.

SUB HEAD :-

NAME OF WORK :-

	words)	(Amount to be quoted by the contractor in words)	be quote	(Amount to	Quated Rate in Words (%)	
	Figure )	(Amount to be quoted by the contractor in Figure )	be quote	(Amount to	Quated Rate in Figure (%)	
98640.00	Total :-					
98640.00	Per Cubic metre	120.00 Rupees one hundred twenty and paise zero only	120.00	822.00 Cubic metres	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials within lift upto 1.50 mtrs. (One decimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 3022.3.5 and 1611, complete including filling of earth with tipper and carriage of material by Mechanical Transport loading, unloading and levelling. Average lead 2.K.M. complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	La
7	6.	(h	4	3	2	11
	3	words	In fig	of the second		No.
Amount	Unit	Rate		Quantity	Description of items	'n

Dharamshala Division, HPPWD Dkaramshala Executive Engineer,

ESTIMATED COST: EARNEST MONEY: TIME LIMIT :

₹ 97133.00 ₹ 1950.00 Two Months

80

NAME OF WORK :-Construction of Jogiwara road from Kotwali Bazar Lower Dharamshala to Mcleodganj Dharamshala, Distt. Knagra H.P. (Deposit work)

SUB-HEAD :-

Providing and laying Cement Concrete Pavement at RD 2/350 to 2/360, 2/400 to 2/408, 2/600 to 2/610 and 2/620 to 2/628

	rds)	to be quoted by the contractor in words)	o be quote	(Amount to	Quated Rate in Words (%)	_
	ure)	to be quoted by the contractor in Figure )	o be quote	(Amount to	Quated Rate in Figure (%)	
97133.00	TOTAL :-					
					malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	
1					within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality,	
					directions and entire satisfaction of the Engineer-In-Charge including carriage of material	_
				70.	carriage of materials, as per approved drawing, design and specifications and as per	
					not less than 330 kgs/ cum ( three hunred thirty kilograms per cubic metre) including	
	metre	eight hundred fifty and metre paise zero only		Cubic	the cost of centering and shuttering - All work up to plinth level with cement contents	
97133.00	Per Cubic	Rupees six thousand	6850.00	14.18	1 Providing and laying in position cement concrete of M-20 ( M- Twenty) grade including	+
7	6	5	4	ė.	2	1
		In words	ln fig			No.
Amount	Unit	RATES		Quantity	Description of items	Ç,

ESTIMATED COST: -

RS.

98910.00

EARNEST MONEY :-

One Month

Repair of link road Dharamshala upto Delek Hospital road km 0/000 to 2/600. Dharamshala in Distt. Kangra H.P. (Deposit work) TIME LIMIT

0	S Description of items Q	Quantity		RATES	Unit	Amount
No.			In fig	In words		
4	T Construction of unlined / line surface drain of average cross-sectional area 0.40 sqm (zero point four zero) square 1 metre in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical 1	1600.00 Running metres	44.00	Rupees forty four and paise zero only	Per running metre	70400.00
	Specification Clause 307. Excavated material to be used in embankment at site, as per direction of Engineer-in- Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including octro- movaling Markana toll tax sale tax or other taxes imposed by the Government.					
N	ing, deepening of side drains as well tion of Engineer-in-Charge. Including Juding octroi, royality, Malkana, toll	1600.00 Running metres	4.50	Rupees four and palse five zero only	nunning metre	7200.00
ω	rass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per uase 1914, as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts cidentals. The rate including octroi, royality, Malkana, toll tax,GST or other taxes imposed by the	950.00 Square metres	5.00	Rupees five and paise zero only	Per Square metre	4750.00
	4 Cutting of shrubs from the road way or with in Row and disposal of the srubs to the suitable location as per technical specification clause 1914 and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including octrol, royality, Malkana, toll tax,GST or other taxes	950.00 Square metres	5.50	Rupees five and paise five zero only	Per Square metre	5225.00
Or	Surface dressing of the ground including removing vegetation and in- equalities not exceeding 15 cm (lifteen centimetre) deep and disposal of rubbish, lead upto 50 m (lifty metre) all kind of soil, as per direction of Engineer-in Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including octroit	150.00 Square metres	20.00	Rupees twenty and paise zero only	Per Square metre	3000.00

104

	vords)	(Amount to be quoted by the contractor in words)	be quote	Amount to	Quated Rate in Words (%)
	igure)	(Amount to be quoted by the contractor in Figure	o be quote	Amount to	Quoted Rate in Figure (%)
98910.00	TOTAL :-	7.			
6150.00	Each	2050.00 Rupees two thousand Each fifty and paise zero only	2050.00	3.00 Numbers	Maintenance of slab type culverts by way of cleaning, cleaning, repair, repair of cracks, parapest wall and protection work as per drawing and technical specification clause 1908, and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including octrol, royality, Makkana, toll tax, GST or other taxes imposed by the Government.
2185,00	Square	paise zero only	11.50	Square metres	scraping etc as per technical specifications Clause 1915 and as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate including octrol, royality, Malkana, toll lax,GST or other taxes imposed by the Government.

ESTINATED COST: 4 94215.00
EARNEST MONEY: 1990.00
TIME LIMIT : Two Months

NAME OF WORK: - Repair of Restoration of rain damages on Dharamshala to Khaniyara road RD 0/000 to 8/000 in Tehsil Dharamshala, Distt. Kangra H.P. (Deposit work)

SUB-HEAD :- Construction of V- Shape drain at RD 0/350 to 0/390

	ords)	(Amount to be quoted by the contractor in words)	o be quoter	Amount to	Quated Rate in Words (%)
77.76.76	(ure)	(Amount to be quoted by the contractor in Figure )	o be quote	Amount t	Quated Rate in Figure (%)
94215.00	-: TV101				
86655.00	Per Cubic metre	Rupees five thousand Per Cubic four hundred fifty metre and paice zero only	5450.00	15.90 Cubic Metres	Providing in laying mechanically mixed and virbrated concrete for plain cement concrete in open foundations complete in road work as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 using P.C.C. grade M-10 (M-Ten) nominal mix (1:3:6) (One cement : Three sand : Six graded crushed stone aggregate 20mm (twenty milimetres) nominal size) in or under water and curing complete including pumping or bailing out water complete for all heights/depths including the cost of form work, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toil tax, sale tax, 65T or any other taxes imposed by the Government.
7560.00	Per Cubic metre	Rupees three hundred sixty and paise zero only	360.00	21,00 Cubic Metres	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 & 1603 and as per direction of the Engineer- in - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and balling out water (surface and sub soil water) upto any depth- and any quantam of water including cleaning of slush which may arrise out during dewatering as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.
7	6	5	4x	3	2
		In words	Infig	SAMONS	
Amount	Unit	RATES		Quantity	Description of items

Executive Engineer, Dharamshall Division, HPPWP Dranamshala.

(6)

ESTIMATED COST: - ₹

TIME LIMIT EARNEST MONEY: 3

Two Months 2000.00

99956,00

Construction of Additional Room and Toilet for Mahila Mandal Bhawan Shiva in ward No. 8 in Tehsil Dharmashala, Distt. Kangra H.P., (Deposit work) Providing and laying Reinforced cement concrete and plastering work etcetera. [Balance work]

SUB-HEAD :-NAME OF WORK :-

Sr.	Description of items	Quantity	γ	In fig		In words	In words
	2		w	u	3 4		
44	2 Providing and laying in position machine batched and machine mixed cement concrete work of grade Mr-20 (M-twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum, (three hundred twenty kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechnically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per 15:	2		netres		Cubic	metres 7650.00
	9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.						
2	Steel reinforcement Thermo-Mechanically Treated bars of grade Fe-5000 or more of Tata/ Sail for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes	ω H	314.00	4.00 Kilogra		mme 95.00	mme 95.00
	incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.						
w	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection 3 plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins	- Lut	305.00	05.00 Kilogra		Kilogra	Kilogra 105.00
	connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and;						
	placing in position complete and applying a coat of red lead paint, as per approved drawing, design						
	and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including						
	carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality,						
	malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.						

		to be quoted by the contractor in words)	ted by the co	to be quo	(Amount	Quated Rate in Words (%)	
		(Amount to be quoted by the contractor in Figure )	ted by the co	to be quo	Amount	Quated Rate in Figure (%)	
99956.00	TOTAL :-	-					
						malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	L
						carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality,	10
						specifications and as per directions and entire satisfaction of the Engineer-in-Charge including	
						with cement mortar 1:6 (One cement isto six sand), as per approved drawing, design and	
	10000					or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth	
	square	Hundred Ninety		metres		walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and	
11020,00	Per	Rupees Two	290.00	Square	38.00	1.15mm (Fifteen milimetres) thick cement plaster in single coat on rough side of brick/concrete/stone	4
7	6	5	4	3	20	2	H

ESTIMATED COST: - ₹

86940.00 1800.00

EARNEST MONEY : - ₹ TIME LIMIT

One Month

NAME OF WORK :-

(Deposit work) Construction of Toilet Block for Boys ( near B.C.A. & Biotechnology Block) in Govt. College at Dharamshala, Distt. Kangra H.P.

SUB-HEAD :-

Providing and fixing M.S. Steel work etcetera

(Amount to be quoted by the contractor in words)
(Amount to
tees with connection plates or angles, cleat as in trusses, trussed purlins Kilograms
828.00
3
Quantity

#### Schedule of Quantity

Q

8

ESTIMATED COST:- ₹ 98400.00

EARNEST MONEY:- ₹ 2000.00

TIME LIMIT : One month

NAME OF WORK :-Restoration of rain damages on various road under Chamunda & Sidhbari Section in Sub Division No. II, HPPWD Dharamshala in Distt. Kangra H.P.

Removal of slips at various R.D.

SUB HEAD :-

	Figure ) words)	(Amount to be quoted by the contractor in Figure ) (Amount to be quoted by the contractor in words)	be quote	Amount to		
98400.00	Total :-	7			Quated Rate in Figure (%)	
98400.00	Per Cubic metre	hundred twenty and paise zero only	120.00	Cubic metres	mechanical means including cutting and trimming of slips and disposal of cut materials within lift upto 1.50 mtrs. (One decimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 3022.3.5 and 1611, complete including filling of earth with tipper and carriage of material by Mechanical Transport loading, unloading and levelling. Average lead 2.K.M. complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	
7	6	5	4	W	Removal of land clide in hilly area in qualification	. 1
	1	words	In fig			4 00
Amount	Unit	Rate		Quantity	Description of items	2 0

Name of work :- Repair/ Improvement of Black Spot near Kali Mata Mandir Kotwali Bazz

c				
S. Description of Law				Time Limits
No.		Quantity		Rate
Providing bythe spreading and composition in			In Figures	In Word
covering, using spreading and compacting by mechanically means stone aggregate size 53mm to 22 from (6th those millioners of	mm to 22 down (fifty these millimeter	1	225000	100000
twenty two point four millimeter) Grading-III size [78mm] seventy five millimeters) compared to a seventy of a seventy five millimeters to method in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eighty-Hundred) K.N. static normal size at the rate of 0.18cmm (zero point eighteen) cubic metres per 10.5qm (per ten square metres) and to fill up the interstoes of course aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire statisfaction and direction of Engineer—in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octool, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	used to 2.2-mins (trity three millimeter to sss] to water bound macadam specification ed 80-100 (eighty-Hundred) K.N. static to 11.2mm (eleven point two millimetres) the metrics) and to fill up the interstoes of cations section 400 and as per the entire ds, lifts and other incidental. The rate is	2 6 6 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	2250.00	Rupees Two Thousand Two Hundred Fifty Only
2 Back filling with granular material behind abutments, wing walls, return walls and returning walls complete as per drawing and M.O.R.D.	complete as per drawing and M.O.R.I	0. 65.88	1250.00	Rupees One
technical specification clause 1204.3.8 (i) and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	inguieer-in-Charge complete, including liana, Octroe, toll tax, GST or any other		1250.00	Rupees One Thousand Two Hundred Fifty Only
	Total	-		
Quoted Kare( in Figures) Percentage		Excess (+)		
		I ess (-)		
	C'Total in Einner			
	Minde a un mison see			
		-		

Dhuramshala privision, HP.PWO Dungmshala



(SH:- Construction of P.C.C. Retaining wall including unlined surface drain at RD 1/320 to 1/325) Kangra (H.P) Deposit work Name of work :- Construction of link road from 2nd Battalian (IRBN) Sakoh to Chetru via banwala km 0/00 to 1/550 n Tehsil Dharanshala Distt. No so 4 Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick misotry/stone misotry, plain / reinforced 2 Construction of unlined surface drain of average cross-sectional area 0.40 sqm (zero point four zero) square metre in ordinary rock to Providing and Laying mechanically mixed and whrated plain cement concrete as per drawings and MORD technical specifications section Hearth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of Back filling with granular material behind abutments, wing walls, return walls and returning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including rate is including octror, royality, Malkanu, toll tax, GST and any other taxes imposed by the Government. 800, 900, 1200 and 1600 noxminal mix 1:4-8 (One cement isto Four sand isto Eight graded/enusbed stone aggregate) 40mm (Forty taxes imposed by the Government. carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, fell tax, GST or any other The rate is including octroi, royality, Malkana, tell tax, GST and any other taxes imposed by the Government section 700 and 1200 and as per direction of Engineer in- charge including carriage of materials within all lends, lifts and other incidentals slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The milimetres) nominal size). for all type of structure like retaining wall / Breast wall efectra including cost of form work and curing complete incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government used in embankment at site, as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be including octroi, rayality, Malkana, toll tax, GST or other taxes imposed by the Government. dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is probibited) as per Quoted Rate( in Figures) Percentage Description of Item G. Total in Words G. Total in Figures TESS (-) Excess (+) Quantity 4.58 9.00 15.93 171.00 9.40 In Figures 950,00 5050,00 350,00 360.00 45.00 Rate Rupees Nine Hundred In Word Hundred Fifty Only Thousand Fifty Only Hundred Sixty Only Rupces Forty Five Per running Rupees Three Rupces Three Rupees Five Fifty Only Earnest Money Rs. Estimated cost Rs, Time Limits 8 Per cubic Per cubic Per cubic metre SHORE metre Each metre Unit 80447,00 99027.00 4351.00 3150,00 Two Month 7695,00 3384.00 Amount 99,027.00 2,000.00



(8)

EARNEST MONEY: -TIME LIMIT

Two Months 99066.00

NAME OF WORK :-Restoration of rain damages on Sidhpur to Khaniyara road via Mouli road in Km RD 0/000 to 4/000 in Tehsil Dharamshala, Distt. Kangra H.P.

S	Description of items	Quantity		RATES	Unit
No.			In fig	In words	
na	2	63	.4	5	6
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 (fifty) metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 (one cement isto three sand isto six graded stone aggregate) or richer mix (I/c equivalent design mix) as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.40 Cubic metres	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic metre
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 & 1603 and as per direction of the Engineer. In — Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arrise out during dewatering as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.60 Cubic Metres	360.00	Rupees Three Hundred Sixty Only	Per Cubic metre
i.	Providing and laying 1:2:4 (1 cement isto 2 coarse sand isto 4 graded stone aggregate 20 mm (Twenty millimetres nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incldentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any	8,64 Cubic Metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic metre

(Amount to be quoted by the contractor in words)	nount to be quotes		
d by the con	(Amount to be quoted by the contractor in Figure	Quated Rate in Figure (%)	
9			1
		Government	
H		including octrol, royality, Malkana, toll tax, GST or any other taxes imposed by the	
		charge in cement mortar within all leads and lifts and other incidental. The rate is	
		as per direction of Engineer-in-charge in cement mortar as per direction of Engineer-in-	
		required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	
Five Only	ograms	position and applying a priming coat of approved steel primer using structural steel etc. as Kilogram	
Rupees One Hundred Per	70.00 105.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in 370.00	4.
	3	2	1

Name of work :-Construction of Ambulance road from Naddi near sunset point to Dhiyal ward No. 3 upto Wood Whistlers Sechool km in Tehsil Dharamshaln Distt. Kanera (H.P)

								A from the same of the	Octroi, toll tax GST or any a	OSBOTH Sunnitaria issuedance	complete including emission	M.O.R.D. technical specific	The second secon	Back filling with organism		70.	. 4	Old Smith man Child	CSHI'- Providing and I swing Com	The second property of
20 CO 10 CO	G Total in Work	G.Total in Figures			September of Control o	Ounted Rated in Element P.		and was imposed by the Covernment.	there is no and it is not the same of the	of materials with in all leads, lifts and other incidentals. The rate is included in	complete including entire satisfaction of Engineer-in-Charpe	M.O.R.D. technical specification clause 1204 3 8 (i) and to the second s	accreat occurred abutificates, wrong walls, return walls and returning walls				Description of Irem	The state of the s		Bita (ILP)
			1.855(-)		Excess (+)							73.50				Ougarin				
											7,000,000,000	1250.00	Charles Charles	In Figures at						STON OF SOM OF
								And And common	Hand CA. O.	OW L DURSTOOLT	The same of the sa	Rupers One	Digital in	In Wood	Kate		1	Barnest		
			9,0	9%						metre	Mitter 12 s	Day audio		0.3000	Unit		Time Limits	Barnest Money Rs.		Estimated cost Rs.
					210/2/00	01072 00					10/20/01/6	01075 00		100000000000000000000000000000000000000	Amount	And the second second	Two Mont	1,900.0	Ī	91.875.00



ESTIMATED COST:- ₹
EARNEST MONEY:- ₹

99196.00 2000.00 Two Months

TIME LIMIT

SUB-HEAD :-Special Repair to Residence of Executive Engineer (P.W.D.) at Chilgari Dharamshala, Distt. Kangra H.P. Providing and fixing venyl flooring and other minor repair work etectera

NAME OF WORK :-

No. 5	Description of items	Quantity	14 14		Onit	Amount
1	2	w	4	5	6	7
-	1 Providing and fixing 2mm ( two millmetre) thick PVC antistatic venyl flooring coloured, carbed or mosaic/	19.35	852.30	×	Per	16492.00
	metalled finish laid with approved adhesive on sub-floor completein Chief office K.Z at Dharamshala, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-	Square		and palse thirty only metre	Square	
	Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
N	2 Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	467.48 Square metres	105.00	Rupees one hundred Per five and paise zero Squ only mer	Square	49085.00
u,	Finishing walls with Acrylic Smooth exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.57 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	123.75 Square metres	130,00	Rupees one hundred Per thirty and paise zero Square only metre	Per Square metre	16088.00
4.	Providing and applying white cement based putty of Birla / JK average thickness 1 mm (one millmetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	88.68 Square metres	73.50	Rupees seventy Per three and palse fifty square only metre	Per square metre	6518.00



	ords)	Amount to be quoted by the contractor in words)	be quoted	Amount to	(Lagred Rate in Words (%)
	gure)	Amount to be quoted by the contractor in Figure	be quoted	Amount to	Rente water a right (76)
99196,00	TOTAL :-	707			Outrod Bare in Florida NO
6880.00	Per Square metre	Rupees one hundred Per twenty five and squ paise zero only mei	125.00	Square metres	6 Painting with acid proof paint of Asian / Nerolac/ Berger of approved brand and manufacture of required colour to give an even shade Two or more coats on new work, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.
					inclusive of octrol, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government,
					Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is
	anam			and and	as per approved drawing, design and specifications and as per directions and entire satisfaction of the
	square	and paise zero only		Square	manufacture of required colour to give an even shade two or more coats on old work (wood & steel work) .
4133,00	Per	Rupees ninety five	95.00	43,50	5 Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and
7	Ot.	5	4	w	





63

# SCHEDULE OF QUANTITY

ESTIMATED ₹ 32500.00
EARNEST ₹ 700.00
TIME LIMIT One Month

NAME OF WORK :-Special Repair of Health Sub Centre building at Sidhourin Tehsil Dharamshala in Distt. Kangra H.P. (Deposit work)

SUB-HEAD :- Cleaning of Chamber

	r in words)	(Amount to be quoted by the contractor in words)	o be quote	(Amount t	Quated Rate in Words (%)	
	r in Figure )	(Amount to be quoted by the contractor in Figure )	o be quote	(Amount t	Quated Rate in Figure (%)	
32500.00	TOTAL :-					
32500.00	Each	32500.00 Rupees thirty two thousand five hundred and paise zero only	32500.00	Job	I Cleaning of 2 Nos. (two numbers) chamber, septic tank drum (2 Nos. (two numbers) and cleaning of sewerage line, as per directions and entire satisfaction of the Engineer-in-Charge including disposal of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	н
7	6	5	4	w	2	-
		In words	In fig			No.
Amount	Unit	RATES		Quantity	Description of items	Ŝ

ESTIMATED COST: - ₹

EARNEST MONEY: - ₹

TIME LIMIT

96657.00

Two Months

NAME OF WORK :-

SUB-HEAD :-

Construction of Toilet Black for Boys ( near B.C.A. & Biotechnology Block) in Govt. Degree College at Dharamshala, Distt. Kangra H.P.

(Deposit work)

Providing and fixing aluminium work, distempering and painting work etcetra.

No. 1 2
H
2 Brick work using Second Class common burnt day F.P.S. (non modular) bricks of class designation 7.5 (seven decimal five) in super-structure aobve plinth level up to floor V level in all shapes and size in cement mortar 1:6 (One cement isto Six sand) and curing complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of actrol, royality, mallybana troll tax, sale tax. GST and any other taxes imposed by the Government.
3 15mm (Fifteen millimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, malkhana, toll tax.
4 Finishing walls with Acrylic Smooth exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm ( one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm ( two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality, and the satisfaction of the Government.

	0	U1
EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge - (Cost of aluminium snap beading shall be paid in basic item): , With float glass panes of 5 mm ( five milimetres) thickness (weight not less than 12.50 kg/ sqm) ( twelve decimal fifty kilogram per squre metres), as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	Providing and fixing aluminium Frame work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen)) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.
0.58 Square metres	36.77 Kilogram ms	13.42 Kilogram ms
1200.00	680.00	650.00
Rupees One Thousand Two Hundred Only	Rupees Six Hundred Eighty Only	Rupees Six Hundred Fifty Only
Per square metre	d Per Kilogram	d Per Kilogram
696.00	25004.00	8723.00

					11	-		_			10 1					_	_	9 9		_	Til.	-	m	· Cu	_		00	1 2
carriage of material, within all reads, into and other includentals, the following of occasion, regently,	reison of material within all leads. lifts and other incidentals. The rate is inclusive of octrol royality	design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including	to required colour or shade, with necessary screws etcetera complete as per approved drawing,	ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed	Providing and fixing 150x16mm (one hundred fifty into sixty milimetre) size aluminium tower bolts,	malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octrol, royality,	design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including	dyed to required colour or shade, with nuts and screws etcetera complete; as per approved drawing,	bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or	Providing and fixing 250x16 mm ( two hundred fifty into sixteen milimetre) aluminium sliding door	GST and any other taxes imposed by the Government.	leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax,	directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all	millimetres) mild steel U beading as per approved drawing, design , specifications and as per	with wire of dia. 0.50 mm ( zero decimal five zero millimetre) all complete With 12 mm ( twelve	wire gauge with average width of aperture 1.4 mm ( one decimal four millimetre) in both directions	9 Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using	of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive	approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-	partical board with decorative lamination on one side and balancing lamination on other side, as per	etcetera complete as per architectural drawing and direction of Engineer- in- charge. Pre-laminated	aluminium doors, windows shutters and partition frames with C.P. brass/stainless steel screws	Tesa / Greelam / Merinolam / Kitlam / Vista of approved shade Grade - I, Type II, in panelling fixed in	matt finish flat pressed three layer or graded wood partical board conforming to IS: 12823 of Action	Providing and fixing 12mm thick Phenol bonded (both side) prelaminated BWP Grade partical board in	
				Numbers	14.00					Number	1.00					metres	Square	0.58							metres	Square	1.26	
					90.00					551.00	250.00			Ī	Ī			1050.00		Ī		Ī	Ī				1250.00	
					Rupees Ninety Only					Hundred Hitty Only	Rupees Two			7			Thousand Fifty Only						٠	,	100	Hundred Fifty Only	-	
				7	Each						Each				Ī			Each				100			7007757	metre	Per	
					1260.00						250.00							609,00									1575.00	

	words)	(Amount to be quoted by the contractor in words)	o be quote	Amount t	
	n Figure	president to be quoted by the contractor in Figure	o ne duor	T. S.	Quotad Rate in Words (%)
	1	od hwith continue	ho more	Amount	Quated Rate in Figure (%)
96657,00	TOTAL :-	71			
1000.00	Each	Rupees One Hundred Twenty Five Only	125.00	8.00 Numbers	anodised (anodic coating not less than grade AC 10 (ten) as per IS: 1868) transparent or dyed to Numbers required colour or shade, with necessary screws etcetera complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.
7	6	5	4	w	Providing and fixing 125mm (One hundred tweets five will not 1.

Name of work - Repair of Path from link road to Ashok Kumar house Ward No. 3 G.P. Rakkar in Tehsil Dharamshala, Distt. Kangra .(Deposit work). (SH.- Providing

1000	Quota	Quot	ceme upto within Four block separ of the rate is		1 Pro
	Quoted rate in Words (%)	Quoted rate in figure (%)	cement concrete of NTC or as approved by the HPPWD inter locking paver blocks vibro compacted upto M-50 (M-Fifty) grade including border or kurb block Grey or coloured over sub-base of concrete withn 25mm (Twenty five milimetres) thick average thickness of cement mortar 1:4 (One cement: Four sand) taid over and jointed with neat cement sturry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub-base concrete floor to be paid for separately) as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The Total	1.3.6 (One coment isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeter) nominal size), on ground or under water for all type of structure, in drain,edge wall and the fike etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths including cost of form work and curing complete for 14 (fourteen) days as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	ing and laving mochanicals, mixed and the second
Amount to be q		Amount to be o	52.40 Square 1500.00 metre	3.65 Cubic metre	Quantity
uoted by ti	for manner	noted by	1500.00	5450.00	Figures
(Amount to be quoted by the contractor in words)	the contractor in	(Amount to be guoted by the contractor in figure)	Rupees One Thousand Five Hundred Only	Rupees Five Thousand Four Hundred Fifty Only	Words
words)	rigure)		Per Square metre	Per Cubic metre	Unit
		98493.00	78600.00	19893.00	Amount

