

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-
To,

2236-86

Dated:- 27/6/2025

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec(PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 03.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 04.07.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 05.07.2025 upto 11.00AM |
| 4. Date and time of opening of tenders: | 05.07.2025 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class Contrac
1	Construction of Retaining wall near the house of Pritam Singh S/O Madhu Ram Ward No. 1 Mohal Dhameta (Under SDRF) Deposit work (SH:- Construction of Retaining wall).	Rs.75,317/-	Rs.1900/-	One Month	350/-	Class D&C
2	Construction of Pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P Nagal Under (MLALAD) Deposit work (SH:- Providing and Laying Cement concrete pavement).	Rs.92,016/-	Rs.1900/-	One Month	350/-	Class D&C
3	Construction of Retaining wall near the land of Balwan Singh till road village Thathar Under (MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/010).	Rs.94,969/-	Rs.1900/-	One Month	350/-	Class D&C
4	Re-Co Restoration of rain damage on Badukhar Diyana road Km. 0/0 to 5/0 Under (SDRF) Deposit work (SH:- Construction of Edge wall with U-shape drain at RD. 2/400 to 2/428).	Rs.95,865/-	Rs.2000/-	One Month	350/-	Class D&C
5	Construction of Pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P Nagal Under (MMGPY) Deposit work (SH:- Providing and Laying Cement concrete pavement).	Rs.95,807/-	Rs.2000/-	One Month	350/-	Class D&C
6	Construction of Retaining wall near house of Dhian Singh Swarna Devi in Ward No. 03 Under (SDRF) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/010).	Rs.95,301/-	Rs.1900/-	One Month	350/-	Class D&C
7	Construction of Retaining wall near the house of Sh. Vikas Kalia village ROD Under (MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/005).	Rs.46,464/-	Rs.1000/-	One Month	350/-	Class D&C
8	Construction of Pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P Nagal Under (MLALAD) Deposit work (SH:- Providing and Laying Cement concrete pavement).	Rs.92499/-	Rs.1900/-	One Month	350/-	Class D&C
9	Construction of road from Dispensary to Pooran Singh house village Nanooh ward No. 5 Under (MLALAD) Deposit work (SH:- Providing and Laying 60mm interlocking paver block at RD. 0/00 to 0/029).	Rs.94797/-	Rs.1900/-	One Month	350/-	Class D&C
10	Construction of Pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P Nagal Under (MLALAD) Deposit work (SH:- Providing and Laying Cement concrete pavement).	Rs.92016/-	Rs.1900/-	One Month	350/-	Class D&C
11	Construction of Drainage near the house of Onkar Singh etc. village Bhatoli Pakwan in G.P Bhatian (Under MLALAD) Deposit work (SH:- Construction of Retaining wall at RD. 0/0 to 0/007.40)	Rs.48,468/-	Rs. 1000/-	One Month	350/-	Class D&C
12	Construction of Path from Pukhar Talab to Balbir Singh house Ward No. 7 Batlahar G.P. Barot Khas Under (MLALAD) Deposit work (SH:- Providing and Laying Cement concrete Pavement at RD 0/0 to 0/039).	95810/-	2000/-	One Month	350/-	Class D&C
13	Construction of pucca path from link road to Ashok Kumar House Ward No. 4 Under (MLALAD) DC Deposit work (SH:- Providing and laying 60 mm interlocking paver blocks)	73322/-	1500/-	One Month	350/-	Class D&C

14	Construction of completion of Mahila Mandal Bhawan at Village Kutkana Under (MLALAD) Deposit work (SH:- Construction of brick work , plastering, Painting, windows , doors and other minor work)	99471/-	2000/-	One Month	350/-	Class D&C
15	Re- Construction of retaining wall near the house of S/O Sh. Jagat Ram village Kutkana Under (SDRF) DC Deposit (SH:- Construction of retaining wall at RD 0/0 to 0/029)	95174/-	1900/-	One Month	350/-	Class D&C
16	Re- Construction of retaining wall near Mahila Mandal Bhawan Polling Booth No. I Dhaneti Charoorian Ward No. 8 Under (SDRF) DC Deposit (SH:- Construction of retaining wall at RD 0/0 to 0/017)	94703/-	1900/-	One Month	350/-	Class D&C
17	Construction of retaining wall near the house of Smt. Asha Devi W/o Joginder Singh village Bancheryati P.O. Dhameta Tehsil Fatehpur Under (SDRF) DC Deposit (SH:- Construction of retaining wall)	95153/-	1900/-	One Month	350/-	Class D&C
18	Construction of Rehan to Bhatoli via Chamral road km 0/0 to 4/0 Under (SDP) Deposit work (SH:- Construction of U-shape drain with edge wall at RD 2/170 to 2/270)	97418/-	2000/-	One Month	350/-	Class D&C
19	A/R & M/O to various Bridges (Jagnoli Khad, Chalal Khad, Luthiyal Khad and Ghaith Khad) Under Dhameta Sub Division (SH:- Providing and applying cement based putty , emulsion and enamel paint)	99851/-	2000/-	One Month	350/-	Class D&C
20	Construction of retaining wall near the house of Ranjeet Singh Village Jharoli Under (SDRF) DC Deposit (SH:- Construction of Retaining wall at RD 0/0 to 0/035)	75998/-	1600/-	One Month	350/-	Class D&C
21	Re- Construction of retaining wall from Ratan Lal , Nand Lal ke Khet se Chaman Lal ke Ghar Tak Ward No. 4 Under (SDRF) DC Deposit (SH:- Construction of Retaining wall at RD 0/0 to 0/022)	94298/-	1900/-	One Month	350/-	Class D&C
22	R/O Mahila Mandal Bhawan at Ward No. 8 Talara Under (SDRF) DC Deposit (SH:- Dismantling of old doors and windows, Providing and fixing aluminium doors and windows, painting work and minor repair work)	94932/-	1900/-	One Month	350/-	Class D&C
23	A/R & M/O to various roads Under Dhameta Sub Division (SH:- Painting, Lettering on road sign boards and Km. stones etc.) Under Khatiar Section	99650/-	2000/-	One Month	350/-	Class D&C
24	R/O (Repair of) Restoration of rain damages on Raja-Ka-Talab to Batrahan Golwan Chhattar road Under (SDRF) DC Deposit Work (SH:- Construction of retaining wall at RD 1/293 to 1/305).	94735/-	1900/-	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

25

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Pritam Singh S/O Madhu Ram Ward No.1 Mohal Dhameta (Under SDRF) Deposit work (SH:-Construction of Retaining wall)

Estimated cost:- Rs.75317/- only

Earnest Money : Rs.1500/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental .	9.72 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3300.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.50 cubic meter	3390.10	Rupees Three Thousand Three Hundred Ninety And Paise Ten Only	Per cubic meter	69497.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	315.00	Rupees Three Hundred Fifteen Only	Each	2520.00
					Total:-	75317.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt Kangra (H.P.)

96 (1)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P. Nagal Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement)

Estimated cost:- Rs.92016/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	6.81 Cubic meter.	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	12231.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.40 Cubic meter.	5540.60	Rupees Five Thousand Five Hundred Forty And Paise Sixty Only	Per cubic meter	79785.00
					Total:-	92016.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division H.P.W.D.
Fatehpur District (Kangra H.P.)
2

3

27

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the land of Balwan Singh till road village Thathar Under (MLALAD) Deposit					Estimated cost:- Rs.94969/- only	
Work (SH):- Construction of retaining wall at R.D. 0/0 to 0/010)					Earnest Money : Rs.1900/- only	
					Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	6.60 Cubic meter.	305.10	Rupees Three Hundred Five And Paise Ten Only	Per cubic meter	2014.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.05 cubic meter	3350.60	Rupees Three Thousand Three Hundred Fifty And Paise Sixty Only	Per cubic meter	90634.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	290.15	Rupees Two Hundred Ninety And Paise Fifteen Only	Each	2321.00
					Total:-	94969.00
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Fathoni Division, Hoshiarpur
 Fathoni Distt. Kangra

28

28

SCHEDULE OF QUANTITY

Name of work:- Re-C/O Restoration of rain damages on Badukhar Diyana road km.0/0 to 5/0 (Under SDRF) Deposit work (SH):- Construction of edge wall with U-shape drain at R.D. 2/400 to 2/428.50).				Estimated cost:- Rs.95865/- only		
				Earnest Money : Rs.2000/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	21.38 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	7259.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	18.81 Cubic meter.	4710.60	Rupees Four Thousand Seven Hundred Ten And Paise Sixty Only	Per cubic meter	88606.00
					Total:-	95865.00
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

(S)

22

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P. Nagal Under (MMGPY) Deposit work (SH:- Providing and laying cement concrete pavement)					Estimated cost:- Rs.95807/- only	
					Earnest Money : Rs.2000/- only	
					Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	7.44 Cubic meter.	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	13363.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.88 Cubic meter.	5540.60	Rupees Five Thousand Five Hundred Forty And Paise Sixty Only	Per cubic meter	82444.00
					Total:-	95807.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division, Meerut
 Fatehpur, Meerut
 201001

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near House of Dhian Singh Swarna Devi in Ward No.03 Under (SDRF) Deposit work
(SH):- Construction of Retaining wall at R.D. 0/00 to 0/08)

Name of work:- Construction of Retaining wall near House of Dhian Singh Swarna Devi in Ward No.03 Under (SDRF) Deposit work (SH:- Construction of Retaining wall at R.D. 0/00 to 0/08)							Estimated cost:- Rs.95301/- only	
							Earnest Money : Rs.1900/- only	
							Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.52 Cubic meter.	300.00	Rupees Three Hundred Only	Per cubic meter	1656.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.65 cubic meter	3300.00	Rupees Three Thousand Three Hundred Only	Per cubic meter	91245.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8 Numbers	300.00	Rupees Three Hundred Only	Each	2400.00		
					Total:-	95301.00		
Amount quoted by the contractor in % Above/Below								

Amount quoted by the contractor in % Above/Below

Engineer
Super Division
District Engineer

31

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Sh.Vikas Kalia Village Rod Under (MLALAD) Deposit Work (SH:- Construction of retaining wall at R.D. 0/0 to 0/005.50)							Estimated cost:- Rs.46464/- only		Earnest Money : Rs.1000/- only		
Sr. No	Description of items	Quantity	Rate		Unit	Amount	Time limit:- one month				
			In words	In figures							
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	3.30 Cubic meter.	308.30	Rupees Three Hundred Eight And Paise Thirty Only	Per cubic meter	1017.00					
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.10 cubic meter	3380.60	Rupees Three Thousand Three Hundred Eighty And Paise Sixty Only	Per cubic meter	44286.00					
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 Numbers	290.15	Rupees Two Hundred Ninety And Paise Fifteen Only	Each	1161.00					
					Total:-	46464.00					
Amount quoted by the contractor in % Above/Below											

Amount quoted by the contractor in % Above/Below

Executive Engineer
Regional Division (RFPWD)
Patna District, Khatwa (R.P.)

2

32

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P. Nagal Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement)				Estimated cost:- Rs.92499/- only		
				Earnest Money : Rs.1900/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	6.77 Cubic meter.	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	12160.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.50 Cubic meter.	5540.60	Rupees Five Thousand Five Hundred Forty And Paise Sixty Only	Per cubic meter	80339.00
					Total:-	92499.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur, Distt. Kangra (H.P.)

33

SCHEDULE OF QUANTITY

Name of work:- Construction of road from Dispensary to Pooran Singh house village Nanooh Ward No.5 Under (MLALAD) Deposit						Estimated cost:- Rs.94797/- only	
Work (SH):- Providing and laying 60mm interlocking paver block at R.D. 0/00 to 0/029)						Earnest Money : Rs.1900/- only	
						Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer-in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	8.15 Cubic meter.	3890.60	Rupees Three Thousand Eight Hundred Ninety And Paise Sixty Only	Per cubic meter	31708.00	
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	79.85 Square meter	790.10	Rupees Seven Hundred Ninety And Paise Ten Only	Per Square meter.	63089.00	
					Total:-	94797.00	
	Amount quoted by the contractor in % Above/Below						

Executive Engineer
 Paver Division HPPWD
 Fatehgarh Distt. Kangra (H.P.)

34 (9)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from main road to the house of Ramesh, Subhash etc. village Nagal SC Basti G.P. Nagal Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement)						Estimated cost:- Rs.92016/- only	
						Earnest Money : Rs.1900/- only	
						Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimeter) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	6.81 Cubic meter.	1796.10	Rupees One Thousand Seven Hundred Ninety Six And Paise Ten Only	Per cubic meter	12231.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythene film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.40 Cubic meter.	5540.60	Rupees Five Thousand Five Hundred Forty And Paise Sixty Only	Per cubic meter	79785.00	
					Total:-	92016.00	

Amount quoted by the contractor in % Above/Below


 Executive Engineer
 Pucca Division HPPWD
 Faizabad Dist. Karjga (H.D.)

SCHEDULE OF QUANTITY

Name of work:- Construction of path from Pukhar Talab to Balbir Singh House Ward No.7 Batlahar G.P. Barot khas Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/039).

Estimated cost:- Rs.95810/- only
Earnest Money : Rs.2000/- only
Time limit:- One month

Sr.No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 Using naturally occurring gravel as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.50 Cubic meter.	840.50	Rupees Eight Hundred Forty And Paise Fifty Only	Per cubic meter	16390.00
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.625 Cubic meter.	5430.40	Rupees Five Thousand Four Hundred Thirty And Paise Forty Only	Per cubic meter	79420.00
					Total:-	95810.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P.)

13

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path from link road to Ashok Kumar House Ward No.4 Under (MLALAD) Deposit work (SH:- Providing and laying 60mm Interlocking Paver Blocks)

Estimated cost:- Rs.73322/- only
Earnest Money : Rs.1500/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	6.25 Cubic meter.	3880.50	Rupees Three Thousand Eight Hundred Eighty And Paise Fifty Only	Per cubic meter	24253.00
2	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	62.50 Square meter	785.10	Rupees Seven Hundred Eighty Five And Paise Ten Only	Per Square meter.	49069.00
					Total:-	73322.00

Amount quoted by the contractor in % Above/Below

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P.D.)

19

SCHEDULE OF QUANTITY

Name of work:- C/O Completion of Mahila Mandal Bhawan at village Kufkara Under (MLALAD) Deposit Work (SH):- Construction of brick work, plastering, painting, windows, doors and other minor work).

Estimated cost:- Rs.99471/- only
Earnest Money : Rs.2000/- only
Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 (fifty metres lead and as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 Numbers	156.25	Rupees One Hundred Fifty Six And Paise Twenty Five Only	Each	625.00
2	Providing and fixing aluminium work for door, windows (minimum thickness of powder coating 50 micron) consisting of tee/ angle sections, of approved make conforming to IS : 733 in frames of false ceiling including aluminium angle cleats with necessary C.P. brass/stainless steel sunk screws, aluminium perimeter angles fixed to wall with stainless steel rawl plugs @ 450 mm (four hundred fifty millimeter) centre to centre and fixing the frame work to G.I. level adjusting hangers 6 mm (six millimeter) dia. with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in charge (level adjusting hangers, ceiling cleats and expansion hold fasteners to be paid for separately) including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.77 kilo gramme	603.50	Rupees Six Hundred Three And Paise Fifty Only	Per kilogram	20984.00
3	Providing and fixing aluminium work for doors, windows, board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade-I Type -II in panelling in aluminium doors, windows shutters and partition frames with C.P. Brass/ stainless steel screws etc. complete as per Architectural drawings and direction of Engineer-in-charge. Prelaminated particle board with decorative lamination on one side and balancing lamination on other side as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.96 Square meter	900.00	Rupees Nine Hundred Only	Per square meter	5364.00
4	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS:1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/stainless steel screws @ 200 mm (two hundred millimeter) centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer in-charge. (Only weight of grill to be measured for payment) as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.78 Square meter	482.50	Rupees Four Hundred Eighty Two And Paise Fifty Only	Per square meter	1824.00
5	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS:2222 in superstructure above plinth level upto floor five level in cement mortar 1:6 (one cement isto six coarse sand) with Modular bricks including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.78 Cubic meter	6230.90	Rupees Six Thousand Two Hundred Thirty And Paise Ninety Only	Per cubic meter	17322.00

6	6 mm (six millimeter) cement plaster of mix 1:3 (one cement isto three fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	46.52 square meter	142.35	Rupees One Hundred Forty Two And Paise Thirty Five Only	Per square meter	6622.00
7	15mm (fifteen millimeter) thick cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement isto six sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	30.04 square meter	185.40	Rupees One Hundred Eighty Five And Paise Forty Only	Per square meter	5569.00
8	12 mm (twelve millimeter) cement plaster of mix 1:4 (one cement isto four fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	58.03 square meter	172.85	Rupees One Hundred Seventy Two And Paise Eighty Five Only	Per square meter	10030.00
9	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade two or more coats on new work including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.03 Square meter	89.50	Rupees Eighty Nine And Paise Fifty Only	Per square meter	5194.00
10	Providing and applying white cement based putty of average thickness 1 mm, (One millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	76.56 Square meter	85.10	Rupees Eighty Five And Paise Ten Only	Per square meter	6515.00
11	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats. including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	76.56 Square meter	74.80	Rupees Seventy Four And Paise Eighty Only	Per square meter	5727.00
12	52 mm (fifty two millimeter) thick cement concrete flooring with concrete hardener topping, under layer 40 mm (forty millimeter) thick cement concrete 1:2:4 (one cement isto two coarse sand isto four) graded stone aggregate 20 mm nominal size) and top layer 12 mm (twelve millimeter) thick cement hardener consisting of mix 1:2 (one cement hardener mix isto two) graded stone aggregate 6 mm (six millimeter) nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete. including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.65 Square meter	579.05	Rupees Five Hundred Seventy Nine And Paise Five Only	Per square meter	13695.00
					Total:-	99471.00
	Amount quoted by the contractor in % Above/Below					


 Engineer
 Planning Division HPWD
 Fatehpur Distt. Kangra (H.P.)

15

SCHEDULE OF QUANTITY

Name of work:- Re construction of Retaining wall near the house of S/O Sh. Jagat Ram village Kutkana Under (SDRF) Deposit Work							Estimated cost:- Rs.95174/- only	
(SH:- Construction of retaining wall at R.D. 0/00 to 0/029) (DC Deposit)							Earnest Money : Rs.1900/- only	
							Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.02 Cubic meter.	317.50	Rupees Three Hundred Seventeen And Paise Fifty Only	Per cubic meter	3499.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.00 cubic meter	3430.60	Rupees Three Thousand Four Hundred Thirty And Paise Sixty Only	Per cubic meter	85765.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00 Numbers	295.50	Rupees Two Hundred Ninety Five And Paise Fifty Only	Each	5910.00		
					Total:-	95174.00		
	Amount quoted by the contractor in % Above/Below							

Executive Engineer
Patancheru Division HPPW
Patancheru Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Re construction of Retaining wall near Mahila Mandal Bhawan Polling Booth No. 1 Dhaneti Charoorian Ward No.8 Under (SDRF) ~~Deposit Work~~ (SH:- Construction of retaining wall at R.D. 0/00 to ~~0/7300~~ ^{0/017}) (OC Deposit)

Estimated cost:- Rs.94703/- only
Earnest Money : Rs.1900/- only
Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.32 Cubic meter.	318.50	Rupees Three Hundred Eighteen And Paise Fifty Only	Per cubic meter	3287.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.00 cubic meter	3420.50	Rupees Three Thousand Four Hundred Twenty And Paise Fifty Only	Per cubic meter	85513.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00 Numbers	295.15	Rupees Two Hundred Ninety Five And Paise Fifteen Only	Each	5903.00
					Total:-	94703.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Smt. Asha Devi W/O Joginder Singh Village Bancheryati P.O.Dhameta Tehsil Fatehpur Under (SDRF) Deposit Work (SH:- Construction of retaining wall) (D.C. Deposit)							Estimated cost:- Rs.95153/- only	
							Earnest Money : Rs.1900/- only	
							Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.65 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3955.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	22.50 cubic meter	3950.10	Rupees Three Thousand Nine Hundred Fifty And Paise Ten Only	Per cubic meter	88877.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00 Numbers	290.15	Rupees Two Hundred Ninety And Paise Fifteen Only	Each	2321.00		
					Total:-	95153.00		
	Amount quoted by the contractor in % Above/Below							

Executive Engineer
Fatehpur District HPPWD
Fatehpur Distt. Kangra (H.P.)

18

SCHEDULE OF QUANTITY

Name of work:- Construction of Rehan to Bhatoli via Chamral road km.0/0 to 4/0 Under (SDP) Deposit Work (SH:- Construction of U-shape drain with edge wall at R.D.2/170 to 2/270).							Estimated cost:- Rs.97418/- only	
							Earnest Money : Rs.2000/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	26.56 Cubic meter.	318.60	Rupees Three Hundred Eighteen And Paise Sixty Only	Per cubic meter	8462.00		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification clause 802, 803, 1202 and 1204 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.88 Cubic meter.	4330.10	Rupees Four Thousand Three Hundred Thirty And Paise Ten Only	Per cubic meter	29791.00		
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter-) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	14.40 Cubic meter.	3790.60	Rupees Three Thousand Seven Hundred Ninety And Paise Sixty Only	Per cubic meter	54585.00		
4	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.00 Numbers	305.30	Rupees Three Hundred Five And Paise Thirty Only	Each	4580.00		
					Total:-	97418.00		
	Amount quoted by the contractor in % Above/Below							

Executive Engineer
 Fatunpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

109

SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O to various Bridges (Jagnoli khad, Chahal khad, Luthiyal khad and Ghaith khad) Under Dhameta Sub Division (SH:- Providing and applying cement based putty, emulsion and enamel paint)			Estimated cost:- Rs.99851/- only			
			Earnest Money:- Rs.2000/- only			
			Time limit:- One Month			
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and applying white cement based putty of average thickness 1mm (One millimeter) of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	177.06 square meter	85.10	Rupees Eighty Five And Paise Ten Only	Per square meter	15068.00
2	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With water thinnable cement primer on wall surface having VOC content less than 50 (Fifty) grams/litre including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	681.00 square meter	37.40	Rupees Thirty Seven And Paise Forty Only	Per square meter	25469.00
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats on new work including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	243.00 square meter	82.40	Rupees Eighty Two And Paise Forty Only	Per square meter	20023.00
4	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	439.00 square meter	89 50	Rupees Eighty Nine And Paise Fifty Only	Per square meter	39291.00
					Total:-	99851.00
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near house of Ranjeet Singh village Jharoli Under (SDRF) ~~Deposit~~ Work (SH:- Construction of retaining wall at R.D. 0/0 to 0/035) *(D.C. deposit)*

Estimated cost:- Rs.75998/- only
Earnest Money : Rs.1600/- only
Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.55 Cubic meter.	315.60	Rupees Three Hundred Fifteen And Paise Sixty Only	Per cubic meter	3645.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.11 cubic meter	3410.50	Rupees Three Thousand Four Hundred Ten And Paise Fifty Only	Per cubic meter	65175.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00 Numbers	299.10	Rupees Two Hundred Ninety Nine And Paise Ten Only	Each	7178.00
					Total:-	75998.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

21

SCHEDULE OF QUANTITY

Name of work:- Re construction of Retaining wall from Ratan Lal, Nand Lal, Ke Khet se Chaman Lal Ke Ghar Tak Ward No.4

Under (SDRF) ~~Deposit Work~~ (SH:- Construction of retaining wall at R.D. 0/0 to 0/022)(D.C. Depositi)

				Estimated cost:- Rs.94298/- only	
				Earnest Money : Rs.1900/- only	
				Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Amount
			In words	In figures	
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.58 Cubic meter.	318.90	Rupees Three Hundred Eighteen And Paise Ninety Only	2736.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for a" heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.97 cubic meter	3430.50	Rupees Three Thousand Four Hundred Thirty And Paise Fifty Only	85660.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00 Numbers	295.10	Rupees Two Hundred Ninety Five And Paise Ten Only	5902.00
				Total:-	94298.00

Amount quoted by the contractor in % Above/Below


Executive Engineer
Patnagar Division HPPW
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Mahila Mandal Bhawan at Ward No.8 Talara Under (SDRF) ~~Deposit~~ Work
(SH:- Dismantling of old doors and windows, providing and fixing aluminium doors and windows, painting work and minor repair works) (D.C. Deposit)

Estimated cost:- Rs.94932/- only
Earnest Money : Rs.1900/- only
Time limit:- one month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 (fifty metres lead and as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00 Numbers	156.25	Rupees One Hundred Fifty Six And Paise Twenty Five Only	Each	781.00
2	Providing and fixing aluminium work for door, windows (minimum thickness of powder coating 50 micron) consisting of tee/ angle sections, of approved make conforming to IS : 733 in frames of false ceiling including aluminium angle cleats with necessary C.P. brass/stainless steel sunk screws, aluminium perimeter angles fixed to wall with stainless steel rawl plugs @ 450 mm (four hundred fifty millimeter) centre to centre and fixing the frame work to G.I. level adjusting hangers 6 mm (six millimeter) dia. with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in charge (level adjusting hangers, ceiling cleats and expansion hold fasteners to be paid for separately) including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	60.48 kilo gramme	570.60	Rupees Five Hundred Seventy And Paise Sixty Only	Per kilogram	34510.00
3	Providing and fixing aluminium work for doors, windows, board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade-I Type -II in panelling in aluminium doors, windows shutters and partition frames with C.P. Brass/ stainless steel screws etc. complete as per Architectural drawings and direction of Engineer-in-charge. Prelaminated particle board with decorative lamination on one side and balancing lamination on other side as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.84 square meter	810.00	Rupees Eight Hundred Ten Only	Per square meter	5510.00
4	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS:1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/stainless steel screws @ 200 mm (two hundred millimeter) centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer in-charge. (Only weight of grill to be measured for payment) as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.72 Square meter	382.50	Rupees Three Hundred Eighty Two And Paise Fifty Only	Per square meter	3718.00

5	Repairs to plaster of thickness 12 mm to 20 mm (twelve millimeter to twenty millimeter) in patches of area 2.5 (two point five) sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in Charge with cement mortar 1:4 (One cement isto four coarse sand) including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	69.00	276.15	Rupees Two Hundred Seventy Six And Paise Fifteen Only	Per square meter	19054.00
6	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade two or more coats on new work including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	70.73	89.50	Rupees Eighty Nine And Paise Fifty Only	Per square meter	6330.00
7	Providing and applying white cement based putty of average thickness 1 mm, (One millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	89.34	85.10	Rupees Eighty Five And Paise Ten Only	Per square meter	7603.00
8	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coats. including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	127.25	74.80	Rupees Seventy Four And Paise Eighty Only	Per square meter	9518.00
9	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, 1.5 m x 3 m finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 kg/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/ 450N/ 5cm. Tear strength in longitudinal and transverse direction as 300/ 250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.20	410.30	Rupees Four Hundred Ten And Paise Thirty Only	Per square meter	7878.00
					Total:-	94932.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Panchayat Division HPPWD
 Fatehpur Distt. Kangra (HP)

23

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads Under Dhameta Sub Division (SH:- Painting Lettering on road sign boards and Km. stones etc.) Under Khatiar Section.							Estimated Cost:- Rs.	99650.00
							Earnest Money:- Rs.	2000.00
							Time limit:- The Months	
Sr. No.	Description of items	Quantity	Rate		Unit	Amount.		
			In words	In figures				
1	Painting steel work with Deluxe Multi Surface paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sam (Zero point nine zero litre/ten square meter) over an under coat of primer @ 0.80 ltr./10 sqm (Zero point eight zero litre/ ten square meter) of approved brand and manufacture as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	33.50	99.20	Rupees Ninety Nine And Paise Twenty Only	Per square metre	3323.00		
2	Finishing walls with textured exterior paint shade Old work (one or more coats) applied @ 1.82 Ltr./10 Sqm. (Zero point eight two litre/ten square meter)including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	40.00	95.30	Rupees Ninety Five And Paise Thirty Only	Per square metre	3812.00		
3	Writing letters of figures on any surface with black japan paint (Stop commas, hyphens and like not to be measured and paid separately)							
	(a) Indian Letter/Figure.	15800.00	3.20	Rupees Three And Paise Twenty Only	Per letter Per centi metre Height	50560.00		
	(b) Block letter/Figure.	12100.00	3.30	Rupees Three And Paise Thirty Only	Per letter Per centi metre Height	39930.00		
4	Painting index hand normal size or arrows (up to 40cm) long on any surfaces either black japan paint including carriage of material with in all leads & lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	30.00	67.50	Rupees Sixty Seven And Paise Fifty Only	Per Figure	2025.00		
					Total:-	99650.00		
	Amount quoted by the contractor in % Above/Below							

Executive Engineer
Painting Division (P.P.W.D.)
Patel, Dhameta, Kangra

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Restoration of rain damages on Raja-Ka-Talab to Batrahan Golwan Chhattar road Under (SDRF) DC Deposit Work (SH:- Construction of retaining wall at R.D. 1/293 to 1/305)							Estimated cost:- Rs.94735/- only	
							Earnest Money : Rs.1900/- only	
							Time limit:- one month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	7.20 Cubic meter.	318.30	Rupees Three Hundred Eighteen And Paise Thirty Only	Per cubic meter	2292.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush , required at site which may arise at the time of laying or water complete for all heights/depths in parapet including the cost of for r work as per drawing and M.O.R.D. technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.30 cubic meter	3401.60	Rupees Three Thousand Four Hundred One And Paise Sixty Only	Per cubic meter	89462.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00 Numbers	298.10	Rupees Two Hundred Ninety Eight And Paise Ten Only	Each	2981.00		
					Total:-	94735.00		
	Amount quoted by the contractor in % Above/Below							


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)